



KARACHI WATER & SEWERAGE BOARD

OFFICE OF THE DIRECTOR (DESIGN & ESTIMATE)

BID EVALUATION REPORT


| | | |
|----|--|---|
| 1 | Name of Procuring Agency: | KARACHI WATER & SEWERAGE BOARD |
| 2 | Tender Reference No: | SPPRA Serial No.33326 I.D No. _____ |
| 3 | Tender Description/Name of Work/Item: | PROVIDING & FIXING M.S TEE ON 48" DIA PRCC INFRONT OF NAYA NAZIMABAD AND REPAIRING OF HEAVY LEAKAGES ON 48" DIA PRCC (INTERNAL) FROM NAY NAZIMABAD TO DO-RASTA MANGHOPIR ROAD AND CONSTRUCTION OF CHAMBER (8'X8'X8') |
| 4 | Method of Procurement: | <u>Single Stage (One Envelop)</u> |
| 5 | Tender Published: | <u>Through SPPRA Web Site</u> |
| 6 | Total Bid Documents Sold: | <u>2 Nos</u> |
| 7 | Total Bid Received: | <u>2 Nos</u> |
| 8 | Technical Bid Opening Date (if applicable): | <u>N/A</u> |
| 9 | No. of Bid Technically Qualified (if applicable) | <u>N/A</u> |
| 10 | Bid (s) Rejected: | <u>NIL</u> |
| 11 | Financial Bid Opening Date: | <u>06-06-2017</u> |

12 BID EVALUATION REPORT


| S# | Name of Firm / Bidder | COST OFFERED BY THE BIDDER | RANKING IN TERMS OF COST | COMPARISON WITH ESTIMATED COST | REASON FOR ACCEPTANCE / REJECTION | REMARKS |
|----|--------------------------|----------------------------|--------------------------|--------------------------------|--|--------------------------|
| 1 | M/s.Jawab Gul & Co. | Rs.9,97,556/- | 1 st Lowest | @0.127% Below | Pay Order and required documents are available. P.O # 17909411 dt:05-06-2017 Rs.20,000/- from HBL Taimuria Market Branch Karachi | Substantially Responsive |
| 2 | M/s.Techwin Engg.& Const | Rs.10,34,863/- | 2 nd Lowest | @3.608% Above | Pay Order and required documents are available. P.O # 12054547 dt:30-05-2017 Rs.33,000/-from UBL Manghopir Road Branch Karachi | Substantially Responsive |


The all concerned bidders are being informed accordingly.

The E.E Concerned for compliance of Rule-45 of SPPRA 2010 **M/s.Jawab Gul & Company** declared as the lowest responsive bidder by the Committee and recommended for sanction from Competent Authority.


(Wasif Akhtar)
Accounts Officer (W/D)
Member / Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit – KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Owais Malik)
S.E (Water Trunk Main)
Member


(Saleem Ahmed)
Director (Design & Estimate)
Convener

COMPARATIVE STATEMENT

Name of Work: PROVIDING & FIXING M.S TEE ON 48" DIA PRCC INFRONT OF NAYA NAZIMABAD AND REPAIRING OF HEAVY LEAKAGES ON 48" DIA PRCC (INTERNAL) FROM NAY NAZIMABAD TO DO-RASTA MANGHOPIR ROAD AND CONSTRUCTION OF CHAMBER (8'X8'X8')

| Item No | Description of Work | Estimated Cost | | | | M/s.Jawab Gul & Co. | | M/s.Techwin Engg & Const. | | |
|---------|--|----------------|------|----------|--------|---------------------|----------|---------------------------|----------|-----------|
| | | Quantity | Rate | Per | Amount | Rate | Amount | Rate | Amount | |
| 1 | Excavation for pipe line in trenches and pits in Wet Silt Clay or mud i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by Engineer Incharge providing fence guards, lights, flags sand temporary crossing for non-vehicular traffic wherever required lift upto 5 ft (1.52 m) and lead upto one chain (30.5m). 0' to 5' | 551.25 | Cft | 5400.00 | %0Cft | 2,976.75 | 5400.00 | 2,976.75 | 5500.00 | 3,031.88 |
| | 5' to 8' | 330.75 | Cft | 5950.00 | %0Cft | 1,967.96 | 5900.00 | 1,951.43 | 6000.00 | 1,984.50 |
| | 8' to 11' | 193.93 | Cft | 6500.00 | %0Cft | 1,260.55 | 6500.00 | 1,260.55 | 6600.00 | 1,279.94 |
| | 11' to 14' | 195.27 | Cft | 7050.00 | %0Cft | 1,376.65 | 7000.00 | 1,366.89 | 7000.00 | 1,366.89 |
| 2 | Full hire charges of pumping set per day i/c of wages of driver and assistant fuel or electric energy platform for placing the pump etc at lower depth with suction and delivery pipes for pumping out water found at various depth from trenches including the cost of erection and dismantling after completion of the job. Hire charges of pumping set upto 10 HP (but not less than 5 hp) pumping out water from 15 ft deep trench | 52.00 | Days | 1500.00 | P/Day | 78,000.00 | 1500.00 | 78,000.00 | 1600.00 | 83,200.00 |
| 3 | P/F M.S split collar tee for PRCC pipe of 48" dia having width as 48"x48"x4'.3" fabricated with 3/8" thick M.S plate excluding the cost of neck, it includes the cost of 3/4" M.S square bard on both ends, 4 Nos 3/4" thick M.S flnages with a total weight as mentioned, it includes the cost of nuts & bolt, rubber packing, labour and sealing materials and all the tools and plants. 48" x48" x 4'.3" Tee Net Weight = 536.970 Kg | 1.00 | No | 89271.00 | Each | 89,271.00 | 89000.00 | 89,000.00 | 95000.00 | 95,000.00 |
| 4 | Providing & Fixing 0-9" long 3/8" thick M.S Neck to new fixed M.S Tee It includes the cost of fabrication and welding complete. For Neck (24" dia Weight = 76.361 Kg) | 1.00 | No | 12261.00 | Each | 12,261.00 | 12000.00 | 12,000.00 | 15000.00 | 15,000.00 |

Handwritten signature

Handwritten mark

Handwritten mark

Handwritten signature

Name of Work: PROVIDING & FIXING M.S TEE ON 48" DIA PRCC INFRONT OF NAYA NAZIMABAD AND REPAIRING OF HEAVY LEAKAGES ON 48" DIA PRCC (INTERNAL) FROM NAY NAZIMABAD TO DO-RASTA MANGHOPIR ROAD AND CONSTRUCTION OF CHAMBER (8'X8'X8')


| Item No | Description of Work | Estimated Cost | | | | M/s.Jawab Gul & Co. | | M/s.Techwin Engg & Const. | | |
|-------------------------------|--|----------------|------|----------|--------|---------------------|----------|---------------------------|----------|-----------|
| | | Quantity | Rate | Per | Amount | Rate | Amount | Rate | Amount | |
| 5 | Providing & Fixing M.S Flange made of M.S Plate i/c the cost of making holes, facing, welding, nut bolts, rubber packing with lead fitter, cartage etc complete For Neck (24" dia Weight 24.545 Kg) | 1.00 | No | 9828.00 | Each | 9,828.00 | 9800.00 | 9,800.00 | 10000.00 | 10,000.00 |
| 6 | P/F M.S Blank Flange 3/8" thick made of M.S Plate i/c the cost of making holes, facing, fitter, cartage, etc complete (24" dia Net Weight 115.221 Kg) | 1.00 | No | 10892.00 | Each | 10,892.00 | 10800.00 | 10,800.00 | 12000.00 | 12,000.00 |
| 7 | Repair of leaking joints on PRCC Pipe line 48" dia internally. i/c the cost of labour, sealing material complete job. 48" dia PRCC (Internal Vatta) | 60 | Nos | 7706.00 | Each | 462,360 | 7700.00 | 462,000 | 8000.00 | 480,000 |
| 8 | Repairing of leaking joints (External Vatta) on PRCC Pipe 48" diameter. It includes the cost of excavation, labour, sealing materials, gunny bags, de-watering, and refilling of the excavated stuff etc. complete. 48" dia PRCC (External Vatta) | 7.00 | Nos | 35821.00 | Each | 250,747 | 35800.00 | 250,600.00 | 36000.00 | 252,000 |
| 9 | Construction of C.C. 1:3:6 solid Block Masonry chamber of size 8'x8'x8' (inside dimension) with 24"x24" C.I Cover and frame weight 50 Kg fix in 4" RCC 1:2:4 slab with steel 1/2" dia tor main bars @6" C/C bent-up 1/4" dia 8" C.C distribution bars 6" thick C.C 1:3:6 block masonry wall set 1:6 CM 6" CC 1:4:8 in foundation, 2" thick C.C 1:2:4 flooring, 1/2" thick cement plaster 1:3 ratio inside wall surface, 1 foot deep upto roof slab, M.S foot tress 5/8" dia bar at every feet of depth deep including excavation, dewatering, and cuing etc complete job. as per R/A and as desired by the Engineer Incharge. 8'x8'x8' | 1.00 | Nos | 77884.54 | Each | 77,884.54 | 77800.00 | 77,800.00 | 80000.00 | 80,000.00 |
| TOTAL QUOTED / CORRECTED COST | | | | | | 998,825 | | 997,556 | | 1,034,863 |



(Wasif Akhtar)
Accounts Officer (W/D)
Member / Secretary



(Saif-ul-Haque)
Addl. Director Internal Audit
KMC - Member



(Maqsood Ahmed Shaikh)
Superintending Engineer (K.M.C)
Member



(Owais Malik)
S.E (Water Trunk Main)
Member



(Saleem Ahmed)
Director (Design & Estimate)
Convener

Method of Procurement: Single Stage Single Envelope.

Name of Work: PROVIDING & FIXING M.S TEE ON 48" DIA PRCC INFRONT OF NAYA NAZIMABAD AND REPAIRING OF HEAVY LEAKAGES ON 48" DIA PRCC (INTERNAL) FROM NAY NAZIMABAD TO DO-RASTA MANGHOPIR ROAD AND CONSTRUCTION OF CHAMBER (8'X8'X8')

MINUTES OF BID OPENING MEETING.


A meeting of the procurement committee of this department was held on 06-06-2017 for opening the bids received in respect of subject NIT till deadlines of submission. The meeting was attended by all / following members of the procurement committee and the representative of bidders. (Attendance sheet is enclosed).

2. Two bidders submitted their bids till the deadline of submission.
 - i. M/s. Jawab Gul & Company
 - ii. M/s. Techwin Engineering & Construction
3. The bids were opened at 11:30 A.M in the presence of the above mentioned participants and the rates quoted by bidders were read aloud and encircled by Chairman of the Procurement Committee.


| S. No | Name of Firm | Quoted Price | Amount of Bid Security | Pay Order No. / Date |
|-------|----------------------------------|----------------|------------------------|--|
| 01 | M/s.Jawab Gul & Company. | Rs.9,97,556/- | Rs.20,000/- | P.O # 17909411 dt:05-06-2017 from HBL Taimuria Market Branch Karachi |
| 02 | M/s.Techwin Engg. & Construction | Rs.10,34,864/- | Rs.33,000/- | P.O # 12054547 dt:30-05-2017 from UBL Manghopir Road Branch Karachi |


4. The bids do not contain any over-writing or cutting.
5. The committee shall examine all the bids as per the qualification / eligibility criteria provided in the bidding document and verify the documents and bid security submitted by the bidders (if required).

The meeting ended with the vote of thanks to and from the chair.


(Wasif Akhtar)
Accounts Officer (W/D)
Member / Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit – KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Owais Malik)
S.E (Water Trunk Main)
Member


(Saleem Ahmed)
Director (Design & Estimate)
Convener

Method and procedure of procurement: Open Competitive Bidding (National/ International Competitive Bidding) (Single Stage-One Envelope)

Description of work: **PROVIDING & FIXING M.S TEE ON 48" DIA PRCC INFRONT OF NAYA NAZIMABAD AND REPAIRING OF HEAVY LEAKAGES ON 48" DIA PRCC (INTERNAL) FROM NAY NAZIMABAD TO DO-RASTA MANGHOPIR ROAD AND CONSTRUCTION OF CHAMBER (8'X8'X8')**

Date of Opening: 06-06-2017

BIDDERS' ELIGIBILITY/ QUALIFICATION REPORT

Eligibility/ Qualification Criteria:


| S. No. | Eligibility / Qualification Criteria | Bidders' Name | |
|--------|--|---------------------|-----------------------------------|
| | | M/s.Jawab Gul & Co. | M/s.Techwing Engg. & Construction |
| 1. | Registration with PEC (if applicable) | N/A | N/A |
| 2. | NTN | Yes | Yes |
| 3. | Sales Tax Registration (FBR) | N/A | N/A |
| 4. | Registration with Sindh Revenue Board (SRB) | Yes | Yes |
| | Qualification Criteria: | | |
| 5. | Minimum three years' experience of relevant field. | Yes | Yes |
| 6. | Turnover of at least last three years | Yes | Yes |
| 7. | Required Bid Security is attached. | Yes | Yes |
| 8. | Bid is signed, named and stamped by the authorized person of the firm along with Authorization letter. | Yes | Yes |
| 9. | Any other factor deemed to be relevant by the procuring agency subject to provision of Rule-44 | N/A | N/A |
| 10. | Qualified/ disqualified | Qualified | Qualified |



(Wasif Akhtar)
Accounts Officer (W/D)
Member / Secretary



(Saif-ul-Haque)
Additional Director Internal
Audit - KMC Member



(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member



(Owais Malik)
S.E (Water Trunk Main)
Member



(Saleem Ahmed)
06/06/17
Director (Design & Estimate
Convener

ATTENDANCE SHEET OF PARTICIPATE OF CONTRACTOR



(Under Rule-17(1) of SPPRA Rule, 2010 and amended-2013)

NAME OF WORK: PROVIDING & FIXING M.S TEE ON 48"DIA PRCC INFRONT OF NAYA NAZIMABAD AND REPAIRING OF HEAVY LEAKAGES ON 48"DIA PRCC (INTERNAL) FROM NAYA NAZIMABAD TO DO-RASTA MONGHOPIR ROAD AND CONSTRUCTION OF CHAMBER (8X'8X'8).

DATE OF OPENING & TIME: 06-06-2017 at 11:30 A.M

ESTIMATED COST: Rs. 9,99,225.00

SPPRA's SERIAL No. (33326) Dated: 12-05-2017.

| Sr. No. | NAME OF THE FIRM | NAME OF PERSON & DESIGNATION | SIGNATURE |
|---------|-------------------------------|------------------------------|---|
| 1 | M/H. Teshai Engineering & Co. | Hassni Khan (Rep) |  |
| 2 | M/S. Sawab Gul & Co. | Sawab Gul (Rep) |  |
| 3 | | | |
| 4 | | | |
| 5 | | | |
| 6 | | | |
| 7 | | | |
| 8 | | | |
| 9 | | | |
| 10 | | | |