

OFFICE OF THE EXECUTIVE ENGINEER (WATER), (JAMSHED TOWN).
KARACHI WATER AND SEWERAGE BOARD
BLOCK-B, KMC MARKET, SINDHI MUSLIM SOCIETY

NO.EE/J.T/WATER/2018/4412

DATED : 23/05/2018

To,

The Director Capacity Building,
Sindh Public Procurement Regulatory Authority (SPPRA),
Government of Sindh,
Block-8, Sindh Secretariat # 4-A,
Court Road,
Karachi.

SUBJECT :- REPLACEMENT OF 8"DIA, 6"DIA & 4"DIA A.C. PIPE LINE BY 200MM, 160MM AND 110MM P.E. PIPE LINE IN UC NO.2,6 & 5 MANZOOR COLONY HILL TOWN & MEHMOODABAD I/C REPAIRING OF 10"DIA, 8"DIA, 6"DIA & 4"DIA WATER LEAKAGES FOR IMPROVEMENT WATER SUPPLY IN JAMSHED TOWN.

REF'NCE :- SPPRA I.D.No.37391.

With reference of above mentioned subject work, enclosed please find herewith the Bid Evaluation Report, Comparative Statement and other relevant documents in terms of Rule-41(6), (9) and 46(1) of SPP Rules 2010 in original, duly signed by procurement committee of KW&SB are being submitted.

It is therefore, requested to please hoist the above said documents on authority's web site, which NIT has already been hoisted vide Serial No.37391.


EXECUTIVE ENGINEER (WATER)
JAMSHED TOWN, KW&SB.

Enclosed Original:

1. Bid Evaluation Report and Comparative Statement.
2. Attendance sheet, minutes of the meeting and bidders qualification report in terms of Rule-41(6), (9) and 46(1) of SPP Rules 2010.

Copy to :

1. S.E. District East-A, KW&SB.

SPPRA TOWNWARD DIAR
NO : 9268
DATED : 23-05-2018



KARACHI WATER & SEWERAGE BOARD

OFFICE OF THE DIRECTOR (DESIGN & ESTIMATE)

BID EVALUATION REPORT


1	Name of Procuring Agency:	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No:	SPPRA Serial No.37391 I.D No. _____
3	Tender Description/Name of Work/Item:	REPLACEMENT OF 8" DIA, 6" DIA & 4" DIA A.C PIPE LINE BY 200MM, 160MM AND 110MM P.E PIPE LINE IN UC NO.2,6 & 5 MANZOOR COLONY HILL TOWN & MEHMOODABAD I/C REPAIRING OF 10" DIA, 8" DIA, 6" DIA & 4" DIA WATER LEAKAGES FOR IMPROVEMENT WATER SUPPLY IN JAMSHED TOWN
4	Method of Procurement:	<u>Single Stage (One Envelop)</u>
5	Tender Published:	<u>Through SPPRA Web Site</u>
6	Total Bid Documents Sold:	<u>2 Nos</u>
7	Total Bid Received:	<u>2 Nos</u>
8	Technical Bid Opening Date (if applicable):	<u>N/A</u>
9	No. of Bid Technically Qualified (if applicable)	<u>N/A</u>
10	Bid (s) Rejected:	<u>No</u>
11	Financial Bid Opening Date:	10-04-2018

12 BID EVALUATION REPORT


S#	Name of Firm / Bidder	COST OFFERED BY THE BIDDER	RANKING IN TERMS OF COST	COMPARISON WITH ESTIMATED COST	REASON FOR ACCEPTANCE / REJECTION	REMARKS
01	M/s.Nawab & Co.	Rs.9,49,365/-	1 st Lowest	@0.007% Below	Pay Order and required documents are attached. P.O # 17318367 dt:06-04-2018 Rs.20,000/-from HBL Paposh Nagar Branch Karachi	Substantially Responsive
02	M/s.Gul Sawab & Co.	Rs.9,59,636/-	2 nd Lowest	@1.074% Above	Pay Order and required documents are attached. P.O # 17318365 dt:06-04-2018 Rs.20,000/-from HBL Paposh Nagar Branch Karachi	Substantially Responsive

The all concerned bidders are being informed accordingly.


The E.E Concerned for compliance of Rule-45 of SPPRA 2010 **M/s.Nawab & Co.** declared as the lowest responsive bidder by the Committee and recommended for sanction from Competent Authority.


(Muhammad Nawaz Khan)
D.A.O (District East)
Member / Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit – KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Roshin Din Memon)
S.E (District East-A)
Member


(Munir Ahmed Bhatti)
Director (Design & Estimate)
Convener

COMPARATIVE STATEMENT

**Name of Work: REPLACEMENT OF 8" DIA, 6" DIA & 4" DIA A.C PIPE LINE BY 200MM, 160MM AND 110MM P.E PIPE LINE
IN UC NO.2.6 & 5 MANZOOR COLONY HILL TOWN & MEHMOODABAD I/C REPAIRING OF 10" DIA,
8" DIA, 6" DIA & 4" DIA WATER LEAKAGES FOR IMPROVEMENT WATER SUPPLY IN JAMSHED TOWN**

Item No	Description of Work	Estimated Cost				M/s.Nawab & Co.		M/s.Gul Sawab & Co.		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
1	Dismantling and removing road metalling	2980.00	Cft	605.00	%Cft	18,029.00	600.00	17,880.00	600.00	17,880.00
2	Excavation for pipe line in trenches and pits in all kind of soil of murum i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by Engineer Incharge providing fence guards, lights, flags sand temporary crossing for non-vehicular traffic wherever required lift upto 5 ft (1.52 m) and lead upto one chain (30.5m).	4470.00	Cft	4650.00	%0Cft	20,785.50	4500.00	20,115.00	5000.00	22,350.00
3	Excavation for pipe line in trenches and pits in Wet Soils clay or mud i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by Engineer Incharge. Providing fence, lights, flags and temporary crossing for non-vehicular traffic wherever required lift upto 5'-0" ft (1.52m) and lead upto one chain (30.5m).	7351.71	Cft	5400.00	%0Cft	39,699.23	5700.00	41,904.75	6000.00	44,110.26
4	Providing Laying & Fixing of Polyethylene pipe in trench i/c fitting jointing and testing etc. complete in all respect the high density Polyethylene P.E pipes (HDPE-100) for W/S conforming ISO 4427/DIN-8074/8075 B.S 3580 & PSI 3051 (PN-10). 200mm	80.00	Rft	833.00	P/Rft	66,640.00	840.00	67,200.00	830.00	66,400.00
	160 mm	100.00	Rft	530.00	P/Rft	53,000.00	530.00	53,000.00	520.00	52,000.00
	110 mm	315.00	Rft	268.00	P/Rft	84,420.00	270.00	85,050.00	270.00	85,050.00
5	Full hire charges of pumping set per day i/c of wages of driver and assistant fuel or electric energy platform for placing the pump etc at lower depth with suction and delivery pipes for pumping out water found at various depth from trenches including the cost of erection and dismantling after completion of the job. Hire charges of pumping set upto 10 HP pumping out water from 10 ft deep trench	22.00	Days	1500.00	P/Day	33,000.00	1000.00	22,000.00	1500.00	33,000.00

Handwritten signatures and initials on the left margin.


Handwritten signature at the bottom left.


**Name of Work: REPLACEMENT OF 8" DIA, 6" DIA & 4" DIA A.C PIPE LINE BY 200MM, 160MM AND 110MM P.E PIPE LINE
IN UC NO.2,6 & 5 MANZOOR COLONY HILL TOWN & MEHMOODABAD I/C REPAIRING OF 10" DIA,
8" DIA, 6" DIA & 4" DIA WATER LEAKAGES FOR IMPROVEMENT WATER SUPPLY IN JAMSHED TOWN**


Item No	Description of Work	Estimated Cost				M/s. Nawab & Co.		M/s. Gul Sawab & Co.		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
6	Providing & Fixing Split Collar 9" wide on A.C Pipe fabricated with 1/4" thick M.S plate weighting as mentioned against each item it included the cost of 4 Nos 1/4" thick flanged nut & bolt rubber packing labour and sealing material etc complete. 10" dia	15.00	Nos	2800.00	Each	42,000.00	3000.00	45,000.00	2500.00	37,500.00
		10.00	Nos	2510.00	Each	25,100.00	2500.00	25,000.00	3000.00	30,000.00
		06" Dia	Nos	2129.00	Each	42,580.00	2000.00	40,000.00	1800.00	36,000.00
		04" Dia	Nos	1835.00	Each	36,700.00	2000.00	40,000.00	1500.00	30,000.00
7	Repair of spindle by manufacturing S.Steel spindle gun metal i/c nut & bolts rubber packing etc. 12" Dia	3.00	Nos	7843.00	Each	23,529.00	7000.00	21,000.00	6500.00	19,500.00
		10" Dia	Nos	7843.00	Each	23,529.00	7000.00	21,000.00	6500.00	19,500.00
		18" Dia	No	23820.00	Each	23,820.00	23000.00	23,000.00	25000.00	25,000.00
		04" Dia	Nos	2254.00	Each	4,508.00	2000.00	4,000.00	3000.00	6,000.00
8	Refilling the excavated stuff in trench 6" thick layer i/c watering ramming to full compaction etc.	11738.41	Cft	2760.00	%0Cft	32,398.01	3000.00	35,215.23	2500.00	29,346.03
9	Repair of leaking joints (External vatta) on PRCC pipe i/c excavation, labour, sealing material, gunny bags, de-watering andrefillingthe excavated stuff etc complete. 18" dia	10.00	No	13841.00	Each	138,410.00	14000.00	140,000.00	15000.00	150,000.00
		15" Dia	No	10729.00	Each	85,832.00	11000.00	88,000.00	12000.00	96,000.00
		12" Dia	No	9716.00	Each	155,456.00	10000.00	160,000.00	10000.00	160,000.00
	TOTAL QUOTED / CORRECTED COST					949,436		949,365		959,636


(Muhammad Nawaz Khan)
D.A.O (Distt. East)
Member / Secretary


(Saif-ul-Haque)
Addl. Director Internal
Audit KMC - Member


(Magsood Ahmed Shaikh)
Superintending Engineer (K.M.C)
Member


(Roshin Din Memon)
S.E (District East-A)
Member


(Munir Ahmed Bhatti)
Director (Design & Estimate)
Convener

NIT No. SPPRA Serial No.37391

Method and procedure of procurement: Open Competitive Bidding (National/ International Competitive Bidding) (Single Stage-One Envelope)


Description of work: **REPLACEMENT OF 8" DIA, 6" DIA & 4" DIA A.C PIPE LINE BY 200MM, 160MM AND 110MM P.E PIPE LINE IN UC NO.2,6 & 5 MANZOOR COLONY HILL TOWN & MEHMOODABAD I/C REPAIRING OF 10" DIA, 8" DIA, 6" DIA & 4" DIA WATER LEAKAGES FOR IMPROVEMENT WATER SUPPLY IN JAMSHED TOWN**

Date of Opening: 10-04-2018


BIDDERS' ELIGIBILITY/ QUALIFICATION REPORT


Eligibility/ Qualification Criteria:


S. No.	Eligibility / Qualification Criteria	Bidders' Name	
		M/s.Nawab & Co.	M/s.Gul Sawab & Co.
1.	Registration with PEC (if applicable)	N/A	N/A
2.	NTN	Yes	Yes
3.	Sales Tax Registration (FBR)	N/A	N/A
4.	Registration with Sindh Revenue Board (SRB)	Yes	Yes
	Qualification Criteria:		
5.	Minimum three years' experience of relevant field.	Yes	Yes
6.	Turnover of at least last three years	Yes	Yes
7.	Required Bid Security is attached.	Yes	No
8.	Bid is signed, named and stamped by the authorized person of the firm along with Authorization letter.	Yes	Yes
9.	Any other factor deemed to be relevant by the procuring agency subject to provision of Rule-44	N/A	N/A
10.	Qualified/ disqualified	Qualified	Disqualified


(Muhammad Nawaz Khan)
D.A.O (District East)
Member / Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit – KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Roshin Din Memon)
S.E (District East-A)
Member


(Munir Ahmed Bhatti)
Director (Design & Estimate)
Convener

NIT No. SPPRA Serial No.37391

Method of Procurement: Single Stage Single Envelope.

Name of Work: REPLACEMENT OF 8" DIA, 6" DIA & 4" DIA A.C PIPE LINE BY 200MM, 160MM AND 110MM P.E PIPE LINE IN UC NO.2,6 & 5 MANZOOR COLONY HILL TOWN & MEHMOODABAD I/C REPAIRING OF 10" DIA, 8" DIA, 6" DIA & 4" DIA WATER LEAKAGES FOR IMPROVEMENT WATER SUPPLY IN JAMSHED TOWN

MINUTES OF BID OPENING MEETING.


A meeting of the procurement committee of this department was held on 10-04-2018 for opening the bids received in respect of subject NIT till deadlines of submission. The meeting was attended by all / following members of the procurement committee and the representative of bidders. **(Attendance sheet is enclosed).**

2. Two bidders submitted their bids till the deadline of submission.
 - i. M/s. Nawab & Co.
 - ii. M/s. Gul Sawab & Co.
3. The bids were opened at 2:30 P.M in the presence of the above mentioned participants and the rates quoted by bidders were read aloud and encircled by Chairman of the Procurement Committee.


S. No	Name of Firm	Quoted Price	Amount of Bid Security	Pay Order No. / Date
01	M/s.Nawab & Co.	Rs.9,49,365/-	Rs.20,000/-	P.O # 17318367 dt:06-04-2018 from HBL Paposh Nagar Branch Karachi
02	M/s.Gul Sawab & Co.	Rs.9,59,636/-	Rs.20,000/-	P.O # 17318365 dt:06-04-2018 from HBL Paposh Nagar Branch Karachi


4. The bids do not contain any cutting or over-writing.
5. The committee shall examine all the bids as per the qualification / eligibility criteria provided in the bidding document and verify the documents and bid security submitted by the bidders (if required).


The meeting ended with the vote of thanks to and from the chair.


(Muhammad Nawaz Khan)
D.A.O (District East)
Member / Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit – KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Roshin Din Memon)
S.E (District East-A)
Member


(Munir Ahmed Bhatti)
Director (Design & Estimate)
Convener

