

OFFICE OF THE EXECUTIVE ENGINEER (SEW)-II, (JAMSHED TOWN).
KARACHI WATER AND SEWERAGE BOARD
BLOCK-B, KMC MARKET, SINDHI MUSLIM SOCIETY

NO.EE/J.T/SEW-II/2018/274

DATED :01-06-2018

To,

The Director Capacity Building,
Sindh Public Procurement Regulatory Authority (SPPRA),
Government of Sindh,
Block-8, Sindh Secretariat # 4-A,
Court Road,
Karachi.

SUBJECT :- REPLACEMENT OF 12"DIA & 8"DIA SUNK DOWN/DAMAGED SEWERS NEAR WATER GROUND UC-09 AT KACHA DHOBI GHAT, JAMSHED TOWN (SEWERAGE)-II.

REF'NCE :- PPMS Serial No.T00708-17-0002.

With reference of above mentioned subject work, enclosed please find herewith the Bid Evaluation Report, Comparative Statement and other relevant documents in terms of Rule-41(6), (9) and 46(1) of SPP Rules 2010 in original, duly signed by procurement committee of KW&SB are being submitted.

It is therefore, requested to please hoist the above said documents on authority's web site, which NIT has already been hoisted vide Serial No.**T00708-17-0002.**


**EXECUTIVE ENGINEER (SEW)-II
JAMSHED TOWN, KW&SB.**

Enclosed Original:

1. Bid Evaluation Report and Comparative Statement.
2. Attendance sheet, minutes of the meeting and bidders qualification report in terms of Rule-41(6), (9) and 46(1) of SPP Rules 2010.

Copy to :

1. S.E. District East-A, KW&SB.
2. Office Copy.

SPPRA INWARD DIARY
NO : 9566
DATED : 01-06-2018



KARACHI WATER & SEWERAGE BOARD

OFFICE OF THE CHIEF ENGINEER (IPD)

BID EVALUATION REPORT


1	Name of Procuring Agency:	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No:	PPMS Serial No. T00708-17-0002
3	Tender Description/Name of Work/Item:	EMERGENT REPLACEMENT OF 12" DIA & 8" DIA RUBBER RING SEWERS AT SABZI WALI GALI & NOOR MASJID UC-9 LINES AREA IN JAMSHED TOWN (SEWERAGE)-II
4	Method of Procurement:	Single Stage (One Envelop)
5	Tender Published:	Through SPPRA Web Site
6	Total Bid Documents Sold:	2 Nos
7	Total Bid Received:	2 Nos
8	Technical Bid Opening Date (if applicable):	N/A
9	No. of Bid Technically Qualified (if applicable)	N/A
10	Bid (s) Rejected:	No
11	Financial Bid Opening Date:	03-05-2018

12 BID EVALUATION REPORT


S #	Name of Firm / Bidder	COST OFFERED BY THE BIDDER	RANKING IN TERMS OF COST	COMPARISON WITH ESTIMATED COST	REASON FOR ACCEPTANCE / REJECTION	REMARKS
01	M/s.Tooba Enterprises	Rs.4,98,467/-	1 st Lowest	@0.028% Below	Pay Order and required documents are attached. P.O # 19906852 dt:02-05-2018 Rs.10,000/-from HBL Iqbal Library Branch Karachi	Substantially Responsive
02	M/s.Shah Faisal & Brothers	Rs.4,98,835/-	2 nd Lowest	@0.046% Above	Pay Order and required documents are attached. P.O # 19906853 dt:02-05-2018 Rs.10,000/-from HBL Iqbal Library Branch Karachi	Substantially Responsive


The all concerned bidders are being informed accordingly.


The E.E Concerned for compliance of Rule-45 of SPPRA 2010 **M/s.Tooba Enterprises** declared as the lowest responsive bidder by the Committee and recommended for sanction from Competent Authority.


(Muhammad Nawaz Khan)
D.A.O (District East)
Member / Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit – KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Roshin Din Memon)
S.E (District East-A)
Member


(Saleem Ahmed)
Chief Engineer (IPD)
Convener

COMPARATIVE STATEMENT

Name of Work: EMERGENT REPLACEMENT OF 12" DIA & 8" DIA RUBBER RING SEWERS
AT SABZI WALI GALI & NOOR MASJID UC-9 LINES AREA IN JAMSHED TOWN (SEWERAGE)-II

Item No	Description of Work	Estimated Cost				M/s: Tooba Enterprises		M/s: Shah Faisal & Brothers		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
1	Dismantling and removing road metalling	2075.00	Cft	605.00	%Cft	12,553.75	605.00	12,553.75	605.00	12,553.75
2	Excavation for pipe line in trenches and pits in all kind of soil of murum i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by Engineer Incharge providing fence guards, lights, flags sand temporary crossing for non-vehicular traffic wherever required lift upto 5 ft (1.52 m) and lead upto one chain (30.5m). i) Lift 00' - 05ft	8072.50	Cft	4650.00	%Cft	37,537.13	4650.00	37,537.13	4650.00	37,537.13
3	Providing Manhole 4' feet inside without manhole cover with C.I Frame 15 Kg 5 feet clear depth 1:2:4 cast in situ with in 9" thick wall, 1:4:8: C.C in 6ft dia and 6" inch thick in foundation 1:2:4 C.C in benching 1/2" thick cement plaster with 1:3 cement mortar on all inside wall surfaces of channel and benching i/c making required nos of main and branch channels, 3/4" dia M.S Foot rest @12" c/c i/c cost of excavation in all kinds of soil, backfilling and disposal of excavated stuff etc complete as per design and instruction of Engineer Incharge. Reduced rate without C.I frame 15 KG.	7.00	Nos	13479.29	Each	94,355.03	13479.00	94,353.00	13480.00	94,360.00
4	Full hire charges of pumping set per day i/c of wages of driver and assistant fuel or electric energy platform for placing the pump etc at lower depth with suction and delivery pipes for pumping out water found at various depth from trenches including the cost of erection and dismantling after completion of the job. Hire charges of pumping set upto 10 HP pumping out water from 10 ft deep trench	14.00	Days	1500.00	P/Day	21,000.00	1495.00	20,930.00	1500.00	21,000.00
5	Providing & Laying of RCC Pipes with Rubber Ring Joint and fitting in trench including cutting, fittings, jointing with rubber ring i/c testing with water to specified pressure. i. 12" Dia	540.00	Rft	367.00	P/Rft	198,180.00	367.00	198,180.00	367.00	198,180.00
	ii. 08" Dia	182.00	Rft	206.00	P/Rft	37,492.00	206.00	37,492.00	207.00	37,674.00
6	Manufacturing and supplying of RCC Manhole covers cast in situ 1:2:4 concrete ratio 3" deep at centre, reinforced with 1/2" dia tor steel bars @ 4" C/C welded to a 3/16" thick 2" wide M.S plate two hook of 3/8" dia tor bar including compacting i/c cutting and transportation with in 10 miles. 21" dia.	7.00	Nos	913.63	Each	6,395.41	913.00	6,391.00	914.00	6,398.00

M/S Tooba Enterprises
M/S Shah Faisal & Brothers

**Name of Work: EMERGENT REPLACEMENT OF 12" DIA & 8" DIA RUBBER RING SEWERS
AT SABZI WALI GALI & NOOR MASJID UC-9 LINES AREA IN JAMSHED TOWN (SEWERAGE)-II**

Item No	Description of Work	Estimated Cost			M/s. Tooba Enterprises		M/s. Shah Faisal & Brothers			
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
7	Making connection with the existing manhole including the cost of cutting hole in wall, making them good in C.C 1:2:4 and making the required channel etc. complete	10.00	Nos	180.00	Each	1,800.00	180.00	1,800.00	182.00	1,820.00
8	Manufacturing and supplying of RCC Ring Slab of 21" dia (inside) and 36" dia outside 7 1/2" width and 6" thick i/c 3/8" dia tor steel bars two concentric rings with 3/8" dia 8 Nos cross linked bars welded and two sunk type hooks, casted in 1:1 1/2:3 concrete with embedded 15 Kg C.I. Frame in perfect position i/c transportation charges for an average lead of 20 Km per trip from casting yard to town office. (A minimum of 25 slabs per trip will be transported.	7.00	Nos	1906.60	Each	13,346.20	1905.00	13,335.00	1906.00	13,342.00
9	Shifting to the site and fixing 36" dia ring slab in perfect position on damaged manhole i/c cutting of the position of damaged manhole in proper shape laying in layer of C.M in 2" thickness and disposal of the debris.	7.00	Nos	563.09	Each	3,941.63	563.00	3,941.00	564.00	3,948.00
10	Sand Haro or any other source sand of same modules of the fineness (Hill Sand)	1620.00	Cft	2425.00	%Cft	39,285.00	2424.00	39,268.80	2425.00	39,285.00
11	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete.	5690.46	Cft	2760.00	%Cft	15,705.67	2755.00	15,677.22	2760.00	15,705.67
12	Carriage of 100 Cft / 5 Tons of all materials like stone aggregate, spawl, coal, lime, surkhi etc B.G Rail fastening points and crossing bridges, Girders, pipes sheet Rail, M.S Bars etc. or 1000 Nos bricks, 10"x 5"x3" or 1000 Nos: tiles, 12" x6"x2" or 150 Cft of timber or 100 Maunds of fuel wood by trucks or any other means owned by the Contractors. Carriage for 05 Miles	2382.04	Cft	714.29	%Cft	17,014.67	714.00	17,007.77	715.00	17,031.59
TOTAL QUOTED / CORRECTED COST						498,606		498,467		498,835

(Muhammad Nawaz Khan)
D.A.O (Dist. East)
Member / Secretary

(Saif-ul-Haque)
Addl. Director Internal Audit
KMC - Member

(Magsood Ahmed Shaikh)
Superintending Engineer (K.M.C)
Member

(Roshin Din Memon)
S.E (District East-A)
Member

(Saleem Ahmed)
Chief Engineer (IPD)
Convener

NIT No. PPMS Serial No. T00708-17-0002

Method and procedure of procurement: Open Competitive Bidding (National/ International Competitive Bidding) (Single Stage–One Envelope)


Description of work: EMERGENT REPLACEMENT OF 12" DIA & 8" DIA RUBBER RING SEWERS AT SABZI WALI GALI & NOOR MASJID UC-9 LINES AREA IN JAMSHED TOWN (SEWERAGE)-II

Date of Opening: 03-05-2018


BIDDERS' ELIGIBILITY/ QUALIFICATION REPORT


Eligibility/ Qualification Criteria:


S. No.	Eligibility / Qualification Criteria	Bidders' Name	
		M/s.Tooba Enterprises	M/s.Shah Faisal & Brothers
1.	Registration with PEC (if applicable)	N/A	N/A
2.	NTN	Yes	Yes
3.	Sales Tax Registration (FBR)	N/A	N/A
4.	Registration with Sindh Revenue Board (SRB)	Yes	Yes
	Qualification Criteria:		
5.	Minimum three years' experience of relevant field.	Yes	Yes
6.	Turnover of at least last three years	Yes	Yes
7.	Required Bid Security is attached.	Yes	No
8.	Bid is signed, named and stamped by the authorized person of the firm along with Authorization letter.	Yes	Yes
9.	Any other factor deemed to be relevant by the procuring agency subject to provision of Rule-44	N/A	N/A
10.	Qualified/ disqualified	Qualified	Disqualified


(Muhammad Nawaz Khan)
D.A.O (District East)
Member / Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit – KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Roshin Din Memon)
S.E (District East-A)
Member


(Saleem Ahmed)
Chief Engineer (IPD)
Convener

NIT No. PPMS, Serial No. T00708-17-0002

Method of Procurement: Single Stage Single Envelope.

Name of Work: EMERGENT REPLACEMENT OF 12" DIA & 8" DIA RUBBER RING SEWERS AT SABZI WALI GALI & NOOR MASJID UC-9 LINES AREA IN JAMSHED TOWN (SEWERAGE)-II

MINUTES OF BID OPENING MEETING.

A meeting of the procurement committee of this department was held on 03-05-2018 for opening the bids received in respect of subject NIT till deadlines of submission. The meeting was attended by all / following members of the procurement committee and the representative of bidders. **(Attendance sheet is enclosed).**

2. Two bidders submitted their bids till the deadline of submission.

- i. M/s. Tooba Enterprises
- ii. M/s. Shah Faisal & Brothers


3. The bids were opened at 2:30 P.M in the presence of the above mentioned participants and the rates quoted by bidders were read aloud and encircled by Chairman of the Procurement Committee.

S. No	Name of Firm	Quoted Price	Amount of Bid Security	Pay Order No. / Date
01	M/s.Tooba Enterprises	Rs.4,98,468/-	Rs.10,000/-	P.O # 19906852 dt:02-05-2018 from HBL Iqbal Library Branch Karachi
02	M/s.Shah Faisal & Brothers	Rs.4,98,839/-	Rs.10,000/-	P.O # 19906853 dt:02-05-2018 from HBL Iqbal Library Branch Karachi


4. The bids do not contain any cutting or over-writing.


5. The committee shall examine all the bids as per the qualification / eligibility criteria provided in the bidding document and verify the documents and bid security submitted by the bidders (if required).


The meeting ended with the vote of thanks to and from the chair.


(Muhammad Nawaz Khan)
D.A.O (District East)
Member / Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit – KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Roshin Din Memon)
S.E (District East-A)
Member


(Saleem Ahmed)
03/05/18
Chief Engineer (IPD)
Convener

