



KARACHI WATER & SEWERAGE BOARD

OFFICE OF THE EXECUTIVE ENGINEER (WATER)

NORTH NAZIMABAD

No. KW&SB/EE/N.N.T/W/2018/ 45

Dated:- 04/06/2018

The Director,
Capacity Building
S.P.P.R.A
Karachi.

SUBJECT: **SUBMISSION OF RULE-45 FOR THE WORK OF.**

REPAIR OF CRITICAL WATER LEAKAGE OF 15" DIA AND 12" DIA PRCC PIPE AT SHARAH -E-NOOR JAHAN AND AT PAHAR GANJ AND REPLACEMENT OF DAMAGED PIPE BY 110, 190MM DIA P.E. PIPE AT PAHAR GANJ OF NORTH NAZIMABAD FOR THE IMPROVEMENT OF WATER SUPPLY AND RECTIFICATION OF CONTAMINATION.

REF: **SPPRA Website I.D No. T00737-17-0001.**

With reference to cited above, the Bid Evaluation report on standard format, Minutes of Bid Opening Meeting, Comparative Statement, Attendance Sheet & Bid Qualification Report for the work noted above is enclosed herewith for up hosting on SPPRA website.

EXECUTIVE ENGINEER (WATER)
NORTH NAZIMABAD TOWN, KW&SB

Copy to:-

1- All concerned

SPPRA INWARD DIARY
NO : 9568
DATED : 04-06-2018

Method and procedure of procurement: Open Competitive Bidding (National/ International Competitive Bidding) (Single Stage–One Envelope)


Description of work: REPAIR OF CRITICAL WATER LEAKAGE OF 15" DIA AND 12" DIA PRCC PIPE AT SHARAH-E-NOOR JAHAN AND AT PAHAR GANJ AND REPLACEMENT OF DAMAGED PIPE BY 110, 190MM DIA P.E PIPE AT PAHAR GANJ OF NORTH NAZIMABAD FOR THE IMPROVEMENT OF WATER SUPPLY AND RECTIFICATION OF CONTAMINATION

Date of Opening: 08-05-2018


BIDDERS' ELIGIBILITY/ QUALIFICATION REPORT

Eligibility/ Qualification Criteria:


| S. No. | Eligibility / Qualification Criteria | Bidders' Name | |
|--------|--|-------------------------|-------------------|
| | | M/s.M.Shafiq & Brothers | M/s.Jawaid & Sons |
| 1. | Registration with PEC (if applicable) | N/A | N/A |
| 2. | NTN | Yes | Yes |
| 3. | Sales Tax Registration (FBR) | N/A | N/A |
| 4. | Registration with Sindh Revenue Board (SRB) | Yes | Yes |
| | Qualification Criteria: | | |
| 5. | Minimum three years' experience of relevant field. | Yes | Yes |
| 6. | Turnover of at least last three years | Yes | Yes |
| 7. | Required Bid Security is attached. | Yes | Yes |
| 8. | Bid is signed, named and stamped by the authorized person of the firm along with Authorization letter. | Yes | Yes |
| 9. | Any other factor deemed to be relevant by the procuring agency subject to provision of Rule-44 | N/A | N/A |
| 10. | Qualified/ disqualified | Qualified | Qualified |


Arshad Ali
D.A.O (District Central)
Member / Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit – KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Muhammad Ali Shaikh)
S.E (District Central-A)
Member


08/05/18
(Saleem Ahmed)
Chief Engineer (IPD)
Convener

Method of Procurement: Single Stage Single Envelope.

Name of Work: REPAIR OF CRITICAL WATER LEAKAGE OF 15" DIA AND 12" DIA PRCC PIPE AT SHARAH-E-NOOR JAHAN AND AT PAHAR GANJ AND REPLACEMENT OF DAMAGED PIPE BY 110, 190MM DIA P.E PIPE AT PAHAR GANJ OF NORTH NAZIMABAD FOR THE IMPROVEMENT OF WATER SUPPLY AND RECTIFICATION OF CONTAMINATION

MINUTES OF BID OPENING MEETING.

A meeting of the procurement committee of this department was held on 08-05-2018 for opening the bids received in respect of subject NIT till deadlines of submission. The meeting was attended by all / following members of the procurement committee and the representative of bidders. (Attendance sheet is enclosed).

2. Two bidders submitted their bids till the deadline of submission.
 - i. M/s. M.Shafiq & Brothers
 - ii. M/s. Jawaid & Sons
3. The bids were opened at 2:30 p.m in the presence of the above mentioned participants and the rates quoted by bidders were read aloud and encircled by Chairman of the Procurement Committee.


| S. No | Name of Firm | Quoted Price | Amount of Bid Security | Pay Order No. / Date |
|-------|-------------------------|---------------|------------------------|---|
| 01 | M/s.M.Shafiq & Brothers | Rs.9,99,002/- | Rs.20,000/- | P.O # 04340601 dt:07-05-2018 from Meezan Bank Joffa Tower Branch Karachi |
| 02 | M/s.Jawaid & Sons | Rs.9,99,352/- | Rs.20,000/- | P.O # 16681134 dt:07-05-2018 from HBL IBB Delhi Mercantile Society Branch Karachi |

4. The bids do not contain any cutting or over-writing.
5. The committee shall examine all the bids as per the qualification / eligibility criteria provided in the bidding document and verify the documents and bid security submitted by the bidders (if required).


The meeting ended with the vote of thanks to and from the chair.


Arshad Ali
D.A.O (District Central)
Member / Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit – KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Muhammad Ali Shaikh)
S.E (District Central-A)
Member


08/05/18
(Saleem Ahmed)
Chief Engineer (IPD)
Convener



KARACHI WATER & SEWERAGE BOARD

OFFICE OF THE CHIEF ENGINEER (IPD)

BID EVALUATION REPORT


| | | |
|----|--|--|
| 1 | Name of Procuring Agency: | KARACHI WATER & SEWERAGE BOARD |
| 2 | Tender Reference No: | SPPRA NIT ID No. T00737-17-0001 |
| 3 | Tender Description/Name of Work/Item: | REPAIR OF CRITICAL WATER LEAKAGE OF 15" DIA AND 12" DIA PRCC PIPE AT SHARAH-E-NOOR JAHAN AND AT PAHAR GANJ AND REPLACEMENT OF DAMAGED PIPE BY 110, 190MM DIA P.E PIPE AT PAHAR GANJ OF NORTH NAZIMABAD FOR THE IMPROVEMENT OF WATER SUPPLY AND RECTIFICATION OF CONTAMINATION |
| 4 | Method of Procurement: | <u>Single Stage (One Envelop)</u> |
| 5 | Tender Published: | <u>Through SPPRA Web Site</u> |
| 6 | Total Bid Documents Sold: | <u>2 Nos</u> |
| 7 | Total Bid Received: | <u>2 Nos</u> |
| 8 | Technical Bid Opening Date (if applicable): | <u>N/A</u> |
| 9 | No. of Bid Technically Qualified (if applicable) | <u>N/A</u> |
| 10 | Bid (s) Rejected: | <u>NIL</u> |
| 11 | Financial Bid Opening Date: | 08-05-2018 |


12 BID EVALUATION REPORT

| S# | Name of Firm / Bidder | COST OFFERED BY THE BIDDER | RANKING IN TERMS OF COST | COMPARISON WITH ESTIMATED COST | REASON FOR ACCEPTANCE / REJECTION | REMARKS |
|----|-------------------------|----------------------------|---------------------------|--------------------------------|---|--------------------------|
| 1 | M/s.M.Shafiq & Brothers | Rs.9,99,002/- | 1 st Lowest | @0.015% Below | Pay Order and required documents are attached. P.O # 04340601 dt:07-05-2018 Rs.20,000/-from Meezan Bank Joffa Tower Branch Karachi | Substantially Responsive |
| 2 | M/s.Jawaid & Sons | Rs.9,99,352/- | 2 nd Lowest | @0.020% Above | Pay Order and required documents are attached. P.O # 16681134 dt:07-05-2018 Rs.20,000/-from HBL IBB Delhi Mercantile Society Branch Karachi | Substantially Responsive |


The all concerned bidders are being informed accordingly.


The E.E Concerned for compliance of Rule-45 of SPPRA 2010 **M/s.M.Shafiq & Brothers** declared as the lowest responsive bidder by the Committee and recommended for sanction from Competent Authority.


Arshad Ali
D.A.O (District Central)
Member / Secretary


(Muhammad Ali Shaikh)
S.E (District Central-A)
Member


(Saif-ul-Haque)
Additional Director Internal
Audit -- KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Saleem Ahmed)
Chief Engineer (IPD)
Convener

COMPARATIVE STATEMENT

Name of Work: REPAIR OF CRITICAL WATER LEAKAGE OF 15" DIA AND 12" DIA PRCC PIPE AT SHARAH-E-NOOR JAHAN AND AT PAHAR GANJ AND REPLACEMENT OF DAMAGED PIPE BY 110, 190MM DIA P.E PIPE AT PAHAR GANJ OF NORTH NAZIMABAD FOR THE IMPROVEMENT OF WATER SUPPLY AND RECTIFICATION OF CONTAMINATION

| Item No | Description of Work | Estimated Cost | | | | M/s.M.Shafiq & Brothers | | M/s.Jawaid & Sons | |
|---------|---|----------------|----------|-------|------------|-------------------------|------------|-------------------|------------|
| | | Quantity | Rate | Per | Amount | Rate | Amount | Rate | Amount |
| 1 | Repair of leakages on PRCC Pipe line. It includes the cost of excavation, labour, sealing material, gunny bags, de-watering and refilling of the excavation stuff etc. complete. 15" Dia | 20.00 Nos | 10729.00 | Each | 214,580.00 | 10729.00 | 214,580.00 | 10729.00 | 214,580.00 |
| | 12" Dia | 24.00 Nos | 9716.00 | Each | 233,184.00 | 9716.00 | 233,184.00 | 9716.00 | 233,184.00 |
| 2 | Dismantling and removing road metalling | 3500.00 Cft | 605.00 | %0Cft | 21,175.00 | 605.00 | 21,175.00 | 605.00 | 21,175.00 |
| 3 | Excavation for pipe line in trenches and pits in all kind of soils of murum i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by Engineer Incharge providing fence guards, lights, flags sand temporary crossing for non-vehicular traffic wherever required lift upto 5 ft (1.52 m) and lead upto one chain (30.5m). | 7000.00 Cft | 4650.00 | %0Cft | 32,550.00 | 4650.00 | 32,550.00 | 4650.00 | 32,550.00 |
| 4 | Excavation for pipe line in trenches and pits in Wet Soil clay or mud i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by Engineer Incharge. Providing fence, lights, flags and temporary crossing for non-vehicular traffic wherever required lift upto 5'-0" ft (1.52m) and lead upto one chain (30.5m). | 10500.00 Cft | 5400.00 | %0Cft | 56,700.00 | 5400.00 | 56,700.00 | 5400.00 | 56,700.00 |
| 5 | Providing Laying & Fixing in trenches i/c fitting jointing and testing etc. complete in all respect the high density Polyethylene P.E pipes (HDPE-100) for W/S conforming ISO 4427 DIN-8074-8075 B.S 3580 & PSI 3051 (PN-10). 110 MM 4" DIA | 600.00 Rft | 268.00 | P/Rft | 160,800.00 | 268.00 | 160,800.00 | 268.00 | 160,800.00 |
| | 90MM 3" DIA | 800.00 Rft | 178.00 | P/Rft | 142,400.00 | 178.00 | 142,400.00 | 178.00 | 142,400.00 |
| 6 | Providing C.I Sluice Valve heavy pattern (Test Pressure 21.0 Kg/sq.com or 300 lb/sq.inch) (Imported) | 1.00 No | 5460.00 | Each | 5,460.00 | 5460.00 | 5,460.00 | 5460.00 | 5,460.00 |
| | 3" Dia | 2.00 Nos | 4290.00 | Each | 8,580.00 | 4290.00 | 8,580.00 | 4290.00 | 8,580.00 |

Qumma

MS

Signature

Signature

Signature

**Name of Work: REPAIR OF CRITICAL WATER LEAKAGE OF 15" DIA AND 12" DIA PRCC PIPE AT SHARAH-E-NOOR JAHAN
AND AT PAHAR GANJ AND REPLACEMENT OF DAMAGED PIPE BY 110, 190MM DIA P.E PIPE AT PAHAR GANJ OF
NORTH NAZIMABAD FOR THE IMPROVEMENT OF WATER SUPPLY AND RECTIFICATION OF CONTAMINATION**

| Item No | Description of Work | Estimated Cost | | | | M/s. M. Shafiq & Brothers | | M/s. Jawaid & Sons | | |
|-------------------------------|---|----------------|-----------|--------------------|--------------|---------------------------|--------------------|----------------------|----------|----------------|
| | | Quantity | Rate | Per | Amount | Rate | Amount | Rate | Amount | |
| 7 | Fixing of sluice valve with 2 cast iron tail pieces one end flanged & other with socket i/c the cost of nut, bolts & rubber packing, labour etc complete 4" Dia 3" Dia | 1.00 2.00 | No Nos | 1532.00 1254.00 | Each Each | 1,532.00 2,508.00 | 1532.00 1254.00 | 1,532.00 2,508.00 | | |
| 8 | Full hire charges of pumping set per day i/c of wages of driver and assistant fuel or electric energy platform for placing the pump etc at lower depth with suction and delivery pipes for pumping out water found at various depth from trenches including the cost of erection and dismantling after completion of the job. Hire charges of pumping set upto 10 HP pumping out water from 10 ft deep trench | 10.00 | Days | 1500.00 | P/Day | 15,000.00 | 1485.00 | 14,850.00 | 1520.00 | 15,200.00 |
| 9 | Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete. | 17380.16 | Cft | 2760.00 | %0Cft | 47,969.24 | 2760.00 | 47,969.24 | 2760.00 | 47,969.24 |
| 10 | Providing chamber inside diamension with 24" x 24" C.I cover & frame Weight 65 kg fixed in RCC Slab 1:2:4: 6" thick with steel 1/2" dia bars 6" C/C bend up both way, 12" inch thick C.C: 1:3:6 block masonry 6" inch C.C 1:4:8 in foundation, 2" thick C.C 1:2:4 flooring, 1/2" thick cement plaster i/c P/F M.S footrest 5/8" bars at every 2'.0" feet deep i/c curing watering excavation refilling and disposal of surplus earth complete. Chamber 4'x4'x4' | 2.00 | Nos | 28357.00 | Each | 56,714.00 | 28357.00 | 56,714.00 | 28357.00 | 56,714.00 |
| TOTAL QUOTED / CORRECTED COST | | | | | | 999,152 | | 999,002 | | 999,352 |

Amir
 (Arshad Ali)
 D.A.O (Distt Central)
 Member / Secretary

S
 (Saif-ul-Haque)
 Addl. Director Internal Audit
 KMC - Member

Wahid
 (Magsood Ahmed Shaikh)
 Superintending Engineer (K.M.C)
 Member

Muhammad Anwar Shaikh
 (Muhammad Anwar Shaikh)
 S.E (District Central-A)
 Member

Saleem Ahmed
 (Saleem Ahmed)
 Chief Engineer (IPD)
 Convener

