

# DISTRICT COUNCIL KARACHI

## Bid Evaluation Report

(Work No. 02)


NIT-08 Works (Tender Notice 140) opening 09-12-2015


1	Name of Procuring Agency:	<b>District Council Karachi</b>
2	Tender Reference No	Tender Notice No. D.C.K / Administrator / 140/ 2015, Dated 10-11-2015
3	Tender Description/name of Work / item	<b>Providing / Laying / Jointing &amp; Testing Water Line Ali Muhammad Goth Bund Murad UC Shah Mureed</b>
4	Method of Procurement	Single Stage (one envelop)
5	Tender Published:	Through SPPRA website
6	Total Bid documents Sold:	03 Nos
7	Total Bids Received	03 Nos
8	Technical Bid Opening date (if applicable):	N/A
9	No. of Bid technically qualified (if applicable)	N/A
10	Bid(s) Rejected	(Nil)
11	Financial Bid Opening date	09-12-2015


### 1. Bid Evaluation Report:

S.No	Name of Firm or Bidder	Cost offered by the Bidder	Ranking in terms of cost	Comparison with Estimated cost	Reasons for acceptance/rejection	Remarks
1	2	3	4	5	6	7
1	<b>M/S Naveed &amp; Azan Enterprises</b>	<b>9,94,959/=</b>	<b>1<sup>st</sup> lowest</b>	<b>19.50% Above</b>	Substantially Responsive	Pay order No.303833 Amount Rs. 20,000/= Sindh Bank Gizri Branch
2	M/S U.S Construction Company	9,97,040/=	2 <sup>nd</sup> Lowest	19.75% Above	Substantially Responsive	Pay order No00130106 Amount Rs. 20,000/= Al-Habib Bank
3	M/S Zeenat Construction Company	9,97,873/=	3 <sup>rd</sup> Lowest	19.85% Above	Substantially Responsive	Pay order No.00130167 Amount Rs. 20,000/= Al- nHabib Bank

- The all concerned bidder are being informed accordingly.
- The E.E concerned for compliance of rule 45 of SPPRA-2010 **M/S Naveed & Azan Enterprises** declared has the lowest responsive bidder by the committee and recommended for sanctioned from Competent Authority.

  
**Mr.Khan Muhammad/Malik (Member)**  
Accounts Officer  
District Council Karachi

  
**Mr.Liaquat Ali Mughal (Member)**  
Assistant Executive Engineer  
D.M.C Malir

  
**Mr.Shakeel Ahmed Memon (Chairman)**  
District Engineer  
District Council Karachi


# DISTRICT COUNCIL KARACHI


## EVALUATION CRITERIA

Eligibility / Qualification Criteria:

Name of Work **Providing / Laying / Jointing & Testing Water Line Ali Muhammad Goth Bund Murad**  
**UC Shah Mureed**

S. No.	Eligibility Criteria	M/S Naveed & Azan Enterprises	M/S U.S Construction Company	M/S Zeenat Construction Company
1.	NTN	Available	Available	Available
2.	Sales Tax Registration	N.A	N.A	N.A
3.	Professional Tax	N.A	N.A	N.a
4.	Registration certificate with Sindh Revenue Board	Available	Available	Available
	<b><u>QUALIFICATION CRITERIA:</u></b>			
5	Minimum Two year's experience of relevant field.	Yes	Yes	Yes
6	Turnover of at least last three years	Available	Available	Available
7	Required Bid Security is attached.	Attached	Attached	Attached
8	Bid is signed, named and stamped by the authorized person of the firm along with authorization letter.	Yes	Yes	Yes
9	Qualified / Disqualified	Qualified	Qualified	Qualified

  
Mr. Khan Muhammad Malik (Member)  
Accounts Officer  
District Council Karachi

  
Mr. Liaquat Ali Mughal (Member)  
Assistant Executive Engineer  
D.M.C Malir

  
Mr. Shakeel Ahmed Memon (Chairman)  
District Engineer  
District Council Karachi

# DISTRICT COUNCIL KARACHI

## COMPARATIVE STATEMENT

**Work No. 01**


N.I.T - 08 Works. Tender Notice 140 opening date  
09-12-2015

**SUBJECT: Providing / Laying / Jointing & Testing Water Line at Jogi Goth UC Shah Mureed**

Sr No	Description of Work	Engineer's Estimate			M/S U.S Construction Company			M/S Malhar Construction Company			M/S Zeenat Construction Company		
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount	Rate	Amount		
1	Excavation of pipe line in trenches and pits in all kind of soils i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade, cutting joints holes and disposal of surplus earth within a one chain as directed by Engineer Incharge providing fence guards lights flags and temporary crossings for non-vehicular traffic where ever required lift upto 5 ft & lead upto one chain (PHED Sch P.No.62/5)	35052.00 Cft	4650.00	%Cft	1,62,992/=	4650.00	1,62,992/=	4650.00	1,62,992/=	4650.00	1,62,992/=		
2	Providing / Laying / jointing & testing of Polyethylene pipe (HDPE-100) SDR-13.6/PH-6 conforming to ISO 4427/DIN8074/8075 & PS 3380.94 manufactured by API certified fixing in trench i/c cutting fitting and jointing i/c testing with water to specified pressure also i/c transportation charges pipe etc complete (PHEDSchW.Space26/1)	2003.00 Rft 2003.00 Rft	109/= 148/=	P Rft P Rft	2,18,327/= 2,96,444/=	109/= 148/=	2,18,327/= 2,96,444/=	109/= 148/=	2,18,327/= 2,96,444/=	109/= 148/=	2,18,327/= 2,96,444/=		
3	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete (PHED Sch P.No. 77/24)	31547.00 Cft	2760.00	% Cft	87,070/=	2760.00	87,070/=	2760.00	87,070/=	2760.00	87,070/=		
4	Supplying and fixing Polyethylene (P-E) fitting joint pipes etc. Complete (i) Elbow 90 Degree (90mm) (ii) Elbow 45 Degree (iii) Cross Tee Equal 90mm	04 Nos 04 Nos 07 Nos	1676/= 1341/= 2218/=	Each Each Each	6,704/= 5,364/= 15,526/=	1676/= 1341/= 2218/=	6,704/= 5,364/= 15,526/=	1676/= 1341/= 2218/=	6,704/= 5,364/= 15,526/=	1676/= 1341/= 2218/=	6,704/= 5,364/= 15,526/=		
5	Construction small wheel valve chamber clear inside size 18" x 18" x 18" with walls of 9" thick of B.B in cement mortar 1:3 over 4" thick cement concrete 1:3:6 cement plastered ½" thick 1:3 inside i/c supplying and fixing C.I light weight manhole over with frame and locking arrangement of 18" x 18" clear opening etc complete (PH Sch P-53 1-9)	04 Nos	4103/=	Each	16,412/=	4103/=	16,412/=	4103/=	16,412/=	4103/=	16,412/=		
6	Providing / Fixing Full way gun metal valves with wheel threaded or flanged ends with rubber washer standard pattern etc complete (PHED W.S Sch 17 / 4-A)	04 Nos	1940/84	Each	7,763/=	1940/84	7,763/=	1940/84	7,763/=	1940/84	7,763/=		
7	Supplying / Fixing 3" dia Air valve with flange ends rubber washer nut bolts heavy pattern etc complete (R.A)	04 Nos	4000/=	Each	16,000/=	4000/=	16,000/=	4000/=	16,000/=	4000/=	16,000/=		
		<b>Total Amount of Schedule Rate</b>			<b>8,32,602/=</b>		<b>8,32,602/=</b>		<b>8,32,602/=</b>		<b>8,32,602/=</b>		
		Add 20% Above			1,66,521/=	19.70% Above	1,64,022/=	19.85% Above	1,65,271/=	19.90% Above	1,65,687/=		
		<b>Total Amount:-</b>			<b>9,99,123/=</b>		<b>9,96,624/=</b>		<b>9,97,873/=</b>		<b>9,98,289/=</b>		

  
**Mr. Khan Muhammad Malik (Member)**  
Accounts Officer  
District Council Karachi

  
**Mr. Liaquat Ali Mughal (Member)**  
Assistant Executive Engineer  
D.M.C Malir

  
**Mr. Shakeel Ahmed Memon (Chairman)**  
District Engineer  
District Council Karachi

# DISTRICT COUNCIL KARACHI

## Bid Evaluation Report

(Work No. 03)


NIT-08 Works (Tender Notice 140) opening 09-12-2015


1	Name of Procuring Agency:	District Council Karachi
2	Tender Reference No	Tender Notice No. D.C.K / Administrator / 140/ 2015, Dated 10-11-2015
3	Tender Description/name of Work / item	Providing / Laying / Jointing & Testing Water Line at Dumba Goth UC Konkar
4	Method of Procurement	Single Stage (one envelop)
5	Tender Published:	Through SPPRA website
6	Total Bid documents Sold:	03 Nos
7	Total Bids Received	03 Nos
8	Technical Bid Opening date (if applicable):	N/A
9	No. of Bid technically qualified (if applicable)	N/A
10	Bid(s) Rejected	(Nil)
11	Financial Bid Opening date	09-12-2015


### 1. Bid Evaluation Report:

S.No	Name of Firm or Bidder	Cost offered by the Bidder	Ranking in terms of cost	Comparison with Estimated cost	Reasons for acceptance/rejection	Remarks
1	2	3	4	5	6	7
1	M/S Naveed & Azan Enterprise	9,95,791/=	1 <sup>st</sup> lowest	19.60% Above	Substantially Responsive	Pay order No. 303788 Amount Rs. 20,000/= Sindh Bank Gizri Branch
2	M/S Samma Construction Company	9,97,457/=	2 <sup>nd</sup> Lowest	19.80% Above	Substantially Responsive	Pay order No. 0590324 Amount Rs. 20,000/= Islami Bank
3	M/S Hi-Tech Enterprises	9,98,289/=	3 <sup>rd</sup> Lowest	19.90% Above	Substantially Responsive	Pay order No. 9481688 Amount Rs. 20,000/= UBL Memon Goth

- The all concerned bidder are being informed accordingly.
- The E.E concerned for compliance of rule 45 of SPPRA-2010 M/S Naveed & Azan Enterprises declared has the lowest responsive bidder by the committee and recommended for sanctioned from Competent Authority.

  
Mr. Khan Muhammad Malik (Member)  
Accounts Officer  
District Council Karachi

  
Mr. Liaquat Ali Mughal (Member)  
Assistant Executive Engineer  
D.M.C Malir

  
Mr. Shakeel Ahmed Memon (Chairman)  
District Engineer  
District Council Karachi


# DISTRICT COUNCIL KARACHI


## EVALUATION CRITERIA


Eligibility / Qualification Criteria:

Name of Work: Providing / Laying / Jointing & Testing Water Line at Dumba Goth UC Konkar

S. No.	Eligibility Criteria	M/S Naveed & Azan Enterprise	M/S Samma Construction Company	M/S Hi-Tech Enterprises
1.	NTN	Available	Available	Available
2.	Sales Tax Registration	N.A	N.A	N.A
3.	Professional Tax	N.A	N.A	N.a
4.	Registration certificate with Sindh Revenue Board	Available	Available	Available
	<b><u>QUALIFICATION CRITERIA:</u></b>			
5	Minimum Two year's experience of relevant field.	Yes	Yes	Yes
6	Turnover of at least last three years	Available	Available	Available
7	Required Bid Security is attached.	Attached	Attached	Attached
8	Bid is signed, named and stamped by the authorized person of the firm along with authorization letter.	Yes	Yes	Yes
9	Qualified / Disqualified	Qualified	Qualified	Qualified

  
**Mr. Khan Muhammad Malik (Member)**  
Accounts Officer  
District Council Karachi

  
**Mr. Liaquat Ali Mughal (Member)**  
Assistant Executive Engineer  
D.M.C Malir

  
**Mr. Shakeel Ahmed Memon (Chairman)**  
District Engineer  
District Council Karachi

# DISTRICT COUNCIL KARACHI

## COMPARATIVE STATEMENT

**SUBJECT: Providing / Laying / Jointing & Testing Water Line at Dumba Goth UC Konkar**

**Work No. 03**

N.I.T - 08 Works: Tender Notice 140 opening date 09-12-2015

Sr No	Description of Work	Engineer's Estimate			M/S Naveed & Azan Enterprise			M/S Samma Construction Company			M/S Hi-Tech Enterprises	
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount	Rate	Amount	
1	Excavation of pipe line in trenches and pits in all kind of soils i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade, cutting joints holes and disposal of surplus earth within a one chain as directed by Engineer Incharge providing fence guards lights flags and temporary crossings for non-vehicular traffic where ever required lift upto 5 ft & lead upto one chain (PHED Sch P.No.62/5)	35052.00 Cft	4650.00	%Cft	1,62,992/=	4650.00	1,62,992/=	4650.00	1,62,992/=	4650.00	1,62,992/=	
2	Providing / Laying / Jointing & testing of Polyethylene pipe (HDPE-100) SDR-13.6/PH-6 conforming to ISO 4427/DIN8074/8075 & PS 3380-94 manufactured by API certified fixing in trench i/c cutting fitting and jointing i/c testing with water to specified pressure also i/c transportation charges pipe etc complete (PHEDSch.W.Space26/1)	2003.00 Rft 2003.00 Rft	109/= 148/=	P Rft P Rft	2,18,327/= 2,96,444/=	109/= 148/=	2,18,327/= 2,96,444/=	109/= 148/=	2,18,327/= 2,96,444/=	109/= 148/=	2,18,327/= 2,96,444/=	
3	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete (PHED Sch P.No. 77/24)	31547.00 Cft	2760.00	% Cft	87,070/=	2760.00	87,070/=	2760.00	87,070/=	2760.00	87,070/=	
4	Supplying and fixing Polyethylene (P-E) fitting joint pipes etc. Complete (i) Elbow 90 Degree (90mm) (ii) Elbow 45 Degree (iii) Cross Tee Equal 90mm	04 Nos 04 Nos 07 Nos	1676/= 1341/= 2218/=	Each Each Each	6,704/= 5,364/= 15,526/=	1676/= 1341/= 2218/=	6,704/= 5,364/= 15,526/=	1676/= 1341/= 2218/=	6,704/= 5,364/= 15,526/=	1676/= 1341/= 2218/=	6,704/= 5,364/= 15,526/=	
5	Construction small wheel valve chamber clear inside size 18" x 18" x 18" with walls of 9" thick of B.B in cement mortar 1:3 over 4" thick cement concrete 1:3:6 cement plastered 1/2" thick 1:3 inside i/c supplying and fixing C.I light weight manhole over with frame and locking arrangement of 18" x 18" clear opening etc complete (PH Sch P-53 I-9)	04 Nos	4103/=	Each	16,412/=	4103/=	16,412/=	4103/=	16,412/=	4103/=	16,412/=	
6	Providing / Fixing Full way gun metal valves with wheel threaded or flanged ends with rubber washer standard pattern etc complete (PHED W.S Sch 17/4-A)	04 Nos	1940/84	Each	7,763/=	1940/84	7,763/=	1940/84	7,763/=	1940/84	7,763/=	
7	Supplying / Fixing 3" dia Air valve with flange ends rubber washer nut bolts heavy pattern etc complete (R.A)	04 Nos	4000/=	Each	16,000/=	4000/=	16,000/=	4000/=	16,000/=	4000/=	16,000/=	
		<b>Total Amount of Schedule Rate</b>			<b>8,32,602/=</b>		<b>8,32,602/=</b>		<b>8,32,602/=</b>		<b>8,32,602/=</b>	
		Add 20% Above			1,66,521/=	19.60% Above	1,63,189/=	19.80% Above	1,64,855/=	19.90% Above	1,65,887/=	
		<b>Total Amount:-</b>			<b>9,99,123/=</b>		<b>9,95,791/=</b>		<b>9,97,457/=</b>		<b>9,98,289/=</b>	

**Mr. Khan Muhammad Malik (Member)**  
Accounts Officer  
District Council Karachi

**Mr. Liaquat Ali Mughal (Member)**  
Assistant Executive Engineer  
D.M.C Malir

**Mr. Shakeel Ahmed Memon (Chairman)**  
District Engineer  
District Council Karachi

# DISTRICT COUNCIL KARACHI

## Bid Evaluation Report

(Work No. 04)


NIT-08 Works (Tender Notice 140) opening 09-12-2015


1	Name of Procuring Agency:	District Council Karachi
2	Tender Reference No	Tender Notice No. D.C.K / Administrator / 140/ 2015, Dated 10-11-2015
3	Tender Description/name of Work / item	Providing / Laying / Jointing & Testing Sewerage line / Construction of Streets at Dumba Goth UC Konkar
4	Method of Procurement	Single Stage (one envelop)
5	Tender Published:	Through SPPRA website
6	Total Bid documents Sold:	03 Nos
7	Total Bids Received	03 Nos
8	Technical Bid Opening date (if applicable):	N/A
9	No. of Bid technically qualified (if applicable)	N/A
10	Bid(s) Rejected	(Nil)
11	Financial Bid Opening date	09-12-2015


### 1. Bid Evaluation Report:

S.No	Name of Firm or Bidder	Cost offered by the Bidder	Ranking in terms of cost	Comparison with Estimated cost	Reasons for acceptance/rejection	Remarks
1	2	3	4	5	6	7
1	M/S U.S Construction Company	9,96,674/=	1 <sup>st</sup> lowest	Part-A 8.75% Above Part-B 24.90% Above	Substantially Responsive	Pay order No. 303790 Amount Rs. 20,000/= Sindh Bank Gizri Branch
2	M/S Naveed & Azan Enterprises	9,97,401/=	2 <sup>nd</sup> Lowest	Part-A 8.90% Above Part-B 24.95% Above	Substantially Responsive	Pay order No. 8136973 Amount Rs. 20,000/= UBL Memon Goth
3	M/S Zeenat Construction Company	9,98,365/=	3 <sup>rd</sup> Lowest	Part-A 8.95% Above Part-B 25.10% Above	Substantially Responsive	Pay order No. 12528049 Amount Rs. 20,000/= HBL Memon Goth

- The all concerned bidder are being informed accordingly.
- The E.E concerned for compliance of rule 45 of SPPRA-2010 M/S U.S Construction Company declared has the lowest responsive bidder by the committee and recommended for sanctioned from Competent Authority.

  
Mr. Khan Muhammad Malik (Member)  
Accounts Officer  
District Council Karachi

  
Mr. Liaquat Ali Mughal (Member)  
Assistant Executive Engineer  
D.M.C Malir

  
Mr. Shakeel Ahmed Memon (Chairman)  
District Engineer  
District Council Karachi


# DISTRICT COUNCIL KARACHI


## EVALUATION CRITERIA


Eligibility / Qualification Criteria:

Name of Work: Providing / Laying / Jointing & Testing Sewerage line / Construction of Streets at Dumba Goth UC Konkar

S. No.	Eligibility Criteria	M/S U.S Construction Company	M/S Naveed & Azan Enterprises	M/S Zeenat Construction Company
1.	NTN	Available	Available	Available
2.	Sales Tax Registration	N.A	N.A	N.A
3.	Professional Tax	N.A	N.A	N.a
4.	Registration certificate with Sindh Revenue Board	Available	Available	Available
	<b><u>QUALIFICATION CRITERIA:</u></b>			
5	Minimum Two year's experience of relevant field.	Yes	Yes	Yes
6	Turnover of at least last three years	Available	Available	Available
7	Required Bid Security is attached.	Attached	Attached	Attached
8	Bid is signed, named and stamped by the authorized person of the firm along with authorization letter.	Yes	Yes	Yes
9	Qualified / Disqualified	Qualified	Qualified	Qualified

  
Mr. Khan Muhammad Malik (Member)  
Accounts Officer  
District Council Karachi

  
Mr. Liaquat Ali Mughal (Member)  
Assistant Executive Engineer  
D.M.C Malir

  
Mr. Shakeel Ahmed Memon (Chairman)  
District Engineer  
District Council Karachi



# DISTRICT COUNCIL KARACHI

## COMPARATIVE STATEMENT

Part-A

**SUBJECT: Providing / Laying / Jointing & Testing Sewerage line / Construction of Streets at Dumba Goth UC Konkar**

**Work No. 04** N.I.T - 08 Works: Tender Notice 140 opening date: 09-12-2015

Sr No	Description of Work	Engineer's Estimate			M/S U.S Construction Company			M/S Naveed & Azan Enterprises			M/S Zeenat Construction Company	
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount	Rate	Amount	
1	Excavation of pipe line in trenches and pits in all kind of soils i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade, cutting joints holes and disposal of surplus earth within a one chain as directed by Engineer Incharge providing fence guards lights flags and temporary crossings for non-vehicular traffic where ever required lift upto 5 ft & lead upto one chain (PHED Sch P.No.47/5)	3375.00 Cft	4650.00	%Cft	15,694/=	4650.00	15,694/=	4650.00	15,694/=	4650.00	15,694/=	
2	Providing R.C.C pipes of rubbering joints and fixing in trenches i/c cutting fitting and jointing with rubber ring i/c testing with water to specified pressure (PHED Sch P-18/b(2) (1,1,11))	300.00 Rft	367.00	P Rft	1,10,100/=	367.00	1,10,100/=	367.00	1,10,100/=	367.00	1,10,100/=	
3	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete (PHED Sch P-No. 53/24)	3037.00 Cft	2760.00	% Cft	8,382/=	2760.00	8,382/=	2760.00	8,382/=	2760.00	8,382/=	
4	Construction of Manhole 4 ft dia 5 ft depth (inner dimension) as per approved design of K.W & S.B. including the cost of excavation, 6 inch thick C.C 1:4:8 using stone ballast 2 inch and done gauge 9 inch thick C.C 1:2:4 plain walls with finishing refilling the excavated stuff around structure curing etc complete as per directed engineer incharge	16 Nos	13707/=	Each	2,19,312/=	13707/=	2,19,312/=	13707/=	2,19,312/=	13707/=	2,19,312/=	
5	Add or less depth beyond 5 ft depth in manhole etc compete	10,56.00 Rft	3046/=	P Rft	(-) 32,166/=	3046/=	(-) 32,166/=	3046/=	(-) 32,166/=	3046/=	(-) 32,166/=	
6	Manufacturing and supplying of precast RCC ring slab of 21" dia inner side and 36" dia outer side 7.5" width and 6" thick i/c 3/8" dia 8 Nos. cross link bars welded and two sunk type hooks casted in 1:1 1/2:3 concrete with embedded 15kg CI frame in perfect position i/c transportation charges of average lead of 20km per trip from casting yard to town offices (a minimum of 25 slabs per trip will be transported)(PHED Sch P-No. 30/2)	16 Nos	1906.60	Each	30,506/=	1906.60	30,506/=	1906.60	30,506/=	1906.60	30,506/=	
7	Manufacturing and supplying manhole cover cast in 1:2:4 concrete ration 3" deep at center reinforced with 3/8" dia tor steel bars at 4" C.C welded to 1/8" thick 2.5" deep MS plate i/c curing, stacking and transportation within 10 miles. (W.S. Sch P-27 /1(a) 21" dia	16 Nos	913/63	Each	14,618/=	913/63	14,618/=	913/63	14,618/=	913/63	14,618/=	
		<b>Total Amount of Schedule Rate</b>				<b>3,66,466/=</b>		<b>3,66,466/=</b>		<b>3,66,466/=</b>		<b>3,66,466/=</b>
		<b>Add @ 20% Above on item no 4 &amp; 5</b>				<b>35,860/=</b>		<b>8.75% Above</b>		<b>32,065/=</b>		<b>8.95% Above</b>
		<b>Total Amount Rs.</b>				<b>4,02,306/=</b>		<b>3,98,531/=</b>		<b>3,99,018/=</b>		<b>3,99,264/=</b>

# DISTRICT COUNCIL KARACHI

## COMPARATIVE STATEMENT

**SUBJECT: Providing / Laying / Jointing & Testing Water Line at Abdul Ghafoor Goth UC Allah Phai**

**Work No. 05**

N.I.T - 08 Works Tender Notice 140 opening date 09-12-2015

Sr No	Description of Work	Engineer's Estimate				M/S Naveed & Azan Enterprises		M/S Zeenat Construction Company		M/S U.S Construction Company	
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount	Rate	Amount
1	Excavation of pipe line in trenches and pits in all kind of soils i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade, cutting joints holes and disposal of surplus earth within a one chain as directed by Engineer Incharge providing fence guards lights flags and temporary crossings for non-vehicular traffic where ever required lift upto 5 ft & lead upto one chain (PHED Sch P.No.62/5)	35052.00 Cft	4650.00	%Cft	1,62,992/=	4650.00	1,62,992/=	4650.00	1,62,992/=	4650.00	1,62,992/=
2	Providing / Laying / jointing & testing of Polyethylene pipe (HDPE-100) SDR-13.6/PI-6 conforming to ISO 4427/DIN8074/8075 & PS 3380:94 manufactured by API certified fixing in trench i/c cutting fitting and jointing i/c testing with water to specified pressure also i/c transportation charges pipe etc complete (PHEDSchW.SP.26/1)	2003.00 Rft 2003.00 Rft	109/= 148/=	P Rft P Rft	2,18,327/= 2,96,444/=	109/= 148/=	2,18,327/= 2,96,444/=	109/= 148/=	2,18,327/= 2,96,444/=	109/= 148/=	2,18,327/= 2,96,444/=
3	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete (PHED Sch P.No. 77/24)	31547.00 Cft	2760.00	% Cft	87,070/=	2760.00	87,070/=	2760.00	87,070/=	2760.00	87,070/=
4	Supplying and fixing Polyethylene (P-E) fitting joint pipes etc. Complete (i) Elbow 90 Degree (90mm) (ii) Elbow 45 Degree (iii) Cross Tee Equal 90mm	04 Nos 04 Nos 07 Nos	1676/= 1341/= 2218/=	Each Each Each	6,704/= 5,364/= 15,526/=	1676/= 1341/= 2218/=	6,704/= 5,364/= 15,526/=	1676/= 1341/= 2218/=	6,704/= 5,364/= 15,526/=	1676/= 1341/= 2218/=	6,704/= 5,364/= 15,526/=
5	Construction small wheel valve chamber clear inside size 18" x 18" x 18" with walls of 9" thick of B.B in cement mortar 1:3 over 4" thick cement concrete 1:3:6 cement plastered 1/2" thick 1:3 inside i/c supplying and fixing C I light weight manhole over with frame and locking arrangement of 18" x 18" clear opening etc complete (PH Sch P-53-1-9)	04 Nos	4103/=	Each	16,412/=	4103/=	16,412/=	4103/=	16,412/=	4103/=	16,412/=
6	Providing / Fixing Full way gun metal valves with wheel threaded or flanged ends with rubber washer standard pattern etc complete (PHED W.S. Sch 17/4-A)	04 Nos	1940/84	Each	7,763/=	1940/84	7,763/=	1940/84	7,763/=	1940/84	7,763/=
7	Supplying / Fixing 3" dia Air valve with flange ends rubber washer nut bolts heavy pattern etc complete (R.A)	04 Nos	4000/=	Each	16,000/=	4000/=	16,000/=	4000/=	16,000/=	4000/=	16,000/=
		<b>Total Amount of Schedule Rate</b>			<b>8,32,602/=</b>		<b>8,32,602/=</b>		<b>8,32,602/=</b>		<b>8,32,602/=</b>
			Add 20% Above		1,66,521/=		1,64,438/=		1,65,271/=		1,66,104/=
			<b>Total Amount:-</b>		<b>9,99,123/=</b>		<b>9,97,040/=</b>		<b>9,97,873/=</b>		<b>9,98,706/=</b>

**Mr. Khan Muhammad Malik (Member)**  
Accounts Officer  
District Council Karachi

**Mr. Liaquat Ali Mughal (Member)**  
Assistant Executive Engineer  
D.M.C Malir

**Mr. Shakeel Ahmed Memon (Chairman)**  
District Engineer  
District Council Karachi

# DISTRICT COUNCIL KARACHI

## Bid Evaluation Report

(Work No. 06)


NIT-08 Works (Tender Notice 140) opening 09-12-2015

1	Name of Procuring Agency:	District Council Karachi
2	Tender Reference No	Tender Notice No. D.C.K / Administrator / 140/ 2015, Dated 10-11-2015
3	Tender Description/name of Work / item	Repair / Motorable damage portion of road at Khairabad, Haji Mehmood Goth, Haji Ameer Bux Goth, Abdul Rahim Goth, Abdul Rehman Goth, Haji Siddique Goth, Munshi Allah Bux Goth, UC Mai Ghari
4	Method of Procurement	Single Stage (one envelop)
5	Tender Published:	Through SPPRA website
6	Total Bid documents Sold:	03 Nos
7	Total Bids Received	03 Nos
8	Technical Bid Opening date (if applicable):	N/A
9	No. of Bid technically qualified (if applicable)	N/A
10	Bid(s) Rejected	(Nil)
11	Financial Bid Opening date	09-12-2015


### 1. Bid Evaluation Report:

S.No	Name of Firm or Bidder	Cost offered by the Bidder	Ranking in terms of cost	Comparison with Estimated cost	Reasons for acceptance/rejection	Remarks
1	2	3	4	5	6	7
1	M/S Malhar Construction Company	9,95,604/=	1 <sup>st</sup> lowest	9.50% Below	Substantially Responsive	Pay order No.316646 Amount Rs. 20,000/= Sindh Bank Mohd Ali cty
2	M/S G.M Enterprises	9,96,704/=	2 <sup>nd</sup> Lowest	9.40% Below	Substantially Responsive	Pay order No. 9481964 Amount Rs. 20,000/= UBL Memon Goth
3	M/S Wajid Enterprises	9,98,354/=	3 <sup>rd</sup> Lowest	9.25% Above	Substantially Responsive	Pay order No. 284856 Amount Rs. 20,000/= Sindh Bank Memon Goth

- The all concerned bidder are being informed accordingly.
- The E.E concerned for compliance of rule 45 of SPPRA-2010 M/S Malhar Construction Company declared has the lowest responsive bidder by the committee and recommended for sanctioned from Competent Authority.

  
Mr. Khan Muhammad Malik (Member)  
Accounts Officer  
District Council Karachi

  
Mr. Liaquat Ali Mughal (Member)  
Assistant Executive Engineer  
D.M.C Malir

  
Mr. Shakeel Ahmed Memon (Chairman)  
District Engineer  
District Council Karachi


# DISTRICT COUNCIL KARACHI


## EVALUATION CRITERIA


Eligibility / Qualification Criteria:

**Name of Work** Repair / Motorable damage portion of road at Khairabad, Haji Mehmood Goth, Haji Ameer Bux Goth, Abdul Rahim Goth, Abdul Rehman Goth, Haji Siddique Goth, Munshi Allah Bux Goth, UC Mai Ghari

S. No.	Eligibility Criteria	M/S Malhar Construction Company	M/S G.M Enterprises	M/S Wajid Enterprises
1.	NTN	Available	Available	Available
2.	Sales Tax Registration	N.A	N.A	N.A
3.	Professional Tax	N.A	N.A	N.a
4.	Registration certificate with Sindh Revenue Board	Available	Available	Available
	<b><u>QUALIFICATION CRITERIA:</u></b>			
5	Minimum Two year's experience of relevant field.	Yes	Yes	Yes
6	Turnover of at least last three years	Available	Available	Available
7	Required Bid Security is attached.	Attached	Attached	Attached
8	Bid is signed, named and stamped by the authorized person of the firm along with authorization letter.	Yes	Yes	Yes
9	Qualified / Disqualified	Qualified	Qualified	Qualified

  
Mr. Khan Muhammad Malik (Member)  
Accounts Officer  
District Council Karachi

  
Mr. Liaquat Ali Mughal (Member)  
Assistant Executive Engineer  
D.M.C Malir

  
Mr. Shakeel Ahmed Memon (Chairman)  
District Engineer  
District Council Karachi

# DISTRICT COUNCIL KARACHI


## COMPARATIVE STATEMENT

**Work No. 06** N.I.T - 08 Works Tender Notice 140 opening date 09-12-2015  
**SUBJECT:** Repair / Motorable damage portion of road at Khairabad, Haji Mehmood Goth, Haji Ameer Bux Goth, Abdul Rahim Goth,  
 Abdul Rehman Goth, Haji Siddique Goth, Munshi Allah Bux Goth, UC Mai Ghari

Sr No	Description of Work	Engineer's Estimate			M/S Malhar Construction Company			M/S G.M Enterprises			M/S Wajid Enterprises		
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount	Rate	Amount		
1	Earth work road embankment bulldozers i/c plugging mixing clod breaking dressing compaction with optimum moisture contract up to 100ft & lift up to 5ft. in all types of soil expect rock (if) If earth work is done by other departmental agency (H.W Sch P-2 It- 6a)	26365.00 Cft	11375/83	%Cft	2,99,923/=	11375/83	2,99,923/=	11375/83	2,99,923/=	11375/83	2,99,923/=		
2	Providing Subo-Base by Supplying & Spreading Stone Metal 1-1/2", 2" gauge of approved quality from approved quarry in required thickness to proper camber & grade i/c Hand Packing filling voids with 10 Cft Screening & Non-Plastic Quarry fines of approved quality & Gauge from approved source, watering & compacting to achieve 98-100% density as modified AASHTO specification.(Rate I/C all Cost of Material T&P and Carriage upto 3 Chans)	2251.00 Cft	4359/76	%Cft	98,138/=	4359/76	98,138/=	4359/76	98,138/=	4359/76	98,138/=		
3	Providing and Laying Aggregate base coarse in proper grade and camber having CBR 80% AS PER AASHTO Standard specification i/c spreading and compacting by approved mechanical means (Motor Grader, Vibratory Roller and Smooth wheel roller etc watering to maintain the moisture content the compaction of each layer shall 100 percent to the max dry density (Rate i/c all cost of material T&P and carriage upto 3 chans).	10370.00 Cft	6770/04	%Cft	7,02,053/=	6770/04	7,02,053/=	6770/04	7,02,053/=	6770/04	7,02,053/=		
		<b>Total Amount of Schedule Rate</b>			<b>11,00,114/=</b>		<b>11,00,114/=</b>		<b>11,00,114/=</b>		<b>11,00,114/=</b>		
		Ded 15% Below on item no 01 Ded 7% Below on item no 02 & 03			44,988/=	9.50% Below	1,04,510/=	9.40% Below	1,03,410/=	9.25% Below	1,01,760/=		
		<b>Total Amount:-</b>			<b>9,99,113/=</b>		<b>9,95,604/=</b>		<b>9,96,704/=</b>		<b>9,98,354/=</b>		

  
**Mr. Khan Muhammad Malik (Member)**  
 Accounts Officer  
 District Council Karachi

  
**Mr. Liaquat Ali Mughal (Member)**  
 Assistant Executive Engineer  
 D.M.C Malir

  
**Mr. Shakeel Ahmed Memon (Chairman)**  
 District Engineer  
 District Council Karachi

# DISTRICT COUNCIL KARACHI

## Bid Evaluation Report

(Work No. 07)


NIT-08 Works (Tender Notice 140) opening 09-12-2015


1	Name of Procuring Agency:	<b>District Council Karachi</b>
2	Tender Reference No	Tender Notice No. D.C.K / Administrator / 140/ 2015, Dated 10-11-2015
3	Tender Description/name of Work / item	<b>Providing / Laying / Jointing &amp; Testing Sewerage line at Haji Mehmood Goth and Providing / Laying Water Line Khairabad UC Mai Ghari</b>
4	Method of Procurement	Single Stage (one envelop)
5	Tender Published:	Through SPPRA website
6	Total Bid documents Sold:	03 Nos
7	Total Bids Received	03 Nos
8	Technical Bid Opening date (if applicable):	N/A
9	No. of Bid technically qualified (if applicable)	N/A
10	Bid(s) Rejected	(Nil)
11	Financial Bid Opening date	09-12-2015


### 1. Bid Evaluation Report:

S.No	Name of Firm or Bidder	Cost offered by the Bidder	Ranking in terms of cost	Comparison with Estimated cost	Reasons for acceptance/ rejection	Remarks
1	2	3	4	5	6	7
1	M/S G.M Enterprises	9,97,107/=	1 <sup>st</sup> lowest	Part-A 19.75% Above Part-B 6.60% Above	Substantially Responsive	Pay order No.1672829 Amount Rs. 20,000/= MCB Gulistan -e-Johar
2	M/S Malhar Construction Company	9,98,432/=	2 <sup>nd</sup> Lowest	Part-A 19.90% Above Part-B 6.75% Above	Substantially Responsive	Pay order No. 1534194 Amount Rs. 20,000/= Silk Bank
3	M/S Wajid Enterprises	9,99,551/=	3 <sup>rd</sup> Lowest	Part-A 20% Above Part-B 6.90% Above	Substantially Responsive	Pay order No7182605. Amount Rs. 20,000/= Bank Al -Habib Memon Goth

- The all concerned bidder are being informed accordingly.
- The E.E concerned for compliance of rule 45 of SPPRA-2010 **M/S G.M Enterprises** declared has the lowest responsive bidder by the committee and recommended for sanctioned from Competent Authority.

  
Mr.Khan Muhammad Malik (Member)  
Accounts Officer  
District Council Karachi

  
Mr.Liaquat Ali Mughal (Member)  
Assistant Executive Engineer  
D.M.C Malir

  
Mr.Shakeel Ahmed Memon (Chairman)  
District Engineer  
District Council Karachi


# DISTRICT COUNCIL KARACHI


## EVALUATION CRITERIA

Eligibility / Qualification Criteria:

**Name of Work: Providing / Laying / Jointing & Testing Sewerage line at Haji Mehmood Goth and  
Providing / Laying Water Line Khairabad UC Mai Ghari**

S. No.	Eligibility Criteria	M/S G.M Enterprises	M/S Malhar Construction Company	M/S Wajid Enterprises
1.	NTN	Available	Available	Available
2.	Sales Tax Registration	N.A	N.A	N.A
3.	Professional Tax	N.A	N.A	N.a
4.	Registration certificate with Sindh Revenue Board	Available	Available	Available
	<b><u>QUALIFICATION CRITERIA:</u></b>			
5	Minimum Two year's experience of relevant field.	Yes	Yes	Yes
6	Turnover of at least last three years	Available	Available	Available
7	Required Bid Security is attached.	Attached	Attached	Attached
8	Bid is signed, named and stamped by the authorized person of the firm along with authorization letter.	Yes	Yes	Yes
9	Qualified / Disqualified	Qualified	Qualified	Qualified

  
**Mr. Khan Muhammad Malik (Member)**  
Accounts Officer  
District Council Karachi

  
**Mr. Liaquat Ali Mughal (Member)**  
Assistant Executive Engineer  
D.M.C Malir

  
**Mr. Shakeel Ahmed Memon (Chairman)**  
District Engineer  
District Council Karachi

# DISTRICT COUNCIL KARACHI

## COMPARATIVE STATEMENT

**Work No. 07** N.I.T - 08 Works.  
Tender Notice 140 opening date 09-12-2015

**SUBJECT: Providing / Laying / Jointing & Testing Sewerage line at Haji Mehmood Goth and Providing / Laying Water Line Khairabad UC Mai Ghari**  
**Part-A**


Sr No	Description of Work	Engineer's Estimate				M/S G.M Enterprises		M/S Malhar Construction Company		M/S Wajid Enterprises	
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount	Rate	Amount
1	Excavation for pipe lines in trenches and pits in all kinds of soil of manum i/c trimming and dressing sides to true alignment and shape leveling off beds of trenches to correct level and grade, cutting joint holes and disposal of surplus earth within a one chain as directed by Engineer Incharge. Providing fence guards, lights, flags and temporary crossings for non-vehicular traffic where ever required. lift upto 5 ft. (1.52m) and lead up to one chain (30.5m). (PHS. Item No.5 P.No.62) Providing PVC pipe line of class "B" (equivalent make) fixing in trenches i/c cutting fitting and jointing with z-joints with one rubber ring i/c testing with water to head of 61 meter or 200' ft (PHS. Item No. e P.No.22)	12015 Cft	4650/00	% 0 Cft	55,869/=	4650/00	55,869/=	4650/00	55,869/=	4650/00	55,869/=
2	Cast iron sluice valve heavy pattern (test pressure 300 lb/Sq. inch (imported) (PHSMI NO.02 PAGE 09) 2" dia 3" dia 4" dia	1000 Rft 478 Rft 124 Rft	54/00 90/00 137/00	Each Each Each	54000/= 43,020/= 16988/=	54/00 90/00 137/00	54000/= 43,020/= 16988/=	54/00 90/00 137/00	54000/= 43,020/= 16988/=	54/00 90/00 137/00	54000/= 43,020/= 16988/=
3	Cast iron sluice valve heavy pattern (test pressure 300 lb/Sq. inch (imported) (PHSMI NO.02 PAGE 09) 2" dia 3" dia 4" dia	02 Nos 04 Nos 02 Nos	1500/00 4290/00 5460/00	Each Each Each	3000/= 17160/= 10920/=	1500/00 4290/00 5460/00	3000/= 17160/= 10920/=	1500/00 4290/00 5460/00	3000/= 17160/= 10920/=	1500/00 4290/00 5460/00	3000/= 17160/= 10920/=
4	C.I Short Piece (PHSI NO 09 PAGE NO.05) 3" dia 4" dia	08 Nos 04 Nos	375/00 487/00	Each Each	3000/= 1948/=	375/00 487/00	3000/= 1948/=	375/00 487/00	3000/= 1948/=	375/00 487/00	3000/= 1948/=
5	Providing chamber 21/2x2 1/2 (750x750mm) inside dimension 4 1/2", (1372mm) deep as per approved design for sluice valve 3" to 12" dia with 18" (457mm) dia inside xodt uron cover and frame (wt=1 cwt. 3 qt.) fixed in RCC 1:2:4 (102mm) thick (with 5 lb steel cor cft) 9" (299mm) thick brick masonry walls set in 1:6:C:C 6" (152mm) thick C.C 1:3:6 in foundation 1:25mm) thick cc 1:2:4 flooring 1/2" (12.5mm) thick C.C plaster 1:3 to all inside wall surface and to top i/c P/F M.S foot rest at every one foot beyond 2 1/4ft. Depth cutting excavation of back filling and disposal of surplus earth etc complete (PHSI NO. 5PAGE NO. 51)	08 Nos	18820/00	Each	150560/=	18820/00	150560/=	18820/00	150560/=	18820/00	150560/=
6	Refilling of the excavated stuff in trenches 6" thick layers i/c watering ramming to full compacting etc complete (P.H.S.I. No. 24, P/77). 12015 Cft	10813Cft	2760/00	%Cft	29,844/=	2760/00	29,844/=	2760/00	29,844/=	2760/00	29,844/=




Sr No	Description of Work	Engineer's Estimate				M/S G.M Enterprises			M/S Malhar Construction Company			M/S Wajid Enterprises	
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount	Rate	Amount		
7	Special fitting PVC (PHEDSCH -P-18)	Tec 2" Dia	02 Nos	159/00	Each	318/=	159/00	318/=	159/00	318/=	159/00	318/=	
		Tec 3" Dia	04 Nos	361/00	Each	1444/=	361/00	1444/=	361/00	1444/=	361/00	1444/=	
		Tec 4" Dia	02 Nos	725/00	Each	1450/=	725/00	1450/=	725/00	1450/=	725/00	1450/=	
		Elbow 2" dia	02 Nos	225/00	Each	450/=	225/00	450/=	225/00	450/=	225/00	450/=	
		Elbow 3" dia	04 Nos	350/00	Each	1400/=	350/00	1400/=	350/00	1400/=	350/00	1400/=	
		Elbow 4" dia	02 Nos	577/00	Each	1154/=	577/00	1154/=	577/00	1154/=	577/00	1154/=	
		Socket 2 " dia	02 Nos	98/00	Each	196/=	98/00	196/=	98/00	196/=	98/00	196/=	
		Socket 3" dia	04 Nos	350/00	Each	1400/=	350/00	1400/=	350/00	1400/=	350/00	1400/=	
		Socket 4 " dia	02 Nos	500/00	Each	1000/=	500/00	1000/=	500/00	1000/=	500/00	1000/=	
		End Plug 2" dia	02 Nos	85/00	Each	170/=	85/00	170/=	85/00	170/=	85/00	170/=	
		End Plug 3" dia	04 Nos	175/00	Each	700/=	175/00	700/=	175/00	700/=	175/00	700/=	
		End Plug 4" dia	02 Nos	200/00	Each	400/=	200/00	400/=	200/00	400/=	200/00	400/=	
		Reduce bush 2 " dia	02 Nos	80/00	Each	160/=	80/00	160/=	80/00	160/=	80/00	160/=	
		Reduce bush 3 " dia	04 Nos	200/00	Each	400/=	200/00	400/=	200/00	400/=	200/00	400/=	
		Reduce bush 4 " dia	02 Nos	225/00	Each	450/=	225/00	450/=	225/00	450/=	225/00	450/=	
		Bend 2" dia	02 Nos	160/00	Each	320/=	160/00	320/=	160/00	320/=	160/00	320/=	
		Bend 3" dia	02 Nos	475/00	Each	1900/=	475/00	1900/=	475/00	1900/=	475/00	1900/=	
Bend 4" dia	04 Nos	850/00	Each	1700/=	850/00	1700/=	850/00	1700/=	850/00	1700/=			
Tape Core/Socket 2" dia	02 Nos	55/00	Each	110/=	55/00	110/=	55/00	110/=	55/00	110/=			
Tape Core/Socket 2" dia	02 Nos	350/00	Each	1400/=	350/00	1400/=	350/00	1400/=	350/00	1400/=			
Tape core socket 2" dia	02 Nos	450/00	Each	900/=	450/00	900/=	450/00	900/=	450/00	900/=			
8	Air Valve double acting (Local) PHSI NO.08 PAGE 18	2" dia	01 Nos	1200/00	Each	1200/=	1200/00	1200/=	1200/00	1200/=	1200/00	1200/=	
		3" dia	02 Nos	1700/00	Each	3400/=	1700/00	3400/=	1700/00	3400/=	1700/00	3400/=	
		4" dia	02 Nos	4000/00	Each	8000/=	4000/00	8000/=	4000/00	8000/=	4000/00	8000/=	
		<b>Total Amount of Schedule Rate</b>			<b>4,16,331/=</b>		<b>4,16,331/=</b>		<b>4,16,331/=</b>		<b>4,16,331/=</b>		<b>4,16,331/=</b>
	Add @ 20% Above		83,266/=		19.75% Above	82,225/=		19.90% Above	82,849/=		20% Above	83,266/=	
	<b>Total Amount Rs.</b>		<b>4,99,597/=</b>		<b>4,98,556/=</b>		<b>4,99,180/=</b>		<b>4,99,597/=</b>				

## Part-B

Sr No	Description of Work	Engineer's Estimate			M/S G.M Enterprises			M/S Malhar Construction Company			M/S Wajid Enterprises	
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount	Rate	Amount	
1	Excavation of pipe line in trenches and pits in all kind of soils i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade, cutting joints holes and disposal of surplus earth within a one chain as directed by Engineer Incharge providing fence guards lights flags and temporary crossings for non-vehicular traffic where ever required lift upto 5 ft &	4688.0 Cft	4650.00	%Cft	21799/=	4650.00	21799/=	4650.00	21799/=	4650.00	21799/=	
2	Providing R.C.C pipes of rubbering joints and fixing in trenches i/c cutting fitting and jointing with rubber ring i/c testing with water to specified pressure (PHED Sch P-18/6(2)) For 12" dia	500.0Rft	367.00	P Rft	183500/=	367.00	183500/=	367.00	183500/=	367.00	183500/=	
3	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete (PHED Sch P-No. 77/24)	4219 Cft	2760.00	% Cft	11645/=	2760.00	11645/=	2760.00	11645/=	2760.00	11645/=	
4	Construction of Manhole 4 ft dia 5 ft depth (inner dimension) as per approved design of K.W & S.B including the cost of excavation, 6 inch thick C.C 1:4:8 using stone ballast 2 inch and done gauge 9 inch thick C.C. 1:2:4 plain walls with finishing refilling the excavated stuff around structure curing etc complete as per	20 Nos	13707.00	Each	274140/=	13707.00	274140/=	13707.00	274140/=	13707.00	274140/=	
5	Add or less depth beyond 5 ft depth in manhole etc complete (R.A)	-26 Rft	3046.0	P Rft	(-) 79805/=	3046.0	(-) 79805/=	3046.0	(-) 79805/=	3046.0	(-) 79805/=	
6	Manufacturing and supplying of precast RCC ring slab of 21" dia inner side and 36" dia outer side 7.5" width and 6" thick i/c 3/8" dia 8 Nos. cross link bars welded and two sunk type hooks casted in 1:1 1/2:3 concrete with embedded 15kg CI frame in perfect position i/c transportation charges of average lead of 20km per trip from casting yard to town offices (a minimum of 25 slabs per trip will be	20 Nos	1906.60	Each	38132/=	1906.60	38132/=	1906.60	38132/=	1906.60	38132/=	
7	Manufacturing and supplying manhole cover cast in 1:2:4 concrete ration 3" deep at center, reinforced with 3/8" dia tor steel bars at 4" C.C welded to 1/8" thick 2.5" deep MS plate i/c curing, stacking and transportation within 10 miles. approved design of K.W & W.B. (W.S. Sch P-31 / 1 (a)) 21" dia	20 Nos	913/63	Each	18273/=	913/63	18273/=	913/63	18273/=	913/63	18273/=	
		<b>Total Amount of Schedule Rate</b>			<b>4,67,684/=</b>		<b>4,67,684/=</b>		<b>4,67,684/=</b>		<b>4,67,684/=</b>	
		Add 5% Above except item # 2,4,5			4,492/=	6.60%	30,167/=	6.75%	31,568/=	6.90%	32,270/=	
		Add 15% Above on item 2			27,525/=	Above	4,98,551/=	Above	4,99,252/=	Above	4,99,954/=	
		<b>Total Amount Rs.</b>			<b>4,99,701/=</b>		<b>4,98,556/=</b>		<b>4,99,180/=</b>		<b>4,99,597/=</b>	
		<b>Total Amount Part A</b>			<b>4,99,597/=</b>		<b>4,98,556/=</b>		<b>4,99,180/=</b>		<b>4,99,597/=</b>	
		<b>Total Part A+B</b>			<b>9,99,298/=</b>		<b>9,97,107/=</b>		<b>9,98,432/=</b>		<b>9,99,551/=</b>	

  
**Mr. Khan Muhammad Malik (Member)**  
 Accounts Officer  
 District Council Karachi

  
**Mr. Liaquat Ali Mughal (Member)**  
 Assistant Executive Engineer  
 D.M.C Malir

  
**Mr. Shakeel Ahmed Memon (Chairman)**  
 District Engineer  
 District Council Karachi

# DISTRICT COUNCIL KARACHI

## Bid Evaluation Report

(Work No. 08)


NIT-08 Works (Tender Notice 140) opening 09-12-2015


1	Name of Procuring Agency:	District Council Karachi
2	Tender Reference No	Tender Notice No. D.C.K / Administrator / 140/ 2015, Dated 10-11-2015
3	Tender Description/name of Work / item	Providing / Laying / Jointing & Testing Sewerage line at Haji Yar Muhammad Baloch Goth Dargah Usman Shah UC Konkar
4	Method of Procurement	Single Stage (one envelop)
5	Tender Published:	Through SPPRA website
6	Total Bid documents Sold:	03 Nos
7	Total Bids Received	03 Nos
8	Technical Bid Opening date (if applicable):	N/A
9	No. of Bid technically qualified (if applicable)	N/A
10	Bid(s) Rejected	(Nil)
11	Financial Bid Opening date	09-12-2015


### 1. Bid Evaluation Report:

S.No	Name of Firm or Bidder	Cost offered by the Bidder	Ranking in terms of cost	Comparison with Estimated cost	Reasons for acceptance/rejection	Remarks
1	2	3	4	5	6	7
1	M/S Zeenat Construction Company	9,95,120/=	1 <sup>st</sup> lowest	6.50% Above	Substantially Responsive	Pay order No. 13880523 Amount Rs. 20,000/= HBL Korangi Branch
2	M/S Naveed & Azan Enterprises	9,97,455/=	2 <sup>nd</sup> Lowest	6.75% Above	Substantially Responsive	Pay order No. 00130113 Amount Rs. 20,000/= Al-Habib bank
3	M/S Multi Tech Enterprises	9,98,857/=	3 <sup>rd</sup> Lowest	6.90% Above	Substantially Responsive	Pay order No. 228382 Amount Rs. 20,000/= Sindh Bank Memon Goth

- The all concerned bidder are being informed accordingly.
- The E.E concerned for compliance of rule 45 of SPPRA-2010 M/S Zeenat Construction Company declared has the lowest responsive bidder by the committee and recommended for sanctioned from Competent Authority.

  
Mr. Khan Muhammad Malik (Member)  
Accounts Officer  
District Council Karachi

  
Mr. Liaquat Ali Mughal (Member)  
Assistant Executive Engineer  
D.M.C Malir

  
Mr. Shakeel Ahmed Memon (Chairman)  
District Engineer  
District Council Karachi

# DISTRICT COUNCIL KARACHI


## EVALUATION CRITERIA


Eligibility / Qualification Criteria:

Name of Work: **Providing / Laying / Jointing & Testing Sewerage line at Haji Yar Muhammad Baloch  
Goth Dargah Usman Shah UC Konkar**

S. No.	Eligibility Criteria	M/S Zeenat Construction Company	M/S Naveed & Azan Enterprises	M/S Multi Tech Enterprises
1.	NTN	Available	Available	Available
2.	Sales Tax Registration	N.A	N.A	N.A
3.	Professional Tax	N.A	N.A	N.a
4.	Registration certificate with Sindh Revenue Board	Available	Available	Available
	<b><u>QUALIFICATION CRITERIA:</u></b>			
5	Minimum Two year's experience of relevant field.	Yes	Yes	Yes
6	Turnover of at least last three years	Available	Available	Available
7	Required Bid Security is attached.	Attached	Attached	Attached
8	Bid is signed, named and stamped by the authorized person of the firm along with authorization letter.	Yes	Yes	Yes
9	Qualified / Disqualified	Qualified	Qualified	Qualified

  
Mr. Khan Muhammad Malik (Member)  
Accounts Officer  
District Council Karachi

  
Mr. Liaqat Ali Mughal (Member)  
Assistant Executive Engineer  
D.M.C Malir

  
Mr. Shakeel Ahmed Memon (Chairman)  
District Engineer  
District Council Karachi

# DISTRICT COUNCIL KARACHI

## COMPARATIVE STATEMENT

**SUBJECT: Providing / Laying / Jointing & Testing Sewerage line at Haji Yar Muhammad Baloch Goth Dargah Usman Shah UCC Konkar**

Work No. 08 N.I.T-08 Works: Tender Notice 140 opening date 09-12-2015

Sr No	Description of Work	Engineer's Estimate			M/S Zeenat Construction Company			M/S Naveed & Azan Enterprises			M/S Multi Tech Enterprises		
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount	Rate	Amount		
1	Excavation of pipe line in trenches and pits in all kind of soils i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade, cutting joints holes and disposal of surplus earth within a one chain as directed by Engineer Incharge providing fence guards lights flags and temporary crossings for non-vehicular traffic where ever required lift upto 5 ft & lead upto one chain (PHED Sch P.No.62/5)	14250.0 Cft	4650.00	%Cft	66263 /=-	4650.00	66263 /=-	4650.00	66263 /=-	4650.00	66263 /=-		
2	Providing R.C.C pipes of rubbering joints and fixing in trenches i/c cutting fitting and jointing with rubber ring i/c testing with water to specified pressure (PHEDSchp-18/b(2))  For 12" dia	1000.0Rft	367.00	P Rft	367000 /=-	367.00	367000 /=-	367.00	367000 /=-	367.00	367000 /=-		
3	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete (PHED Sch P-No. 77/24)	12825 Cft	2760.00	% Cft	35397 /=-	2760.00	35397 /=-	2760.00	35397 /=-	2760.00	35397 /=-		
4	Construction of Manhole 4 ft dia 5 ft depth (inner dimension) as per approved design of K. W & S.B including the cost of excavation, 6 inch thick C.C 1:4:8 using stone ballast 2 inch and done gauge 9 inch thick C.C. 1:2:4 plain walls with finishing refilling the excavated stuff around structure curing etc complete as per directed engineer incharge. (R/A)	25 Nos	13707.00	Each	342675 /=-	13707.00	342675 /=-	13707.00	342675 /=-	13707.00	342675 /=-		
5	Add or less depth beyond 5 ft depth in manhole etc complete (R.A)	+17.25 Rft	3046.0	P Rft	(+) 52544 /=-	3046.0	(+) 52544 /=-	3046.0	(+) 52544 /=-	3046.0	(+) 52544 /=-		
6	Manufacturing and supplying of precast RCC ring slab of 21" dia inner side and 36" dia outer side 7.5" width and 6" thick i/c 3/8" dia 8 Nos. cross link bars welded and two sunk type hooks casted in 1:1½:3 concrete with embedded 15kg CI frame in perfect position i/c transportation charges of average lead of 20km per trip from casting yard to town offices (a minimum of 25 slabs per trip will be transported) approved design of K.W.& W.B (PHED Sch P.No. 31/2)	25 Nos	1906.60	Each	47665 /=-	1906.60	47665 /=-	1906.60	47665 /=-	1906.60	47665 /=-		
7	Manufacturing and supplying manhole cover cast in 1:2:4 concrete ration 3" deep at center, reinforced with 3/8" dia for steel bars at 4" C.C welded to 1/8" thick 2.5" deep MS plate i/c curing, stacking and transportation within 10 miles: approved design of K.W & W.B (W.S. Sch P-31 / 1 (a))	25 Nos	913/63	Each	22841 /=-	913/63	22841 /=-	913/63	22841 /=-	913/63	22841 /=-		
<b>Total Amount of Schedule Rate</b>					<b>9,34,385 /=-</b>		<b>9,34,385 /=-</b>		<b>9,34,385 /=-</b>		<b>9,34,385 /=-</b>		
Add 5% Above except item no 2,4 & 5					8,608 /=-	6.50% Above	60,735 /=-	6.75% Above	63,070 /=-	6.90% Above	64,472 /=-		
Add 15 % Above on item no 02					55,050 /=-								
<b>Total Amount:-</b>					<b>9,98,043 /=-</b>		<b>9,95,120 /=-</b>		<b>9,97,455 /=-</b>		<b>9,98,857 /=-</b>		

**Mr. Khan Muhammad Malik (Member)**  
Accounts Officer  
District Council Karachi

**Mr. Liaquat Ali Mughal (Member)**  
Assistant Executive Engineer  
D.M.C Malir

**Mr. Shakeel Ahmed Memon (Chairman)**  
District Engineer  
District Council Karachi