

COMPARATIVE STATEMENT

NAME OF WORK: PROVIDING INTERCONNECTION 6" DIA FROM 18" DIA PRCC WATER LINE AND REPLACEMENT OF OLD / BLOCKED 3" DIA WATER LINE WITH UPVC 3" DIA FOR IMPROVEMENT OF WATER SUPPLY IN BLOCK-02 GULBERG TOWN

S.No	Description of Work	Engineer's Estimate			M/s. S.O.H Construction Co.			M/s. Safer Enterprises	
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount
1	Dismantling Cement Concrete plain 1:4:8.	6040 Cft	1,663.75	% Cft	100,490.50	1,663.75	100,490.50	1,663.75	100,490.50
2	Dismantling and removing road metalling	2000 Cft	605.00	% Cft	12,100.00	605.00	12,100.00	605.00	12,100.00
3	Excavation for pipe lines in trenches and pits in all kind of soil of murum i/c trimming and dressing side to true alignment and shape levelling of beds of trenches to correct level and grade, cutting joint holes and disposal of surplus earth with in a one chain as directed by the engineer incharge providing fence guards, lights, flags and temporary crossings for non-vehicular traffic where ever required lift upto 5 ft (1.52m) and lead upto one chain (30.5m)								
4	Providing Laying UPVC Pipes of Class "B" fixing in trenches i/c cutting fitting and jointing with solvent cement i/c testing with water to a head 61 meter or 300 ft	32869.33 Cft	4,650.00	%0 Cft	152,842.38	4,650.00	152,842.38	4,650.00	152,842.38
	3" Dia	3020 RH	90.00	P/RH	271,800.00	88.00	265,760.00	89.00	268,780.00
	6" Dia	600 RH	259.00	P/RH	155,400.00	257.00	154,200.00	258.00	154,800.00
	4" Dia	200 RH	136.00	P/RH	27,200.00	135.00	27,000.00	134.00	26,800.00
5	Refilling the excavated stuff in trenches 6" layer i/c watering ramming to full compaction etc complete.	32731.13 Cft	2,760.00	% 0 Cft	90,337.92	2,760.00	90,337.92	2,760.00	90,337.92

Handwritten signature

Wh

Handwritten signature

2-00

NAME OF WORK: PROVIDING INTERCONNECTION 6" DIA FROM 18" DIA PRCC WATER LINE AND REPLACEMENT OF OLD /
 CHOCKED 3" DIA WATER LINE WITH UPVC 3" DIA FOR IMPROVEMENT OF WATER SUPPLY IN BLOCK-02 GULBERG TOWN

S.No	Description of Work	Engineer's Estimate				M/s. S.O.H Construction Co.		M/s. Safer Enterprises	
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount
6	Full hire charges of pumping set per day inclusive of the wages of driver and assistant, fuel and electric energy plate form required for placing the pump etc. at lower depth with suction and delivery pipe for pumping out water pound at various depth from trenches including the cost of erection and dismantling after completion of job of 10 HP pumping out water from 10 ft deep trenches.	43.00 Day	1,500.00	P/Day	64,500.00	1,450.00	62,350.00	1,475.00	63,425.00
7	C.I. sluice valve heavy pattern test pressure 21.0Kg/sq or 300 lb/sq inch (imported)	1 No	9,360.00	Each	9,360.00	9,000.00	9,000.00	9,300.00	9,300.00
	6" Dia	1 No	5,460.00	Each	5,460.00	5,400.00	5,400.00	5,450.00	5,450.00
8	Fixing of slice valve with 2 cost iron picese one flanged and other with socket including the cost of nuts bolts and rubber packing. labour etc. Complete.	1 No	1,886.00	Each	1,886.00	1,800.00	1,800.00	1,800.00	1,800.00
	6" Dia	1 No	1,532.00	Each	1,532.00	1,400.00	1,400.00	1,400.00	1,400.00
9	VIII upvc fitting (per Each) (Equivalent make) (Class "B")	5 Nos	1,446.00	Each	7,230.00	1,400.00	7,000.00	1,400.00	7,000.00
	(i) Tee	1 Nos	1,650.00	Each	1,650.00	1,650.00	1,650.00	1,650.00	1,650.00
	6" Dia	6 Nos	550.00	Each	3,300.00	500.00	3,000.00	550.00	3,300.00
	(ii) Valves Socket 'B' Class	6 Nos	175.00	Each	1,050.00	175.00	1,050.00	175.00	1,050.00
	6" Dia	1 Nos	200.00	Each	200.00	200.00	200.00	200.00	200.00
	Reducing Bush "B" Class	6 Nos	550.00	Each	3,300.00	500.00	3,000.00	550.00	3,300.00
	6" Dia	6 Nos	175.00	Each	1,050.00	175.00	1,050.00	175.00	1,050.00
	Ends Plugs "B" Class	1 Nos	200.00	Each	200.00	200.00	200.00	200.00	200.00
	3" Dia	6 Nos	175.00	Each	1,050.00	175.00	1,050.00	175.00	1,050.00
	4" Dia	1 Nos	200.00	Each	200.00	200.00	200.00	200.00	200.00

Handwritten signature and initials

Handwritten signature and initials

NAME OF WORK: PROVIDING INTERCONNECTION 6" DIA FROM 18" DIA PRCC WATER LINE AND REPLACEMENT OF OLD / CHOCKED 3" DIA WATER LINE WITH UPVC 3" DIA FOR IMPROVEMENT OF WATER SUPPLY IN BLOCK-02 GULBERG TOWN

S.No	Description of Work	Engineer's Estimate			M/s. S.O.H Construction Co.		M/s. Safeer Enterprises		
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount
10	Providing and fixing 0.9" long 3/8" thick M.S neck to existing M.S Pipe to a Split Collar tee having a total weight as mentioned against each item i/c cost of fabrication and welding the split collar tee.								
11	Weight-10,909 Kg -----6"Dia Construction of C.C block masonry chamber of 4x4x4 (inside dimantion) with 24"x24" C.I cover & frame (weight-65 Kg) fixed on RCC 1:2:4 slab 6" thick with steel 1/2" Dia main bars 06" C/C & 1/4" dia @ 8" C.C distribution bars 6" thick C.C 1:3:6 block masonry wall set in 1:6 C.M 6" thick 1:4:8 in foundation 2" thick C.C 1:2:4 flooring 1/2" thick C.Plaster 1:6 to all in side wall surface top & bottom slab outer side wall surface 1'-0" deep up to roof slab MS foot rest 5/8" dia bars every 2'-0" deep etc.	1 No	1,984.00	Each	1,984.00	1,984.00	1,984.00	1,984.00	1,984.00
12	Repair of leaking joints (external watta) on PRCC pipe of various diameter i/c the cost of execution de-watering, back filling sealing material, geny bags sand spain yain, labours, etc complete. 18" Dia	1 Nos	28,357.00	Each	28,357.00	27,000.00	27,000.00	28,000.00	28,000.00
		1 Nos	13,841.00	Each	13,841.00	13,000.00	13,000.00	13,800.00	13,800.00

Handwritten signatures and initials:
 [Signature] [Signature] [Signature]
 [Initials] [Initials] [Initials]

NAME OF WORK: PROVIDING INTERCONNECTION 6" DIA FROM 18" DIA PRCC WATER LINE AND REPLACEMENT OF OLD / CHECKED 3" DIA WATER LINE WITH UPVC 3" DIA FOR IMPROVEMENT OF WATER SUPPLY IN BLOCK-02 GULBERG TOWN

S.No	Description of Work	Engineer's Estimate			M/s. S.O.H Construction Co.		M/s. Safeer Enterprises		
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount
13	Providing and fixing split collar tee on "PRCC" pipe 18" wide fabricated with 3/8" thick M.S plate 1 1/4" wide 3/8" thick ring at central 3/4" M.S square bar on both ends 04 Nos 3/4" thick M.S flanges i/c cost of nuts, bolts, packing, labour, and sealing material etc complete. Wt=102.88 Kg 18" Dia	1 Nos	19,769.00	Each	19,769.00	19,500.00	19,500.00	19,700.00	19,700.00
	Total Quoted / Corrected Cost				970,289.80		957,064.80		964,209.80
	Say				970,290		957,065		964,210

(Abdul Jabbar Shaikh)
Accounts Officer (Central)
Member/Secretary

(Syed Fahim Akhtar Zaidi)
Chief Engineer (Central)
Member

(Saif-ul-Haque)
Additional Director Internal
Audit - KMC Member

(Abdul Rahim Khattil)
Chief Engineer (IPD), (Convener)

(Magsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member



KARACHI WATER & SEWERAGE BOARD
OFFICE OF THE CHIEF ENGINEER (IP&D)


BID EVALUATION REPORT


1	Name of Procuring Agency	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No	SPPRA Serial No.18559 I.D No. /2013
3	Tender Description/Name of Work/Item	PROVIDING INTERCONNECTION 6" DIA FROM 18" DIA PRCC WATER LINE AND REPLACEMENT OF OLD / CHOCKED 3" DIA WATER LINE WITH UPVC 3" DIA FOR IMPROVEMENT OF WATER SUPPLY IN BLOCK-02 GULBERG TOWN
4	Method of Procurement	Single Stage (One Envelop)
5	Tender Published	Through Web Site
6	Total Bid Documents Sold	02 Nos
7	Total Bid Received	02 Nos
8	Technical Bid Opening Date (if applicable)	N/A .
9	No. of Bid Technically Qualified (if applicable)	N/A .
10	Bid (s) rejected	Nil
11	Financial Bid Opening Date	28/01/2014


12 Bid Evaluation Report


S #	NAME OF FIRM OR BIDDER	COST OFFERED BY THE BIDDERS	RANKING IN TERMS OF CDST	COMPARISON WITH ESTIMATED COST	REASON FOR ACCEPTANCE/ REJECTION	REMARKS
1	M/s. S.O.H Construction Co.	Rs. 957,065/-	1st Lowest	@ 1.3629% Below	Substantially Responsive	P.O # 6578198 Dt:25-01-2014 Rs.19,500/- HBL Rizvia Society .Br
2	M/s. Safer Enterprises	Rs. 964,210/-	2nd Lowest	@ 0.6266% Below	Substantially Responsive	P.O # 6578208 Dt:27-01-2014 Rs.20,000/- HBL Rizvia Society .Br


The all concerned bidder are being informed accordingly.
The E.E Concerned for compliance of rule 45 of SPPRA 2010 M/s. S.O.H Construction Co. declared as the lowest responsive bidder by the Committee and recommended for Sanction from Competent Authority.


(Abdul Jabbar Shaikh)
Accounts Officer (Central)
Member/Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit - KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Syed Fahim Akhtar Zaidi)
Chief Engineer (Central)
Member


(Abdul Rahim Khattai)
Chief Engineer (IPD),
(Convener)