



KARACHI WATER & SEWERAGE BOARD

OFFICE OF THE CHIEF ENGINEER (IPD)

BID EVALUATION REPORT


1	Name of Procuring Agency:	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No:	SPPRA Serial No.37637 I.D No. _____
3	Tender Description/Name of Work/Item:	P/L 4", 6", 8" & 12" DIA P.E PIPE WATER LINE FOR REPLACEMENT OF DAMAGED LINE AT AJMEER PUMP AND K. ELECTRIC OFFICE IN NORTH KARACHI DIVISION
4	Method of Procurement:	Single Stage (One Envelop)
5	Tender Published:	Through SPPRA Web Site
6	Total Bid Documents Sold:	2 Nos
7	Total Bid Received:	2 Nos
8	Technical Bid Opening Date (if applicable):	N/A
9	No. of Bid Technically Qualified (if applicable)	N/A
10	Bid (s) Rejected:	NIL
11	Financial Bid Opening Date:	25-05-2018

12 BID EVALUATION REPORT


S#	Name of Firm / Bidder	COST OFFERED BY THE BIDDER	RANKING IN TERMS OF COST	COMPARISON WITH ESTIMATED COST	REASON FOR ACCEPTANCE / REJECTION	REMARKS
1	M/s.M.A Khan's Group of Const.	Rs.9,68,763/-	1 st Lowest	@0.014% Below	Pay Order and required documents are attached. P.O # 19532612 dt:22-05-2018 Rs.20,000/-from HBL Hassan Square Branch Karachi	Substantially Responsive
2	M/s.B.K Builders	Rs.9,68,880/-	2 nd Lowest	@0.002% Below	Pay Order and required documents are attached. P.O # 19532610 dt:22-05-2018 Rs.20,000/-from HBL Hassan Square Branch Karachi	Substantially Responsive


The all concerned bidders are being informed accordingly.


The E.E Concerned for compliance of Rule-45 of SPPRA 2010 M/s.M.A Khan's Group of Construction declared as the lowest responsive bidder by the Committee and recommended for sanction from Competent Authority.


(Arshad Ali)
D.A.O (District Central)
Member / Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit - KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Muhammad Ali Shaikh)
S.E (District Central-A)
Member


28/05/18
(Saleem Ahmed)
Chief Engineer (IPD)
Convener

Method of Procurement: Single Stage Single Envelope.

Name of Work: P/L 4", 6", 8" & 12" DIA P.E PIPE WATER LINE FOR REPLACEMENT OF DAMAGED LINE AT AJMEER PUMP AND K. ELECTRIC OFFICE IN NORTH KARACHI DIVISION

MINUTES OF BID OPENING MEETING.


A meeting of the procurement committee of this department was held on 25-05-2018 for opening the bids received in respect of subject NIT till deadlines of submission. The meeting was attended by all / following members of the procurement committee and the representative of bidders. (Attendance sheet is enclosed).

2. Two bidders submitted their bids till the deadline of submission.
 - i. M/s. M.A Khan's Group of Construction
 - ii. M/s. B.K Builders
3. The bids were opened at 12:00 Noon in the presence of the above mentioned participants and the rates quoted by bidders were read aloud and encircled by Chairman of the Procurement Committee.


S. No	Name of Firm	Quoted Price	Amount of Bid Security	Pay Order No. / Date
01	M/s.M.A Khan's Group of Const.	Rs.9,68,763/-	Rs.20,000/-	P.O # 19532612 dt:22-05-2018 from HBL Hassan Square Branch Karachi
02	M/s.B.K Builders	Rs.9,68,879/-	Rs.20,000/-	P.O # 19532610 dt:22-05-2018 from HBL Hassan Square Branch Karachi


4. The one bid contain cutting duly signed.
5. The committee shall examine all the bids as per the qualification / eligibility criteria provided in the bidding document and verify the documents and bid security submitted by the bidders (if required).


The meeting ended with the vote of thanks to and from the chair.


(Arshad Ali)
D.A.O (District Central)
Member / Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit - KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Muhammad Ali Shaikh)
S.E (District Central-A)
Member


25/05/18
(Saleem Ahmed)
Chief Engineer (IPD)
Convener

Method and procedure of procurement: Open Competitive Bidding (National/ International Competitive Bidding) (Single Stage–One Envelope)


Description of work: **P/L 4", 6", 8" & 12" DIA P.E PIPE WATER LINE FOR REPLACEMENT OF DAMAGED LINE AT AJMEER PUMP AND K. ELECTRIC OFFICE IN NORTH KARACHI DIVISION**

Date of Opening: 25-05-2018


BIDDERS' ELIGIBILITY/ QUALIFICATION REPORT


Eligibility/ Qualification Criteria:


S. No.	Eligibility / Qualification Criteria	Bidders' Name	
		M/s.M.A.Khan's Group of Const.	M/s.B.K Builders
1.	Registration with PEC (if applicable)	N/A	N/A
2.	NTN	Yes	Yes
3.	Sales Tax Registration (FBR)	N/A	N/A
4.	Registration with Sindh Revenue Board (SRB)	Yes	Yes
	Qualification Criteria:		
5.	Minimum three years' experience of relevant field.	Yes	Yes
6.	Turnover of at least last three years	Yes	Yes
7.	Required Bid Security is attached.	Yes	Yes
8.	Bid is signed, named and stamped by the authorized person of the firm along with Authorization letter.	Yes	Yes
9.	Any other factor deemed to be relevant by the procuring agency subject to provision of Rule-44	N/A	N/A
10.	Qualified/ disqualified	Qualified	Qualified


(Arshad Ali)
D.A.O (District Central)
Member / Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit – KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Muhammad Ali Shaikh)
S.E (District Central-A)
Member


(Saleem Ahmed)
Chief Engineer (IPD)
Convener

COMPARATIVE STATEMENT

**Name of Work: P/L 4", 6", 8" & 12" DIA P.E PIPE WATER LINE FOR REPLACEMENT OF DAMAGED LINE
AT AJMEER PUMP AND K. ELECTRIC OFFICE IN NORTH KARACHI DIVISION**

Item No	Description of Work	Estimated Cost				M/s. M.A. Khan's Group of Const.		M/s. B.K Builders		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
1	Excavation for pipe line in trenches and pits in all kind of soil of murum i/c trimming and dressing sides to correct level and grade cutting joints leveling of beds of trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by Engineer Incharge providing fence guards, lights, flags sand temporary crossing for non-vehicular traffic wherever required lift upto 5 ft (1.52 m) and lead upto one chain (30.5m).	6135.57	Cft	4650.00	%0Cft	28,530.40	4645.00	28,499.72	4650.00	28,530.40
2	Full hire charges of pumping set per day i/c of wages of driver and assistant fuel or electric energy platform for placing the pump etc at lower depth with suction and delivery pipes for pumping out water found at various depth from trenches including the cost of erection and dismantling after completion of the job. Hire charges of pumping set upto 10 HP pumping out water from 10 ft deep trench	15.00	Days	1500.00	P/Day	22,500.00	1495.00	22,425.00	1500.00	22,500.00
3	Providing Laying & Fixing in trenches i/c fitting jointing and testing etc. complete in all respect the high density Polyethylene P.E pipes (HDPE-100) for W/S conforming ISO 4427 DIN-8074-8075 B.S 3580 & PSI 3051 (PN-10).	460.00	Rft	268.00	P/Rft	123,280.00	268.00	123,280.00	268.00	123,280.00
	110MM	65.00	Rft	530.00	P/Rft	34,450.00	530.00	34,450.00	530.00	34,450.00
	160MM	30.00	Rft	833.00	P/Rft	24,990.00	833.00	24,990.00	833.00	24,990.00
	200MM	75.00	Rft	1998.00	P/Rft	149,850.00	1998.00	149,850.00	1998.00	149,850.00
	315MM									
4	P/F M.S tail piece (DHOLKI) on PRCC pipe fabricated with 3/8" thick M.S plate caulking and reduce ends 9" wide provide with 3/4" thick square bar at caulking end having a total weight as mentioned against each item includes the cost of labour and caulking and sealing material etc complete. 12" dia weight 51.810 Kgs M.S Tail Piece.	2.00	Nos	9438.00	Each	18,876.00	9437.00	18,874.00	9437.00	18,874.00
5	P/F High Density polyethylene fittings (PE-100) (Per each) equivalent make) stab end piece (9) 315mm (PN-10)	2.00	Nos	16,332.00	Each	32,664.00	16,331	32,662.00	16,332	32,664.00

QUMI
28/5/18

M.

S. Ahmed
28/05/18

S. Ahmed

**Name of Work: P/L 4", 6", 8" & 12" DIA P.F.E PIPE WATER LINE FOR REPLACEMENT OF DAMAGED LINE
AT AJMEER PUMP AND K. ELECTRIC OFFICE IN NORTH KARACHI DIVISION**

Item No	Description of Work	Estimated Cost				M/s. M.A.Khan's Group of Const.		M/s. B.K Builders		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
6	Repair of leakages on PRCC Pipe line. It includes the cost of excavation, labour, sealing material, gunny bags, de-watering and refilling of the excavation stuff etc. complete. 12" Dia	10.00	Nos	9716.00	Each	97,160.00	9715.00	97,150.00	9715.00	97,150.00
	18" Dia	4.00	Nos	13841.00	Each	55,364.00	13840.00	55,360.00	13840.00	55,360.00
7	Providing C.I Sluice Valve heavy pattern (Test Pressure 21.0 Kg/sq.com or 300 lb/sq.inch) (Imported)	2.00	Nos	5460.00	Each	10,920.00	4289.00	8,578.00	5460.00	10,920.00
	100mm 4" Dia	2.00	Nos	9360.00	Each	18,720.00	10530.00	21,060.00	9360.00	18,720.00
	150 mm 6" Dia	1.00	No	17940.00	Each	17,940.00	17940.00	17,940.00	17940.00	17,940.00
	200mm 8" Dia	1.00	No	78000.00	Each	78,000.00	78000.00	78,000.00	78000.00	78,000.00
	300mm 12" Dia									
8	Fixing of sluice valve with 2 cast iron tail pieces one end flanged & other with socket i/c the cost of nut, bolts & rubber packing, labour etc complete	2.00	Nos	1532.00	Each	3,064.00	1531.00	3,062.00	1531.00	3,062.00
	100mm 4" Dia	2.00	Nos	1886.00	Each	3,772.00	1885.00	3,770.00	1885.00	3,770.00
	150 mm 6" Dia	1.00	No	2790.00	Each	2,790.00	2790.00	2,790.00	2790.00	2,790.00
	200mm 8" Dia	1.00	No	3821.00	Each	3,821.00	3820.00	3,820.00	3821.00	3,821.00
	300mm 12" Dia									
9	Construction of C.C. block masonry chamber of size (inside dimension) with 24" x 24" C.I cover & frame Weight 65 kg fixed in RCC Slab 1:2:4: 6" thick with steel 1/2" dia bars 6" C/C bend up both way, 12" inch thick C:C: 1:3:6 block masonry 6" inch C.C 1:4:8 in foundation, 2" thick C.C 1:2:4 flooring, 1/2" thick cement plaster i/c P/F M.S footrest 5/8" bars at every 2'.0" feet deep i/c curing watering excavation refilling and disposal of surplus earth complete. Chamber 4'-0"x4'-0"x4'-0"	4.00	Nos	28357.00	Each	113,428.00	28356.00	113,424.00	28357.00	113,428.00
	6'-0"x6'-0"x6'-0"	2.00	Nos	55923.00	Each	111,846.00	55922.00	111,844.00	55923.00	111,846.00
10	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete.	6135.57	Ch	2760.00	%0Ch	16,934.17	2760.00	16,934.17	2760.00	16,934.17
	TOTAL QUOTED / CORRECTED COST					968,900		968,763		968,880

(Signature)
D.A.O (Dist. Central)
Member / Secretary

(Signature)
(Saif-ul-Haque)
Addl. Director Internal Audit
KMC - Member

(Signature)
(Masood Ahmed Shaikh)
Superintending Engineer (K.M.C)
Member

(Signature)
(Muhammad Ali Shaikh)
S.E (District Central-A)
Member

(Signature)
(Saleem Akhter)
Chief Engineer (IPD)
Converter

ATTENDANCE SHEET


FIRMS / CONTRACTORS

NAME OF WORK: P/L 4", 6", 8" & 12 DIA P.E PIPE WATER LINE FOR REPLACEMENT OF DAMAGED LINE AT AJMEER PUMP TO K-ELECTRIC OFFICE IN NORTH KARACHI DIVISION, KW&SB.

Date of Opening: 25-05-2018

Time of Opening: _____

Sr. No.: 37637

S. NO.	NAME OF CONTRACTOR	NAME OF FIRMS	SIGNATURE
01	Mr. Noorain Shah M.A. Khan's Group of Co. Ltd	Noorain Shah	
②	Amit Baidya	B.K builder	