

# ATTENDANCE SHEET



## FIRMS / CONTRACTORS

NAME OF WORK: 18" DIA CLEANING INSIDE SEWERAGE LINE COMPLETELY RESTORING ORIGINAL SLIT FREE SPACE DIA METER OF PIPE LINE BY LABOUR AND EQUIPMENT MACHNICALLY ELECTRICITY DRIVEN I.E. LIKE PULLY STEEL ROPE BUCKET DRAGGER SIZING FROM 6" TO 8" DIA TAIMOURIA POLICE PEOPLES CHORANGI.

Date of Opening: 31-08-2017

Time of Opening: 02:30 PM

Serial No.: 34176

S. NO.	NAME OF CONTRACTOR	NAME OF FIRMS	SIGNATURE
01	Raja	M/S L.S. ENTIP	
02	Anshu	M/S. Jango Associates	

Method and procedure of procurement: Open Competitive Bidding (National/ International Competitive Bidding) (Single Stage–One Envelope)


Description of work: 18" DIA CLEANING INSIDE SEWERAGE LINE COMPLETELY RESTORING ORIGINAL SILT FREE SPACE DIA METER OF PIPE LINE BY LABOUR AND EQUIPMENT MACHNICALLY ELECTRICITY DRIVEN I.E LIKE PULLY STEEL ROPE BUCKET DRAGER SIZING FROM 6" TO 8" DIA TAIMOURIA POLICE, PEOPLES CHOWRANGI

Date of Opening: 31-08-2017


**BIDDERS' ELIGIBILITY/ QUALIFICATION REPORT**


Eligibility/ Qualification Criteria:

S. No.	Eligibility / Qualification Criteria	Bidders' Name	
		M/s.Samu Associates	M/s.L.S Enterprises
1.	Registration with PEC (if applicable)	N/A	N/A
2.	NTN	Yes	Yes
3.	Sales Tax Registration (FBR)	N/A	N/A
4.	Registration with Sindh Revenue Board (SRB)	Yes	Yes
	<b>Qualification Criteria:</b>		
5.	Minimum three years' experience of relevant field.	Yes	Yes
6.	Turnover of at least last three years	Yes	Yes
7.	Required Bid Security is attached.	Yes	Yes
8.	Bid is signed, named and stamped by the authorized person of the firm along with Authorization letter.	Yes	Yes
9.	Any other factor deemed to be relevant by the procuring agency subject to provision of Rule-44	N/A	N/A
10.	Qualified/ disqualified	Qualified	Qualified

  
 (Arshad Ali)  
 D.A.O (District Central)  
 Member / Secretary

  
 (Saif-ul-Haque)  
 Additional Director Internal  
 Audit – KMC Member

  
 (Maqsood Ahmed Shaikh)  
 Superintending Engineer (KMC)  
 Member

  
 (Ghulam Muhammad Hub)  
 S.E (District Central-A)  
 Member

  
 (Saleem Ahmed)  
 Director (Design & Estimate)  
 Convener

NIT No. SPPRA Serial No.34176

Method of Procurement: Single Stage Single Envelope.

Name of Work: 18" DIA CLEANING INSIDE SEWERAGE LINE COMPLETELY RESTORING ORIGINAL SILT FREE SPACE DIA METER OF PIPE LINE BY LABOUR AND EQUIPMENT MACHNICALLY ELECTRICITY DRIVEN I.E LIKE PULLY STEEL ROPE BUCKET DRAGER SIZING FROM 6" TO 8" DIA TAIMOURIA POLICE, PEOPLES CHOWRANGI

**MINUTES OF BID OPENING MEETING.**


A meeting of the procurement committee of this department was held on 31-08-2017 for opening the bids received in respect of subject NIT till deadlines of submission. The meeting was attended by all / following members of the procurement committee and the representative of bidders. (Attendance sheet is enclosed).

2. Two bidders submitted their bids till the deadline of submission.
  - i. M/s. Samu Associates
  - ii. M/s. L.S Enterprises
3. The bids were opened at 2:30 P.M in the presence of the above mentioned participants and the rates quoted by bidders were read aloud and encircled by Chairman of the Procurement Committee.


S. No	Name of Firm	Quoted Price	Amount of Bid Security	Pay Order No. / Date
01	M/s.Samu Associates	Rs.9,60,181/-	Rs.20,000/-	P.O # 17909413 dt:05-06-2017 from HBL Taimuria Market Branch Karachi
02	M/s.L.S Enterprises	Rs.9,62,781/-	Rs.20,000/-	P.O # 17909473 dt:10-06-2017 Rs.19,000/- from HBL Taimuria Market Branch Karachi & P.O # 01613480 dt:28-08-2017 Rs.1,000/-from Bank Islami Pakistan Ltd North Nazimabad Block-A Branch, Karachi


4. The bids do not contain any cutting or over-writing.
5. The committee shall examine all the bids as per the qualification / eligibility criteria provided in the bidding document and verify the documents and bid security submitted by the bidders (if required).

The meeting ended with the vote of thanks to and from the chair.

  
Arshad Ali  
D.A.O (District Central)  
Member / Secretary

  
(Saif-ul-Haque)  
Additional Director Internal  
Audit – KMC Member

  
(Maqsood Ahmed Shaikh)  
Superintending Engineer (KMC)  
Member

  
(Ghulam Muhammad Hub)  
S.E (District Central-A)  
Member

  
31/08/17  
(Saleem Ahmed)  
Director (Design & Estimate)  
Convener



# KARACHI WATER & SEWERAGE BOARD

## OFFICE OF THE DIRECTOR (DESIGN & ESTIMATE)

### BID EVALUATION REPORT


1	Name of Procuring Agency:	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No:	SPPRA Serial No.34176 I.D No. _____
3	Tender Description/Name of Work/Item:	<b>18" DIA CLEANING INSIDE SEWERAGE LINE COMPLETELY RESTORING ORIGINAL SILT FREE SPACE DIA METER OF PIPE LINE BY LABOUR AND EQUIPMENT MACHNICALLY ELECTRICITY DRIVEN I.E LIKE PULLY STEEL ROPE BUCKET DRAGER SIZING FROM 6" TO 8" DIA TAIMOURIA POLICE, PEOPLES CHOWRANGI</b>
4	Method of Procurement:	<u>Single Stage (One Envelop)</u>
5	Tender Published:	<u>Through SPPRA Web Site</u>
6	Total Bid Documents Sold:	<u>2 Nos</u>
7	Total Bid Received:	<u>2 Nos</u>
8	Technical Bid Opening Date (if applicable):	<u>N/A</u>
9	No. of Bid Technically Qualified (if applicable)	<u>N/A</u>
10	Bid (s) Rejected:	<u>NIL</u>
11	Financial Bid Opening Date:	31-08-2017

### 12 BID EVALUATION REPORT

S #	Name of Firm / Bidder	COST OFFERED BY THE BIDDER	RANKING IN TERMS OF COST	COMPARISON WITH ESTIMATED COST	REASON FOR ACCEPTANCE / REJECTION	REMARKS
1	M/s.Samu Associates	Rs.9,60,181/-	1 <sup>st</sup> Lowest	@0.135% Below	Pay Order and required documents are available. P.O # 17909413 dt:05-06-2017 Rs.20,000/-from HBL Taimuria Market Branch Karachi	Substantially Responsive
2	M/s.L.S Enterprises	Rs.9,62,781/-	2 <sup>nd</sup> Lowest	@0.135% Above	Pay Order and required documents are available. P.O # 17909473 dt:10-06-2017 Rs.19,000/-from HBL Taimuria Market Branch Karachi & P.O # 01613480 dt:28-08-2017 Rs.1,000/- Total Rs.20,000/- from Bank Islami Pakistan Ltd. North Nazimabad Block-A Branch, Karachi	Substantially Responsive


The all concerned bidders are being informed accordingly.

The E.E Concerned for compliance of Rule-45 of SPPRA 2010 **M/s.Samu Associates** declared as the lowest responsive bidder by the Committee and recommended for sanction from Competent Authority.

  
(Ghulam Muhammad Hub)  
S.E (District Central-A)  
Member

(Ghulam Muhammad Hub)  
S.E (District Central-A)  
Member

  
(Saif-ul-Haque)  
Additional Director Internal  
Audit – KMC Member

  
(Maqsood Ahmed Shaikh)  
Superintending Engineer (KMC)  
Member

  
(Saleem Ahmed)  
Director (Design & Estimate)  
Convener

## COMPARATIVE STATEMENT

Name of Work: 18" DIA CLEANING INSIDE SEWERAGE LINE COMPLETELY RESTORING ORIGINAL SILT FREE SPACE  
DIA METER OF PIPE LINE BY LABOUR AND EQUIPMENT MACHNICALLY ELECTRICITY DRIVEN I.E LIKE PULLY  
STEEL ROPE BUCKET DRAGER SIZING FROM 6" TO 8" DIA TAIMOURIA POLICE, PEOPLES CHOWRANGI

Item No	Description of Work	Estimated Cost				M/s.Samu Associates		M/s.L.S Enterprises		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
1	Cleaning inside Sewerage line completely restoring original silt free space / diameter of pipe lines by labour and equipment (Mechanically / Electrically driven). Including accessories like pulley's steel rope, buckets and draggers sizing from 6" to 18" dia their "to and fro" pulling action (No of passes shall be as many as required) would be undertaken in two phases (First phase entire length from down stream to up stream) bringing down peak hours sewage to flow inside pipe line (as free flow) and in 2nd phase from up stream to down stream of entire length using no silt to observed in bucket (6" dia to 18" dia) except only sewage water finally passing a ball of 12" lesser then the diameter of pipe but no exceeding 48" dia ball even for larger dia pipe to ensure perfect cleaning. The job including all the hire / cost of equipment and accessories of above wincing machine / devises alongwith / Engine with winching drum set having, steel rope pulley mounted over it, steel bucket 6" to 18" dia hocks and other protection like safety barriers, traffic signs, traffic cones ensuring no damages to pipe line alongwith ensuring safety to labourand other public property / lives and removla of silts / solid during desilting and clearance of site etc complete as per full satisfaction of site Engineer. 18" dia	3000.00	Rft	128.80	P/Rft	386,400.00	128.80	386,400.00	128.80	386,400.00
2	Dismantling and removing road matling	600.00	Cft	605.00	%Cft	3,630.00	605.00	3,630.00	605.00	3,630.00
3	Excavation for pipe line in trenches and pits in all kind of soil of murum i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by Engineer Incharge providing fence guards, lights, flags sand temporary crossing for non-vehicular traffic wherever required lift upto 5 ft (1.52 m) and lead upto one chain (30.5m). i) Lift 0' - 5'ft	6000.00	Cft	4650.00	%0Cft	27,900.00	4650.00	27,900.00	4650.00	27,900.00
	ii) Lift upto 05' - 08'	3600.00	Cft	5200.00	%0Cft	18,720.00	5200.00	18,720.00	5200.00	18,720.00
	iii) Lift upto 08' - 11'	3600.00	Cft	5750.00	%0Cft	20,700.00	5750.00	20,700.00	5750.00	20,700.00
	iv) Lift upto 11' - 14'	3200.00	Cft	6300.00	%0Cft	20,160.00	6300.00	20,160.00	6300.00	20,160.00

05/9/17

**Name of Work: 18" DIA CLEANING INSIDE SEWERAGE LINE COMPLETELY RESTORING ORIGINAL SILT FREE SPACE  
DIA METER OF PIPE LINE BY LABOUR AND EQUIPMENT MACHNICALLY ELECTRICITY DRIVEN I.E LIKE PULLY  
STEEL ROPE BUCKET DRAGER SIZING FROM 6" TO 8" DIA TAIMOURIA POLICE, PEOPLES CHOWRANGI**

Item No	Description of Work	Estimated Cost				M/s.Samu Associates		M/s.L.S Enterprises		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
4	Full hire charges of pumping set per day i/c of wages of driver and assistant fuel or electric energy platform for placing the pump etc at lower depth with suction and delivery pipes for pumping out water found at various depth from trenches including the cost of erection and dismantling after completion of the job. Hire charges of pumping set upto 10 HP pumping out water from 10 ft deep trench	20.00	Days	1500.00	P/Day	30,000.00	1450.00	29,000.00	1550.00	31,000.00
5	Providing & Laying of RCC Pipes with Rubber Ring Joint and fitting in trench including cutting, fitting, jointing with rubber ring i/c testing with water to specified pressure. 18" Dia	300.00	Rft	539.00	P/Rft	161,700.00	538.00	161,400.00	540.00	162,000.00
6	Providing manhole 4' feet internal diameter without RCC manhole cover with C.I. Frame (15 KG) and 5 feet clear depth cast in situ with 1:2:4 CC in 9" thick wall, 1:4:8: C.C in 6ft dia and 6" inch thick in foundation 1:2:4 C.C in benching 12" thick cement plastering with 1:3 C.M on all inside wall surfaces, channel and benching i/c making required nos of main and branch channels, 3/4" dia m.s foot rest @12" c/c i/c cost of excavation in all kinds of soil, backfilling and disposal of excavated stuff etc complete as per design and instruction of E/Incharge.	4.00	Nos	14529.29	Each	58,117.16	14529.29	58,117.16	14529.29	58,117.16
7	Extra for depth beyond 5' depth, if less then 5' deduction will be made at the same rate.	34.00	(+)Rft	2538.62	P/Rft	86,313.08	2538.62	86,313.08	2538.62	86,313.08
8	Making connection with the existing manhole including the cost of cutting hole in wall, making them good in C.C 1:2:4 and making the required channel etc. complete	6.00	Nos	180.00	Each	1,080.00	180.00	1,080.00	180.00	1,080.00
9	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete.	16400.00	Cft	2760.00	%0Cft	45,264.00	2760.00	45,264.00	2760.00	45,264.00
10	Manufacturing and supplying of 21" inch dia RCC Manhole Covers cast in 1:2:4 cement concrete ratio 3" inch deep at centre rein-forced with 1/2" dia M.S tor bars with 4" c/c welded to a 3/16" thick 2" wide M.S Plate and two hook of 3/8" dia tor bars including compacting, curing and transportation within 10 miles etc 21" Dia	30.00	Nos	913.63	Each	27,408.90	913.63	27,408.90	913.63	27,408.90

*[Handwritten signatures and dates]*  
 05/9/17

**Name of Work: 18" DIA CLEANING INSIDE SEWERAGE LINE COMPLETELY RESTORING ORIGINAL SILT FREE SPACE  
DIA METER OF PIPE LINE BY LABOUR AND EQUIPMENT MACHNICALLY ELECTRICITY DRIVEN I.E LIKE PULLY  
STEEL ROPE BUCKET DRAGER SIZING FROM 6" TO 8" DIA TAIMOURIA POLICE, PEOPLES CHOWRANGI**

Item No	Description of Work	Estimated Cost				M/s.Samu Associates		M/s.L.S Enterprises		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
11	Manufacturing and supplying of RCC Ring Slab of 21" dia (inside) and 36" dia outside 7.5" width and 6" thick i/c 3/8" dia tor steel bars two concentric rings with 3/8" dia 8 Nos cross linked bars welded and two sunk type hooks, casted in 1:1 1/2" 3 concrete with embedded 15 Kg C.I Frame in perfect position i/c transportation charges for an average lead of 20 Km per trip from casting yard to town office. (A minimum of 25 slabs per trip will be transported.	30.00	Nos	1906.60	Each	57,198.00	1906.60	57,198.00	1906.60	57,198.00
12	Shifting to the site and fixing 36" dia ring slab in perfect position on damaged manhole i/c cutting of the position of damaged mnahole in proper shape laying in layer of C.M in 2" thickness and disposal of the debris.	30.00	Nos	563.09	Each	16,892.70	563.00	16,890.00	563.00	16,890.00
<b>TOTAL QUOTED / CORRECTED COST</b>						<b>961,484</b>		<b>960,181</b>		<b>962,781</b>

*Arshad Ali*  
05/9/17  
(Arshad Ali)  
D.A.O (Distt. Central)  
Member / Secretary

*(Saif-ul-Haque)*  
Addl. Director Internal Audit  
KMC - Member

*(Maqsood Ahmed Shaikh)*  
Superintending Engineer (K.M.C)  
Member

*(Ghulam Muhammad Hub)*  
S.E (District Central-A)  
Member

*(Saleem Ahmed)*  
05/9/17  
Director (Design & Estimate)  
Convener