



KARACHI WATER & SEWERAGE BOARD

OFFICE OF THE CHIEF ENGINEER (IP&D)


BID EVALUATION REPORT


1	Name of Procuring Agency	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No	SPPRA Serial No.18120 I.D No. /2013
3	Tender Description/Name of Work/Item	REPLACEMENT OF DAMAGED AND BROKEN & UNSERVICEABLE SEW LINE BY 12" DIA & 8" DIA RCC PIPE & MANUFACTURING AND SUPPLYING OF 21" DIA RCC MANHOLE COVERS IN SECTOR 51-C HASRAT MOHAN COLONY, UC NO:09 KORANGI DIVISION.
4	Method of Procurement	Single Stage (One Envelop)
5	Tender Published	Through Web Site
6	Total Bid Documents Sold	03 Nos
7	Total Bid Received	03 Nos
8	Technical Bid Opening Date (if applicable)	N/A .
9	No. of Bid Technically Qualified (if applicable)	N/A .
10	Bid (s) rejected	One
11	Financial Bid Opening Date	20/12/2013


12 Bid Evaluation Report


S #	NAME OF FIRM OR BIDDER	COST OFFERED BY THE BIDDERS	RANKING IN TERMS OF COST	COMPARISON WITH ESTIMATED COST	REASON FOR ACCEPTANCE/ REJECTION	REMARKS
1	M/s. Razi Associates	Rs. 999,421/-	1st Lowest	@ 0.0009% Below	Substantially Responsive	P.O # 9797507 Dt: 17-12-2013 Rs 20,000/- HBL University Road Br
2	M/s. Raheel Enterprises	Rs. 999,878/-	2nd Lowest	@ 0.0448% Above	Substantially Responsive	P.O # 07046817 Dt: 30-10-2013 Rs 20,000/- HMBL Paposh Nagar Br
3	M/s. The S.S Contractor	Not Quoted				


The all concerned bidder are being informed accordingly.
The E.E Concerned for compliance of rule 45 of SPPRA 2010 M/s. Razi Associates. declared as the lowest responsive bidder by the Committee and recommended for Sanction from Competent Authority.


(Zafar Javed)
Accounts Officer (L/K)
Member/Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit - KMC Member







(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Jameel Akhtar)
Chief Engineer (L/K)
Member


(Abdul Rahim Khattai)
Chief Engineer (IPD),
(Convener)

**COMPARATIVE STATEMENT
 NAME OF WORK: REPLACEMENT OF DAMAGED AND BROKEN & UNSERVICEABLE SEW LINE BY 12" DIA & 8" DIA RCC PIPE
 & MANUFACTURING AND SUPPLYING OF 21" DIA RCC MANHOLE COVERS IN SECTOR 51-C HASRAT MOHAN COLONY, UC
 NO:09 KORANGI DIVISION.**

S.No	Description of Work	Engineer's Estimate				M/s. Razi Associates		M/s. Raheel Enterprises	
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount
		560 Sft	116.16	%Sft	650.50	116	649.6	116.00	649.6
1	Scarifying the existing road surface. Excavation for pipe lines in trenches and pits in all wet soils clay or mud i/c trimming and dressing side to true alignment and shape levelling of beds of trenches to correct level and grade, cutting joint holes and disposal of surplus earth with in a one chain as directed be engineer incharge providing fence guards, lights, flags and temporary crossings for non-vehicular traffic where ever required lift upto 5 ft (1.52m) and lead upto one chain (30.5m).	17850 Cft	4,650.00	% 0 Cft	83,002.50	4650	83,002.50	4,650.00	83,002.50
3	Excavation for pipe lines in trenches and pits in wet soils clay or mud i/c trimming and dressing side to true alignment and shape levelling of beds of trenches to correct level and grade, cutting joint holes and disposal of surplus earth with in a one chain as directed be engineer incharge providing fence guards, lights, flags and temporary crossings for non-vehicular traffic where ever required lift upto 5 ft (1.52m) and lead upto one chain (30.5m). 5" to 8"	4500 Cft	5,950.00	% 0 Cft	26,775.00	5950	26,775.00	5,952.00	26,784.00


NAME OF WORK: REPLACEMENT OF DAMAGED AND BROKEN & UNSERVICEABLE SEW LINE BY 12" DIA & 8" DIA RCC PIPE & MANUFACTURING AND SUPPLYING OF 21" DIA RCC MANHOLE COVERS IN SECTOR 51-C HASRAT MOHAN COLONY, UC NO:09 KORANGI DIVISION.


S.No	Description of Work	Engineer's Estimate			M/s. Razi Associates		M/s. Raheel Enterprises		
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount
		4	Full hire charges of pumping set i/c wages of driver and Assistant fuel or electric energy plate form required for placing or at lower depths with suction and delivery pipes for pumping and water found at various depth form trenches i/c cost of erection and dismantling after completion of the job. (i) Hire charges of pumping set of upto 10 H.P pumping out water for 10 feet deep trench	20 Day	1,500.00	P/Day	30,000.00	1,500.00	30,000.00
5	Providing, Laying RCC pipes with rubber ring joint and fitting in trenches i/c cutting, fitting and jointing with rubber ring i/c testing with water to specified pressure.	750 Rft	367.00	P/Rft	275,250.00	367.00	275,250.00	367.50	275,625.00
	12" Dia	228 Rft	206.00	P/Rft	46,968.00	206.00	46,968.00	206.00	46,968.00
6	Providing Manholes 4' ft dia (inside) with C.I Frame 15KG 5' ft clear depth 1:2.4 cast in situ in 9" thick wall 1:4.8 cement concrete in 6ft dia and 6" inch thick in foundation, 1:2.4 C in benching 1/2" cement plaster 1:3 cement mortar on inside wall and surface of channel benching i/c making required was of channels 3/4" inch bar M.S foot rest @ 12" C/c including cost of excavation of all kind, back filling and disposal of excavated staff etc complete as per designed extretion of the Engineer Incharge	24 Nos	14,529.29	Each	348,702.96	14,529.25	348,702.00	14,515.00	348,360.00
7	Add for extra depth beyond 5' deduct at the same rate.	32 Rft	2,538.62	P/Rft	81,235.84	2,538.60	81,235.20	2,538.00	81,216.00


[Handwritten Signature]

NAME OF WORK: REPLACEMENT OF DAMAGED AND BROKEN & UNSERVICEABLE SEW LINE BY 12" DIA & 8" DIA RCC PIPE & MANUFACTURING AND SUPPLYING OF 21" DIA RCC MANHOLE COVERS IN SECTOR 51-C HASRAT MOHAN COLONY, UC NO:09 KORANGI DIVISION.


S.No	Description of Work	Engineer's Estimate			M/s. Razi Associates		M/s. Raheel Enterprises		
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount
		8	Manufacturing and supplying of 21" diameter RCC Manhole cover cast in 1:2:4 cement concrete 3" deep at centre reinforced with 1/2" dia M.S bars with 4" c/c welded to 3/16" thick 2" wide M.S plate and two hook of 3/8" dia tor bars i/c compacting, curing & transportation within 10 miles. 21" Dia	51 Nos	913.63	Each	46,595.13	913.50	46,588.50
9	Making Connections with the existing manhole i/c the cost of cutting hole in wall, making them good in CC 1:2:4 and making required channel etc. complete.	8.00 Nos	180.00	Each	1,440.00	180.00	1,440.00	175.00	1,400.00
10	Filling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete	*21308 Cft	2,760.00	% 0 Cft	58,810.08	2,760.00	58,810.08	2,760.00	58,810.08
Total Quoted / Corrected Cost					999,430.01		999,420.88		999,878.18
Say					999,430		999,421		999,878


(Zafar Javed)
 Accounts Officer (L/K)
 Member/Secretary


(Saif-ul-Haque)
 Additional Director Internal
 Audit - KMC Member


(Maqsood Ahmed Shaikh)
 Superintending Engineer (KMC)
 Member


(Jameel Akhtar)
 Chief Engineer (L/K)
 Member


(Abdul Rahim Khattai)
 Chief Engineer (IPD),
 (Convener)