

OFFICE OF THE EXECUTIVE ENGINEER DRAINAGE DIVISION L.B.O.D SHAHEED BENAZIRABAD

No. AC/ G-55/ 180 /2018
Dated: - 13/02 /2018

To,

**M/S Sonari Construction Company,
Govt. Contractor,
House # 246, Ghulam Hyder Shah Colony,
Nawabshah.**

SUBJECT: REPLACEMENT OF DISPOSAL CHANNEL OF PUMPING STATION AND TUBEWELLS AT VILLAGE AYOUB KHAN RIND, UC WALI MUHAMMAD RIND, TALUKA NAWABSHAH, IN DRAINAGE DIVISION LBOD, SHAHEED BENAZIRABAD IN ADP SCHEME NAMEDLY CONSTRUCTION OF PUMPING STATION FOR DISPOSAL OF SIM WATER IN DEH DURMA, TALUKA TANDO ADAM (ADP NO. 1087/2017-18).

WORK ORDER / LETTER OF COMMENCEMENT

The contract agreement (stamp duty paid) for the said work received from your side, has been accepted. Your Bid for the subject work which is already approved by competent authority vide No. CEI/DEV/WB/4308, dated 30.11.2017, for the accepted amount of equivalent Pak Rs. 49,077,175/- (Rupees Forty Nine Million Seventy Seven Thousand One Hundred Seventy Five Only).

You are advised to commence / start the work at the site within (07) Seven days of issuance of this letter of commencement & complete the said work within (22) Twenty Two months at your own risk and cost in the interest of Government. The payment will be made on availability of funds and measurement recorded by Assistant Executive Engineer concerned. The work will be carried out as per PWD specifications. No Carriage of material will be paid separately.

It is further directed to work under the direction of Assistant Executive Engineer, Drainage Sub-Division-I, Nawabshah. Please acknowledge the receipt of this letter.

(Abdul Sattar Sario)
Executive Engineer
Drainage Division LBOD
Shaheed Benazirabad

CC to:

- The Chief Engineer, Irrigation Development in Sindh, Hyderabad for information.
- The Project Director, SCARP, North Rohri, Shaheed Benazirabad for information.
- ✓ The Managing Director, Sindh Public Procurement Regulatory Authority, Karachi.
- The Assistant Executive Engineer, Drainage Sub-Division-I, Nawabshah with the directions to get the works to be executed as per specifications. He is further directed that the date of start and completion of the work may be intimated to this office accordingly. The progress report may also please be communicated regularly.

OFFICE OF THE EXECUTIVE ENGINEER DRAINAGE DIVISION LBOD SHAHEED BENAZIRABAD

No. AC/ G-55/ 180 /2018

Dated: - 13 / 02 /2018

To,

M/S Sonari Construction Company,
Govt. Contractor,
House # 246, Ghulam Hyder Shah Colony,
Nawabshah.

SUBJECT: REPLACEMENT OF DISPOSAL CHANNEL OF PUMPING STATION AND TUBEWELLS AT VILLAGE AYOUB KHAN RIND, UC WALI MUHAMMAD RIND, TALUKA NAWABSHAH, IN DRAINAGE DIVISION LBOD, SHAHEED BENAZIRABAD IN ADP SCHEME NAMEDLY CONSTRUCTION OF PUMPING STATION FOR DISPOSAL OF SIM WATER IN DEH DURMA, TALUKA TANDO ADAM (ADP NO. 1087/2017-18).

WORK ORDER / LETTER OF COMMENCEMENT

The contract agreement (stamp duty paid) for the said work received from your side, has been accepted. Your Bid for the subject work which is already approved by competent authority vide No. CEI/DEV/WB/4308, dated 30.11.2017, for the accepted amount of equivalent Pak Rs. 49,077,175/- (Rupees Forty Nine Million Seventy Seven Thousand One Hundred Seventy Five Only).

You are advised to commence / start the work at the site within (07) Seven days of issuance of this letter of commencement & complete the said work within (22) Twenty Two months at your own risk and cost in the interest of Government. The payment will be made on availability of funds and measurement recorded by Assistant Executive Engineer concerned. The work will be carried out as per PWD specifications. No Carriage of material will be paid separately.

It is further directed to work under the direction of Assistant Executive Engineer, Drainage Sub-Division-I, Nawabshah. Please acknowledge the receipt of this letter.

(Abdul Sattar Sario)
Executive Engineer
Drainage Division LBOD
Shaheed Benazirabad

CC to:

- The Chief Engineer, Irrigation Development in Sindh, Hyderabad for information.
- The Project Director, SCARP, North Rohri, Shaheed Benazirabad for information.
- The Managing Director, Sindh Public Procurement Regulatory Authority, Karachi.
- The Assistant Executive Engineer, Drainage Sub-Division-I, Nawabshah with the directions to get the works to be executed as per specifications. He is further directed that the date of start and completion of the work may be intimated to this office accordingly. The progress report may also please be communicated regularly.

CONTRACT AGREEMENT

THIS CONTRACT AGREEMENT (hereinafter called the "Agreement") made on the 12th Feb'2018 in between Executive Engineer, Drainage Division LBOD, Shaheed Benazirabad (hereafter called the "Procuring Agency") of the one part and M/S SONARI CONSTRUCTION COMPANY. Govt. Contractor (hereafter called the "Contractor") of the other part.

WHEREAS the Procuring Agency is desirous that certain works, REPLACEMENT OF DISPOSAL CHANNEL OF PUMPING STATIONS AND TUBEWELLS AT VILLAGE AYOUB KHAN RIND, UC WALI MUHAMMAD RIND, TALUKA NAWABSHAH, IN DRAINAGE DIVISION LBOD, SHAHEED BENAZIRABAD IN ADP SCHEME NAMEDLY CONSTRUCTION OF PUMPING STATION FOR DISPOSAL OF SIM WATER IN DEH DURMA, TALUKA TANDO ADAM (ADP NO. 1087/2017-18) should be executed by the Contractor and has accepted a bid by the Contractor for the execution and completion of such works and the remedying of any defects therein.

NOW this Agreement witness as follows:

1. In this Agreement words and expressions shall have the same meanings as are respectively assigned to them in the Conditions of Contract hereinafter referred to.
2. The following documents after incorporating addenda, if any, except those parts relating to Instructions to bidders shall be deemed to form and be read and construed as part of this Agreement, viz:
 - (a) The Letter of Acceptance;
 - (c) The completed Form of Bid along with Schedules to Bid;
 - (c) Conditions of Contract & Contract Data;
 - (d) The priced Schedule of Prices / Bill of Quantities
 - (e) The Specifications; and.
 - (f) The Drawings
3. In consideration of the payments to be made by the procuring agency to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the

Stamps Issued on
D/2 Month 2 Year 2018

12/2/18

procuring agency to execute and complete the works and remedy defects therein in conformity and in all respects with the provisions of the contract.

4. Procuring agency hereby covenants to pay the contractor, in consideration of the execution and completion of the works as per provisions of the contract, the contract Price or such other sum as may become payable under the provisions of the contract at the times and in the manner prescribed by the contract.

IN WITNESS WHEREOF the parties hereto have caused this Agreement to be executed on the day, month and year first before written in accordance with their respective laws.


M/S SONARI
Signature of the Contractor
Construction Company

(Seal)


Signature of Procuring Agency

ABDUL SATTAR SARIO
Executive Engineer
Drainage Division L.B.O.D
Shaheed Benazirabad

Signed, Sealed and Delivered in the presence of:


Witness:

45402-4327977-1

Witness:


(ANWAR BAIG)

Divisional Accounts Officer
Drainage Division LBOD
Shaheed Benazirabad

NAME OF SCHEME :-

"CONSTRUCTION OF PUMPING STATION FOR DISPOSAL OF SIM WATER IN DEH DURMA,
TALUKA TANDO ADAM (ADP NO. 1087/2017-18)"

NAME OF WORK :-

"REPLACEMENT OF DISPOSAL CHANNEL OF PUMPING STATIONS AND TUBEWELLS AT
VILLAGE AYOUB KHAN RINDH, UC WALI MUHAMMAD RIND, TALUKA NAWABSHAH, IN
DRAINAGE DIVISION LBOD, SHAHEED BENAZIRABAD"

Bill No.	Description	Amount
1	Construction of Pumping Station (02 Pumps)	9,069,320/-
2	Earth Work for New Leading Channel/Drain	1,22,48,591/-
3	Construction of Village Road Culverts over leading channel.	9,86,56,841/-
4	Construction of Watercourse Aqueduct over leading Channel / Drain	18,78,188/-
5	Construction of Box Culvert (Small Size)	5,19,407/-
6	Construction of Packa Disposal Channel	3,83,78,831/-
7	Construction of Direct Disposal Channel	1,37,60,338/-
Total amount (in words) :-		40,55,681/-
Add 22.75% above on schedule items Rs 2		8,92,14,941/-
Forty nine million Seventy Seven thousand one hundred		49,07,77,751/-
Seventy five only -		

(Signature)

M/S SONARI
Construction Company

NAME OF
SCHEME:-

"REPLACEMENT OF DISPOSAL CHANNEL OF PUMPING STATIONS AND TUBEWELLS AT VILLAGE AYOUB KHAN RINDH, UC WALI MUHAMMAD RIND, TALUKA NAWABSHAH, IN DRAINAGE DIVISION LBOD, SHAHEED BENAZIRABAD"

NAME OF
WORK:-


BILL NO. 1:- CONSTRUCTION OF PUMPING STATION (02 PUMPS)

ABSTRACT SHEET


Sr. No.	Description	Qty	Rate	Unit	Amount
1	Excavation in foundation of buildings, bridges and other structures i/c dag, belling dressing, refilling around structure with excavated earth watering and ramming lead up to one chain and lift up to 5ft: b) In ordinary soil. (GSS-2012, P-4, Item-18)(b)	104,625 Cft ✓	3,176.25 ✓	%0 Cft ✓	332,315 ✓
2	Extra for wet earth work. (GSS-2012, P-3, Item-15)	83,700 Cft ✓	1,058.75 ✓	%0 Cft ✓	88,617 ✓
3	Rehandling of earth work. b) Up to lead of 50 ft: (GSS\2012, P-3, Item-9(b). (02 Times)	94,163 Cft ✓	2,117.50 ✓	%0 Cft ✓	199,389 ✓
4	Cement concrete plain i/c placing compacting, finishing and curing complete (i/c screening and washing of stone aggregate without shuttering). i) Ratio 1:4:8. (GSS-2012, P-15, Item-56(i).	1,649 Cft ✓	11,288.75 ✓	% Cft ✓	186,095 ✓
5	Erection and removal of centering for R.C.C or plain cement concrete works of partial wood (2nd class) a) Vertical. (GSS-2012, P-17, Item-19(a).	305 Sft: ✓	3,127.41 ✓	% Sft: ✓	9,523 ✓
6	Reinforced cement concrete work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms, molds, lifting shuttering, curing, rendering and finishing and exposed surface (i/c screening and washing of shingle). a) R.C work in roof, slab, beams, columns, rafts, lintels and other structural members laid in site or precast laid in position. i) Ratio 1:2:4 90Lbs: cement sand 4Cft shingle 1/8" to 1/4" . (GSS-2012, P-16, Item-6)(i)	5,026 Cft ✓	337.00 ✓	P. Cft ✓	1,693,902 ✓

Sr. No.-	Description	Qty	Rate	Unit	Amount
7	Fabrication of mild steel reinforcement for cement concrete i/c cutting, bending laying in position making joints and fastenings i/c cost of binding wire (also includes removal of rust from bars (b) using Tar Bars. (GSS-2012, P-16, Item-8(b))	314.151 Cwt: ✓	5,001.70 ✓	P.Cwt:	1,571,289 ✓
8	Pacca bricks work other than building i/c sticking of joints upto 20 ft. height in cement sand mortar 1:5 (GSS-2012, P-21, I-7(d))	671 Cft ✓	12,574.38 ✓	% Cft	84,402 ✓
9	Cement Plaster 1:6 up to 20' height. b) 3/4" thick (GSS-2012, P-58, Item-13 (c)).	1,310 Sft: ✓	2,590.50 ✓	% Sft:	33,936 ✓
10	Cement Plaster 1:2 up to 20' height. b) 1/2" thick. (GSS-2012, P-51, Item-10(b)).	1,310 Sft: ✓	2,344.59 ✓	% Sft:	30,714 ✓
11	White washing. (c) Three coats. (GSS-2012, P-53, Item-26(c)).	1,310 Sft: ✓	829.95 ✓	% Sft:	10,872 ✓
12	Distemping (c) Three coats. (GSS-2012, P-53, Item-24(c)).	1,310 Sft: ✓	1,079.65 ✓	% Sft	14,143 ✓
13	Supplying and fixing steel grated door with 1/16" thick sheeting i/c angle iron frame 2"x2"x3/8" and 3/4" square bars 4" c/c with locking arrangement. (GSS-2012, P-91, Item-24).	108 Sft: ✓	726.72 ✓	P.Sft:	78,486 ✓
14	Painting new surfaces:- (c) preparing surface and painting doors and windows any type (including edges). Three Coats. (GSS-2012, P-69, Item-5(c)).	216 Sft: ✓	2,116.41 ✓	% Sft:	4,571 ✓
15	Supplying and fixing in position iron steel grill of 4"x1/4" size flat iron of approved design i/c painting 3 coats etc. complete weight not be less than 3-7Lbs:/Sq: of finishing grill. (GSS-2012, P-92, Item-26).	216 Sft: ✓	180.50 ✓	P.Sft:	38,988 ✓
16	Boring for Tubewell in all water bearing, soils from ground level up to 100' or 30.50 meter depth i/c sinking and with drawing. (a) 200 mm. (8" dia). (PHES-2012, P-41, Item-1) (a)	800 Rft: ✓	535.00 ✓	P.Rft:	428,000 ✓
17	Supplying M.S bail plug (PHES-2012, part-VI, Vol-IV 2012, P-43 Item 8(b)).	10 Nos. ✓	2,607.00 ✓	Each	26,070 ✓


 EXECUTIVE ENGINEER
 Drainage Division LBOD


M/S SONARI
Construction Company

Sr. No.	Description	Qty	Rate	Unit	Amount
18	Supplying and fixing local make coir stainer of approved quality complete. (b) for 150 mm. (6" dia). (PHES-2012, P-44, Item-10(b)).	300 Rft: ✓	647.00 ✓	P.Rft:	194,100 ✓
19	Supplying and installing M.S blind pipe 3/16" thick (5 mm.) of best and approved quality and make including necessary socket etc. complete. (d) for 150 mm. (6" dia) blind pipe. (PHES-2012, P-44, Item-11(b)).	500 Rft: ✓	762.50 ✓	P.Rft:	381,250 ✓
20	Full hire charges of pumping set per day inclusive of the wages of driver and assistant fuel or electric energy plate form required for placing pumps etc. at lower depths with suction and delivery pipes for pumping out water found at various depths from trenches including the cost of erection and dismantling after completion of the job. (iii) Hire charges of pumping set above 10 H.P pumping out water from 20' deep trench. (PHES-2012, P-77, Item-23- (ii)).	720 Days ✓	2,000.00 ✓	P.Day	1,440,000 ✓
21	NOTE:- For working the pump beyond 8 hours the following payment shall be made, the higher of the pumping set it self being for 24 hours. (i) For pumping set of above 10 H.P. (PHES-2012, P-44, Item-23(i) Note).	8,640 Hours ✓	250.00 ✓	P.Hour	2,160,000 ✓
22	Barrow pit excavation undressed lead up to 100'. (a) Ordinary soil. (GSS-2012, P-1, Item-3(a)).	22,500 Cft ✓	2,117.50 ✓	%0Cft	47,644 ✓
23	Dressing and Leveling of earth work to designed section etc complete GSS-2012, P-3, I-11 (b)	22,500 Cft ✓	187.55 ✓	%0Cft	4,220 ✓
24	Wiring for plug point with 1/1.13 (3/029) PVC insulated wire in 20 mm. (3/4") PVC conduit on surface as required. (Electric Schedule-2012, P-2, Item-12).	6 Points ✓	669.00 ✓	P.Point	4,014 ✓
25	Wiring for light or fan with 3/0 PVCE ins, wire 3/4" PVC conduct released wall or col. As required (GSS-2012, P-15, I- 124 Electrical	6 Points ✓	1,130.00 ✓	P.Point	6,780 ✓
Total Amount (Rs:-)					9,069,320 ✓


 EXECUTIVE ENGINEER
 Division I BOD


M/S SONARI
Construction Company

NAME OF
SCHEME:-


"REPLACEMENT OF DISPOSAL CHANNEL OF PUMPING STATIONS AND
TUBEWELLS AT VILLAGE AYOUB KHAN RINDH, UC WALI MUHAMMAD
RIND, TALUKA NAWABSHAH, IN DRAINAGE DIVISION LBOD, SHAHEED
BENAZIRABAD"

NAME OF
WORK:-

BILL NO. 02:- EARTH WORK FOR NEW LEADING CHANNEL/DRAIN

ABSTRACT SHEET

Sr. No.	Description	Qty	Rate	Unit	Amount
1	Barrow pit excavation undressed lead up to 100'. (a) ordinary soil. (GSS-2012, V-III, Part-II P-01, Item-03(a).	104,625 Cft: ✓	2,117.50 ✓	%0 Cft:	221,543 ✓
2	Carriage of 100 cft / 05 Tons of all materials like stone, aggregate, spawl, surkhi, etc (carriage 01 Mile) Schedule of Carriage P-1, Item-I	52,313 Cft: ✓	407.00 ✓	%Cft:	212,912 ✓
3	Earth work excavation in Irrigation Channels, Drains etc Dressed to designed section (a) Ordinary Soil. (GSS-2012, P-01, Item-05 (a).	230,175 Cft: ✓	2,420.00 ✓	%0 Cft:	557,024 ✓
4	Extra for wet earth work. (GSS-2012, P-03, Item-15.)	161,123 Cft: ✓	1,058.75 ✓	%0 Cft:	170,588 ✓
5	Dressing and leveling of earth work to designed section etc complete in Ordinary soil. (GSS-2012, P-3, Item- 11 (b)	334,800 ✓	187.55 ✓	% 0Cft	62,792 ✓
Total Amount Rs:-					1,224,859 ✓


EXECUTIVE ENGINEER
Drainage Division LBOD
Shaheed Benazirabad


M/S SONARI
Construction Company

NAME OF
SCHEME:-

"REPLACEMENT OF DISPOSAL CHANNEL OF PUMPING STATIONS AND TUBEWELLS AT VILLAGE AYOUB KHAN RINDH, UC WALI MUHAMMAD RIND, TALUKA NAWABSHAH, IN DRAINAGE DIVISION LBOD, SHAHEED BENAIZIRABAD"

NAME OF
WORK:-

BILL NO. 03:- CONSTRUCTION OF VILLAGE ROAD CULVERTS OVER LEADING CHANNEL


ABSTRACT SHEET


Sr. No.	Description	Qty	Rate	Unit	Amount
1	Excavation in foundation of buildings bridges and other structures i/c dag, belling, dressing refilling around structures with excavated earth watering & ramming earth lead up to 5'. b) Ordinary Soil. (GSS-2012, P-4, Item-18 (b).	41,250 Cft ✓	3,176.25 ✓	%0 Cft:	131,020 ✓
2	Re-handling of earth work. b) Up to lead of 50 ft: Item-9, P-2.	28,875 Cft ✓	1,058.75 ✓	%0Cft:	30,571 ✓
3	Extra for wet earth work. (GSS-2012, P-3, Item-15)	33,000 Cft ✓	1,058.75 ✓	%0 Cft:	34,939 ✓
4	Erection and removal of centering for R.C.C or plain cement concrete works of partal wood (2nd class) b) Vertical. (GSS-2012, P-19, Item-17 (b).	140 Sft ✓	3,127.41 ✓	%Sft:	4,378 ✓
5	Cement concrete plain i/c placing compacting, finishing and curing complete (i/c screening and washing of stone aggregate without shuttering)i) Ratio 1:4:8. (GSS-2012, P-15, Item-5)	904 Cft ✓	11,288.75 ✓	% Cft:	102,050 ✓
6	Reinforced cement concrete work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms, molds, lifting shuttering, curing, rendering and finishing and exposed surface (i/c screening and washing of shingle). a) R.C work in roof, slab, beams, columns, rafts, lintels and other structural members laid in site or pre-cast laid in position. i) Ratio 1:2:4 90Lbs: cement sand 4Cft: shingle 1/8" to 1/4" (GSS-2012, P-16, Item-6).	1,612 Cft ✓	337.00 ✓	P.Cft:	543,076 ✓


EXECUTIVE ENGINEER


**M/S SONARI
Construction Company**

Sr. No.	Description	Qty	Rate	Unit	Amount
7	Fabrication of mild steel reinforcement for cement concrete i/c cutting, bending laying in position making joints and fastenings i/c cost of binding wire (also includes removal of rust from bars. (b) using Tar Bars. (GSS-2012, P-16, Item-8 (b).	100.719 Cft ✓	5,001.70 ✓	P.Cwt:	503,765 ✓
8	Pacca brick work other than building including striking of joints up to 20 feet height in cement sand mortar 1:5. (GSS-2012, P-21, Item-7)(d)	2,366 Cft ✓	12,574.38 ✓	% Cft:	297,510 ✓
9	Cement Plaster 1:3 up to 20' height. C) 3/4" thick. (GSS-2012, P-51, Item-10(C).	786 Sft ✓	2,795.30 ✓	% Sft:	21,971 ✓
10	Barrow pit excavation undressed lead up to 100'. a) Ordinary soil. (GSS-2012, P-1, Item-3 (a).	4,500 Cft ✓	2,117.50 ✓	%0 Cft:	9,529 ✓
11	Dressing and Leveling of earth work to designed section ect complete GSS-2012. P-3. I-11 (b)	4,500 Cft ✓	187.55 ✓	%0 Cft:	844 ✓
12	Boring for Tube well in all water bearing, soils from ground level up to 100' or 30.50 meter depth i/c sinking and with drawing. e) 200 mm. (8" dia). (PHES-2012, P-41, Item-1)(e)	320 Rft ✓	535.00 ✓	P.Rft:	171,200 ✓
13	Supplying M.S Bail Plug of approved quality d) for 150 mm, (6" dia) (PHES-part-III, Vol-IV 2012, P-42 Item 8)(b)	4 Nos ✓	2,607.00 ✓	Each	10,428 ✓
14	Supplying and fixing local make coir stainer of approved quality complete. b) for 150 mm. (6" dia) (PHES-2012, P-44, Item-10 (b).	120 Rft ✓	647.00 ✓	P.Rft:	77,640 ✓
15	Supplying and installing M.S blind pipe 3/16" thick (5 mm.) of best and approved quality and make including necessary socket etc. complete. b) for 150 mm. (6" dia) blind pipe (PHES-2012, P-44, Item-11 (b)	200 Rft ✓	762.50 ✓	P.Rft:	152,500 ✓


 EXECUTIVE ENGINEER
 Drainage Division LBOD
 Chhatrapati Sangli


M/S SONARI
Construction Company

Sr. No.	Description	Qty	Rate	Unit	Amount
16	Full hire charges of pumping set per day inclusive of the wages of driver and assistant fuel or electric energy plate form required for placing pumps etc. at lower depths with suction and delivery pipes for pumping out water found at various depths from trenches including the cost of erection and dismantling after completion of the job. (ii) Hire charges of pumping set above 10 H.P pumping out water from 15' deep trench. (PHES-2012, P-77, Item-23 (ii).	75 Day ✓	2,000.00 ✓	P.Day	150,000 ✓
17	NOTE:- For working the pump beyond 8 hours the following payment shall be made, the higher of the pumping set it self being for 24 hours. i) For pumping set of above 10 H.P. (PHES-2012, P-77, Item-23 (i)	900 Hrs ✓	250.00 ✓	P. Hour	225,000 ✓
Total Amount for 01 No. VRC Rs:-					2,466,421 ✓
Total Amount for 04 No. VRC's Rs:-					9,865,684


 EXECUTIVE ENGINEER
 Drainage Division LBOD
 Shaheed Benazirabad


 M/S SONARI
 Construction Company

NAME OF
SCHEME:-


"REPLACEMENT OF DISPOSAL CHANNEL OF PUMPING STATIONS AND
TUBEWELLS AT VILLAGE AYOUB KHAN RINDH, UC WALI MUHAMMAD
RIND, TALUKA NAWABSHAH, IN DRAINAGE DIVISION LBOD, SHAHEED
BENAZIRABAD"

NAME OF
WORK:-

BILL NO. 04:- CONSTRUCTION OF WATERCOURSE AQUEDUCT OVER
LEADING CHANNEL / DRAIN

ABSTRACT SHEET

Sr. No.	Description	Qty	Rate	Unit	Amount
1	Providing ad casting in site RCC bored piles in class (B) using sulphate resistant cement of diameter 22" dia of 1:1/2:3 Ratio (Market Rate)	240 Rft ✓	3,730.00 ✓	P. Rft	895,200 ✓
2	Steel linear consist of 1/4" thick steel sheet welded in round shape including epoxy painting complete in all respect 22" dia (Market Rate)	10 Rft ✓	4,512.00 ✓	P. Rft	45,120 ✓
3	Reinforced cement concrete work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms, molds, lifting shuttering, curing, rendering and finishing and exposed surface (i/c screening and washing of shingle). a) R.C work in roof, slab, beams, columns, rafts, lintels and other structural members laid in site or pre-cast laid in position. i) Ratio 1:2:4 90Lbs: cement sand 4Cft: shingle 1/8" to 1/4" (GSS-2012, P-16, Item-6).	1,140 Cft ✓	337.00 ✓	P. Cft	384,180 ✓
4	Fabrication of mild steel reinforcement for cement concrete i/c cutting, bending laying in position making joints and fastenings i/c cost of binding wire (also includes removal of rust from bars. (GSS-2012 P-16 Item-8 (b).	110.700 Cwt ✓	5,001.70 ✓	P. Cwt	553,688 ✓
Total Amount Rs:-					1,878,188 ✓


EXECUTIVE ENGINEER
Drainage Division LBOD
Shaheed Benazirabad


M/S SONARI
Construction Company

NAME OF
SCHEME:-

"REPLACEMENT OF DISPOSAL CHANNEL OF PUMPING STATIONS AND
TUBEWELLS AT VILLAGE AYOUB KHAN RINDH, UC WALI MUHAMMAD
RIND, TALUKA NAWABSHAH, IN DRAINAGE DIVISION LBOD, SHAHEED
BENAZIRABAD"

NAME OF
WORK:-

BILL NO. 05:- CONSTRUCTION OF BOX CULVERT (SMALL SIZE)

ABSTRACT SHEET

Sr. No.	Description	Qty	Rate	Unit	Amount
1	Excavation in foundation of buildings bridges and other structures i/c dag, belling, dressing refilling around structures with excavated earth watering and ramming earth lead up to 5'. b) Ordinary Soil. (GSS-2012, P-4, Item-18 (b).	3,000 Cft ✓	3,176.25 ✓	%0 Cft:	9,529 ✓
2	Extra for wet earth work. (GSS-2012, P-4, Item-15)	1,500 Cft ✓	1,058.75 ✓	%0 Cft:	1,588 ✓
3	Erection and removal of centering for R.C.C or plain cement concrete works of partal wood (2nd class) b) Vertical. (GSS-2012, P-19, Item-18 (b).	94 Sft ✓	3,127.41 ✓	%Sft:	2,940 ✓
4	Cement concrete plain i/c placing compacting, finishing and curing complete (i/c screening and washing of stone aggregate without shuttering) h) Ratio 1:3:6. (GSS-2012, P-17, Item-5 (h).	620 Cft ✓	11,288.75 ✓	% Cft:	69,990 ✓
5	Reinforced cement concrete work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms, molds, lifting shuttering, curing, rendering and finishing and exposed surface (i/c screening and washing of shingle). a) R.C work in roof, slab, beams, columns, rafts, lintels and other structural members laid in site or pre-cast laid in position. i) Ratio 1:2:4 90Lbs: cement sand 4Cft: shingle 1/8" to 1/4" (GSS-2012, P-18, Item-6).	740 Cft ✓	337.00 ✓	P.Cft:	249,380 ✓


EXECUTIVE ENGINEER


M/S SONARI
Construction Company

NAME OF
SCHEME:-

"REPLACEMENT OF DISPOSAL CHANNEL OF PUMPING STATIONS AND
TUBEWELLS AT VILLAGE AYOUB KHAN RINDH, UC WALI MUHAMMAD
RIND, TALUKA NAWABSHAH, IN DRAINAGE DIVISION LBOD, SHAHEED
BENAZIRABAD"


NAME OF
WORK:-

BILL NO. 06:- CONSTRUCTION OF PACCA DISPOSAL CHANNEL

ABSTRACT SHEET

Sr. No.	Description	Qty	Rate	Unit	Amount
1	Excavation in foundation of building, bridges, and other structure including dressing refilling around structure with excavated earth watering and ramming lead upto 5 FT b) in ordinary soil [GSS-2012, Page-4, Item-18]	11,183 Cft ✓	3,176.25 ✓	%Cft	35,518 ✓
2	Cement concrete plain i/c placing compacting, finishing and curing complete (i/c screening and washing of stone aggregate without shuttering) (Ratio 1:4:8	11,183 Sft ✓	11,288.75 ✓	%Sft	1,262,364 ✓
3	Pacca bricks foundation & plinth i) cement sand mortar.1:4 (GSS-2012, P-20, Item- 4(c)	9,628 Cft ✓	12,501.41 ✓	%Cft	1,203,586 ✓
4	Cement concrete plain i/c placing compacting, finishing and curing complete (i/c screening and washing of stone aggregate without shuttering) (Ratio 1:2:4	1,065 Sft ✓	14,429.25 ✓	%Sft	153,672 ✓
5	Cement plaster (1:5) upto 20" height b) 1/2" thick [GSS-2012, Page-52, Item-12(b)]	15,464 Sft ✓	2,241.80 ✓	%Sft	346,667 ✓
6	Cement plaster (1:3) upto 20" height b) 1/2" thick [GSS-2012, Page-52, Item-10(b)]	15,464 Sft ✓	2,344.59 ✓	%Sft	362,563 ✓
7	Reinforcement cement concrete work i/c all labour for bending and binding which will be paid separately, this rate also includes all ,kind of forms, moulds, lifting shuttering , curing, rendering, and finishing the exposed surface (i/c screening and washing of shingle). a) R.C.C work in roof slab beams columns rafts lintels and other structural members laid in situ or precast laid in position complete in all respects. (i) Ratio (1:2:4) 90 lbs. cement 4 cft sand 2 cft. Shingle 1/8" to 1/4" gauge [GSS-2012, Page-17, Item-6(i)]	255 Cft ✓	337.00 ✓	P.Cft	85,935 ✓

Sr. No.	Description	Qty	Rate	Unit	Amount
8	Fabrication of mild steel reinforcement for cement concrete including cutting, bending laying in position making joints and fastenings i/c cost of binding wire (also i/c removal of rust from bars) Main & distribution bars 1/2" 6" C/C. [GSS-2012, Page-17, Item-8(a)]	27,321 Cwt ✓	4,820.20 ✓	P.Cwt	131,693 ✓
9	Barrow pit excavation undressed lead up to 100'. (a) ordinary soil. (GSS-2012, V-III, Part-II P-01, Item-03(a).	55,380 Cft ✓	2,117.50 ✓	%0 Cft:	117,267 ✓
10	Carriage of 100 cft / 05 Tons of all materials like stone, aggregate, spawl, surkhi, etc (Carriage 01 Mile) Schedule of Carriage P-1, Item-I	27,690 Cft ✓	407.00 ✓	%Cft:	112,698 ✓
11	Excavation for pipe line in trenches, and pits in soft soil i/c trimming and dressing sides to true alignment and shape levelling of beds of trenches to correct level and grade, cutting joints holes and display traffic, flages and temporary crossings for Non-vehicular lift lead upto 5ft GSS-2012, P-60, I-1	7,200 Cft ✓	3,600.00 ✓	%0 Cft	25,920 ✓
Total Amount Rs:-					3,837,883 ✓


EXECUTIVE ENGINEER
 Drainage Division LBOD
 Shaheed Benazirabad


M/S SONARI
Construction Company

NAME OF
SCHEME:-

"REPLACEMENT OF DISPOSAL CHANNEL OF PUMPING STATIONS AND
TUBEWELLS AT VILLAGE AYOUB KHAN RINDH, UC WALI MUHAMMAD
RIND, TALUKA NAWABSHAH, IN DRAINAGE DIVISION LBOD, SHAHEED
BENAZIRABAD"

NAME OF
WORK:-

BILL NO. 07:- MAKING DIRECT DISPOSAL ARRANGEMENT OF PUMPS


ABSTRACT SHEET

Sr. No.	Description	Qty	Rate	Unit	Amount
1	Excavation in foundation of building, bridges and other Structures i/c dag belling dressing refilling around structure with excavated earth watering ramming earth lead up to one chain and lift up to 5 ft: b) In ordinary soil. (GSS-2012, P-5, Item-18(b)).	180 Cft ✓	3,176.25 ✓	% Cft	572 ✓
2	Cement Concrete plain i/c finishing and currying complete i/c screening and washing of stone aggregate without shuttering: b) Ratio 1:3:6. (GSS-2012, P-17, Item-5h).	120 Cft ✓	12,595.00 ✓	% Cft	15,114 ✓
3	Pacca brick work other than building i/c sticking of joints up to 20' height in cement sand mortar 1:5. (GSS-2012, P-23, Item-7).	180 Cft ✓	12,574.38 ✓	% Cft	22,634 ✓
4	Cement Plaster 1:5 up to 20' height: b) 1/2" thick. (GSS-2012, P-53, Item-12(b)).	900 Sft ✓	2,241.80 ✓	% Sft:	20,176 ✓
5	M.S black steel pipe made out of M.S sheet of 5.56mm, W.T, 6.4mm W.T.7.1 mm W.T, 7.9 mm W.T 8.74mm, W.T, 9.5mm W.T, 10.31mm W.T 11.13mm W.T thickness confirming to APL 5L grade X-42 (Spirally Welled) (12" dia) (PHES- 2012, Material, V-III, Part-I, P-23, Item No: 06 (b)).	200 Rft: ✓	2,093.57 ✓	P.Rft	418,714 ✓
6	C.I. Bends 45 12" dia with flanged ends with holes including turning and facing of flanges for all sizes. (PHES-2012, Material, V-III, Part-I, P-09, Item-2).	8 Nos.	6,581.25 ✓	Each	52,650 ✓
7	Reflex valve heavy pattern (test pressure 21.0 kg/Sq or 300 Lbs/Sq: inch) (h) 300 mm 12" dia (PHE-Material-2012, Vol-III, Part-I, P-97, Item-6-g).	2 Nos.	21,937.50 ✓	Each	43,875 ✓

[Signature]
EXECUTIVE ENGINEER

**M/S SONARI
Construction Company**

Sr. No.	Description	Qty	Rate	Unit	Amount
8	Manufacturing and supplying M.S Reducer 12" x 10" dia from M.S sheet 3/16" thick sheeting i/c cutting and folding etc. complete. (PHES-2012, Vol-III, Part-I, P- 102, Item-11)	2 Nos.	4,260.00	Each	8,520
9	Jointing C.I./M.S flanged pipes and specials flanged inside a trench i/c supplying rubber packing as required for joints to a specified pressure etc. complete. 300 mm (12"dia). (PHES-2012, Vol-III, Part-III, P-40, Item-1-h).	46 Joints	2,239.00	P. Joints	102,994
10	Barrow pit excavation undressed lead up to 100'. (a) Ordinary Soil. (GSS-2012, P-1, Item-3(a).	25,600 Cft	2,117.50	% 0Cft	54,208
11	Dressing and leveling of earth work to designed section etc complete in Ordinary soil.	25,600 Cft	187.55	% 0Cft	4,801
12	Excavation for pipe line in trenches, and pits in soft soil i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade, cutting joints holes and display traffic, flanges and temporary crossings for Non-vahicularlift lead upto 5ft GSS-2012,P-60, I-1	52,800 Cft	3,600.00	% 0 Cft	190,080
13	Providing & Laying & fixing in trench i/c fitting, jointing and testing etc complete in all respect the high Density Polyethylene PE Pipe (HDPE-100) for W/S confirming ISO 4427/DIN/8074/8075 B.S 3580 & PSI 3051, 250 mm 12" dia. (PHES-2012, P-28, Vol-III, Part-III, Item-1 PN-16).	4,400 Rft:	2,915.00	P.Rft	12,826,000
Total Amount Rs:-					13,760,338


 EXECUTIVE ENGINEER
 Drainage Division LBOD
 Shaheed Benazirabad


 M/S SONARI
 Construction Company

CONTRACT EVALUATION FORM

TO BE FILLED IN BY ALL PROCURING AGENCIES FOR PUBLIC CONTRACTS OF WORKS, SERVICES & GOODS

1)	NAME OF THE ORGANIZATION /DEPTT.	Irrigation Department Govt. of Sindh
2)	PROVINCIAL / LOCAL GOVT / OTHER	Provincial
3)	TENDER DESCRIPTION / NAME OF WORK / ITEM	REPLACEMENT OF DISPOSAL CHANNEL OF PUMPING STATIONS AND TUBEWELLS AT VILLAGE AYOUB KHAN RINDH, UC WALI MUHAMMAD RIND, TALUKA NAWABSHAH, IN DRAINAGE DIVISION LBOD, SHAHEED
4)	Tender reference NUMBER	Single Stage Single Envelope Bidding Procedure
5)	BRIEF DESCRIPTION OF CONTRACT	REPLACEMENT OF DISPOSAL CHANNEL OF PUMPING STATIONS AND TUBEWELLS AT VILLAGE AYOUB KHAN RINDH, UC WALI MUHAMMAD RIND, TALUKA NAWABSHAH, IN DRAINAGE DIVISION LBOD, SHAHEED
6)	FORUM THAT APPROVED THE SCHEME	The Chief Engineer, Irrigation Development in Sindh, Region-I, Hyderabad
7)	TENDER ESTIMATED VALUE	Rs. 49,077,175 /-
8)	ENGINEER'S ESTIMATE (For civil works only)	Rs. 42,743,933 /-
9)	ESTIMATED COMPETION PERIOD (AS PER CONTRACT)	24 Months
10)	TENDER OPENED ON (DATE & TIME)	19.12.2017 at 1.30 P.M
11)	NUMBER OF TENDER DOCUMENT SOLD (Attach list of buyers)	17 Nos.
12)	NUMBER OF BIDS RECEIVED	09 Nos.
13)	NUMBER OF BIDDERS PRESENT AT THE TIME OF OPENING OF BID	17 Nos.
14)	BID EVALUATION REPORT (Enclosed a copy)	Enclose
15)	NAME AND ADDRESS OF THE SUCCESSFUL BIDDER	M/S Sonari Construction Company, Govt. Contractor
16)	CONTRACT AWARD PRICE	Rs. 49,077,175 /-

17)	RANKING OF SUCCESSFUL BIDDER IN EVALUATION REPORT (i.e. 1 st , 2 nd , 3 rd EVALUATION BID)	1 st Lowest M/S Sonari Construction Company, Govt. Contractor, = Rs: 49,077,175 /- 2 nd Lowest M/S United Engineers Construction Company. Govt. Contractor = Rs: 49,371,290/- 3 rd Lowest M/S MBC & Sons, Builders & Developers, Govt. Contractor, = Rs: 49,567,367/- 4th Lowest M/S Kamran Ali Jalbani, Govt. Contractor = Rs: 49,998,736/- 5th Lowest M/S Ali Builders, Govt. Contractor = Rs: 56,681,797/-
-----	---	---

18) METHOD OF PROCUREMENT USED : - (Tick one)

- a) SINGLE STAGE - ONE ENVELOPE PROCEDURE _____
- b) SINGLE STAGE-TWO ENVELOPE PROCEDURE _____
- c) TWO STAGE – TWO ENVELOPE BIDDING PROCEDURE _____
- d) TWO STAGE – TWO ENVELOPE BIDDING PROCEDURE _____

PLEASE SPECIFY IF ANY OTHER METHOD OF PROCUREMENT WAS ADOPTED I.E. EMERGENCY, DIRECT CONTRACTING ETC. WITH BRIEF REASONS:

19) APPROVING AUTHORITY FOR AWARD OF CONTRACT Chief Engineer Irrigation Development in Sindh Hyderabad

20) WHETHER THE PROCUREMENT WAS INCLUDING IN ANNUAL PROCUREMENT PLAN?

YES	<input checked="" type="checkbox"/>	NO	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

21) ADVERTISEMENT:

i) SPPRA Website
(if yes, give date and SPPRA identification No.)

Yes	Yes
No	

ii) News papers
(if yes, give names of newspapers and dates.)

Yes	Yes
No	

22) NATURE OF CONTRACT

23) WHETHER QUALIFICATION CRITERIA WAS INCLUDED IN BIDDING / TENDER DOCUMENT?
(If yes, enclosed a copy)

YES	<input checked="" type="checkbox"/>	NO	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

24) WHETHER QUALIFICATION CRITERIA WAS INCLUDED IN BIDDING / TENDER DOCUMENT?
(If yes, enclosed a copy)

YES	<input checked="" type="checkbox"/>	NO	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

25) WHETHER APPROVAL OF COMPETENT AUTHORITY WAS OBTAINED FOR USE A METHOD OTHER THAN OPEN COMPETITIVE BIDDING
(If yes, enclosed a copy)

YES	<input type="checkbox"/>	NO	<input checked="" type="checkbox"/> N.A
-----	--------------------------	----	---

26) WAS BID SECURITY OBTAINED FROM ALL THE BIDDERS?

YES	<input checked="" type="checkbox"/>	NO	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

27) WHETHER THE SUCCESSFUL BID WAS LOWEST EVALUATED BID / BEST EVALUATED BID (in case of consultancies)

YES	<input type="checkbox"/>	NO	<input checked="" type="checkbox"/>
-----	--------------------------	----	-------------------------------------

28) WHETHER THE SUCCESSFUL BIDDER WAS TECHNICALLY COMPLIANT?

YES	<input type="checkbox"/>	NO	<input checked="" type="checkbox"/>
-----	--------------------------	----	-------------------------------------

29) WHETHER NAMES OF THE BIDDERS AND THEIR QUOTED PRICE WERE READ OUT AT THE TIME OF OPENING OF BIDS?

YES	<input checked="" type="checkbox"/>	NO	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

30) WHETHER EVALUATION REPORT GIVEN TO BIDDERS BEFORE THE AWARD OF CONTRACT?
(Attached copy of the bid evaluation report)

YES	<input checked="" type="checkbox"/>	NO	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

31) ANY COMPLAINT RECEIVED
(if yes, result thereof)

Yes	
No	No

32) ANY DEVIATION FROM SPECIFICATIONS GIVEN IN THE TENDER NOTICE / DOCUMENTS.
(if yes, give details)

Yes	
No	No

33) WAS THE EXTENSION MADE IN RESPONSE TIME?
(if yes, give reasons)

Yes	
No	No

34) DEVIATION FROM QUALIFICATION CRITERIA
(if yes, give detailed reasons).

Yes	
No	No

* NA: Not Applicable

35) WAS IT ASSURED BY THE PROCURING AGENCY THAT THE SLECTED FIRM IS NOT BLACK LISTED?

YES	<input checked="" type="checkbox"/>	NO	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

36) WAS A VISIT MADE BY ANY OFFICER /OFFICIAL OF THE PROCURING AGENCY TO THE SUPPLIER'S PREMISES IN CONNECTION WITH THE PROCUREMENT? IF SO, DETAIL TO BE ASCERTAINED REGARDING FINANCING OF VISIT, IF ABROAD:


YES	<input type="checkbox"/>	NO	<input checked="" type="checkbox"/>
-----	--------------------------	----	-------------------------------------


37) WERE PROPER SAFEGUARDS PROVIDED ON MOBILIZATION ADVANCE PAYMENT IN THE CONTRAT (BANK GUARNTEE ETC). ?


YES	<input checked="" type="checkbox"/>	NO	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

38) SPECIAL CONDITIONS, IF ANY (if yes, give Brief Description).

Yes	
No	No


(Nadeem Ahmed Jokhro)
Executive Engineer
Drainage Division, LBOD,
Shaheed Benazirabad
(Member / Secretary)


(Shaifque Ahmed Nizamani)
Executive Engineer
Provincial Highway Division
Shaheed Benazirabad
(Member)


(Pritam Das)
Project Director
SCARP (North Rohri)
Shaheed Benazirabad
(Chairman)

(INTEGRITY PACT)
 DECLARATION OF FEES, COMMISSION AND BROKERAGE ETC
 PAYABLE BY CONTRACTORS
 (FOR CONTRACTS WORTH RS. 10.00 MILLION OR MORE)

Contract No. AC/E-148/1145 Dated 21/11/2017

Contract Value: 49077175/-


Contract Title: "REPLACEMENT OF DISPOSAL CHANNEL OF PUMPING STATIONS AND TUBEWELLS AT VILLAGE AYOUB KHAN RINDH, UC WALI MUHAMMAD RIND, TALUKA NAWABSHAH, IN DRAINAGE DIVISION LBOD, SHAHEED BENAZIRABAD".

Sonari Construction Co. hereby declares that it has not obtained or induced the procurement of any contract, right, interest, privilege or other obligation or benefit from Government of Sindh (GoS) or any administrative subdivision or agency thereof or any other entity owned or controlled by it (GoS) through any corrupt business practice.

Without limiting the generality of the foregoing, Sonari Construction Co. represents and warrants that it has fully declared the brokerage, commission, fees etc. paid or payable to anyone and not given or agreed to give and shall not give or agree to give to anyone within or outside Pakistan either directly or indirectly through any natural or juridical person, including its affiliate, agent, associate, broker, consultant, director, promoter, shareholder, sponsor or subsidiary, any commission, gratification, bribe, finder's fee or kickback, whether described as consultation fee or otherwise, with the object of obtaining or inducing the procurement of a contract, right, interest, privilege or other obligation or benefit in whatsoever form from, from Procuring Agency (PA) except that which has been expressly declared pursuant hereto.

Sonari Construction Co. accepts full responsibility and strict liability that it has made and will make full disclosure of all agreements and arrangements with all persons in respect of or related to the transaction with PA and has not taken any action or will not take any action to circumvent the above declaration, representation or warranty.

Sonari Construction Co. accepts full responsibility and strict liability for making any false declaration, not making full disclosure, misrepresenting facts or taking any action likely to defeat the purpose of this declaration, representation and warranty. It agrees that any contract, right, interest, privilege or other obligation or benefit


 EXECUTIVE ENGINEER
 Drainage Division LBOD


 M/S SONARI
 Construction Company

obtained or procured as aforesaid shall, without prejudice to any other rights and remedies available to PA under any law, contract or other instrument, be voidable at the option of PA.

Notwithstanding any rights and remedies exercised by PA in this regard,

Sonari Construction Co. agrees

to indemnify PA for any loss or damage incurred by it on account of its corrupt business practices and further pay compensation to PA in an amount equivalent to ten times the sum of any commission, gratification, bribe, finder's fee or kickback given by Sonari Construction Co.


as aforesaid for the purpose of obtaining or inducing the procurement of any contract, right, interest, privilege or other obligation or benefit in whatsoever form from PA.

Executive Engineer,
Drainage Division LBOD,
Shaheed Benazirabad

[Procuring Agency]



M/S SONARI
[Contractor]
Construction Company


EXECUTIVE ENGINEER
Drainage Division LBOD
Shaheed Benazirabad

CHALAN No. 72

Challan of Cash paid into the National Bank of Pakistan

12-2-18

ORIGINAL

To be filled in by the remitter

By whom tendered (Name)

M/s Sonari Construction Company
Govt Contractor
House # 246 Ghulam Hyder Shah Colony Nawab Shah

Head of Account

0271003
B02701

Full particulars of the remittance
& the authority if any

Amount
Rs. Ps.

Received Cash on account of stamp Duty
@ 0.35 / on Tenders cost amounting to
Rs. 4907775/- in ADP Scheme Name
Construction of Pumping Station for
Disposal of Sim Water in Deh
Dusma Taluka Tando Adam.

172000

Date:

61
~~Special Accounts Officer~~
~~Nawabshah~~
~~Executive Engineer~~
Drainage Division L.B.O.
Shaheed Benazirabad
of the Office holding the
money to be paid in

EXECUTIVE ENGINEER
Drainage Division L.B.O.
Shaheed Benazirabad

Total 172000/-

In words (Rupees) One hundred Seventy two thousand only

Received Payment
Main Branch
12 FEB 2018
TREASURY RECEIVED

Accountant

For National Bank of Pakistan
Main Branch Nawabshah (3040)
Treasurer / Agent

FOR MANAGER

Handwritten signature and notes at the bottom of the page.