

## BID EVALUATION REPORT

1	Name of Procuring Agency	Executive Engineer Drainage Division Badin
2	Tender Reference No.	No. TC/G-55/DD/ 33, Dated: 01-02-2016.
3	Name of Work	<b>CONSTRUCTION OF PROPOSED DRAIN AND STONE PITCHING FROM RD. 0.0 TO 14.0 IN CANTONMENT AREA BADIN. (Package No. 1)</b>
4	Method of Procurement	Singe Stage - One Envelope Procedure
5	Tender Published	Hosted through website of SPPRA vide S. No. 264/14 Dated: 11.02.2016, published in the Newspapers "Daily Ibrat dated: 03.02.2016, Daily Jang, Dated: 03.02.2016 & Tribune Dated: 03.02.2016.
6	Total Bid Documents Sold	05 Nos.
7	Total Bid Received	03 Nos.
8	Technical Bid Opening Date	22.02.2016
9	No. of Bid Technically Qualified	03 Nos.
10	Bid (s) Rejected	02 No. Bid Rejected
11	Financial Bid Opening date	22.02.2016

### 12 EVALUATION

S. No.	Name of Firm or Bidder	Cost offered by the Bidders	Ranking in Terms of cost	Comparison with etsimated cost without W.C & M.E	Reasons for acceptance / rejection	Remarks
1	2	3	4	5	6	7
1	M/s Thadani Enterprises	49,979,332	1st.	14.88% above	1st. Lowest Reasonable	Lowest accepted
2	M/s Haji Sirajuddin Soomro Contractor & Engineers	57,640,522	2nd	32.50% above	Higher	Rejected
3	M/s Malani Construction Company	62,015,522	3rd.	42.55% above	Higher	Rejected

~~CHAIRMAN~~

(Khair Muhammad Dahri)  
DIRECTOR  
Left Bank Canals (AWB)  
BADIN

Member / Secretary  
(Fawad Ahmed Memon)  
EXECUTIVE ENGINEER  
DRAINAGE DIVISION  
BADIN

Member  
(Rao Mushtague Ahmed)  
Divisional Accounts Officer  
Drainage Division  
BADIN

Member  
(Bhawani Shankar)  
EXECUTIVE ENGINEER  
Public Health Department  
BADIN

Member  
(Akbar Azam Rashidi)  
TECHNICAL OFFICER  
SIDA, HYDERABAD

Member  
IFTIKHAR  
MAJOR  
Head Quarter 206-Brigade  
Badin Cantonment

Member  
Syed Aijaz Ali Shah  
Executive Engineer  
Akram Wah Division, Badin

*Post Evaluation Report is hereby approved -*

*Checked -*  
*Admi*  
*Checked -*

Technical Officer  
Sindh Irrigation & Drainage Authority  
Hyderabad.

Managing Director  
Sindh Irrigation & Drainage Authority  
Hyderabad.

## BID EVALUATION REPORT

1 Name of Procuring Agency	Executive Engineer Drainage Division Badin
2 Tender Reference No.	No. TC/G-55/DD/ 33, Dated: 01-02-2016.
3 Name of Work	<b>CONSTRUCTION OF INTERNAL DISPOSAL CHANNELS FROM TUBE WELLS TO PROPOSED DRAIN I/C ROAD CULVERT AND RCC PIPE ALONG BADIN CANTT:</b> a) Construction of Internal Disposal Channels from Tube wells to proposed drain. b) Construction of (01 No.) Road Culvert, C) Construction of (02 No.) RCC Pipe Inlets. (Package No. 2)
4 Method of Procurement	Singe Stage - One Envelope Procedure
5 Tender Published	Hosted through website of SPPRA vide S. No. 26449 Dated: 11.02.2016, published in the Newspapers "Daily Ibrat dated: 03.02.2016, Daily Jang, Dated: 03.02.2016 & Tribune Dated: 03.02.2016.
6 Total Bid Documents Sold	06 Nos.
7 Total Bid Received	03 Nos.
8 Technical Bid Opening Date	22.02.2016
9 No. of Bid Technically Qualified	03 Nos.
10 Bid (s) Rejected	02 No. Bid Rejected
11 Financial Bid Opening date	22.02.2016


### 12 EVALUATION


S. No.	Name of Firm or Bidder	Cost offered by the Bidders	Ranking in Terms of cost	Comparison with etsimated cost without W.C & M.E	Reasons for acceptance / rejection	Remarks
1	2	3	4	5	6	7
1	M/s Haji Sirajuddin Soomro Contractor & Engineers	19,257,612	1st.	14.87% above	1st. Lowest Reasonable	Lowest accepted
2	M/s Thadani Enterprises	22,149,283	2nd.	32.12% above	Higher	Rejected
3	M/s Malani Construction Company	25,361,964	3rd.	51.29% above	Higher	Rejected


  
**CHAIRMAN**

(Khair Muhammad Dahri)  
**DIRECTOR**  
Left Bank Canals (AWB)  
BADIN


  
Member / Secretary  
(Fawad Ahmed Memon)  
EXECUTIVE ENGINEER  
DRAINAGE DIVISION  
BADIN

  
Member  
(Rao Mushtaque Ahmed)  
Divisional Accounts Officer  
Drainage Division  
BADIN

  
Member  
(Bhawani Shankar)  
EXECUTIVE ENGINEER  
Public Health Department  
BADIN

  
Member  
(Akbar Azam Rashidi)  
TECHNICAL OFFICER  
SIDA, HYDERABAD


  
Member  
IFTIKHAR  
MAJOR  
Head Quarter 206-Brigade  
Badin Cantonment

  
Member  
Syed Aijaz Ali Shah  
Executive Engineer  
Akram Wah Division, Badin

*Bid Evaluation Report is hereby approved -*

*Checked -*  
*Checked -*

  
Technical Officer  
Sindh Irrigation & Drainage Authority  
Hyderabad.

  
Managing Director  
Sindh Irrigation & Drainage Authority  
Hyderabad.

## BID EVALUATION REPORT


1	Name of Procuring Agency	Executive Engineer Drainage Division Badin
2	Tender Reference No.	No. TC/G-55/DD/ 33, Dated: 01-02-2016.
3	Name of Work	<b>DISPOSAL CHANNEL ALONG CANTT: AREA @ BADIN.</b> a) Construction of Pump House, b) Construction RCC Sump /Tank 16'x8' c) Providing & laying, Jointing & Testing A.C Rising Main 24" Q dia for disposal of wet weather flow from Cantt. Badin 2050 Rft. d) Supplying & Installing 60 BHP A.C Electric Motor for disposal of storm water flow from cantt. Badin and adjoining area e) External Electrification.f) Diesel Generator 50 KVA (02 No.) along Cantonment Area @ Badin (Package No.3)
4	Method of Procurement	Singe Stage - One Envelope Procedure
5	Tender Published	Hosted through website of SPPRA vide S. No. 2644, Dated: 11.02.2016, published in the Newspapers "Daily Ibrat dated: 03.02.2016, Daily Jang, Dated: 03.02.2016 & Tribune Dated: 03.02.2016.
6	Total Bid Documents Sold	03 Nos.
7	Total Bid Received	03 Nos.
8	Technical Bid Opening Date	22.02.2016
9	No. of Bid Technically Qualified	03 Nos.
10	Bid (s) Rejected	02 No. Bid Rejected
11	Financial Bid Opening date	22.02.2016


### 12 EVALUATION


S. No.	Name of Firm or Bidder	Cost offered by the Bidders	Ranking in Terms of cost	Comparison with etsimated cost without W.C & M.E	Reasons for acceptance / rejection	Remarks
1	2	3	4	5	6	7
1	M/s Thadani Enterprises	42,120,260	1st.	14.90% above	1st. Lowest Reasonable	Lowest accepted
2	M/s Haji Sirajuddin Soomro Contractor & Engineers	46,317,586	2nd.	26.35% above	Higher	Rejected
3	M/s Shaikh Baz Khan & Brothers	50,932,991	3rd.	38.94% above	Higher	Rejected


  
CHAIRMAN

(Khair Muhammad Dahri)  
DIRECTOR  
Left Bank Canals (AWB)  
BADIN


  
Member /Secretary  
(Fawad Ahmed Memon)  
EXECUTIVE ENGINEER  
DRAINAGE DIVISION  
BADIN

  
Member  
(Rao Mushtaque Ahmed)  
Divisional Accounts Officer  
Drainage Division  
BADIN

  
Member  
(Bhawani Shankar)  
EXECUTIVE ENGINEER  
Public Health Department  
BADIN


  
Member  
(Akbar Azam Rashidi)  
TECHNICAL OFFICER  
SIDA, HYDERABAD


  
Member  
IFTIKHAR  
MAJOR  
Head Quarter 206-Brigade  
Badin Cantonment

  
Member  
Syed Aijaz Ali Shah  
Executive Engineer  
Akram Wah Division, Badin

check -  
ami  
check -

*Post Evaluation Report is duly apprd -*

  
Technical Officer  
Sindh Irrigation & Drainage Authority  
Hyderabad.

  
Managing Director  
Sindh Irrigation & Drainage Authority  
Hyderabad.

## BID EVALUATION REPORT

1	Name of Procuring Agency	Executive Engineer Drainage Division Badin
2	Tender Reference No.	No. TC/G-55/DD/ 33, Dated: 01-02-2016.
3	Name of Work	<b>CONSTRUCTION OF (13 NO.) SOLAR TUBE WELL (80 FT. DEPTH) OF 1.0 CUSEC CAPACITY ALONG IN &amp; OUT CANTONMENT AREA @ BADIN.</b> <b>(Package No. 4)</b>
4	Method of Procurement	Singe Stage - One Envelope Procedure
5	Tender Published	Hosted through website of SPPRA vide S. No. 26444, Dated: 11.02.2016, published in the Newspapers "Daily Ibrat dated: 03.02.2016, Daily Jang, Dated: 03.02.2016 & Tribune Dated: 03.02.2016.
6	Total Bid Documents Sold	04 Nos.
7	Total Bid Received	03 Nos.
8	Technical Bid Opening Date	22.02.2016
9	No. of Bid Technically Qualified	03 Nos.
10	Bid (s) Rejected	02 No. Bid Rejected
11	Financial Bid Opening date	22.02.2016

### 12 EVALUATION


S. No.	Name of Firm or Bidder	Cost offered by the Bidders	Ranking in Terms of cost	Comparison with estimated cost without W.C & M.E	Reasons for acceptance / rejection	Remarks
1	2	3	4	5	6	7
1	M/s Thadani Enterprises	46,621,640	1st.	14.94% above	1st. Lowest Reasonable	Lowest accepted
2	M/s Haji Sirajuddin Soomro Contractor & Engineers	49,999,560	2nd.	23.27% above	Higher	Rejected
3	M/s Umar Jan & Company	56,592,900	3rd.	39.52% above	Higher	Rejected


  
CHAIRMAN

(Khair Muhammad Dahri)  
DIRECTOR  
Left Bank Canals (AWB)  
BADIN


  
Member / Secretary  
(Fawad Ahmed Memon)  
EXECUTIVE ENGINEER  
DRAINAGE DIVISION  
BADIN

  
Member  
(Rao Mushtaq Ahmed)  
Divisional Accounts Officer  
Drainage Division  
BADIN


  
Member  
(Bhawani Shankar)  
EXECUTIVE ENGINEER  
Public Health Department  
BADIN

  
Member  
(Akbar Azam Rashidi)  
TECHNICAL OFFICER  
SIDA, HYDERABAD


  
Member  
IFTIKHAR  
MAJOR  
Head Quarter 206-Brigade  
Badin Cantonment

  
Member  
Syed Aijaz Ali Shah  
Executive Engineer  
Akram Wah Division, Badin

*Bid Evaluation Report is hereby approved -*

*checked -*  
  
*checked -*

  
Technical Officer  
Sindh Irrigation & Drainage Authority  
Hyderabad.

  
Managing Director  
Sindh Irrigation & Drainage Authority  
Hyderabad.

## BID EVALUATION REPORT

1	Name of Procuring Agency	Executive Engineer Drainage Division Badin
2	Tender Reference No.	No. TC/G-55/DD/ 33, Dated: 01-02-2016
3	Name of Work	<b>CONSTRUCTION OF (13 NO.) SOLAR TUBE WELL (80 FT. DEPTH) OF 1.0 CUSEC CAPACITY ALONG IN &amp; OUT CANTONMENT AREA @ BADIN.</b> <b>(Package No. 5)</b>
4	Method of Procurement	Singe Stage - One Envelope Procedure
5	Tender Published	Hosted through website of SPPRA vide S. No. 2644, Dated: 11.02.2016, published in the Newspapers "Daily Ibrat dated: 03.02.2016, Daily Jang, Dated: 03.02.2016 & Tribune Dated: 03.02.2016.
6	Total Bid Documents Sold	04 Nos.
7	Total Bid Received	03 Nos.
8	Technical Bid Opening Date	22.02.2016
9	No. of Bid Technically Qualified	03 Nos.
10	Bid (s) Rejected	02 No. Bid Rejected
11	Financial Bid Opening date	22.02.2016

### 12 EVALUATION

S. No.	Name of Firm or Bidder	Cost offered by the Bidders	Ranking in Terms of cost	Comparison with estimated cost without W.C & M.E	Reasons for acceptance / rejection	Remarks
1	2	3	4	5	6	7
1	M/s Haji Sirajuddin Soomro Contractor & Engineers	46,635,940	1st.	14.97% above	1st. Lowest Reasonable	Lowest accepted
2	M/s Thadani Enterprises	49,999,560	2nd.	23.27% above	Higher	Rejected
3	M/s Umar Jan & Company	56,592,900	3rd.	39.52% above	Higher	Rejected

  
CHAIRMAN

(Khair Muhammad Dahri)  
DIRECTOR  
Left Bank Canals (AWB)  
BADIN

Member Secretary  
(Fawad Ahmed Memon)  
EXECUTIVE ENGINEER  
DRAINAGE DIVISION  
BADIN

Member  
(Rao Mushtaqe Ahmed)  
Divisional Accounts Officer  
Drainage Division  
BADIN

Member  
(Bhawani Shankar)  
EXECUTIVE ENGINEER  
Public Health Department  
BADIN

Member  
(Akbar Azam Rashidi)  
TECHNICAL OFFICER  
SIDA, HYDERABAD


Member  
IFTIKHAR  
MAJOR  
Head Quarter 206-Brigade  
Badin Cantonment

Member  
Syed Aijaz Ali Shah  
Executive Engineer  
Akram Wah Division, Badin

*Post Evaluation Report is hereby approved -*

*Checked -*  
*Amir*  
*checked -*

  
Technical Officer  
Sindh Irrigation & Drainage Authority  
Hyderabad.

  
Managing Director  
Sindh Irrigation & Drainage Authority,  
Hyderabad.

## BID EVALUATION REPORT

1	Name of Procuring Agency	Executive Engineer Drainage Division Badin
2	Tender Reference No.	No. TC/G-55/DD/ 33, Dated: 01-02-2016.
3	Name of Work	<b>CONSTRUCTION OF (12 NO.) SOLAR TUBE WELL (80 FT. DEPTH) OF 1.0 CUSEC CAPACITY ALONG IN &amp; OUT CANTONMENT AREA @ BADIN.</b> <b>(Package No. 6)</b>
4	Method of Procurement	Singe Stage - One Envelope Procedure
5	Tender Published	Hosted through website of SPPRA vide S. No. 26444 Dated: 11.02.2016, published in the Newspapers "Daily Ibrat dated: 03.02.2016, Daily Jang, Dated: 03.02.2016 & Tribune Dated: 03.02.2016.
6	Total Bid Documents Sold	04 Nos.
7	Total Bid Received	03 Nos.
8	Technical Bid Opening Date	22.02.2016
9	No. of Bid Technically Qualified	03 Nos.
10	Bid (s) Rejected	02 No. Bid Rejected
11	Financial Bid Opening date	22.02.2016

### 12 EVALUATION

S. No.	Name of Firm or Bidder	Cost offered by the Bidders	Ranking in Terms of cost	Comparison with estimated cost without W.C & M.E	Reasons for acceptance / rejection	Remarks
1	2	3	4	5	6	7
1	M/s Haji Sirajuddin Soomro Contractor & Engineers	43,048,560	1st.	14.97% above	1st. Lowest Reasonable	Lowest accepted
2	M/s Thadani Enterprises	46,153,440	2nd.	23.27% above	Higher	Rejected
3	M/s Umar Jan & Company	52,239,600	3rd.	39.52% above	Higher	Rejected


  
CHAIRMAN


(Khair Muhammad Dahri)  
DIRECTOR  
Left Bank Canals (AWB)  
BADIN


  
Member Secretary  
(Fawad Ahmed Memon)  
EXECUTIVE ENGINEER  
DRAINAGE DIVISION  
BADIN

  
Member  
(Rao Mushtaqe Ahmed)  
Divisional Accounts Officer  
Drainage Division  
BADIN

  
Member  
(Bhawani Shankar)  
EXECUTIVE ENGINEER  
Public Health Department  
BADIN

  
Member  
(Akbar Azam Rashidi)  
TECHNICAL OFFICER  
SIDA, HYDERABAD


  
Member  
IFTIKHAR  
MAJOR  
Head Quarter 206-Brigade  
Badin Cantonment

  
Member  
Syed Aijaz Ali Shah  
Executive Engineer  
Akram Wah Division, Badin

*For Evaluation Report is here prepared -*

*checked -*  
*Amir*  
*checked -*

  
Technical Officer  
Sindh Irrigation & Drainage Authority  
Hyderabad.

  
Managing Director  
Sindh Irrigation & Drainage Authority  
Hyderabad.

## BID EVALUATION REPORT


1	Name of Procuring Agency	Executive Engineer Drainage Division Badin
2	Tender Reference No.	No. TC/G-55/DD/ 33, Dated: 01-02-2016.
3	Name of Work	<b>CONSTRUCTION OF (12 NO.) SOLAR TUBE WELL (80 FT. DEPTH) OF 1.0 CUSEC CAPACITY ALONG IN &amp; OUT CANTONMENT AREA @ BADIN. (Package No. 7)</b>
4	Method of Procurement	Single Stage - One Envelope Procedure
5	Tender Published	Hosted through website of SPPRA vide S. No. 26444, Dated: 11.02.2016, published in the Newspapers "Daily Ibrat dated: 03.02.2016, Daily Jang, Dated: 03.02.2016 & Tribune Dated: 03.02.2016.
6	Total Bid Documents Sold	04 Nos.
7	Total Bid Received	03 Nos.
8	Technical Bid Opening Date	22.02.2016
9	No. of Bid Technically Qualified	03 Nos.
10	Bid (s) Rejected	02 No. Bid Rejected
11	Financial Bid Opening date	22.02.2016

### 12 EVALUATION


S. No.	Name of Firm or Bidder	Cost offered by the Bidders	Ranking in Terms of cost	Comparison with estimated cost without W.C & M.E	Reasons for acceptance / rejection	Remarks
1	2	3	4	5	6	7
1	M/s Haji Sirajuddin Soomro Contractor & Engineers	43,048,560	1st.	14.97% above	1st. Lowest Reasonable	Lowest accepted
2	M/s Thadani Enterprises	46,153,440	2nd.	23.27% above	Higher	Rejected
3	M/s Umar Jan & Company	52,239,600	3rd.	39.52% above	Higher	Rejected


  
CHAIRMAN

(Khair Muhammad Dahri)  
DIRECTOR  
Left Bank Canals (AWB)  
BADIN


  
Member / Secretary  
(Fawad Ahmed Memon)  
EXECUTIVE ENGINEER  
DRAINAGE DIVISION  
BADIN

  
Member  
(Rao Mushtaque Ahmed)  
Divisional Accounts Officer  
Drainage Division  
BADIN

  
Member  
(Bhawani Shankar)  
EXECUTIVE ENGINEER  
Public Health Department  
BADIN

  
Member  
(Akbar Azam Rashidi)  
TECHNICAL OFFICER  
SIDA, HYDERABAD


  
Member  
IFTIKHAR  
MAJOR  
Head Quarter 206-Brigade  
Badin Cantonment

  
Member  
Syed Aijaz Ali Shah  
Executive Engineer  
Akram Wah Division, Badin

*Bid Evaluation Report is hereby approved -*

*checked -*  
*Admin*  
*checked -*

  
Technical Officer  
Sindh Irrigation & Drainage Authority  
Hyderabad.

  
Managing Director  
Sindh Irrigation & Drainage Authority  
Hyderabad.



**COMPARATIVE STATEMENT**  
**GOVERNMENT OF SINDH IRRIGATION DEPARTMENT**  
**Executive Engineer Drainage Division Badin**

Tenders invited vide this office Letter No. TC/G-55/DD/33, Dated: 01.02.2016.

Name of Work:- CONSTRUCTION OF PROPOSED DRAIN AND STONE PITCHING FROM RD. 0.0 TO 14.0 IN CANTONMENT AREA BADIN.  
(Package No. 1) (ADP No. 648)

S. No.	Name of Contractor	Date of Receipt of Sealed Quotation	Percentage rate entered in contract documents	Remarks.
1.	M/s Malani Construction Company	22.02.2016	42.55% above	CD No. FWDC 0301696, Dated: 22.02.2016 of First Women Bank Ltd. Hyderabad Branch for Rs. 1,300,000/-
2.	M/s Thadani Enterprises	22.02.2016	14.88% above	CDR No. 4998, Dated: 22.02.2016 of Summit Bank Hyderabad Branch for Rs. 1,120,000/-
3.	M/s Haji Sirajuddin Soomro Contractor & Engineers	22.02.2016	32.50% above	CDR 0685206, Dated: 22.02.2016, Bank Alfalah Limited Main Branch Saddar Hyderabad for Rs. 1,255,000/-

**Chairman**

**Mr. Khair Mohammad Dahri**  
Director  
Left Bank Canals (AWB), Badin

**Member / Secretary**  
**Fawad Ahmed Memon**  
Executive Engineer  
Drainage Division, Badin

**Member**  
**Bhawani Shankar**  
Executive Engineer  
Public Health Department  
Badin

**Member**  
**MAJOR IFTIKHAR**  
Head Quarter 206-Brigade  
Badin Cantonment

**Member**  
**Rao Mushtaque Ahmed**  
Divisional Accounts Officer  
Drainage Division, Badin

**Member**  
**Akbar Azam Rashdi**  
Technical Officer  
SIDA Hyderabad

**Member**  
**Syed Aijaz Ali Shan**  
Executive Engineer  
Akram Wah Division, Badin





**COMPARATIVE STATEMENT**  
**GOVERNMENT OF SINDH IRRIGATION DEPARTMENT**  
**Executive Engineer Drainage Division Badin**

Tenders invited vide this office Letter No. TC/G-55/DD/33, Dated: 01.02.2016.

Name of Work:- **CONSTRUCTION OF INTERNAL DISPOSAL CHANNELS FROM TUBE WELLS TO PROPOSED DRAIN I/C ROAD CULVERT AND RCC PIPE ALONG BADIN CANTT:**

a) Construction of Internal Disposal Channels from Tube wells to proposed drain. b) Construction of (01 No.) Road Culvert, C) Construction of (02 No.) RCC Pipe Inlets. (Package No. 2) (ADP No. 648)

S. No.	Name of Contractor	Date of Receipt of Sealed Quotation	Percentage rate entered in contract documents	Remarks.
1.	M/s Thadani Enterprises	22.02.2016	32.14% As per	CDR No. 4999, Dated: 22.02.2016 of Summit Bank Hyderabad Branch for Rs. 470,000/-
2.	M/s Haji Sirajuddin Soomro Contractor & Engineers	22.02.2016	14.87% As per	CDR 0685207, Dated: 22.02.2016 Bank Alfalah Limited Main Branch Saddar Hyderabad for Rs. 440,000/-
3.	M/s Malani Construction Company	22.02.2016	51.29% As per	CD No. FWDC 0301697, Dated: 22.02.2016 of First Women Bank Ltd. Hyderabad Branch for Rs. 500,000/-

**Chairman**

**Mr. Khair Mohammad Dahri**  
Director  
Left Bank Canals (AWB), Badin

**Member / Secretary**  
**Fawad Ahmed Memon**  
Executive Engineer  
Drainage Division, Badin

**Member**  
**Rao Mushtaque Ahmed**  
Divisional Accounts Officer  
Drainage Division, Badin

**Member**  
**Bhawani Shankar**  
Executive Engineer  
Public Health Department  
Badin

**Member**  
**Akbar Azam Rashdi**  
Technical Officer  
SIDA Hyderabad

**Member**  
**MAJOR**  
**JETIKHAR**  
Head Quarter 206-Brigade  
Badin Cantonment

**Member**  
**Syed Aijaz Ali Shah**  
Executive Engineer  
Akram Wah Division Badin



**COMPARATIVE STATEMENT**  
**GOVERNMENT OF SINDH IRRIGATION DEPARTMENT**  
**Executive Engineer Drainage Division Badin**

Tenders invited vide this office Letter No. TC/G-55/DD/33, Dated: 01/02.2016.

Name of Work: - **DISPOSAL CHANNEL ALONG CANTT: AREA @ BADIN.**

a) Construction of Pump House, b) Construction RCC Sump /Tank 16'x8' c) Providing & laying, Jointing & Testing A.C Rising Main 24" Q dia for disposal of wet weather flow from Cantt. Badin 2050 Rft. d) Supplying & Installing 60 BHP A.C Electric Motor for disposal of storm water flow from cantt. Badin and adjoining area e) External Electrification. f) Diesel Generator 50 KVA (02 No.) along Cantonment Area @ Badin. **(Package No. 3) (ADP No. 648)**

S. No.	Name of Contractor	Date of Receipt of Sealed Quotation	Percentage rate entered in contract documents	Remarks.
1.	M/s Shaikh Baz Khan & Brothers	22.02.2016	38.94% above	PO No. 01900920, Dated: 22.02.2016 Mezan Bank Saddar Hyderabad for Rs. 1,245,000/-
2.	M/s Thadani Enterprises		14.97% above	CDR No. 5000, Dated: 22.02.2016 of Summit Bank Hyderabad Branch for Rs. 1,120,000/-
3.	M/s Haji Sirajuddin Soomro Contractor & Engineers	22.02.2016	26.35% above	CDR 0685208, Dated: 22.02.2016, Bank Alfalah Limited Main Branch Saddar Hyderabad for Rs. 1,225,000/-

**Chairman**

**Mr. Khair Mohammad Dahri**  
Director  
Left Bank Canals (AWB), Badin

**Member / Secretary**  
**Fawad Ahmed Memon**  
Executive Engineer  
Drainage Division, Badin

**Member**  
**Bhawani Shankar**  
Executive Engineer  
Public Health Department  
Badin

**Member**  
**MAJOR IFTIKHAR**  
Head Quarter 206-Brigade  
Badin Cantonment

**Member**  
**Rac Mushtaque Ahmed**  
Divisional Accounts Officer  
Drainage Division, Badin

**Member**  
**Akbar Azam Rashdi**  
Technical Officer  
SIDA Hyderabad

**Member**  
**Syed Aijaz Ali Shah**  
Executive Engineer  
Akram Wah Division, Badin



**COMPARATIVE STATEMENT**  
**GOVERNMENT OF SINDH IRRIGATION DEPARTMENT**  
**Executive Engineer Drainage Division Badin**

Tenders invited vide this office Letter No. TC/G-55/DD/33, Dated: 01.02.2016.

Name of Work:- **CONSTRUCTION OF (13 NO.) SOLAR TUBE WELL (80 FT. DEPTH) OF 1.0 CUSEC CAPACITY ALONG IN & OUT CANTONMENT AREA @ BADIN. (Package No. 4) (ADP No. 648)**

S. No.	Name of Contractor	Date of Receipt of Sealed Quotation	Percentage rate entered in contract documents	Remarks.
1.	M/s Umar Jan & Company	22.02.2016	39.52% 95 one	CD No. FWDC 0327364, Dated 22.02.2016 of First Women Bank Ltd. Sukkur Branch for Rs. 1,000,000/-
2.	M/s Thadani Enterprises Brothers	22.02.2016	14.94% 76 one	CDR No. 5001, Dated: 22.02.2016 of Summit Bank Hyderabad Branch for Rs. 1,000,000/-
3.	M/s Haji Sirajuddin Soomro Contractor & Engineers	22.02.2016	23.27% 96 one	CDR 0685209, Dated: 22.02.2016, Bank Alfalah Limited Main Branch Saddar Hyderabad for Rs. 1,000,000/-

Chairman

**Mr. Khair Mohammad Dahri**  
Director  
Left Bank Canals (AWB), Badin

**Member / Secretary**  
**Fawad Ahmed Memon**  
Executive Engineer  
Drainage Division, Badin

**Member**  
**Rao Mushtaque Ahmed**  
Divisional Accounts Officer  
Drainage Division, Badin

**Member**  
**Bhawani Shankar**  
Executive Engineer  
Public Health Department  
Badin

**Member**  
**Akbar Azam Rashdi**  
Technical Officer  
SIDA Hyderabad

**Member**  
**MAJOR IFTIKHAR**  
Head Quarter 206-Brigade  
Badin Cantonment

**Member**  
**Syed Aijaz Ali Shah**  
Executive Engineer  
Akram Wah Division, Badin



**COMPARATIVE STATEMENT**  
**GOVERNMENT OF SINDH IRRIGATION DEPARTMENT**  
**Executive Engineer Drainage Division Badin**

Tenders invited vide this office Letter No. TC/G-55/DD/33, Dated: 01.02.2016.

Name of Work:- **CONSTRUCTION OF (13 NO.) SOLAR TUBE WELL (80 FT. DEPTH) OF 1.0 CUSEC CAPACITY ALONG IN & OUT CANTONMENT AREA @ BADIN. (Package No. 5) (ADP No. 648)**

S. No.	Name of Contractor	Date of Receipt of Sealed Quotation	Percentage rate entered in contract documents	Remarks.
1.	M/s Umar Jan & Company	22.02.2016	39.52% Bare	CD No. FWDC 0327361, Dated: 22.02.2016 of First Women Bank Ltd. Sukkur Branch for Rs. 1,000,000/-
2.	M/s Thadani Enterprises Brothers	22.02.2016	23.27% Bare	CDR No. 5002, Dated: 22.02.2016 of Summit Bank Hyderabad Branch for Rs. 1,000,000/-
3.	M/s Haji Sirajuddin Soomro Contractor & Engineers	22.02.2016	14.97% Bare	CDR 0685210, Dated: 22.02.2016, Bank Alfalah Limited Main Branch Saddar Hyderabad for Rs. 1,000,000/-

**Chairman**

**Mr. Khair Mohammad Dahri**  
Director  
Left Bank Canals (AWB), Badin

**Member / Secretary**  
**Fawad Ahmed Memon**  
Executive Engineer  
Drainage Division, Badin

**Member**  
**Rao Mushtaque Ahmed**  
Divisional Accounts Officer  
Drainage Division, Badin

**Member**  
**Bhawani Shankar**  
Executive Engineer  
Public Health Department  
Badin

**Member**  
**Akbar Azam Rashdi**  
Technical Officer  
SIDA Hyderabad

**Member**  
**MAJOR IFTIKHAR**  
Head Quarter 206-Brigade  
Badin Cantonment

**Member**  
**Syed Aijaz Ali Shan**  
Executive Engineer  
Akram Wah Division, Badin



**COMPARATIVE STATEMENT**  
**GOVERNMENT OF SINDH IRRIGATION DEPARTMENT**  
**Executive Engineer Drainage Division Badin**

Tenders invited vide this office Letter No. TC/G-55/DD/33, Dated: 01.02.2016.

Name of Work:- **CONSTRUCTION OF (12 NO.) SOLAR TUBE WELL (80 FT. DEPTH) OF 1.0 CUSEC CAPACITY ALONG IN & OUT CANTONMENT AREA @ BADIN. (Package No. 6) (ADP No. 648)**

S. No.	Name of Contractor	Date of Receipt of Sealed Quotation	Percentage rate entered in contract documents	Remarks.
1.	M/s Haji Sirajuddin Soomro Contractor & Engineers	22.02.2016	14.99% above	CDR 0685211, Dated: 22.02.2016, Bank Alfalah Limited Main Branch Saddar Hyderabad for Rs. 915,000/-
2.	M/s Umar Jan & Company	22.02.2016	39.52% above	CD No. FWDC 0327362, Dated: 22.02.2016 of First Women Bank Ltd. Sukkur Branch for Rs. 1,000,000/-
3.	M/s Thadani Enterprises Brothers	22.02.2016	23.29% above	CDR No. 5003, Dated: 22.02.2016 of Summit Bank Hyderabad Branch for Rs. 925,000/-

**Chairman**

**Mr. Khair Mohammad Dahri**  
Director  
Left Bank Canals (AWB), Badin

**Member / Secretary**  
**Fawad Ahmed Memon**  
Executive Engineer  
Drainage Division, Badin

**Member**  
**Bhawani Shankar**  
Executive Engineer  
Public Health Department  
Badin

**Member**  
**MAJOR**  
**IFTIKHAR**  
Head Quarter 206-Brigade  
Badin Cantonment

**Member**  
**Rao Mushtaque Ahmed**  
Divisional Accounts Officer  
Drainage Division, Badin

**Member**  
**Akbar Azam Rashdi**  
Technical Officer  
SIDA Hyderabad

**Member**  
**Syed Aijaz Ali Shah**  
Executive Engineer  
Akram Wah Division, Badin



**COMPARATIVE STATEMENT**  
**GOVERNMENT OF SINDH IRRIGATION DEPARTMENT**  
**Executive Engineer Drainage Division Badin**

Tenders invited vide this office Letter No. TC/G-55/DD/33, Dated: 01.02.2016.

Name of Work:- CONSTRUCTION OF (12 NO.) SOLAR TUBE WELL (80 FT. DEPTH) OF 1.0 CUSEC CAPACITY ALONG IN & OUT CANTONMENT AREA @ BADIN. (Package No. 7) (ADP No. 648)

S. No.	Name of Contractor	Date of Receipt of Sealed Quotation	Percentage rate entered in contract documents	Remarks.
1.	M/s Umar Jan & Company	22.02.2016	39.52% above	CD No. FWDC 0327363, Dated: 22.02.2016 of First Women Bank Ltd. Sukkur Branch for Rs. 1,000,000/-
2.	M/s Thadani Enterprises Brothers	22.02.2016	23.27% above	CDR No. 5004, Dated: 22.02.2016 of Summit Bank Hyderabad Branch for Rs. 925,000/-
3.	M/s Haji Sirajuddin Soomro Contractor & Engineers	22.02.2016	14.97% above	CDR 0685212, Dated: 22.02.2016, Bank Alfalah Limited Main Branch Saddar Hyderabad for Rs. 915,000/-

~~Chairman~~

**Mr. Khair Mohammad Dahri**  
Director  
Left Bank Canals (AWB), Badin

**Member / Secretary**  
**Fawad Ahmed Memon**  
Executive Engineer  
Drainage Division, Badin

**Member**  
**Rao Mushtaque Ahmed**  
Divisional Accounts Officer  
Drainage Division, Badin

**Member**  
**Bhawani Shankar**  
Executive Engineer  
Public Health Department  
Badin

**Member**  
**Akbar Azam Rashdi**  
Technical Officer  
SIDA Hyderabad

**Member**  
**MAJOR IFTIKHAR**  
Head Quarter 206-Brigade  
Badin Cantonment

**Member**  
**Syed Aijaz Ali Shah**  
Executive Engineer  
Akram Wah Division, Badin



# OFFICE OF THE EXECUTIVE ENGINEER DRAINAGE DIVISION, BADIN

E-mail : drainagedivisionbadin@gmail.com

Off. No. 022-9210347


## TECHNICAL EVALUATION REPORT / BIDDERS QUALIFICATION REPORT

NIT No. TC/G-55/DD/33, Dated: 01.02.2016

1.	Name of Procuring Agency	Executive Engineer Drainage Division, Badin
2.	Tender Reference No.	No. TC/G-55/DD/33, Dated: 01.02.2016
3.	Tender description / Name of work / item	CONSTRUCTION OF PROPOSED DRAIN AND STONE PITCHING FROM RD. 0.0 TO 14.0 IN CANTONMENT AREA BADIN. (Package No. 1)
4.	Method of Procurement	Single Stage – One Envelope Procedure
5.	Name of Firm / Bidder	M/s Thadani Enterprises
6.	N. T. N	Available
7.	Registration with P.E.C	Available
8.	Relevant Experience	Available
9.	Turnover of at least last three years	Available
10.	Funds / Budget	Available
11.	02% Earnest Money	Available
12.	Tender Fee / Cost of Bidding Documents.	Deposited.


  
Chairman

**Mr. Khair Mohammad Dahri**  
Director  
Left Bank Canals (AWB), Badin

  
**Member / Secretary**  
**Fawad Ahmed Memon**  
Executive Engineer  
Drainage Division, Badin

  
**Member**  
**Rao Mushtaque Ahmed**  
Divisional Accounts Officer  
Drainage Division, Badin

  
**Member**  
**Bhawani Shankar**  
Executive Engineer  
Public Health Department  
Badin

  
**Member**  
**Akbar Azam Rashdi**  
Technical Officer  
SIDA Hyderabad

  
**Member**  
**IFTIKHAR**  
**MAJOR**  
Head Quarter 206-Brigade  
Badin Cantonment

  
**Member**  
**Syed Aijaz Ali Shah**  
Executive Engineer  
Akram Wah Division, Badin



# OFFICE OF THE EXECUTIVE ENGINEER DRAINAGE DIVISION, BADIN

E-mail : drainagedivisionbadin@gmail.com

Off. No. 022-9210347


## TECHNICAL EVALUATION REPORT / BIDDERS QUALIFICATION REPORT

NIT No. TC/G-55/DD/33, Dated: 01.02.2016

1.	Name of Procuring Agency	Executive Engineer Drainage Division, Badin
2.	Tender Reference No.	No. TC/G-55/DD/33, Dated: 01.02.2016
3.	Tender description / Name of work / item	CONSTRUCTION OF INTERNAL DISPOSAL CHANNELS FROM TUBE WELLS TO PROPOSED DRAIN I/C ROAD CULVERT AND RCC PIPE ALONG BADIN CANTT: a) Construction of Internal Disposal Channels from Tube wells to proposed drain. b) Construction of (01 No.) Road Culvert, C) Construction of (02 No.) RCC Pipe Inlets. (Package No. 2)
4.	Method of Procurement	Single Stage – One Envelope Procedure
5.	Name of Firm / Bidder	M/s. Haji Sirajuddin Soomro Contractor & Engineers
6.	N. T . N	Available
7.	Registration with P.E.C	Available
8.	Relevant Experience	Available
9.	Turnover of at least last three years	Available
10.	Funds / Budget	Available
11.	02% Earnest Money	Available
12.	Tender Fee / Cost of Bidding Documents.	Deposited.

  
Chairman


**Mr. Khair Mohammad Dahri**  
Director  
Left Bank Canals (AWB), Badin

  
**Member / Secretary**  
**Fawad Ahmed Memon**  
Executive Engineer  
Drainage Division, Badin

  
**Member**  
**Bhawani Shankar**  
Executive Engineer  
Public Health Department  
Badin

  
**Member**  
**IFTIKHAR MAJOR**  
Head Quarter 206-Brigade  
Badin Cantonment

  
**Member**  
**Rao Mushtaque Ahmed**  
Divisional Accounts Officer  
Drainage Division, Badin

  
**Member**  
**Akbar Azam Rashdi**  
Technical Officer  
SIDA Hyderabad

  
**Member**  
**Syed Aijaz Ali Shah**  
Executive Engineer  
Akram Wah Division, Badin





# OFFICE OF THE EXECUTIVE ENGINEER DRAINAGE DIVISION, BADIN

E-mail : drainagedivisionbadin@gmail.com

Off. No. 022-9210347


## TECHNICAL EVALUATION REPORT / BIDDERS QUALIFICATION REPORT

NIT No. TC/G-55/DD/33, Dated: 01.02.2016

1.	Name of Procuring Agency	Executive Engineer Drainage Division, Badin
2.	Tender Reference No.	No. TC/G-55/DD/33, Dated: 01.02.2016
3.	Tender description / Name of work / item	DISPOSAL CHANNEL ALONG CANTT: AREA @ BADIN. a) Construction of Pump House, b) Construction RCC Sump /Tank 16'x8' c) Providing & laying, Jointing & Testing A.C Rising Main 24" Q dia for disposal of wet weather flow from Cantt. Badin 2050 Rft. d) Supplying & Installing 60 BHP A.C Electric Motor for disposal of storm water flow from cantt. Badin and adjoining area e) External Electrification.(f) Diesel Generator 50 KVA (02 No.) along Cantonment Area @ Badin (Package No.3)
4.	Method of Procurement	Single Stage – One Envelope Procedure
5.	Name of Firm / Bidder	M/s. Thadani Enterprises
6.	N. T . N	Available
7.	Registration with P.E.C	Available
8.	Relevant Experience	Available
9.	Turnover of at least last three years	Available
10.	Funds / Budget	Available
11.	02% Earnest Money	Available
12.	Tender Fee / Cost of Bidding Documents.	Deposited.

  
~~Chairman~~


**Mr. Khair Mohammad Dahri**  
Director  
Left Bank Canals (AWB), Badin

  
**Member / Secretary**  
**Fawad Ahmed Memon**  
Executive Engineer  
Drainage Division, Badin

  
**Member**  
**Bhawani Shankar**  
Executive Engineer  
Public Health Department  
Badin

  
**Member**  
**FTIKHAR MAJOR**  
Head Quarter 206-Brigade  
Badin Cantonment

  
**Member**  
**Rao Mushtaque Ahmed**  
Divisional Accounts Officer  
Drainage Division, Badin

  
**Member**  
**Akbar Azam Rashdi**  
Technical Officer  
SIDA Hyderabad

  
**Member**  
**Syed Aijaz Ali Shah**  
Executive Engineer  
Akram Wah Division, Badin



# OFFICE OF THE EXECUTIVE ENGINEER DRAINAGE DIVISION, BADIN

E-mail : drainagedivisionbadin@gmail.com

Off. No. 022-9210347


## TECHNICAL EVALUATION REPORT / BIDDERS QUALIFICATION REPORT

NIT No. TC/G-55/DD/33, Dated: 01.02.2016

1.	Name of Procuring Agency	Executive Engineer Drainage Division, Badin
2.	Tender Reference No.	No. TC/G-55/DD/33, Dated: 01.02.2016
3.	Tender description / Name of work / item	CONSTRUCTION OF (13 NO.) SOLAR TUBE WELL (80 FT. DEPTH) OF 1.0 CUSEC CAPACITY ALONG IN & OUT CANTONMENT AREA @ BADIN. (Package No. 4)
4.	Method of Procurement	Single Stage – One Envelope Procedure
5.	Name of Firm / Bidder	M/s. Thadani Enterprises
6.	N. T. N	Available
7.	Registration with P.E.C	Available
8.	Relevant Experience	Available
9.	Turnover of at least last three years	Available
10.	Funds / Budget	Available
11.	02% Earnest Money	Available
12.	Tender Fee / Cost of Bidding Documents.	Deposited.

  
**Chairman**


**Mr. Khair Mohammad Dahri**  
Director  
Left Bank Canals (AWB), Badin

  
**Member / Secretary**  
**Fawad Ahmed Memon**  
Executive Engineer  
Drainage Division, Badin

  
**Member**  
**Bhawani Shankar**  
Executive Engineer  
Public Health Department  
Badin

  
**Member**  
**IFTIKHAR MAJOR**  
Head Quarter 206-Brigade  
Badin Cantonment

  
**Member**  
**Rao Mushtaque Ahmed**  
Divisional Accounts Officer  
Drainage Division, Badin

  
**Member**  
**Akbar Azam Rashdi**  
Technical Officer  
SIDA Hyderabad

  
**Member**  
**Syed Aijaz Ali Shah**  
Executive Engineer  
Akram Wah Division, Badin



# OFFICE OF THE EXECUTIVE ENGINEER DRAINAGE DIVISION, BADIN

E-mail : drainagedivisionbadin@gmail.com

Off: No. 022-9210347


## TECHNICAL EVALUATION REPORT / BIDDERS QUALIFICATION REPORT

NIT No. TC/G-55/DD/33, Dated: 01.02.2016

1.	Name of Procuring Agency	Executive Engineer Drainage Division, Badin
2.	Tender Reference No.	No. TC/G-55/DD/33, Dated: 01.02.2016
3.	Tender description / Name of work / item	CONSTRUCTION OF (13 NO.) SOLAR TUBE WELL (80 FT. DEPTH) OF 1.0 CUSEC CAPACITY ALONG IN & OUT CANTONMENT AREA @ BADIN. (Package No. 5)
4.	Method of Procurement	Single Stage – One Envelope Procedure
5.	Name of Firm / Bidder	M/s. Haji Sirajuddin Soomro Contractor & Engineers
6.	N. T. N	Available
7.	Registration with P.E.C	Available
8.	Relevant Experience	Available
9.	Turnover of at least last three years	Available
10.	Funds / Budget	Available
11.	02% Earnest Money	Available
12.	Tender Fee / Cost of Bidding Documents.	Deposited.



**Chairman**  
**Mr. Khair Mohammad Dahri**  
Director  
Left Bank Canals (AWB), Badin



**Member / Secretary**  
**Fawad Ahmed Memon**  
Executive Engineer  
Drainage Division, Badin




**Member**  
**Bhawani Shankar**  
Executive Engineer  
Public Health Department  
Badin



**Member**  
**IFTIKHAR MAJOR**  
Head Quarter 206-Brigade  
Badin Cantonment



**Member**  
**Rao Mushtaque Ahmed**  
Divisional Accounts Officer  
Drainage Division, Badin



**Member**  
**Akbar Azam Rashdi**  
Technical Officer  
SIDA Hyderabad



**Member**  
**Syed Aijaz Ali Shah**  
Executive Engineer  
Akram Wah Division, Badin



# OFFICE OF THE EXECUTIVE ENGINEER DRAINAGE DIVISION, BADIN

E-mail : drainagedivisionbadin@gmail.com

Off. No. 022-9210347


## TECHNICAL EVALUATION REPORT / BIDDERS QUALIFICATION REPORT

NIT No. TC/G-55/DD/33, Dated: 01.02.2016

1.	Name of Procuring Agency	Executive Engineer Drainage Division, Badin
2.	Tender Reference No.	No. TC/G-55/DD/33, Dated: 01.02.2016
3.	Tender description / Name of work / item	CONSTRUCTION OF (12 NO.) SOLAR TUBE WELL (80 FT. DEPTH) OF 1.0 CUSEC CAPACITY ALONG IN & OUT CANTONMENT AREA @ BADIN. (Package No. 6)
4.	Method of Procurement	Single Stage – One Envelope Procedure
5.	Name of Firm / Bidder	M/s. Haji Sirajuddin Soomro Contractor & Engineers
6.	N. T . N	Available
7.	Registration with P.E.C	Available
8.	Relevant Experience	Available
9.	Turnover of at least last three years	Available
10.	Funds / Budget	Available
11.	02% Earnest Money	Available
12.	Tender Fee / Cost of Bidding Documents.	Deposited.

  
Chairman


**Mr. Khair Mohammad Dahri**  
Director  
Left Bank Canals (AWB), Badin

  
Member / Secretary  
**Fawad Ahmed Memon**  
Executive Engineer  
Drainage Division, Badin

  
Member  
**Bhawani Shankar**  
Executive Engineer  
Public Health Department  
Badin

  
Member  
**IFTIKHAR  
MAJOR**  
Head Quarter 206-Brigade  
Badin Cantonment

  
Member  
**Rao Mushtaque Ahmed**  
Divisional Accounts Officer  
Drainage Division, Badin

  
Member  
**Akbar Azam Rashdi**  
Technical Officer  
SIDA Hyderabad

  
Member  
**Syed Aijaz Ali Shah**  
Executive Engineer  
Akram Wah Division, Badin



# OFFICE OF THE EXECUTIVE ENGINEER DRAINAGE DIVISION, BADIN

E-mail : drainagedivisionbadin@gmail.com

Off: No. 022-9210347

## TECHNICAL EVALUATION REPORT / BIDDERS QUALIFICATION REPORT

NIT No. TC/G-55/DD/33, Dated: 01.02.2016

1.	Name of Procuring Agency	Executive Engineer Drainage Division, Badin
2.	Tender Reference No.	No. TC/G-55/DD/33, Dated: 01.02.2016
3.	Tender description / Name of work / item	CONSTRUCTION OF (12 NO.) SOLAR TUBE WELL (80 FT. DEPTH) OF 1.0 CUSEC CAPACITY ALONG IN & OUT CANTONMENT AREA @ BADIN. (Package No. 7)
4.	Method of Procurement	Single Stage – One Envelope Procedure
5.	Name of Firm / Bidder	M/s. Haji Sirajuddin Soomro Contractor & Engineers
6.	N. T . N	Available
7.	Registration with P.E.C	Available
8.	Relevant Experience	Available
9.	Turnover of at least last three years	Available
10.	Funds / Budget	Available
11.	02% Earnest Money	Available
12.	Tender Fee / Cost of Bidding Documents.	Deposited.

**Chairman**  
**Mr. Khair Mohammad Dahri**  
Director  
Left Bank Canals (AWB), Badin

**Member / Secretary**  
**Fawad Ahmed Memon**  
Executive Engineer  
Drainage Division, Badin

**Member**  
**Bhawani Shankar**  
Executive Engineer  
Public Health Department  
Badin

**Member**  
**IFTIKHAR MAJOR**  
Head Quarter 206-Brigade  
Badin Cantonment

**Member**  
**Rao Mushtaque Ahmed**  
Divisional Accounts Officer  
Drainage Division, Badin

**Member**  
**Akbar Azam Rashdi**  
Technical Officer  
SIDA Hyderabad

**Member**  
**Syed Aijaz Ali Shah**  
Executive Engineer  
Akram Wah Division, Badin



# OFFICE OF THE EXECUTIVE ENGINEER DRAINAGE DIVISION, BADIN

E-mail : drainagedivisionbadin@gmail.com

Off. No. 022-9210347

No. TC/ G-148/DD/ 65 of 2016 Badin, Dated: 22/ 02 / 2016

Subject:- PROCUREMENT COMMITTEE MEETING HELD ON 22.02.2016.

1/- A meeting of the procurement committee was held in the office of Executive Engineer, Drainage Division, Badin @ Head Quarter 206 Brigade Badin Cantonment under the Chairmanship of Director, Left Bank Canals Area Water Board, Badin.

2/- The below mentioned member of committee attended the meeting to discuss the bids invited for the procurement of the works vide Executive Engineer Drainage Division, Badin vide letter No. TC/G-55/DD/33, Dated: 01.02.2016 and subsequently hoisted on the web site at S. # 26452, Dated: 11.02.2016 of Sindh Public Procurement Regulatory Authority Government of Sindh.

Following attended the meeting.

1. Khair Muhammad Dahri  
DIRECTOR  
Left Bank Canals (AWB), Badin Chairman
2. Fawad Ahmed Memon  
Executive Engineer  
Drainage Division, Badin Secretary / Member
3. Rao Mushtaque Ahmed  
Divisional Accounts Officer  
Drainage Division, Badin Member
4. Bhawani Shankar  
Executive Engineer  
Public Health Department, Badin Member
5. Akbar Azam Rashdi  
Technical Officer  
SIDA, Hyderabad Member
6. Iftikhar  
Major  
Head Quarter 206 Brigade  
Badin Cantonment Member
7. Syed Aijaz Ali Shah  
Executive Engineer  
Akram Wah Division, Badin Member

3/- During the course of meeting following discussion were made by the committee.

- i. The tender received back on 22.02.2016 @ 3:00 PM and was Opened before the procure committee in presence of representatives of participants.
- ii. The method of the bidding documents observed as single envelop.
- iii. The tender was opened on 22.02.2016 before the tendering opening committee.

**P. # 01) CONSTRUCTION OF PROPOSED DRAIN AND STONE PITCHING FROM RD. 0.0 TO 14.0 IN CANTONMENT AREA BADIN. (ADP No. 648)**

4/- The Committee was informed that (05) five Nos. bidders have purchase the bidding documents up to 19.02.2016 and (03) three Nos. have responded the bids on 22.02.2016 upto 2:00 PM in the office of Executive Engineer Drainage Division, Badin @ Head Quarter 206 Brigade Badin Cantonment.

5/- During the opening of tender received following status was found.

S. No.	Name of Firm or Bidder	Ranking in terms of cost	Remarks
1.	M/s Thadani Enterprises	1 <sup>st</sup>	Lowest
2.	M/s Haji Sirajuddin Soomro Contractor & Engineers	2 <sup>nd</sup>	Highest
3.	M/s Malani Construction Company	3 <sup>rd</sup>	Highest

**P.# 2) CONSTRUCTION OF INTERNAL DISPOSAL CHANNELS FROM TUBE WELLS TO PROPOSED DRAIN I/C ROAD CULVERT AND RCC PIPE ALONG BADIN CANTT:**

a) Construction of Internal Disposal Channels from Tube wells to proposed drain. b) Construction of (01 No.) Road Culvert, C) Construction of (02 No.) RCC Pipe Inlets. (ADP No. 648)

4/- The Committee was informed that (06) Six Nos. bidders have purchase the bidding documents up to 19.02.2016 and (03) three Nos. have responded the bids on 22.02.2016 upto 2:00 PM in the office of Executive Engineer Drainage Division, Badin @ Head Quarter 206 Brigade Badin Cantonment.

5/- During the opening of tender received following status was found.

S. No.	Name of Firm or Bidder	Ranking in terms of cost	Remarks
1.	M/s Haji Sirajuddin Soomro Contractor & Engineers	1 <sup>st</sup>	Lowest
2.	M/s Thadani Enterprises	2 <sup>nd</sup>	Highest
3.	M/s Malani Construction Company	3 <sup>rd</sup>	Highest

**P. # 3) DISPOSAL CHANNEL ALONG CANTT: AREA @ BADIN.**

a) Construction of Pump House, b) Construction RCC Sump /Tank 16'x8' c) Providing & laying, Jointing & Testing A.C Rising Main 24" Q dia for disposal of wet weather flow from Cantt. Badin 2050 Rft. d) Supplying & Installing 60 BHP A.C Electric Motor for disposal of storm water flow from cantt. Badin and adjoining area e) External Electrification.f) Diesel Generator 50 KVA (02 No.) along Cantonment Area @ Badin. **(ADP No. 648)**

4/- The Committee was informed that (03) Three Nos. bidders have purchase the bidding documents up to 19.02.2016 and (03) three Nos. have responded the bids on 22.02.2016 upto 2:00 PM in the office of Executive Engineer Drainage Division, Badin @ Head Quarter 206 Brigade Badin Cantonment.

5/- During the opening of tender received following status was found.

S. No.	Name of Firm or Bidder	Ranking in terms of cost	Remarks
1.	M/s Thadani Enterprises	1 <sup>st</sup>	Lowest
2.	M/s Haji Sirajuddin Soomro Contractor & Engineers	2 <sup>nd</sup>	Highest
3.	M/s Shaikh Baz Khan & Brothers	3 <sup>rd</sup>	Highest

**P. # 4) CONSTRUCTION OF (13 NO.) SOLAR TUBE WELL (80 FT. DEPTH) OF 1.0 CUSEC CAPACITY ALONG IN & OUT CANTONMENT AREA @ BADIN. (ADP No. 648)**

4/- The Committee was informed that (04) Three Nos. bidders have purchase the bidding documents up to 19.02.2016 and (03) three Nos. have responded the bids on 22.02.2016 upto 2:00 PM in the office of Executive Engineer Drainage Division, Badin @ Head Quarter 206 Brigade Badin Cantonment.

5/- During the opening of tender received following status was found.

S. No.	Name of Firm or Bidder	Ranking in terms of cost	Remarks
1.	M/s Thadani Enterprises	1 <sup>st</sup>	Lowest
2.	M/s Haji Sirajuddin Soomro Contractor & Engineers	2 <sup>nd</sup>	Highest
3.	M/s Umar Jan & Company	3 <sup>rd</sup>	Highest

**P. # 5) CONSTRUCTION OF (13 NO.) SOLAR TUBE WELL (80 FT. DEPTH) OF 1.0 CUSEC CAPACITY ALONG IN & OUT CANTONMENT AREA @ BADIN. (ADP No. 648)**

4/- The Committee was informed that (04) Three Nos. bidders have purchase the bidding documents up to 19.02.2016 and (03) three Nos. have responded the bids on 22.02.2016 upto 2:00 PM in the office of Executive Engineer Drainage Division, Badin @ Head Quarter 206 Brigade Badin Cantonment.



5/-

During the opening of tender received following status was found.

S. No.	Name of Firm or Bidder	Ranking in terms of cost	Remarks
1.	M/s Haji Sirajuddin Soomro Contractor & Engineers	1 <sup>st</sup>	Lowest
2.	M/s Thadani Enterprises	2 <sup>nd</sup>	Highest
3.	M/s Umar Jan & Company	3 <sup>rd</sup>	Highest

**P. # 6) CONSTRUCTION OF (12 NO.) SOLAR TUBE WELL (80 FT. DEPTH) OF 1.0 CUSEC CAPACITY ALONG IN & OUT CANTONMENT AREA @ BADIN. (ADP No. 648)**

4/-

The Committee was informed that (04) Three Nos. bidders have purchase the bidding documents up to 19.02.2016 and (03) three Nos. have responded the bids on 22.02.2016 upto 2:00 PM in the office of Executive Engineer Drainage Division, Badin @ Head Quarter 206 Brigade Badin Cantonment.

5/-

During the opening of tender received following status was found.

S. No.	Name of Firm or Bidder	Ranking in terms of cost	Remarks
1.	M/s Haji Sirajuddin Soomro Contractor & Engineers	1 <sup>st</sup>	Lowest
2.	M/s Thadani Enterprises	2 <sup>nd</sup>	Highest
3.	M/s Umar Jan & Company	3 <sup>rd</sup>	Highest

**P.# 7) CONSTRUCTION OF (12 NO.) SOLAR TUBE WELL (80 FT. DEPTH) OF 1.0 CUSEC CAPACITY ALONG IN & OUT CANTONMENT AREA @ BADIN. (ADP No. 648)**

4/-

The Committee was informed that (04) Three Nos. bidders have purchase the bidding documents up to 19.02.2016 and (03) three Nos. have responded the bids on 22.02.2016 upto 2:00 PM in the office of Executive Engineer Drainage Division, Badin @ Head Quarter 206 Brigade Badin Cantonment.

5/-

During the opening of tender received following status was found.

S. No.	Name of Firm or Bidder	Ranking in terms of cost	Remarks
1.	M/s Haji Sirajuddin Soomro Contractor & Engineers	1 <sup>st</sup>	Lowest
2.	M/s Thadani Enterprises	2 <sup>nd</sup>	Highest
3.	M/s Umar Jan & Company	3 <sup>rd</sup>	Highest

6/-

The Committee thoroughly scrutinized each case / tender documents by comparing earthematically and financially with sanction estimates / bill of quantities and criteria for eligibility and minimum qualification as per bidding documents.

### RECOMMENDATION

7/-

After due deliberation / scrutiny of each Tender Document by the Committee, it was recommended that lowest evaluated responsive Bidder may be awarded the respective Tender.


### DECISION


5/-

In view of Para No. 7 of this report it is decided that Tenders are being awarded to above mention lowest responsive Bidders accordingly.


  
**Chairman**

**Mr. Khair Mohammad Dahri**  
Director  
Left Bank Canals (AWB), Badin

  
**Member / Secretary**  
**Fawad Ahmed Memon**  
Executive Engineer  
Drainage Division, Badin

  
**Member**  
**Rao Mushtaque Ahmed**  
Divisional Accounts Officer  
Drainage Division, Badin

  
**Member**  
**Bhawani Shankar**  
Executive Engineer  
Public Health Department  
Badin

  
**Member**  
**Akbar Azam Rashdi**  
Technical Officer  
SIDA Hyderabad

  
**Member**  
**MAJOR**  
**IFTIKHAR**  
Head Quarter 206-Brigade  
Badin Cantonment

  
**Member**  
**Syed Aijaz Ali Shah**  
Executive Engineer  
Akram Wah Division, Badin

اس کا شہر  
پتوئل و  
اس کے اہل  
کا کٹر کٹر  
نایا کٹر  
ان سے اس  
ہزار کی ہر

نمبر 16  
نمبر 9  
نمبر 8

رہی، ان موقعی تی فیصلہ سرتکی جی امز  
سکتی ۽ والد عبدالرزاق سرتکی چو تہ اسان  
جی جگر جی تکزوی کی اغوا نئی پو 9 سال  
ٹی ویا آهن سرتیر کورت جی پاتمردی  
نو تینس بعد کیس ای تی سی کورت  
شکاریو ڏانهن منتقل کیو ویو جتی پن 2  
سالن کان حاضریون هلی رهینون آهن پولیس  
نیائی کی آزاد کرائی پر ناکار وئی آھی،  
کیترائی ایس ایس بی آیا آهن پر کتھن بہ  
ہارزی کی آزاد ناهی کرایو، هنن چو تہ اغوا  
مامری جو سنڌ جی وڌی وزیر سید ناصر علی  
شاھ نو تیس ورتو آھی، انھی تی عمل کیو  
وئی، ضلعي جیکب آباد ۾ مقرر کیل ایس  
ایس بی ۽ ڳوڙھی حسن ٿاڻی تی مقرر کیل ڊی  
ایس بی تی تبدیل کري تحرک ورتو وئی تہ  
نیگري زادی وئی ویندی، هنن چو تہ منهنجي  
نیگري جو کيس فوجی کورت ڏانهن منتقل  
کیو وئی، هو ڏانهن بک هڙتالی کتھن تی  
ایس تی پی جی ضلعي صدر هارون الرشید  
نومری، هومي عوامی تحریک جی ایڊووکیٹ  
روشن کترائی، اعجاز کترائی، جی یو آ جی  
میر حسن پری، قاری سجاد احمد سومری ۽  
بین بهی حمایت کئی، هنن چو تہ فیضیلا  
سرتکی اغوا معاملی تی جی آئی تی قاتر کئی  
وئی، ایس تی پی آڳوڻ چو تہ سبھی سنڌ ۾  
فیضیلا سرتکی جی آزادی لاءِ احتجاج کیو  
ویندو، بی پی پی آھی، پنج اطلاع آهن تہ وڌی  
وزیر جی نو تیس بعد پولیس تحرک ویندی  
فیضیلا جی وارنن کی ڏنگائی ڏیندو تہ جوابدارن  
کی گرفتار کري ورتو آھی، فیضیلا سرتکی  
جی آزادی لاءِ سمورین پارٽین سنڌ سطح تی  
احتجاج کري چکین آهن، ضلعي ۾ کيس

مولانا طارق جمیل ۽ کرکٽر شاھد آفریدی  
۽ انهن جی سرپرستی جی دعویٰ ڪندڙ سمیت  
سورن ماڻهو گرفتار ٿیندا، مولا بخش چانڊیو  
چو تہ وفاقی حکومت کی گهرجي تہ ضویغ  
جی اختیارین جو احترام کري اسین وفاق جا  
آھی حکر تہ مجتدائین جی عوام جی  
خلاف هوندا وفاق حکومت پنجاب ۾ ڏندی  
جی زور تی اکثریت سان کامیاب ٿئی تی،  
کئی اچن کانپوءِ انھی ۾ تڪراری وئی ٿو ۽  
آھی تینن صون جو احترام ۽ عزت تہ ٿا ڪن ۽  
مینڊیت کئی تسلیم نہ ٿا ڪن، مولا بخش  
چانڊیو چو تہ آدم شماری شفاف هئڻ گهرجي  
۽ سنڌ جی اصلوکی وارنن جی اکثریت کی  
تسلیم ڪرڻ گهرجي جیکڏهن سنڌ جی  
وارنن کی اقلیت ۾ تبدیل ڪرڻ جی سازش  
کئی وئی تہ اهو پاکستان پیپلز پارٽی  
فیصلو قبول نہ ڪندی پاکستان پیپلز پارٽی  
۽ سنڌ حکومت ان لاءِ ڪوششون کري رهی  
آھی، هڪ سوال جی جواب ۾ مولا بخش  
چانڊیو چو تہ سنڌ ۾ غیر ملکین جی آبادی  
وڌو، مسئلو آھی اسان کی ان تی خدشا آهن  
انهی مسئلی تی سنڌ حکومت ۽ بی بی قدر  
کئی رهی آھی، جیکڏهن سازش تحت سنڌ  
جی آدمشماری گهٽ ڏیکاری وئی تہ ان کی  
قبول نہ ڪنداسین نار نهاد سول حکومتن  
اسان جو احتساب ڪرڻ فرض سمجهیو آھی پر  
اڄ تائین بین پارٽین جو احتساب نہ ٿیو آھی،  
صرف بی بی جو احتساب چو پيو ٿی، هنن چو  
تہ ذوالفقار علی ڀٽو جی گهر کان علاوه ٻئي  
کتن گهر جو احتساب نہ ٿیو آھی، ان موقعی  
تی ملیر پریس ڪلب جی صدر، صوبائی

تیکس آھی، هن چو  
ارب رینن جا قرض وٺی ناهی  
وزیر جو گهر بچائڻ لاءِ روت جو روح  
آبادی ڏانهن کیو ویو 3303

جرمن ماهر مقرر

کیو ویو آھی، پی آئی آر حرمان ان مقرری جی  
تصدیق کئی آھی، هلدان بران برن کی بی آئی  
آئی کی نغو ڏیندو ادارو بڻائڻ جی ذميواری بہ  
ڏنی وئی آھی، ڊی ٽرینسپورٽ جی نالی سان  
مشهور جرمن آفیسر ملائیشیا ۽ بین ملکن  
جی ایئر لائنز کی منافعی بخش بڻائڻ لاءِ هزار  
ملازم برطرف کري چڪو آھی، 3302

ملازم

منجھیل رهيو، جڏهن تہ احتجاج ڪندڙ  
ملازم جو اهو الزام هو تہ گولی رینجرز هلائی،  
بی بی سی موجب احتجاج ڪندڙ گلشن جو  
چوڻ هو تہ رینجرز تحفظ ڪرڻ جی لاءِ آھی یا  
ماڻهو مارڻ لاءِ آھی؟، جیکڏهن انهن جی  
جسر تان وڊیون لاهی سندن ٻارن جی وات  
مان گرھ کسيو وئی تہ پوءِ انهن جی دل تی چا  
گذرندو، جڏهن تہ ملازم کئی ڪن کان ڏک  
لڳڻ کري رت وھی رهيو هو جنهن جو چوڻ هو  
تہ رینجرز اهلڪار ڪلاشنڪوف جو بت هنیو  
آھی، میڊیا رپورٽن موجب رینجرز اهلڪارن  
پهريان ملازم کی ڏکا ڏئي پوئتی ڪرڻ جی  
ڪوشش کئی جنهن دوران ملازم اهو چوندا  
رهيا تہ اسان پاڪستاني آھيون، اسان کی نہ  
ماریو، اسان کی پاڪستاني فوج تی فخر آھی  
پر رینجرز اهلڪارن اڳتي وڌندي لنبازي شروع

سنڌ اسيمبلي ۾ ۽ ۾ نهراءُ منظور

۽ 2008 کان 2015 ع تائين شهري  
کوٽا مطابق ٻه ٽيون ڪيون پر عامر پيرزاده  
چو تہ ٻرتين جی جیڪا لسٽ فراهم کئی  
وئی آھی، ان ۾ شهري کوٽا تی عمل ناهی  
کیو ویو، سينئر وزير نثار احمد کهڙي چو تہ  
لاڙڪاڻو، خيرپور، نوشهروفيروز ۽ قمبر بہ شهر  
آهن سنڌ جا رڳو هڪ بہ شهر ناهن، ٻين شهرن  
جو ڊوميسائل بہ شهري هوندو، اير ڪيو اير  
جی سيد سردار احمد چو تہ 1971 ع ۾  
شهري ۽ بهراڙي کوٽا جی تعريف آئين ۾  
ڏنی وئی هئي، جنهن مطابق ڪراچي،  
حيدرآباد ۽ سکر جی ٽن شهرن لاءِ 40 سيڪڙو  
شهري کوٽا مقرر کئی وئی هئي جڏهن تہ  
سنڌ جی ٻين شهرن ۽ بهراڙين لاءِ 60 سيڪڙو  
کوٽا مقرر کیو ویو هو اجلاس دوران سينئر  
وزير نثار احمد کهڙي ۽ مسر ليگ فنڪشنل  
جی ميمبر نصرت سحر عباسي وچ ۾ جملن  
جی ڏي وٺ تی، نصرت سحر عباسي ضمني  
سوال ڪندي چو تہ حيرت جی ڳالهه آھی جو  
ڪيترن سالن کانپوءِ بہ سوالن جا جواب مڪمل  
نہ ڏنا ویا آهن، لاڳاپيل وزير تياری کري ناهی

# آفيس آف ڊي اگريڪيوٽو انجنيئر ڊرينيج ڊويزن، بلين



No.TC/G\_148/DD/33 of 2016 Badin Dated:01/02/2016

## ٽينڊر جی طلبی جو نوٽيس

انٽن بي بي آري رولڊ 2010 مطابق اهليت جی معيار تي پورو لهندڙ پارٽيز فرمن ۽ ليڪيڊران کان جيڪي انڪر ٽيڪس ڊپارٽمينٽ، سنڌ روٽيو بورڊ ۽ پاڪستان انجنيئرنگ ڪائونسل وٽ گهريل ڪيٽيگري ۾ رجسٽرڊ هجن کان اي ڊي بي اسڪيم نمبر 648 جی هيٺين ڪمن لاءِ اڳريڪيوٽو انجنيئر ڊرينيج ڊويزن بلين طرفان مھرينڊ ٽينڊر گھراجن ٿا.

اين نمبر	ڪم جو نالو	ڪم ٿيل ملهه	سوٽي رقم	ٽينڊر في	منو
1.	ڪنٽونمينٽ ايريا بلين ۾ آر ڊي 0.0 کان 14.0 تائين اسٽون پھنجڻ ۽ ڄاڻايل ڊرين جی تعمير	47,203,313/-	2 سيڪڙو	3000/-	(03) مهينا
2.	بلين ڪينٽ وٽ ٽيوب ويل کان تجويز ڪيل ڊرين سان گڏ روڊ ڪلورٽ سميت ۽ آرس سي پائپ ٽائين انٽرنل ڊسپوزل چينل جی تعمير (اي) ٽيوب ويل کان تجويز ڪيل ڊرين تائين انٽرنل ڊسپوزل چينل جی تعمير (بي) روڊ ڪلورٽ (01 عدد) جی تعمير (سي) آرس سي پائپ انٽيلس (02 عدد) جی تعمير	18,456,036/-	2 سيڪڙو	3000/-	(03) مهينا
3.	ڪينٽ ايريا بلين سان لڳو لڳ ڊسپوزل چينل (اي) پمپ هائوس جی تعمير (بي) آرس سي سمپ /ٽينڪ 16'x8' جی تعمير (سي) ڪينٽ بلين 2050 آرائف تي کان وٺي وڊر فلڊر جی ڊسپوزل لاءِ اي سي راتنگ مين 24" Q لاپا جی کستنگ، جوڙڻ، رچائڻ ۽ فراهمي ڊي اڪينٽ بلين ۽ ل جي پراسي ولن علائقن تائين اسٽار وائر فلڊر جي لاپا، 60 بي ليج بي اي سي اليڪٽرڪ موٽر جي فراهمي ۽ تنصيب (اي) ايڪسٽرنل اليڪٽريڪيشن (ايڍ) ڪنٽونمينٽ ايريا بلين وٽ ڊيزل جنريٽر 50 ڪي وي اي (02 عدد)	46,646,563/-	2 سيڪڙو	3000/-	(03) مهينا
4.	ڪنٽونمينٽ ايريا بلين اندر ۽ ٻاهر وٽ 1 ڪيورس گنجائش جی (80 فوٽ گهرائي رکندڙ) سولر ٽيوب ويل (13 عدد) جی تعمير	41,372,645/-	2 سيڪڙو	3000/-	(03) مهينا
5.	ڪنٽونمينٽ ايريا بلين اندر ۽ ٻاهر وٽ 1 ڪيورس گنجائش جی (80 فوٽ گهرائي رکندڙ) سولر ٽيوب ويل (13 عدد) جی تعمير	41,372,645/-	2 سيڪڙو	3000/-	(03) مهينا
6.	ڪنٽونمينٽ ايريا بلين اندر ۽ ٻاهر وٽ 1 ڪيورس گنجائش جی (80 فوٽ گهرائي رکندڙ) سولر ٽيوب ويل (12 عدد) جی تعمير	38,190,134/-	2 سيڪڙو	3000/-	(03) مهينا
7.	ڪنٽونمينٽ ايريا بلين اندر ۽ ٻاهر وٽ 1 ڪيورس گنجائش جی (80 فوٽ گهرائي رکندڙ) سولر ٽيوب ويل (12 عدد) جی تعمير	38,190,134/-	2 سيڪڙو	3000/-	(03) مهينا

امٽينڊر ڊنگ دستاويزن ۾ اشتھار جی اشاعت واري تاريخ کان وٺي 2016-02-22 بوقت 01:00 وڳي تائين هر ڪم سامھون ڄاڻايل ٽينڊر في تقابلي واپسي جی اھليگي تي جاري ڪيا ويندا. ۽ 2016-02-22 تي بوقت 02:00 وصول ڪيا ۽ ساڳئي ڏينھن تي بوقت 03:00 وڳي خواهشمند ليڪيڊران يا سندن مجاز نمائندن جی موجودگي ۾ و کوليا ويندا.

### ڪواليفڪيشن:

- گذريل 3 سالن دوران ڪيل پن ساڳئي قسم جي مليل ڪمن جي فهرست
- گذريل 3 سالن دوران فنانشل اسٽيٽمينٽ (سمري) انڪر ٽيڪس ريترنس
- فرور رٽ ڪر ڪندڙ ٽيڪنيڪل اسٽاف جو نالو، قابليت ۽ تجربو
- پروڪيورمينٽ جو طريقو ڪار: سنڪل اسٽيج، سنڪل انويٽ
- شرط ۽ ضابطا:
- مشروط / ٽيليفرئانڪ واک / ٽينڊر، قبول نہ ڪيو ويندو
- گهريل رقم جي سيڪيورٽي بنا واک قبول نہ ڪيو ويندو
- ڄاڻايل تاريخ ۽ وقت کانپوءِ وصول ٿيندڙ واک نہ قبول نہ ڪيو ويندو
- هيٺ صحيح ڪندڙ کي حق آهي تہ هو ايس بي بي آري رولڊ 2010 جی لاڳاپيل شق مطابق ڪوبہ ٽينڊر يا سمورو ٽينڊر رد / قبول کري.

SAY NO TO CORRUPTION

منھن جی نالی تي نفرت جی پرچار ڪندڙن کي سڃاڻو



سنڌ ۾ تعليم جي بهتری لاءِ، علمي + پنھنجو بهادر لکي 8 3 9 8

A. Awaz



اس کا شیرازہ گھر میں آنا ہوتو وہاں رکھو یا کرتا تھا انہ کے ارادے سے واقف نہ کیا کہ اس نے ٹھکانے میں جا کر کھانا کھا کر اور اسکی شیرازگی بیوی کو گرفتار کیا۔

**منیبل گبول**  
 ہے تو اسے مقدمات کیوں نہیں لے کر عزیر بلوچ کے پاس ڈرافٹ نمبرزا کو کہتے ہوں گا کہ یہ تھا کہ ڈرافٹ نمبرزانے نے 6 ماہ قبل کہا تھا کہ عزیر اپنا بے آئی ٹی میں وہ اپنا بیان ب کے نام بتا دیئے ہیں۔

**قاتل بیوی گرفتار**  
 اس کی پستول منگوائی اور یہ کوئی شام 5 بجے کا وقت تھا ڈرافٹ کو پستول دے کر چلا گیا بیجے جب لاسٹ گئی ہوئی تھی آچکا تھا جسے پکڑ لیا۔

**بیٹوں کا اعلان**  
 کے زیر استعمال چار (4) (تھکیاں) کرچی کے گرٹی ہیں۔ اس بابت جنوری 2016 کو درج ہے تو برائے مہربانی فوری

کا عدم تنظیم کا مکالمہ بڑیا میں عرف پو کو گرفتار کر لیا گیا ہے، ملزم لیاری میں میں مختلف جھلموں میں ملوث ہے۔ ذرائع کے مطابق ملزم کا ساتھی محمد علی عرف ماہر بیڈی پولیس کے ساتھ مقابلے میں مارا۔

**مددگار 15**  
 دن قادیمر غلط یا تفریح کی غرض سے کی گئی کا لڑکی تعداد 3 لاکھ 4 ہزار 743 ہے جبکہ صرف 6 ہزار 205 کا لڑکی نہیں تھی۔ ایمر جنسی ہیولٹ پر جنسی کا لڑ کر تینوں کے خلاف مہم شروع کی جا رہی ہے۔

**حب تصادم**  
 تصادم کے نتیجے میں ایک پولیس اہلکار کا ٹیبل ٹیبل روٹیجولڈ محمد موسیٰ روٹیجولڈ پری ہلاک ہو گیا متوفی کی نعش کو فوری طور پر حب سول اسپتال منتقل کی گئی دانے کی اطلاع ملنے پر پولیس بھی جانے وقوعہ پر پہنچی گئی پولیس کے مطابق متوفی سبیلہ کارہائشی اور حب سنی تھانے میں تعینات اور SHO حب سنی بخش کا مگن مین تھا، متوفی اپنے دیگر پولیس اہلکاروں کے ہمراہ ایک چیکر بشیر بروہی کے ہمراہ سڑک پر جا کر تصادم کے نتیجے میں جاں بحق ہوئے تھے کہ بد قسمتی

تا مریاں ہو رہا ہے۔ ہمیں نہیں قائم ہی شاہ نواسی فرصت کہاں کہ عزیر جیسا جرائم پیشہ انسان سے مل سکے۔ آج کل تو کوئی بھی انگٹھا نکلا سکی شہرت کے لیے فوٹو شاپ کر سکتا ہے۔ آپ کہیں تو میں عزیر بلوچ کو اہامیا کے ساتھ دکھا دوں۔ ہم سیاسی لوگ ہیں ہمارا ہمسلا کسی گینگسٹر سے کیا لینا دینا۔ اگر پیٹیز اس کیس میں ہم نے بنائی ہوئی تو ہم ہی اسے کیوں کا عدم قرار دیتے؟ ڈرافٹ نمبرزا آج بھی عزیر بلوچ کو بھائی کہتا ہے تو کہتا ہے۔ مرزا سے پوچھیں کہ بطور وزیر داخلہ اس نے اسٹے کے ہزاروں لائسنس کیوں جاری کیے۔ انہی حرکتوں پر تو مرزا کو پیٹیز پارٹی سے نکالا گیا۔ وہ تمام باجمیر صحافی جو عزیر بلوچ کی دعوت اظہار میں شرکت کے لیے نونے پڑتے تھے، وہ تمام اینکریڈ اور اینکریڈ جیون عزیرجان کا ٹوکا شو میں مدعو کئے تھے آج غلطی کی طرح اس کی سفاکیوں کا پردہ فاش کر رہے ہیں۔ پیٹیز اس کیس میں 2008ء میں زروری حکومت سے قیام کے بعد رحمان ڈیکٹ عرف سردار رحمان خان بلوچ کی سربراہی میں قائم ہوئی۔ جب رحمان ڈیکٹ نے سیاسی پر ریزے لگانے شروع کیے تو 9 اگست 2009ء کو انٹیل ناڈن کے قریب پولیس مقابلے

**عزیر بلوچ صحافی**  
 انفران کے بعد پیسے اور تحائف لینے والے صحافیوں کے نام بھی بتانا شروع کر دیئے ہیں۔ صحافی ماہانہ 5 ہزار سے ایک لاکھ روپے تک وصول کرتے تھے۔ صحافیوں کو دی گئی رقم کا تمام حساب منقول ظفر بلوچ رکھتا تھا۔

**پیٹرول نایاب**  
 میں کی کے بعد شہر میں پیٹرول نایاب ہو گیا متعدد پیٹرول پمپوں نے پیٹرول کی فروخت بند کر دی جبکہ شہر کے بعض پیٹرول پمپوں پر پرائے نرخ پر پیٹرول کی فروخت جاری رہی قیمت کم کرنے والے پیٹرول پمپوں پر عوام کا جھوم اٹھا لہذا پیٹرول میں گنگ کر پیٹرول خرید اعوام کے رش کے باعث پیٹرول پمپوں پر جلد پیٹرول ختم ہو گیا۔ شہر میں فیصل پر شارع قائم نفلانی اور کے قریب واقع پیٹرول پمپ کے ملازمین نے بتایا کہ شہر میں پیٹرول پمپ بند ہونے سے عوام کے رش کے باعث چند پمپوں میں 40 ہزار لیٹر پیٹرول فروخت ہوا۔ پیٹرول ختم ہونے کے باعث رات کو پیٹرول

ہی کارکنان... کیں، تان زبیر... جاری رہا۔ الطاف حسین... تندرستی اور ناگہانی آفات سے بچاؤ... اجتماعات کا سلسلہ بھی جاری رہا۔ لیڈر ڈویژن... تحت لال قلعہ گراؤنڈ میں قرآن خوانی کی گئی۔ اجتماع میں رابطہ کمیٹی کے ڈپٹی کنوینر کیف الوری، رابطہ کمیٹی کے ارکان عبدالحمید، اقبال مقدم، عارف خان ایڈووکیٹ، محمد حسین، مطیع الرحمن، زاہد منصور، محترمہ زریں مجید، ارشد حسین، عبدالقادر خانزادہ، عادل خان، اسلم آفریدی، ارکان قومی صوبائی اسمبلی، بلدیاتی انتخابات میں منتخب چیئرمین، وائس چیئرمین اور کنٹرولر سمیت کارکنان اور ہمدردوں نے بڑی تعداد میں شرکت کی۔ بعد ازاں حق پرست سینئر مولانا تنویر الحق تھانوی نے اجتماع کی دعا کرائی، علاوہ ازیں حیدر آباد میر پور خاص، سکھر، خیر پور، لاہور، اسلام آباد، فیصل آباد سمیت ملک بھر میں ایم کے ایم کے تنظیمی دفاتر میں کارکنان کی جانب سے جشن منایا گیا۔

**انگریزی ٹیکنیسیان نکیسی ڈویژن بدین آفس**  
 Email: [drainagedivisionbadin@gmail.com](mailto:drainagedivisionbadin@gmail.com)

آفس نمبر: 022-9210347

**ٹینڈر طلبی نوٹس**

بدین مورخہ 01-02-2016 TC/G-148/DD/33/2016

انگریزی ٹیکنیسیان نکیسی ڈویژن بدین آفس میں پارٹیوں اور فرمز/انجینئروں سے سرپرہیزڈ ریلوے میں تعمیراتی کاموں کی فراہمی کے لیے 2016ء کے مطابق حصہ لینے کی اہلیت کے معیار پر پورا تراتے ہوں اور اسے ڈی ڈی ٹی ایکس نمبر 648 میں مندرجہ ذیل کاموں کی فراہمی کے لیے ایکٹو ہو کر اپنا پتہ مندرجہ ذیل پتہ پر ارسال کرنا چاہیے۔

نمبر شمار	کام کا نام	لاگت کا تخمینہ	بیگانے کی رقم	ٹینڈر فیس	تعمیل کی مدت
1	کنٹونمنٹ ایریا بدین میں آڑی 0-0-140 تک مجوزہ ہالے کی تعمیر اور پتھر بچھانا	47,203,313/-	2%	3000	03 سال
2	کنٹونمنٹ بدین کے ساتھ جھول ٹوب ویزر مجوزہ نالے کے اندر ڈی ڈی سہیل آئی آر ڈی پمپ کی تعمیر (1) مجوزہ نالے سے ٹوب ویوں تک اندر ڈی ڈی سہیل جھول ٹوب کی تعمیر (2) سڑک پر ایک عدد دیبا کی تعمیر (3) عدد ڈی ڈی پمپ کی گزرگاہوں کی تعمیر	18,456,036/-	2%	3000/-	03 سال
3	کینٹ ایریا بدین کے ساتھ ڈی سہیل جھول ٹوب (1) پمپ پائپ کی تعمیر (2) 16x8 پمپ کے سب اینٹیک کی تعمیر (3) اسے رازنگ کی فراہمی، مجوزہ نالے اور اسے ٹیسٹ کرنا (4) کینٹ بدین اور ملحقہ علاقوں سے برساتی پانی کی نکالی کیلئے 60 لی انچ پی اسے الیکٹریک موٹر کی فراہمی اور تنصیب (5) بیرونی طور پر بجلی کی فراہمی (6) کنٹونمنٹ ایریا بدین کے ساتھ 50 گلوٹ اینجینئر کے 22 ہزار جزیئر کی تنصیب	46,646,563/-	2%	3000/-	03 سال
4	کنٹونمنٹ ایریا بدین کے ساتھ اندر اور باہر 1.0 کیوسک گھنٹوں کے 80 فٹ گہرائی کے سٹی ٹوانے سے چلنے والے 3 عدد ٹوب ویوں کی تعمیر	41,372,645/-	2%	3000/-	03 سال
5	کنٹونمنٹ ایریا بدین کے ساتھ اندر اور باہر 1.0 کیوسک گھنٹوں کے 80 فٹ گہرائی کے 13 عدد سٹی ٹوانے سے چلنے والے 13 عدد ٹوب ویوں کی تعمیر	41,372,645/-	2%	3000/-	03 سال
6	کنٹونمنٹ ایریا بدین میں اندر اور باہر 1.0 کیوسک گھنٹوں کے 80 فٹ گہرائی کے سٹی ٹوانے سے چلنے والے 12 عدد ٹوب ویوں کی تعمیر	38,190,134/-	2%	3000/-	03 سال
7	کنٹونمنٹ ایریا بدین میں اندر اور باہر 1.0 کیوسک گھنٹوں کے 80 فٹ گہرائی کے سٹی ٹوانے سے چلنے والے 12 عدد ٹوب ویوں کی تعمیر	38,190,134/-	2%	3000/-	03 سال

معیاری بولی کی دستاویز اخبار میں اس اشتہار کی اشاعت کے بعد سے مورخہ 22-02-2016 کی دوپہر ایک بجے تک بدین کنٹونمنٹ سے ٹینڈر فیس (قابل واپسی) کی ادائیگی کے بعد بدین کنٹونمنٹ سے جاری کیا جائے گا اور مورخہ 22-02-2016 کی دوپہر تک واپس لے لیا جائے گا اور اس دن سہ پہر 3 بجے بدین کنٹونمنٹ میں انجینئروں یا ان کے مجاز ایجنٹوں کی موجودگی میں کھولا جائیگا جو حصہ لینے کا ارادہ رکھتے ہیں۔

**تالیف**  
 (1) گزشتہ 3 سالوں میں شروع کئے گئے ایسے 2 اسٹیمس کی فہرست۔ (2) فرم/انجینئروں کی طرف سے ملکی ساز و سامان، مشینوں اور ٹرانسپورٹ کی تفصیلات۔ (3) فیئٹل اسٹیمس کا (خلاصہ) اور گزشتہ 3 سالوں کیلئے انکم ٹیکس گوشوارے (4) قانونی چارہ جوئی کی فہرست (اگر کوئی ہو) اور قانونی چارہ جوئی کی نوٹس (5) فرم کے ساتھ کام کرنے والے انجینئروں کے نام، تالیف اور تجربہ  
 حصولی کا طریقہ کار  
 مستقل ایجنٹ، واحد الحاف نظام  
 شرائط و ضوابط  
 (1) شرط اور ڈیٹیلز آف کے ذریعے موصول ہونے والی بولی اٹینڈ قبول کیا جائیگا۔ (2) سکیرٹی کی منظوری کے بغیر موصول ہونے والی بولی قبول نہیں کی جائے گی۔ (3) مخصوص وقت اور تاریخ کے بعد موصول ہونے والی بولی قبول نہیں کی جائے گی۔ (4) ایس بی پی آرا نے تو ان میں 2010 کی متعلقہ شق کے مطابق زبردستی کسی بھی یا تمام ٹینڈرز کو قبول کرنے یا منسوخ کرنے کا حق محفوظ رکھتا ہے۔

(نواد احمد حسین)  
 انگریزی ٹیکنیسیان  
 نکیسی ڈویژن بدین

کرپشن سے انکار

INF-KRY-144/16

*Q. Akhsbar - Klaus*





**تاریخ پیدائش**

جیئن تہ منهنجي ٽريزي ڏيئا وڃي  
پيدائش جي تاريخ 04:03:1962  
رهي آهي جنهن کي درست ڪري  
شناختي ڪارڊ ۽ اسڪول سٽيڊنڪن موجب  
04:03:1963 ۽ درست ڪري لکي ۽ پڙهي  
رهي هي منهنجو ڪل اشتهار ڪارڊ تي رکيو  
وڃي تہ جيئن وقت سر ڪر اچي سگهي  
الھستھن  
غلام الله سيلرو ولد پٺاڻ خان سيلرو ڳوٺ الله  
ڏنوسيلرو پوسٽ آفيس رتوديرو پنجولورڙ  
تعلقو رتوديرو ضلع لاڙڪاڻو

**عام اطلاع**

جیئن تہ نالی شاهنواز والد خانوند بخش ۽  
محمد انور والد سلطان خان وپل ڳوٺ عالم  
خان جتوئي جن درخواست ڪئي آهي تہ هنن  
جا والد خانوند بخش ۽ سلطان خان والد قلندرو  
بخش فوت ٿي ويا آهن جنهن جي ملڪيت  
دير پنوغلار عيالي ۽ دير اراه ۽ سروري نمبر  
155 ۽ 154 آهي جنهن ۾ وارثن پاران فوتي  
ڪانو قرايو ويندو ڪنهن به ماڻهن کي محمد  
انور ۽ شاهنواز جتوئي کان اعتراض آهي تہ  
ستن ڏينهن اندر پاڻ کي ظاهر ڪري تہ ٻي  
صورت ۾ درخواست گذارن کي فوتي ڪانو  
تبدیل ڪري ڏنو ويندو  
مختيار ڪارو روينيو پنوغلار

**ڊاڊو / ميڊيڪل ڪيمپ**

محمد خان خشڪ ۽ مفت ميڊيڪل ڪئمپ  
لکائي وئي جنهن ۾ ٻارن جو ماهر ڊاڪٽر  
ڪيپٽن ڊاڪٽر جاويد خشڪ، يورلاجسٽ  
ڊاڪٽر ابراهيم ميمڻ، اکين جو ماهر ڊاڪٽر  
سهيل احمد، ڊاڪٽر حمزه، دل جي بيمارين جو  
ماهر ڊاڪٽر ظهرو احمد شيخ ڳوٺ جي سوين  
ٻارڙن، مردن توڙي عورتن جو مفت چڪاس  
بعد مفت ڊوائون فراهم ڪيون ان موقعي تي  
ڪيپٽن ڊاڪٽر جاويد خشڪ ميڊيڪل سان  
ڳالهائيندي چيو تہ پاڪ رينجرس پنهنجن  
فرائض سرانجام ڏيندي اڄ کان ڊاڊو ضلعي  
جي مختلف ڳوٺن ۽ شهرن ۾ تن مهينن تائين  
مفت ميڊيڪل ڪئمپون قائم ڪندي جنهن  
۾ هزارين غريب مسڪين ماڻهن جو مفت  
علاج ڪيو ويندو هون چيو تہ هيڻ ڳوٺ ۾  
ڪجهه مريض اهڙا آهن جيڪي غربت سبب  
پنهنجو علاج ڪرائڻ کان قاصر آهن جنهن مان  
16 مريضن جو آپريشن ٿيندو جنهن کي  
حيدرآباد ريفر ڪيو ويندو ۽ اتي به پاڪ  
رينجرس جي اسپتال ۾ مفت آپريشن ڪيو  
ويندو.

**ماتلي / تعلقه اسپتال**

ايندڙ مريضن کي ڪا به سهولت ميسر نه آهي  
جنهن ڪري اڄوڃ ماڻهو پرائيوٽ اسپتالن جون  
ڳريون فيون ڀرڻ تي مجبور آهن اسپتال جو  
آپريشن ٿيڻ گڏريل اٺن سالن کان بند پيل  
آهي اسپتال جا ٻيا شعبا جنهن ڇمڙي اک  
ڪن دل دماغ سميت ڪنهن به شعبي جو ڪو  
به ڊاڪٽر مقرر نه آهي.

**شهدادڪوٽ / بيلبل ڪارچوري**

نامعلوم چور انجنيئر سيف الله مگسي ڪئنال  
محمد بخش سيرو جي گهر آڏو بيلبل لاک ٽيل  
جي ايل آءِ ڪار ڪاهي فرار ٿي ويا. چوري ٿيل  
ڪار جي قيمت 17 لک روپيا بڻائي وڃي  
ٿي. ان ڏس ۾ انجنيئر سيف الله مگسي  
ڪئنال محمد بخش سيرو بڻايو تہ معمول  
جيان ڪار گهر پاران بيلبل هڻي جنهن کي چور  
ماسٽر جابي سان کولي ڪاهي ويا آهن اهڙو  
اطلاع حد جي پوليس کي پڻ ڏنو ويو آهي.

سموريون بھڪا اھيسون بند ۽ سن جڊس  
ريورٽ تي قائم ڪائونٽري تي به عملو  
رد ناهي. بئي طرف رينجرس ترجمان پي آءِ  
لازمي تي فائرنگ جي ترديد ڪندي چيو  
تہ رينجرس اهلڪارن طرفان فائرنگ ناهي  
ٿي وئي. ڊي آءِ جي ايسٽ ڪامران فضل جو  
آرٽي ۾ فائرنگ پوليس ناهي ڪئي ڪيئن  
ڪيئن ڏٺي وئي هئي تہ مظاهرو ڪندڙن سان  
اٺيون ڪيون وڃن هن چيو تہ ڪيئن مظاهرين  
سرخي ڪرڻ جي هدايت نه ڪئي وئي  
رڳو ڪيئن روڪڻ جي هدايت ڪئي وئي

**ٺٽو / احتجاج**

ماڃي مظاهرو ۽ ڌڻي روڊ بلاڪ، ٽرينڪ  
لل.

**ميهڙ / پيرس لاڏاڻو**

نهرين پاران اهڙو اطلاع ڏيڻ تي پوليس  
بي واري هنڌ پهچي لاش تحويل ۾ وٺڻ  
پوءِ کيس سڃاڻپ ڪرائڻ لاءِ تعلقه اسپتال  
ٺاڙيو.

**ميرپور ماٿيلو / نينگر جو ڪيس**

بازو ۾ جوابدارن مينيڊ بڊفعلی بعد نينگر  
شيخ کي قتل ڪيو هيس پير ڏهرڪي  
س جوابدارن سان ڏي وٺ ڪرڻ بعد  
املائي مٿي ڪري چڏيو

**رتوديرو / جاويد احمد جاگيرائي**

پو جتي اسپتال جي عملي کي هدايتون  
يو ڪيون جنهن کان پوءِ رتوديرو شهر جو  
ڊاڪٽر ڪيو جنهن ۾ محل ميرل جڪرو ۾

INDH  
RTMENT  
CTION  
IAT 4B  
ACH  
رڳو ڪيئن روڪڻ جي هدايت ڪئي وئي

**ميرپور ماٿيلو / نينگر جو ڪيس**

بازو ۾ جوابدارن مينيڊ بڊفعلی بعد نينگر  
شيخ کي قتل ڪيو هيس پير ڏهرڪي  
س جوابدارن سان ڏي وٺ ڪرڻ بعد  
املائي مٿي ڪري چڏيو

**رتوديرو / جاويد احمد جاگيرائي**

پو جتي اسپتال جي عملي کي هدايتون  
يو ڪيون جنهن کان پوءِ رتوديرو شهر جو  
ڊاڪٽر ڪيو جنهن ۾ محل ميرل جڪرو ۾

**ميرپور ماٿيلو / نينگر جو ڪيس**

بازو ۾ جوابدارن مينيڊ بڊفعلی بعد نينگر  
شيخ کي قتل ڪيو هيس پير ڏهرڪي  
س جوابدارن سان ڏي وٺ ڪرڻ بعد  
املائي مٿي ڪري چڏيو

**رتوديرو / جاويد احمد جاگيرائي**

پو جتي اسپتال جي عملي کي هدايتون  
يو ڪيون جنهن کان پوءِ رتوديرو شهر جو  
ڊاڪٽر ڪيو جنهن ۾ محل ميرل جڪرو ۾

**آفيس آف ڊي اگريڪيٽو انجنيئر ڊرينيج ڊويزن، بدين**



**ٽينڊر جي طلبي جو نوٽيس**

No. TC/G-148/DD/33 of 2016 Badin, Dated: 01/02/2016  
اڳريڪيٽو انجنيئر ڊرينيج ڊويزن، بدين کي آفيس پي آري روز 2010 جي تحت انڪر ٽيڪس ڊپارٽمينٽ وٽ رجسٽرڊ، سنڌ روينيو بورڊ ۽ پاڪستان انجنيئرسنگ  
ڪائونسل وٽ مناسب ڪيٽيگري ۾ رجسٽرڊ خواهشمند حضرات / فرمز / ڪانٽريڪٽرز کان هيٺين ڪمن لاءِ ڊي پي اسڪيم نمبر 648 تحت ٽينڊر گهريل آهن

سپيڊ نمبر	ڪم جو نالو	سوٽي رقم	لاڳت	ٽينڊر في	ٽوٽل وقت
1	ڪيٽونمينٽ ايريا بدين ۾ ارڊي 0.0 کان 14.0 تائين ڊرين ۽ اسٽون پھنگ جو ڪم	47203313	2 سيڪڙو	3000	3 سال
2	بدين ڪينٽ ۾ انٽرنيٽ ڊسپوزل چينل کان ٽيوب ويل روڊ ڪلورٽ ۽ آرسني سي پائپ جو ڪم (اي) انٽرنيٽ ڊسپوزل چينل کان ٽيوب ويل تائين ڊرين جو ڪم (بي) روڊ ڪلورٽ (01) جي تعمير (سي) آرسني سي پائپ (02) جي تعمير	18456036	2 سيڪڙو	3000	3 سال
3	ڪينٽ ايريا بدين ۾ ڊسپوزل چينل جي تعمير (اي) پمپ هائوس جي تعمير (بي) آرسني سي سمب / ٽينڪ 16x8 جي تعمير (سي) ڪينٽ بدين 2050 آريٽ تي کان پروويڊنگ، جوائنٽنگ ۽ ٽيسٽنگ اي سي مينهن جي نيڪالي جو ڪم (ڊي) ڪينٽ بدين ۾ پاڻيءَ جي نيڪال لاءِ 60 بي ايڇ بي اليڪٽرڪ موٽر جي فراهمي ۽ فنڊنگ (اي) بجليءَ جي مرمت جو ڪم (ايف) ڪيٽونمينٽ ايريا ۾ 50 ڪي وي اي (2) جي جرنير جي فراهمي	46646563	2 سيڪڙو	3000	3 سال
4	ڪيٽونمينٽ ايريا بدين ۾ (13 نمبر) سولر ٽيوب ويل (80 فوٽ گهرائي) جي تعمير	41372645	2 سيڪڙو	3000	3 سال
5	ڪيٽونمينٽ ايريا بدين ۾ (13 نمبر) سولر ٽيوب ويل (80 فوٽ گهرائي) جي تعمير	41372645	2 سيڪڙو	3000	3 سال
6	ڪيٽونمينٽ ايريا بدين ۾ (12 نمبر) سولر ٽيوب ويل (80 فوٽ گهرائي) جي تعمير	38190134	2 سيڪڙو	3000	3 سال
7	ڪيٽونمينٽ ايريا بدين ۾ (12 نمبر) سولر ٽيوب ويل (80 فوٽ گهرائي) جي تعمير	38190134	2 سيڪڙو	3000	3 سال

معياري ٻوليءَ جا ڪاغذ بدين ڪيٽونمينٽ بورڊ کان هن اشتهار جي جاري ٿيڻ کان 22.2.2016 ع تائين 1:00 تائين ٽينڊر في (واپس نه ٿيڻ جوڳي) تحت جاري ڪيا ويندا، ۽  
22.2.2016 ع تي منجهند 2:00 وڃي کوليا ويندا ۽ ساڳئي ئي ڏينهن بدين ڪيٽونمينٽ ۾ منجهند 3:00 وڃي ڪانٽريڪٽريا سندس مجاز نمائندگي آڏو کوليا ويندا.  
ڪواليفڪيشن:

- گذريل 3 سالن دوران ساڳين ئي 2 ڪمن جي لسٽ
  - اوزارن جو تفصيل، مشين ۽ فرور / ڪانٽريڪٽرز جي پنهنجي ٽرانسپورٽ
  - فنانشل اسٽيٽمينٽ (سمری) 3 سالن جي انڪر ٽيڪس
  - ڪم جو طريقيڪار
  - فرور جي ٽيڪنيڪل اسٽاف جو نالو، تعليم ۽ تجربو
- واڪ جو طريقيڪار:  
سنگل اسٽيج، سنگل اينولپ  
شرط ۽ ضابطا:  
غير مشروط، ٽيليوگرافڪ واڪ / ٽينڊر قبول ڪيا ويندا.  
ٻڌ سيڪيورٽي جي گهريل رقم کانسواءِ واڪ تسليور نه ڪيو ويندو  
واڪ مقرر ڪيل ٽائيم ۽ تاريخ کانپوءِ قبول نه ڪيو ويندو  
هيٺ صحي ڪندڙ کي ڪنهن به ٽينڊريا سمورن کي آفيس پي آري روز 2010 تحت  
قبول ڪرڻ / يارڊ ڪرڻ جو اختيار حاصل آهي.

**ايگريڪيٽو انجنيئر ڊرينيج ڊويزن بدين**

**SAY NO TO CORRUPTION**

مذهب جي نالي تي نفرت جي پرچار ڪندڙن کي سڃاڻو



سنڌ ۾ تعليم جي بهتري لاءِ،  
علمي + پنهنجو بهادر لکي 8 3 9 8  
ٺٽي آفيس آف ايس ايم

Sindh Mahran






**ATTENDANCE SHEET OF CONTRACTORS FOR OPENING OF TENDERS / BIDS**

FOR


ADP No. 648


1.	Construction of proposed drain and Stone Pitching from RD. 0.0 to 14.0 in Cantonment Area Badin.
2.	<b>Construction of Internal Disposal Channels from Tube wells to proposed drain i/c Road Culvert and RCC Pipe along Badin Cantt:</b> a) Construction of Internal Disposal Channels from Tube wells to proposed drain. b) Construction of (01 No.) Road Culvert. c) Construction of (02 No.) RCC Pipe Inlets
3.	<b>Disposal Channel along Cantt: area @ Badin.</b> a) Construction of Pump House, b) Construction RCC Sump /Tank 16'x8' c) Providing & laying, Jointing & Testing A.C Rising Main 24" Q dia for disposal of wet weather flow from Cantt. Badin 2050 Rft. d) Supplying & Installing 60 BHP A.C Electric Motor for disposal of storm water flow from cantt. Badin and adjoining area. e) External Electrification. f) Diesel Generator 50 KVA (02 No.) along Cantonment Area @ Badin.
4.	Construction of (13 No.) Solar Tube well (80 ft. depth) of 1.0 Cusec Capacity along In & Out Cantonment Area @ Badin.
5.	Construction of (13 No.) Solar Tube well (80 ft. depth) of 1.0 Cusec Capacity along In & Out Cantonment Area @ Badin.
6.	Construction of (12 No.) Solar Tube well (80 ft. depth) of 1.0 Cusec Capacity along In & Out Cantonment Area @ Badin.
7.	Construction of (12 No.) Solar Tube well (80 ft. depth) of 1.0 Cusec Capacity along In & Out Cantonment Area @ Badin.

**In Drainage Division Badin**


S. No.	Name of Contractor / Agency	Signature of Contractor / Authorized Representative	Remarks
1.	HSS (HAJISI RAJ UD-DINI & COMPANY)		CONSTRUCTION MANAGER
2.	SBK (ShaiKh Bary Khom & Brothers)		QOS
3.	Umar Jan & Company		Manager Finance Accounts
4.	M/s Malami Construction Company		Engineer


5.	M/s Madani Enterprises	Ashar	280
6.			
7.			
8.			
9.			
10.			
11.			

  
**Mr. Khair Mohammad Dahri**  
 Director  
 Left Bank Canals (AWB), Badin

  
**Fawad Ahmed Memon**  
 Executive Engineer  
 Drainage Division, Badin

  
**Rao Mushtaque Ahmed**  
 Divisional Accounts Officer  
 Drainage Division, Badin

  
**Bhawani Shankar**  
 Executive Engineer  
 Public Heal Health Department  
 Badin

  
**Akbar Azam Rashdi**  
 Technical Officer  
 SIDA Hyderabad

  
**MAJOR**  
**IFTIKHAR**  
 Head Quarter 206-Brigade  
 Badin Cantonment

# SPPRA BIDDING DOCUMENTS



## GOVERNMENT OF SINDH

Name of Department: **IRRIGATION DEPARTMENT**

Name of Project/Scheme: ADP NO. 648 "POCKET DRAINAGE SYSTEM FOR PART COMMAND DEHS KALHORKI, JHURKANDI, KERANDDI AND CHORHAL CANTONMENT AREA TAPO, TALUKA AND DISTRICT BADIN"

Name of Work:- PACKAGE NO.1) CONSTRUCTION OF PROPOSED DRAIN AND STONE PITCHING FROM RD. 0.0 TO 14.0 IN CANTONMENT AREA BADIN.

Name of Procuring Agency: **Executive Engineer, Drainage Division, Badin**

Document issued to:


M/S Madani Enterprises

DR No. & Amount:

77/01 dt: 17-02-2016

*for*   
Executive Engineer  
Drainage Division  
Badin

24" dia (600 mm) pipe	P/Rft	857.00	12250.00	TWELVE THOUSAND TWO HUNDRED FIFTY	10,498,250.00
20" dia (500 mm) pipe	P/Rft	510.00	8600.00	EIGHT THOUSAND SIX HUNDRED	4,386,000.00
16" dia (400 mm) pipe	P/Rft	150.00	6100.00	SIX THOUSAND ONE HUNDRED	915,000.00
12" dia (300 mm) pipe	P/Rft	180.00	3500.00	THREE THOUSAND FIVE HUNDRED	630,000.00
10" dia (250 mm) pipe	P/Rft	205.00	2800.00	TWO THOUSAND EIGHT HUNDRED	574,000.00
8" dia (200 mm) pipe	P/Rft	2000.00	2240.00	TWO THOUSAND TWO HUNDRED FORTY	4,480,000.00
6 Restoration of Asphalt pavement/ Road including base course sub base course, and wearing course; complete with compaction and as shown in the drawings as directed / approved by the Engineer	P/Sft	3200.00	390.00	THREE HUNDRED NINETY ONLY	1248,000.00
Total Bid Price (the amount to entered in paragraph 1 of the form of Bid) In words					49,979,332.00
FOURTY NINE MILLION NINE HUNDRED SEVENTY NINE THOUSAND THREE HUNDRED THIRTY TWO ONLY					



Signature:  
Company Name:

EXECUTIVE ENGINEER  
Drainage Division  
Badli.


**SCHEDULE OF PRICE**

**Name of Work:- CONSTRUCTION & STONE PITCHING OF PROPOSED DRAIN FROM RD. 0.0 TO 14.0**

**ALONG CANTT AREA @ BADIN**

**Bill No. 1: Earth Work**

Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	Earth work excavation in Irrigation channels drain etc dressed to designed section grades and profiles excavated material disposed off and dressed within 50' lead in ordinary soil.	P/Cft		663000.00	8.0	EIGHT RUPEES only	5,304,000.00
2	Dressing & leveling of earth work to design section etc complete. (b) Ordinary Soil	P/Cft		663000.00	0.5	FIFTY PAISA only	331,500.00
3	Stone pitching including sub base with hammer dressed stone on surface laid in courses including carriage of materials chain.	P/Cft		221000.00	42.0	FOURTY TWO only	9,282,000.00
4	Supplying and stacking at site stone metal of size 3/4" - 1 1/2" (19mm to 38 mm) ring i/c screening washing and spreading the same in filter beds to correct level etc complete.	P/Cft		28887.77	75.0	SEVENTY FIVE only	2,166,582.00
5	Manufacturing, supplying, laying and fixing of high density PE corrugated pipe						
	32" dia (800 mm) pipe	P/Rft		605.00	16800.0	SIXTEEN THOUSAND EIGHT HUNDRED	10,164,000.00




**EXECUTIVE ENGINEER**  
**Drainage Division**  
**Badin**

PACKAGE NO. 01

**SUMMARY OF BID PRICE**

**CONTRACT NAME** CONSTRUCTION & STONE PITCHING OF PROPOSED DRAIN FROM RD. 0.0 TO 14.0  
ALONG CANTT AREA @ BADIN

Bill Nr.	Description	Amount
1	Earth Work i) EARTH WORK	49,979,332.0
	Total Bid Price (the amount to entered in paragraph 1 to 2 of the form of bid in words <i>FOURTY NINE MILLION NINE HUNDRED SEVENTY NINE THOUSAND THREE HUNDRED THIRTY TWO ONLY</i> )	49,979,332.0



Signature:  
Company Name:

*[Handwritten Signature]*

**EXECUTIVE ENGINEER**  
Drainage Division  
Badin.

Hyderabad Branch

Phone: 022-2730911-5 Fax: 022-2730911-5

Telex: SUMBPKKA

R. 1,120,000.00

RECEIVED FROM

IN FAVOUR OF

EXECUTIVE ENGINEER DRAINAGE DIVISION BADIN ON A/C OF THADANI ENTERPRISES

THE SUM OF RUPEES PAK RUPEE ONE MILLION ONE HUNDRED AND TWENTY THOUSAND ONLY

As a deposit AT CALL bearing NO PROFIT subject to the general rules of the Bank with respect to such deposits.

This receipt is Non-Transferable and Payable to Beneficiary or Purchaser.

In the event that this instrument is not encashed within 6 months

of issue. The Bank reserves the right to validate the same before encashment.

Encashment of this instrument is subject to payment of withholding tax, as per applicable law.

CDR: 00004998

**NON TRANSFERABLE**

**CALL DEPOSIT RECEIPT**

CDR No. 4998

DATE: 22-Feb-2016

For Summit Bank Limited

AUTHORIZED SIGNATURE

AUTHORIZED SIGNATURE

⑈00004998⑈0810036⑈

⑈080⑈

# SPPRA BIDDING DOCUMENTS



## GOVERNMENT OF SINDH

Name of Department: **IRRIGATION DEPARTMENT**

Name of Project/Scheme: ADP NO. 648 "POCKET DRAINAGE SYSTEM FOR PART COMMAND DEHS KALHORKI, JHURKANDI, KERANDDI AND CHORHAL CANTONMENT AREA TAPO, TALUKA AND DISTRICT BADIN"

Name of Work:- PACKAGE NO.1) CONSTRUCTION OF PROPOSED DRAIN AND STONE PITCHING FROM RD. 0.0 TO 14.0 IN CANTONMENT AREA BADIN.


Name of Procuring Agency: **Executive Engineer, Drainage Division, Badin**

Document issued to:

M/S Haji Saajuddin Soomro  
Contractors & Engineers

DR No. & Amount:

76/01 dt: 17-02-2016

  
Executive Engineer  
Drainage Division  
Badin



PACKAGE NO. 01

**SUMMARY OF BID PRICE**

**CONTRACT NAME** CONSTRUCTION & STONE PITCHING OF PROPOSED DRAIN FROM RD. 0.0 TO 14.0  
ALONG CANTT AREA @ BADIN

Bill Nr.	Description	Amount
1	Earth Work i) EARTH WORK	57640522/-
	Total Bid Price (the amount to entered in paragraph 1 to 2 of the form of bid in words Five crore seventy six lac forty thousand five hundred twenty two only)	57640522/-


Signature:   
Company Name: 

**SCHEDULE OF PRICE**

**Name of Work:- CONSTRUCTION & STONE PITCHING OF PROPOSED DRAIN FROM RD. 0.0 TO 14.0**  
**ALONG CANTT AREA @ BADIN**

**Bill No. 1: Earth Work**

Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	Earth work excavation in Irrigation channels drain etc dressed to designed section grades and profiles excavated material disposed off and dressed within 50' lead in ordinary soil.	P/ Cft		663000.00	9	Nine only	59,67,000/-
2	Dressing & leveling of earth work to design section etc complete. (b) Ordinary Soil	P/ Cft		663000.00	1	one only	663,000/-
3	Stone pitching including sub base with hammer dressed stone on surface laid in courses including carriage of materials chain.	P/ Cft		221000.00	60	sixty only	13,260,000/-
4	Supplying and stacking at site stone metal of size 3/4" - 1 1/2" (19mm to 38 mm) ring i/c screening washing and spreading the same in filter beds to correct level etc complete.	P/ Cft		28887.77	80	eighty only	2311,021.60/-
5	Manufacturing, supplying, laying and fixing of high density PE corrugated pipe						
	32" dia (800 mm) pipe	P/Rft		605.00	17500	Seventeen thousand five hundred only	10,587,500/-

  
 J. N. S.

	24" dia (600 mm) pipe	P/Rft	857.00	13500	Thirteen thousand five hundred only	11569500/2
	20" dia (500 mm) pipe	P/Rft	510.00	9000	Nine thousand only	4590000/2
	16" dia (400 mm) pipe	P/Rft	150.00	7000	Seven thousand only	1050000/2
	12" dia (300 mm) pipe	P/Rft	180.00	4000	Four thousand only	720000/2
	10" dia (250 mm) pipe	P/Rft	205.00	2900	Two thousand nine hundred only	594000/2
	8" dia (200 mm) pipe	P/Rft	2000.00	2500	Two thousand five hundred only	5000000/2
6	Restoration of Asphalt pavement/ Road including base course sub base course, and wearing course; complete with compaction and as shown in the drawings as directed / approved by the Engineer	P/Sft	3200.00	415	Four hundred fifteen only	1328000/2
<b>Total Bid Price (the amount to entered in paragraph 1 of the form of Bid) in words</b>						
Five crore seventy six thousand five hundred Twenty Two only						
57,640,522/2						

Signature: *[Handwritten Signature]*  
Company Name: *[Handwritten Name]*





بنك الفلاح المحدود  
BANK ALFALAH LIMITED

(0045) Main Branch Saddar Hyderabad

### Call Deposit Receipt

No. CDRHYD 0685206

Ref. No. F116053345843225

Date: 22 FEB 2016

Amount not over PKR 1,255,000.00 only

Rs. 1,255,000.00

Received from M/S. HAJI SIRAJUDDIN SOOMRO

On Account EXECUTIVE ENGINEER DRAINAGE DIVISION BADIN DN A/C M/S. HAJI SIRAJUDDIN Soomro

Rupees ONE MILLION TWO HUNDRED FIFTY FIVE THOUSAND ONLY

as a deposit at call bearing no Interest/Profit subject to general rules of the Bank with respect to such deposits.

THIS RECEIPT IS NON TRANSFERABLE  
PAYABLE TO BENEFICIARY ONLY

*[Handwritten Signature]*  
13w

Authorised Signature

*[Handwritten Signature]*  
Authorised Signature

# SPPRA BIDDING DOCUMENTS



## GOVERNMENT OF SINDH

Name of Department: **IRRIGATION DEPARTMENT**

Name of Project/Scheme: ADP NO. 648 "POCKET DRAINAGE SYSTEM FOR PART COMMAND DEHS KALHORKI, JHURKANDI, KERANDDI AND CHORHAL CANTONMENT AREA TAPO, TALUKA AND DISTRICT BADIN"

Name of Work:- PACKAGE NO.1) CONSTRUCTION OF PROPOSED DRAIN AND STONE PITCHING FROM RD. 0.0 TO 14.0 IN CANTONMENT AREA BADIN.

Name of Procuring Agency: **Executive Engineer, Drainage Division, Badin**

Document issued to:

M/S <sup>Construction</sup> Malami Contractors Company

DR No. & Amount:

79/01 dt 17-02-2016

*[Signature]*  
Executive Engineer  
Drainage Division  
Badin


PACKAGE NO. 01

**SUMMARY OF BID PRICE**

**CONSTRUCTION & STONE PITCHING OF PROPOSED DRAIN FROM RD. 0.0 TO 14.0  
ALONG CANTT AREA @ BADIN**

**CONTRACT NAME**

Bill Nr.	Description	Amount
1	Earth Work i) EARTH WORK	62,015,522/-
		-
	Total Bid Price (the amount to entered in paragraph 1 to 2 of the form of bid in words <i>Sixty Two Million Fifteen Thousand Five Hundred Twenty Two only</i> )	62,015,522/-



Signature:

Company Name:

**SCHEDULE OF PRICE**

Name of Work:- **CONSTRUCTION & STONE PITCHING OF PROPOSED DRAIN FROM RD. 0.0 TO 14.0**

**ALONG CANTT AREA @ BADIN**

Bill No. 1: Earth Work

Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	Earth work excavation in Irrigation channels drain etc dressed to designed section grades and profiles excavated material disposed off and dressed within 50' lead in ordinary soil.	P/ Cft		663000.00	10 <sup>1/2</sup>	Ten Rupees only	6,630,000/-
2	Dressing & leveling of earth work to design section etc complete. (b) Ordinary Soil	P/ Cft		663000.00	1.50 <sup>1/2</sup>	one Rupees Kitty Parsha only	994,500/-
3	Stone pitching including sub base with hammer dressed stone on surface laid in courses including carriage of materials chain.	P/ Cft		221000.00	68 <sup>1/2</sup>	Sixty Eight Rupees only	15,028,000/-
4	Supplying and stacking at site stone metal of size 3/4" - 1 1/2" (19mm to 38 mm) ring i/c screening washing and spreading the same in filter beds to correct level etc complete.	P/ Cft		28887.77	80 <sup>1/2</sup>	Eighty Rupees only	2,311,022/-
5	Manufacturing, supplying, laying and fixing of high density PE corrugated pipe						
	32" dia (800 mm) pipe	P/Rft		605.00	18000 <sup>1/2</sup>	Sixteen Thousand only	10,890,000/-

9

	24" dia (600 mm) pipe	P/Rft		857.00	14,000 <sup>±</sup>	Fourteen Thousand only	11,998,000 <sup>±</sup>
	20" dia (500 mm) pipe	P/Rft		510.00	9,500 <sup>±</sup>	Nine Thousand Five Hundred only	4,845,000 <sup>±</sup>
	16" dia (400 mm) pipe	P/Rft		150.00	7,700 <sup>±</sup>	Seven Thousand Seven Hundred only	1,155,000 <sup>±</sup>
	12" dia (300 mm) pipe	P/Rft		180.00	4,600 <sup>±</sup>	Four Thousand Six Hundred only	828,000 <sup>±</sup>
	10" dia (250 mm) pipe	P/Rft		205.00	3,200 <sup>±</sup>	Three Thousand Two Hundred only	656,000 <sup>±</sup>
	8" dia (200 mm) pipe	P/Rft		2000.00	2,700 <sup>±</sup>	Two Thousand Seven Hundred only	5,400,000 <sup>±</sup>
6	Restoration of Asphalt pavement/ Road including base course sub base course, and wearing course; complete with compaction and as shown in the drawings as directed / approved by the Engineer	P/St		3200.00	400 <sup>±</sup>	Four Hundred only	1,280,000 <sup>±</sup>
<b>Total Bid Price (the amount to entered in paragraph 1 of the form of Bid) In words</b> <i>Thousand Five Hundred Twenty Two only.</i>							69,015,524 <sup>±</sup>



Signature:  
Company Name:





First Women Bank Ltd. HYDERABAD BRANCH.

No. FWDC 0301696

NOT OVER Rs. 1300000/-  
DEPOSIT AT CALL



22-08-2016

Received from Executive Engineer Drainage Div. Badm  
Rupees One million three hundred thousand only.  
as a Deposit repayable at call.

NOT TRANSFERABLE

For First Women Bank Limited

Rs. 1300000/-

*[Signature]*  
Authorised Signature

*[Signature]*  
Authorised Signature

This receipt must be returned to the Bank duly discharged by the depositor.

Do not write below this line

⑈0301696⑈0470017⑈000000000000⑈080⑈

# SPPRA BIDDING DOCUMENTS



## GOVERNMENT OF SINDH

Name of Department: **IRRIGATION DEPARTMENT**

Name of Project/Scheme: ADP NO. 648 "POCKET DRAINAGE SYSTEM FOR PART COMMAND DEHS KALHORKI, JHURKANDI, KERANDDI AND CHORHAL CANTONMENT AREA TAPO, TALUKA AND DISTRICT BADIN"

Name of Work:- PACKAGE NO. 2) CONSTRUCTION OF INTERNAL DISPOSAL CHANNELS FROM TUBE WELLS TO PROPOSED DRAIN I/C ROAD CULVERT AND RCC PIPE ALONG BADIN CANTT:

- a) Construction of Internal Disposal Channels from Tube wells to proposed drain.
- b) Construction of (01 No.) Road Culvert.
- c) Construction of (02 No.) RCC Pipe Inlets

Name of Procuring Agency: **Executive Engineer, Drainage Division, Badin**

Document issued to:

Haji  
M/S Sirajuddin Soomro

DR No. & Amount:

76/02 dt: 17-02-2016

  
Executive Engineer  
Drainage Division  
Badin

PACKAGE NO. 02

**SUMMARY OF BID PRICE**

**CONTRACT NAME** CONSTRUCTION OF INTERNAL DISPOSAL CHANNELS FROM TUBEWELLS TO PROPOSED DRAINAGE ROAD CULVERT AND RCC PIPE ALONG BADIN CANTT:

Bill Nr.	Description	Amount
1	Earth Work A) EARTH WORK	17309,683.86/-
2	Structures B) ROAD CULVERT C) R.C.C PIPE INLETS	702,558/- 1245370/-
	Total Bid Price (the amount to entered in paragraph 1 to 2 of the form of bid in words ONE crore Ninety two lac Fifty seven thousand six hundred eleven only and eighty six paise only	19257,611.86



Signature: \_\_\_\_\_  
Company Name: \_\_\_\_\_

**EXECUTIVE ENGINEER**  
Drainage Division  
Badin.

## SCHEDULE OF PRICE

Name of Work:- (A) Construction internal disposal From Tubewell to Proposed Drain in Cantt: Badin

Bill No. 1: Earth Work

Item Nr.	Description	Unit	Specification Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	Earth work excavation in Irrigation channels drain etc dressed to designed section grades and profiles excavated material disposed off and dressed within 50' lead in-ordinary soil.	P/ Cft		150000.00	8	Eight only	12,00,000/2
2	Dressing & leveling of earth work to design section etc complete.(b) Ordinary Soil	P/ Cft		150000.00	0.25	Twenty five Paisa only	37,500/2
3	Stone pitching including sub base with hammer dressed stone on surface laid in courses including carriage of materials chain.	P/ Cft		131250.00	42	Forty Two only	SS 12,500/2
4	Supplying and stacking at site stone metal of size 3/4" -1 1/2" (19 mm to 38 mm) ring i/c screening washing and spreading the same in filter beds to correct level etc complete.	P/ Rft		3110.37	78	Seventy eight only	242,609/2
5	Providing, Laying & Fixing in trench i/c fitting, jointing & testing etc complete in all respect the high Density polyethylene PE pipes (HDPE-100)						
	8" dia (200 mm) pipe	P/ Rft		4555.00	22.65	Two thousand Two hundred Sixty five only	10317,075/2
Total Bid Price (the amount to entered in paragraph 1 of the form of Bid) in words							
ONE Crore Seventy Three Lacs Nine thousand Six hundred Eighty four only							17309684/2



Signature: *[Signature]*  
Company Name:

**EXECUTIVE ENGINEER**  
**Drainage Division**  
**Badin.**

**SCHEDULE OF PRICE**

Name of Work:- **(B) ROAD CULVERT OVER BADIN CANTT. LINK DRAIN OUT FALLING IN LOWARI BRANCH DRAIN**

Bill No. 2] Structures

Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	Excavation in foundation of building bridges and other structures with excavated earth watering and ramming lead one chain and lift upto 5' in ordinary soil.	P/ Cft		1636	7	Seven only	11452/2
2	Cement concrete plain including placing compacting finishing and curing complete including screening and washing of stone aggregate without shuttering ratio 1:3:6.	P/ Cft		440	150	one hundred Fifty only	66000/2
3	Cement Concrete Plain including placing compacting finishing curing up to 20 ft height in sand cement concrete Ratio 1:2:4	P/ Cft		240	290	Two hundred Ninety only	69600/2
4	Pacca Brick work in foundation and plinth cement sand mortar Ratio 1:5	P/ Cft		661.00	200	Two hundred only	132200/2
5	Pacca brick other than bldg. including striking of joints upto 20 ft height in cement sand mortar ratio 1:5.	P/ Cft		900.00	210	Two hundred Ten only	189000/2
7	Fabrication of mild steel reinforcement for cement concrete including cutting, bending, laying in position making joints and fastening including cost of binding wire (also includes removal of rust from bars).	Per Cwt		7.95	7200	Seven thousand Two hundred only	57096/2

**EXECUTIVE ENGINEER**  
Drainage Division  
Badin.

*J. N. S.*



6	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms, moulds, lifting, shuttering, curring, rendering and finishing the exposed surface (including screening and washing of shingle). (a) R.C.C work in roof slabs beams columns, rafts, lintels and other structural members laid in situ or precast laid in position complete in all respects (i) Ratio (1:2:4) 90 lbs cement 2 Cft Sand, 4 Cft Shingle 1/8" to 1/4" gauge.	Per Cft	148.00	500	five hundred only	74,000/-
8	Cement Plaster 1:3 up to 20 ft height 3/4" thick.	P/ Cft	1003	70	Seventy only	70,210/-
9	Borrow pit excavation undressed lead upto 100 ft	100/ Cft	4000	8	eight only	32,000/-
10	Dressing & leveling of earth work to design section etc complete. (b) Ordinary Soil	100/ Cft	4000	0.25	Twenty five Paise only	1000/-
<b>Total Bid Price of 1 No. Road Culvert (the amount to entered in paragraph 1 of the form of Bid) in words</b> <i>Seven lac Two thousand five hundred fifty eight only</i>						

Signature: *[Signature]*  
Company Name: *[Signature]*



**EXECUTIVE ENGINEER**  
**Drainage Division**  
**Bahawalpur**

**SCHEDULE OF PRICE**

Name of Work:- (C) CONSTRUCTION OF (02 NO.) RCC PIPE INLET OVER BADIN CANTT. LINK DRAIN  
 Bill No. 2) Structures

Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	Excavation in foundation of building bridges and other structures with excavated earth watering and ramming lead one chain and lift upto 5' in ordinary soil.	P/Cft		3875	7	Seven only	27,125/-
2	Cement concrete plain including placing compacting finishing and curing complete including screening and washing of stone aggregate without shuttering ratio 1:3:6.	P/Cft		908	150	one hundred fifty only	136,200/-
3	Pacca Brick work in foundation and plinth cement sand mortar Ratio 1:5	P/Cft		855	200	Two hundred only	17,000/-
4	Pacca brick other than bldg. including striking of joints upto 20 ft height in cement sand mortar ratio 1:5.	P/Cft		414	210	Two hundred Ten only	86,940/-
5	Providing & laying and jointing RCC pipes ASTM C-96-62 T/C-76-70 Class-II WALL B and fixing in trench i.e cutting fitting and jointing with rubber ring i/c testing with water to specified pressure. 24" dia	P. Rft		32	500	five hundred only	16000/-

**EXECUTIVE ENGINEER**  
 Drainage Division  
 Badin

*[Signature]*  


6	Cement Plaster 1:3 up to 20 ft. height 3/4" thick.	P/ Sft	881	70.	Seventy only	616.70/2
7	Borrow pit excavation undressed lead upto 100 ft. In ordinary soil.	100/ Cft	15000	8	eight only	120,000/2
8	Dressing & leveling of earth work to design section etc complete. (b) Ordinary Soil	100/ Cft	15000	0.25	Twenty Five Paisa only.	3750/2
<b>Total Bid Price of 1 No. Pipe Inlet</b>						
<b>Total Bid Price of 02 No. Pip Inlets (the amount to entered in paragraph 1 of the form of Bid) In words</b>						
<i>Twelve lac forty five thousand three hundred seventy only</i>						

*[Signature]*  
**EXECUTIVE ENGINEER**  
**Drainage Division**  
**Badin.**

Signature: *[Signature]*  
Company Name: *[Signature]*



1245370/2





بنك الفلاح المحدود

BANK ALFALAH LIMITED

(0045) Main Branch Saddar Hyderabad

# Call Deposit Receipt

No. CDRHYD 0685207

Ref. No. FT16053733000005

Date: 22 FEB 2016

Amount not over PKR 440,000.00 only

Rs. 440,000.00


Received from M/S. HAJI, SIRAJUDDIN SOOMRO


On Account EXECUTIVE ENGINEER DRAINAGE DIVISION BADIN ON A/C M/S. HAJI SIRAJUDDI  
N SOOMRO

Rupees FOUR HUNDRED FORTY THOUSAND ONLY

as a deposit at call bearing no Interest/Profit subject to general rules of the Bank with respect to such deposits.

THIS RECEIPT IS NON TRANSFERABLE  
PAYABLE TO BENEFICIARY ONLY

  
13  
Authorized Signature

  
Authorized Signature

# SPPRA BIDDING DOCUMENTS



## GOVERNMENT OF SINDH

Name of Department: **IRRIGATION DEPARTMENT**

Name of Project/Scheme: ADP NO. 648 "POCKET DRAINAGE SYSTEM FOR PART COMMAND DEHS KALHORKI, JHURKANDI, KERANDDI AND CHORHAL CANTONMENT AREA TAPO, TALUKA AND DISTRICT BADIN"

Name of Work:- PACKAGE NO. 2) CONSTRUCTION OF INTERNAL DISPOSAL CHANNELS FROM TUBE WELLS TO PROPOSED DRAIN I/C ROAD CULVERT AND RCC PIPE ALONG BADIN CANTT:

- a) Construction of Internal Disposal Channels from Tube wells to proposed drain.
- b) Construction of (01 No.) Road Culvert.
- c) Construction of (02 No.) RCC Pipe Inlets


Name of Procuring Agency: **Executive Engineer, Drainage Division, Badin**

Document issued to:

M/S Thadavi Enterprises

DR No. & Amount:

77/02 dt: 17/02/2016.

  
Executive Engineer  
Drainage Division  
Badin

PACKAGE NO. 02


**SUMMARY OF BID PRICE**

**CONTRACT NAME** CONSTRUCTION OF INTERNAL DISPOSAL CHANNELS FROM TUBEWELLS TO PROPOSED DRAI I/C ROAD CULVERT AND RCC PIPE ALONG BADIN CANTT:

Bill Nr.	Description	Amount
1	Earth Work A) EARTH WORK	19764471.0
2	Structures B) ROAD CULVERT C) R.C.C PIPE INLETS	8284321.0 1556380.0
	Total Bid Price (the amount to entered in paragraph 1 to 2 of the form of bid in words <i>Twenty Two million one HUNDRED SEVENTY NINE THOUSAND TWO HUNDRED EIGHTY THREE one</i> )	22149283.0

Signature:

Company Name:



**SCHEDULE OF PRICE**

Name of Work:- (A) Construction internal disposal From Tubewell to Proposed Drain in Cantt: Badin  
 Bill No. 1: Earth Work

Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	Earth work excavation in Irrigation channels drain etc dressed to designed section grades and profiles excavated material disposed off and dressed within 50' lead in ordinary soil.	P/ Cft		150000.00	9.0	NINE RUPEES only	1,350,000.00
2	Dressing & leveling of earth work to design section etc complete. (b) Ordinary Soil	P/ Cft		150000.00	0.5	FIFTY PAISA only	75,000.00
3	Stone pitching including sub base with hammer dressed stone on surface laid in courses including carriage of materials chain.	P/ Cft		131250.00	60.0	SIXTY RUPEES only	7,875,000.00
4	Supplying and stacking at site stone metal of size 3/4" - 1 1/2" (19 mm to 38 mm) ring i/c screening washing and spreading the same in filter beds to correct level etc complete.	P/ Rft		3110.37	84.0	EIGHTY FOUR only	261,271.08
5	Providing, Laying & Fixing in trench i/c fitting, jointing & testing etc complete in all respect the high Density polyethylene PE pipes (HDPE-100)	P/ Rft					
	8" dia (200 mm) pipe	P/ Rft		4555.00	2240.0	TWO THOUSAND TWO HUNDRED forty	10,203,200.00
Total Bid Price (the amount to entered in paragraph 1 of the form of Bid) In words NINETEEN MILLION SEVEN HUNDRED SIXTY FOUR THOUSAND FOUR HUNDRED SEVENTY one only 19,764,471.08							




Signature: *[Handwritten Signature]*  
 Company Name:

SCHEDULE OF PRICE

Name of Work:- (5) ROAD CULVERT OVER BADIN CANTT. LINK DRAIN OUT FALLING IN LOWARI BRANCH DRAIN  
 Bill No. 2 Structures

Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	Excavation in foundation of building bridges, and other structures with excavated earth watering and ramming lead one chain and lift upto 5' in ordinary soil.	P/ Cft		1636	8.0	EIGHT RUPEES only	13,088.0
2	Cement concrete plain including placing compacting finishing and curing complete including screening and washing of stone aggregate without shuttering ratio 1:3:6.	P/ Cft		440	170.0	one HUNDRED SEVENTY only	74,800.0
3	Cement Concrete Plain including placing compacting finishing curing up to 20 ft height in sand cement concrete Ratio 1:2:4	P/ Cft		240	320.0	THREE HUNDRED TWENTY only	76,800.0
4	Pacca Brick work in foundation and plinth cement sand mortar Ratio 1:5	P/ Cft		661.00	250.0	TWO HUNDRED FIFTY only	165,250.0
5	Pacca brick other than bidg: including striking of joints upto 20 ft height in cement sand mortar ratio 1:5.	P/ Cft		900.00	250.0	TWO HUNDRED FIFTY only	225,000.0
7	Fabrication of mild steel reinforcement for cement concrete including cutting, bending, laying in position making joints and fastening including cost of binding wire (also includes removal of rust from bars)	Per Cwt		7.93	7800.0	SEVEN THOUSAND EIGHT HUNDRED only	61,854.0



6	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms, moulds, lifting, shuttering, curring, rendering and finishing the exposed surface (including screening and washing of shingle). (a) R.C.C work in roof slabs beams columns, rafts, lintels and other structural members laid in situ or precast laid in position complete in all respects (i) Ratio (1:2:4) 90 lbs cement 2 Cft Sand, 4 Cft Shingle 1/8" to 1/4" gauge.	Per Cft	148.00	550.0	FIVE HUNDRED FIFTY ONLY	81,400.0
8	Cement Plaster 1:3 up to 20 ft height 3/4" thick.	P/ Cft	1003	80.0	EIGHTY ONLY	80,240.0
9	Borrow pit excavation undressed lead upto 100 ft	100/ Cft	4000	12.0	TWELVE ONLY	48,000.0
10	Dressing & leveling of earth work to design section etc complete. (b) Ordinary Soil	100/ Cft	4000	0.5	FIFTY PAISA	2,000.0
Total Bid Price of 1 No. Road Culvert (the amount to entered in paragraph 1 of the form of Bid) In words						828,432.0
EIGHT HUNDRED TWENTY EIGHT THOUSAND FOUR HUNDRED THIRTY TWO ONLY						




Signature:  
Company Name:

**SCHEDULE OF PRICE**

Name of Work:- (C) CONSTRUCTION OF (02 NO.) RCC PIPE INLET OVER BADIN CANTT. LINK DRAIN  
 Bill No. 2) Structures

Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	Excavation in foundation of building bridges and other structures with excavated earth watering and ramming lead one chain and lift upto 5' in ordinary soil.	P/ Cft		3875	8.0	EIGHT RUPEES only	31,000.0
2	Cement concrete plain including placing compacting finishing and curing complete including screening and washing of stone aggregate without shuttering ratio 1:3:6.	P/ Cft		908	170.0	ONE HUNDRED SEVENTY only	154,360.0
3	Pacca Brick work in foundation and plinth cement sand mortar Ratio 1:5	P/ Cft		855	250.0	TWO HUNDRED FIFTY only	213,750.0
4	Pacca brick other than bldg: including striking of joints upto 20 ft height in cement sand mortar ratio 1:5.	P/ Cft		414	250.0	TWO HUNDRED FIFTY only	103,500.0
5	Providing & laying and jointing RCC pipes ASTM C-96-62 T/C-76-70 Class-II WALL B and fixing in trench i.e cutting fitting and jointing with rubber ring i/c testing with water to specified pressure. 24" dia	P. Rft		32	550	FIVE HUNDRED FIFTY only	17,600.0




*[Handwritten Signature]*

6	Cement Plaster 1:3 up to 20 ft. height 3/4" thick.	P/ Sft	881	80.0	EIGHTY ONLY	70,480.0
7	Borrow pit excavation undressed lead upto 100 ft. In ordinary soil.	100/ Cft	15000	12.0	TWELVE ONLY	180,000.0
8	Dressing & leveling of earth work to design section etc complete. (b) Ordinary Soil	100/ Cft	15000	0.5	FIFTY PAISA ONLY	7500.0
Total Bid Price of 1 No. Pipe Inlet SEVEN HUNDRED SEVENTY EIGHT THOUSAND ONE HUNDRED NINETY ONLY						
Total Bid Price of 02 No. Pip Inlets (the amount to entered in paragraph 1 of the form of Bid) In words ONE MILLION FIVE HUNDRED FIFTY SIX THOUSAND THREE HUNDRED EIGHTY ONLY						
778190.0						
1556380.0						

Signature:

Company Name:





**NON TRANSFERABLE**

**CALL DEPOSIT RECEIPT**

Branch

Phone: 022-2730911-5 Fax: 022-2730911-5

Telex: SUMBPKKA

CDR No: 4999

DATE: 22 Feb 2016

RS. 470,000.00

RECEIVED FROM

IN FAVOUR OF

EXECUTIVE ENGINEER DRAINAGE DIVISION BADIN ON A/C OF THADANI ENTERPRISES

THE SUM OF RUPEES PAK RUPEE FOUR HUNDRED AND SEVENTY THOUSAND ONLY

As a deposit AT CALL bearing NO PROFIT subject to the general rules of the Bank with respect to such deposits.

This receipt is Non-Transferable and Payable to Beneficiary or Purchaser.

In the event that this instrument is not encashed within 6 months of issue. The Bank reserves the right to validate the same before encashment.

Encashment of this instrument is subject to payment of withholding tax, as per applicable law.

CDR. 00004999

For Summit Bank Limited

AUTHORIZED SIGNATURE

AUTHORIZED SIGNATURE

⑈00004999⑈0810036⑈

⑈080⑈

# SPARA BIDDING DOCUMENTS



## GOVERNMENT OF SINDH

Name of Department: **IRRIGATION DEPARTMENT**

Name of Project/Scheme: ADP NO. 648 "POCKET DRAINAGE SYSTEM FOR PART COMMAND DEHS KALHORKI, JHURKANDI, KERANDDI AND CHORHAL CANTONMENT AREA TAPO, TALUKA AND DISTRICT BADIN"

Name of Work:- PACKAGE NO. 2) CONSTRUCTION OF INTERNAL DISPOSAL CHANNELS FROM TUBE WELLS TO PROPOSED DRAIN I/C ROAD CULVERT AND RCC PIPE ALONG BADIN CANTT:

- a) Construction of Internal Disposal Channels from Tube wells to proposed drain.
- b) Construction of (01 No.) Road Culvert.
- c) Construction of (02 No.) RCC Pipe Inlets

H

Name of Procuring Agency: **Executive Engineer, Drainage Division, Badin**

Document issued to:

M/S Malani Construction Company

DR No. & Amount:

79/02, dt: 17/02/2016 -


  
Executive Engineer  
Drainage Division  
Badin

PACKAGE NO. 02

**SUMMARY OF BID PRICE**

**CONTRACT NAME** CONSTRUCTION OF INTERNAL DISPOSAL CHANNELS FROM TUBEWELLS TO PROPOSED DRAI I/C ROAD CULVERT AND RCC PIPE ALONG BADIN CANTT.

Bill Nr.	Description	Amount
1	Earth Work A) EARTH WORK	23,130,080/-
2	Structures B) ROAD CULVERT C) R.C.C PIPE INLETS	792,894/- 1438,990/-
	Total Bid Price (the amount to entered in paragraph 1 to 2 of the form of bid in words <i>Twenty Five Million Three Hundred Sixty one Thousand Nine Hundred Sixty four only</i> )	25,361,964/-



Signature:


Company Name:

## SCHEDULE OF PRICE

Name of Work:- (A) Construction internal disposal From Tubewell to Proposed Drain in Cantt: Badin  
 Bill No. 1: Earth Work

Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	Earth work excavation in Irrigation channels drain etc dressed to designed section grades and profiles excavated material disposed off and dressed within 50' lead in ordinary soil.	P/ Cft		150000.00	10/-	Ten Rupees only	1,500,000/-
2	Dressing & leveling of earth work to design section etc complete. (b) Ordinary Soil	P/ Cft		150000.00	1/-	one Rupees only	150,000/-
3	Stone pitching including sub base with hammer dressed stone on surface laid in courses including carriage of materials chain.	P/ Cft		131250.00	75/-	Seventy five Rupees only	9,843,750/-
4	Supplying and stacking at site stone metal of size 3/4" - 1 1/2" (19 mm to 38 mm) ring i/c screening washing and spreading the same in filter beds to correct level etc complete.	P/ Rft		3110.37	80/-	Eighty Rupees only	248,830/-
5	Providing, Laying & Fixing in trench i/c fitting, jointing & testing etc complete in all respect the high Density polyethylene PE pipes (HDPE-100)	P/ Rft					
	8" dia (200 mm) pipe	P/ Rft		4555.00	2500/-	Two Thousand Five Hundred only	11,387,500/-
Total Bid Price (the amount to entered in paragraph 1 of the form of Bid) In words				Twenty Three Million on Hundred			23,130,080/-

*Twenty Three Million on Hundred only.*



Signature: \_\_\_\_\_  
 Company Name: \_\_\_\_\_

**SCHEDULE OF PRICE**

Name of Work:- **(B) ROAD CULVERT OVER BADIN CANTT. LINK DRAIN OUT FALLING IN LOWARI BRANCH DRAIN**  
 Bill No. 2] Structures

Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	Excavation in foundation of building bridges and other structures with excavated earth watering and ramming lead one chain and lift upto 5' in ordinary soil.	P/ Cft		1636	9/2	Nine Rupees only	14,724/-
2	Cement concrete plain including placing compacting finishing, and curing complete including screening and washing of stone aggregate without shuttering ratio 1:3:6.	P/ Cft		440	140/-	One Hundred forty only	61,600/-
3	Cement Concrete Plain including placing compacting finishing curing up to 20 ft height in sand cement concrete Ratio 1:2:4	P/ Cft		240	250/-	Two Hundred fifty only	60,000/-
4	Pacca Brick work in foundation and plinth cement sand mortar Ratio 1:5	P/ Cft		661.00	190/-	one hundred Ninety Rupees only	125,590/-
5	Pacca brick other than bldg: including striking of joints upto 20 ft height in cement sand mortar ratio 1:5.	P/ Cft		.900.00	250/-	Two Hundred Fifty Rupees only	225,000/-
7	Fabrication of mild steel reinforcement for cement concrete including cutting, bending, laying in position making joints and fastening including cost of binding wire (also includes removal of rust from bars)	Per Cwt		7.93	7000/-	Seven thousand only	55,510/-

6	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms, moulds, lifting, shuttering, curring, rendering and finishing the exposed surface (including screening and washing of shingle). (a) R.C.C work in roof slabs beams columns, rafts, lintels and other structural members laid in situ or precast laid in position complete in all respects (i) Ratio (1:2:4) 90 lbs cement 2 Cft Sand, 4 Cft Shingle 1/8" to 1/4" gauge.	Per Cft	148.00	650/-	Six Hundred Fifty Rupees only	96,200/-
8	Cement Plaster 1:3 up to 20 ft height 3/4" thick.	P/ Cft	1003	90/-	Ninety Rupees only	90,270/-
9	Borrow pit excavation undressed lead upto 100 ft	100/ Cft	4000	15/-	Fifteen Rupees only	60,000/-
10	Dressing & leveling of earth work to design section etc complete. (b) Ordinary Soil	100/ Cft	4000	1/-	one Rupee only	4000/-
Total Bid Price of 1 No. Road Culvert (the amount to entered in paragraph 1 of the form of Bid) In words						792,894/-
Seven Hundred Ninety Two Thousand Eight Hundred ninety four only						



Signature:  
Company Name:

**SCHEDULE OF PRICE**

Name of Work:- (C) CONSTRUCTION OF (02 NO.) RCC PIPE INLET OVER BADIN CANTT. LINK DRAIN  
 Bill No. 2) Structures

Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	Excavation in foundation of building bridges and other structures with excavated earth watering and ramming lead one chain and lift upto 5' in ordinary soil.	P/ Cft		3875	9/2	Nine Rupees only	34,875/2
2	Cement concrete plain including placing compacting finishing and curing complete including screening and washing of stone aggregate without shuttering ratio 1:3:6.	P/ Cft		908	140/	One hundred forty only	127,120/2
3	Pacca Brick work in foundation and plinth cement sand mortar Ratio 1:5	P/ Cft		855	250/	Two hundred fifty only	213,750/2
4	Pacca brick other than bldg: including striking of joints upto 20 ft height in cement sand mortar ratio 1:5.	P/ Cft		414	190/	One hundred ninety only	78,660/2
5	Providing & laying and jointing RCC pipes ASTM C-96-62 T/C-76-70 Class-II WALL B and fixing in trench i.e cutting fitting and jointing with rubber ring i/c testing with water to specified pressure. 24" dia	P. Rft		32	650/	Six hundred fifty only	20,800/2



6	Cement Plaster 1:3 up to 20 ft. height 3/4" thick.	P/ Sft	881	90%	Ninety Rupees only	79,250/-
7	Borrow pit excavation undressed lead upto 100 ft. In ordinary soil.	100/ Cft	15000	10%	Ten Rupees only	150,000/-
8	Dressing & leveling of earth work to design section etc complete. (b) Ordinary Soil	100/ Cft	15000	1%	One Rupee only	15000/-
<b>Total Bid Price of 1 No. Pipe Inlet</b>						
<b>Total Bid Price of 02 No. Pip Inlets (the amount to entered in paragraph 1 of the form of Bid) In words</b>						
One Million Four Hundred Thirty Eight Thousand Nine Hundred ninety only						



Signature:  
Company Name:





**First Women Bank Ltd.** HYDERABAD BRANCH.

No. FWDC 0301697

*500000 only*

**DEPOSIT AT CALL**

*22-02-2016*

Received from *Executive Engineer Drainage Div. Badin*  
Rupees *Five hundred thousand only.*  
as a Deposit repayable at call.

For First Women Bank Limited

NOT TRANSFERABLE

Rs. *500000/-*

*[Signature]*  
Authorised Signature

*[Signature]*  
Authorised Signature

This receipt must be returned to the Bank duly discharged by the depositor.

Do not write below this line

⑈0301697⑈0470017⑈000000000000⑈080⑈

# SPPRA BIDDING DOCUMENTS



## GOVERNMENT OF SINDH

Name of Department: **IRRIGATION DEPARTMENT 3**

Name of Project/Scheme: ADP NO. 648 "POCKET DRAINAGE SYSTEM FOR PART COMMAND DEHS KALHORKI, JHURKANDI, KERANDDI AND CHORHAL CANTONMENT AREA TAPO, TALUKA AND DISTRICT BADIN"

Name of Work:- **PACKAGE NO. 03: DISPOSAL CHANNEL ALONG CANTT: AREA @ BADIN.**

- a) Construction of Pump House,
- b) Construction RCC Sump /Tank 16'x8'
- c) Providing & laying, Jointing & Testing A.C Rising Main 24" Q dia for disposal of wet weather flow from Cantt. Badin 2050 Rft.
- d) Supplying & Installing 60 BHP A.C Electric Motor for disposal of storm water flow from cantt. Badin and adjoining area.
- e) External Electrification.
- f) Diesel Generator 50 KVA (02 No.) along Cantonment Area @ Badin

Name of Procuring Agency: **Executive Engineer, Drainage Division, Badin**

Document issued to:

M/S Thadani Enterprises

DR No. & Amount:

77/03 At: 17-02-2016

*[Signature]*  
Executive Engineer  
Drainage Division  
Badin

PACKAGE NO. 03

**SUMMARY OF BID PRICE**

**CONTRACT NAME** DISPOSAL CHANNEL ALONG CANTT: AREA @ BADIN.

Bill Nr.	Description	Amount
1	Earth Work	
2	Structures A) PUMP HOUSE B) R.C.C SUMP / TANK 16'X 8' C) PROVIDING LAYING JOINTING & TESTING AC RISING MAIN 24" DIA D) SUPPLYING & INSTALLING 60 BHP A.C ELECTRIC MOTOR E) SUPPLYING & INSTALLING 60 BHP A.C ELECTRIC MOTOR F) SUPPLYING DIESEL GENERATOR	1171056.80 1895363.50 25163820.0 3620000.0 4270020.0 6000650.0
Total Bid Price (the amount to entered in paragraph 1 to 2 of the form of bid in words <i>FOURTY Two million one Hundred Twenty THOUSAND Two Hundred SIXTY RUPEES and THIRTY PaISA only.</i>		42120260.30



Signature: \_\_\_\_\_  
Company Name: \_\_\_\_\_

**EXECUTIVE ENGINEER**  
Drainage Division  
Badin

**SCHEDULE OF PRICE**

Name of Work:- (A) CONSTRUCTION OF PUMP HOUSE  
 Bill No. 2) Structures


Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	Excavation in foundation of building bridges and other structure including dabelling dressing refilling around structure with excavated earth watering and ramming lead upto 5 ft in soft soil.	P/Cft		396.00	7.8	SEVEN ROPEES EIGHTY PAISSA only	3088-8
2	Cement concrete brick or stone ballast 1 1/2" to 2" guage Ratio 1:4:8.	P/Cft		256.00	180.0	one Hundred Eighty only	46080.0
3	Random rubble masonry (uncoursed) ratio 1:6.	P/Cft		223.00	300.0	THREE Hundred only	66900.0
4	Coursed Rubble Masonry including hammer dressing, cement mortar ratio 1:6.	P/Cft		624.00	400.0	four Hundred only	249600.0
5	Damp proof course with (cement sand and shingle concrete 1:2:4 i/e 2 coats asphaltic mixture.	P/Sft		149.00	50.0	fifty only	7450.0
6	Pacca brick work in ground floor i/c of joints in cement sand mortar (1:6)	P/Sft		707.00	330.0	THREE Hundred THIRTY only	233310.0



*Handwritten signature*

**EXECUTIVE ENGINEER**  
 Drainage Division


7	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms, moulds, lifting, shuttering, curring, rendering and finishing the exposed surface (including screening and washing of shingle). (a) R.C.C work in roof stabs beams columns, rafts, lintels and other structural members laid in situ or precast laid in position complete in all respects (i) Ratio (1:2:4) 90 lbs cement 2 Cft Sand, 4 Cft Shingle 1/8" to 1/4" guage.	P/Cft	324.00	639.00	SIX HUNDRED THIRTY NINE only 207036.00
8	Fabrication of mild steel reinforcement for cement concrete including cutting, bending, laying in position making joints and fastening including cost of binding wire (also includes removal of rust from bars)	P/Cwt	6.65	7800.00	SEVEN THOUSAND EIGHT HUNDRED only 51870.00
9	Cement concrete plain including placing compacting finishing and curing complete including screening and washing of stone aggregate without shuttering ratio 1:3:6.	P/Cft	128.00	280.00	TWO HUNDRED EIGHTY only 35840.00
10	Cement Plaster 1:4 up to 20 ft height.	P/Sft	866.00	70.00	SEVENTY only 60620.00
11	Cement plaster 1:4 upto 20' height 3/8" thick	P/Sft	866.00	65.00	SIXTY FIVE only 56290.00
12	Making and fixing steel grated door with 1 1/6" thick as binding i/c angle iron frame 2"x2x3/3 and 3/4" sq. bars 4" centre to centre with locking arrangement.	P/Sft	23.00	1000.00	ONE THOUSAND only 23000.00
13	Cement pointing flush on stone work. (in cement mortar 1:3)	P/Sft	2500.00	30.00	THIRTY only 75000.00



EXECUTIVE ENGINEER  
Drainage Division  
Badin.

14	Supplying and fixing in position iron steel grill of 3/4" x 1/4" size flat iron of approved design i/c painting and 3 coats etc complete weight not to be less than 3.7 pounds / Sq. ft. of finish grill.	P/ Sft	36.00	300.0	THREE Hundred only	10800.0
15	Supplying and fixing windows of Z section 3/4" x 3/4" x 1/8" partly fixed partly open i/c fixing with 2408 x z glass fitting and painting 3 coat etc complete	P/ Sft	80.00	300.0	THREE Hundred only	24000.0
16	White washing 3 coats	P/ Sft	1956.00	5.0	FIVE only	9780.0
17	Colour washing 2 coats	P/ Sft	866.00	8.0	EIGHT only	6928.0
18	White washing 2 coats	P/ Sft	866.00	4.0	FOUR only	3464.0
Total Bid Price of PUMP HOUSE (the amount to entered in paragraph 1 of the form of Bid) In words one million one Hundred SEVENTY one THOUSAND						1171056.80

FIFTY SIX RUPEES EIGHTY PAISA only.



Signature:  
Company Name:


EXECUTIVE ENGINEER  
Drainage Division  
Badli.

**SCHEDULE OF PRICE**

Name of Work:- **(B) CONSTRUCTION OF R.C.C SUMP / TANK 16' X 8' ALONG CANTT: AREA @ BADIN.**

Bill No. 2 Structures


Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	Excavation of well in dry upto 20' below ground level and disposal of soil within one chain 0-3' depth	P/ Cft		582.75	18.0	EIGHTEEN RUPEES only	10489.50
2	Wet sinking of wells for depth below spring level by means of i/c all charges for shoring leading and ramming excavated material with one chain in (ordinary soil)						
i	0-5' depth	P/ Cft		389.00	15.0	FIFTEEN only	5835.0
ii	5-10' depth	P/ Cft		971.00	30.0	THIRTY only	29130.0
iii	10-15' depth	P/ Cft		971.00	45.0	FOURTY FIVE only	43695.0
iv	15-20' depth	P/ Cft		971.00	55.0	FIFTY FIVE only	53405.0
3	Cement concrete brick or stone ballast 1 1/2" x 2" gauge in cement sand mortar ratio 1:4:8.	P/ Cft		224.00	170.0	one Hundred SEVENTY only	38080.0
4	Cement concrete including washing of aggregate and ramming						
i.	Ratio 1:3:6	P/ Cft		116.25	280.0	Two Hundred Eighty	32550.0
ii.	Ratio 1:2:4	P/ Cft		116.25	300.0	THREE Hundred	34875.0



*(Signature)*

EXECUTIVE ENGINEER  
Drainage Division  
Badin

5	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms, moulds, lifting, shuttering, curring, rendering and finishing the exposed surface (including screening and washing of shingle). (a) R.C.C work in roof slabs beams columns, rafts, lintels and other structural members laid in situ or precast laid in position complete in all respects (i) Ratio (1:2:4) 90 lbs cement 2 Cft Sand, 4 Cft Shingle 1/8" to 1/4" gauge.	P/Cft		1052.00	639.0	Six Hundred THIRTY NINE only	672228.0	
6	Fabrication of mild steel reinforcement for cement concrete including cutting, bending, laying in position making joints and fastening including cost of binding wire (also includes removal of rust from bars)	P/cwt		61.17	7800.0	SEVEN THOUSEND Eight Hundred only	477126.0	
7	Providing and fixing C.C foundation 1:3:6 M.S Leader M.S angle iron 2" x 2" x 1/4" 1-0 sport with M.S bars 3/4" dia 1-0 sport i/c painting 3 coats with anticorrosive sheet paint etc complete	P/Rft		20.00	2000.0	Two THOUSEND only	40000.0	
8	Providing construction joints in concrete work of 9' wide corrugated P.V.C water stopper with bulb i/c soldering cost of material and labour	P/Rft		1224.00	300.0	THREE Hundred only	367200.0	
9	Cement Plaster 1:4 up to 20 ft height.	P/Sft		1020.00	70.0	SEVENTY only	71400.0	
10	Supply Hi-bond pre-packaged paymer modified mortar (DHPMM) Hi-bond (sector)	P/Kg		215.00	90.0	NINETY only	19350.0	
Total Bid Price of R.C.C SUMP / TANK (the amount to entered in paragraph 1 of the form of Bid) In words							THREE	1895363.0



one million Eight Hundred NINETY FIVE THOUSEND THREE Hundred SIXTY THREE Rupees FIFTY PAISA only

Signature:  
Company Name:


EXECUTIVE ENGINEER  
Drainage Division  
Badin.



**SCHEDULE OF PRICE**

**Name of Work:- (C) PROVIDING LAYING JOINTING & TESTING AC RISING MAIN 24" DIA FOR DISPOSAL OF WT WEATHER FLOW FROM CANTT. BADIN AND ADJOINING AREA DISTRICT BADIN**

Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	Dismantling & remaining Road metalling	P/Cft		125.00	10.0	Ten only	1250.0
2	Excavation of pipe line in trenches and pits i/e terimming and dressing side to true alignment and shape leveling of beds of trenches correct level i/e cutting joints holes and disposal of surplus earth one chain as directed by engineer in charge i/e providing fence guards light flag and wherever required lift upto 5 ft. and lead up to one	P/Cft		21525.00	12.0	TWELVE only	258300.0
3	Excavation of pipe line in trenches and pits in wet soil clay or mud i/e trimming and dressing side to alignment and shape leveling of beds of trenches and where ever required lift upto 5 ft. and lead one chain (PHSI No. 14, p-66) correct level i/e cutting joint holes, and disposal flag.	P/Cft		22525.00	12.0	TWELVE only	270300.0
4	Full Hire charges of Pumping set per day including of the wages of driver and assistant fuel or electric energy required plate form with suction and delivery pipe for pumping out water from trench i/c the cost of erection and dismantling of acopements after completion of job.	P/day		40.00	1500.0	one THOUSAND FIVE HUNDRED only	60000.0




**CALCUTIVE ENGINEER**  
Drainage Division  
Badin.

5	Providing asbestos cement pressure pipes and cement joint of class B and fixing in IC cutting fitting and jointing with rabble ring i/c testing with water to a head of 122 meter or 400 ft.	P/Rft	2050.00	10120.0	TEN THOUSEND one Hundred Twenty only 20746000.0
6	Cost Iron special for A.C pressure pipe	Each	4.00	45000.0	FOURTY FIVE THOUSEND 180000.0
	Bend 90 Deg	Each	4.00	45000.0	FOURTY FIVE THOUSEND 180000.0
	Bend 45 Deg	Each	4.00	30000.0	THIRTY THOUSEND 120000.0
7	Five Hydrant tee 24" dia	Each	4.00	29000.0	TWENTY NINE THOUSEND 116000.0
8	Air valve double acting 3" x 1" 24" dia	Each	4.00	18000.0	EIGHTEEN THOUSEND only 72000.0
9	C. I short pieces) 24" dia	Each	7.00	6800.0	SIX THOUSEND 47600.0
10	A. C Collar "B" Class 24" dia	Each	7.00	2500.0	EIGHT THOUSEND 17500.0
11	One pair of Rubber Rings for AC pressure pipe "B" class cement joints 24" dia	Each	106.00	9900.0	TWO THOUSEND FIVE HUNDRED NINE THOUSEND 1049400.0
12	Manufacturing supplying Mild steel pipe 1/4" thick cutting bending etc complete. 24" dia	P/Rft	12.00	8000.0	NINE HUNDRED EIGHT THOUSEND 96000.0
13	Manufacturing supplying Mild steel flange of different dia made out of MS sheet of various thickness i/c cutting drilling holes and welding of flanges with M.S pipe etc complete (PHSM) 24" dia	Each	36.44	8000.0	EIGHT THOUSEND 291520.0
14	C.I bend with flanged ends with holes i/c turning and facing of flanges for all size.	P/Cwt			



EXECUTIVE ENGINEER  
Drainage Division  
Badin.

15	Making joint C.I special fitting i/c laying of the required Dia meter and testing the joints along with abestos cement pressure pipe line to the specified pressure and making good all leaky joints etc. complete.	Each	6.00	350.0	THREE HUNDRED FIFTY ONLY	2100.0
16	Providing chamber 3 1/2 x 2 1/2 inside dimension 4 ft deep as apposed designed for sloc valve chamber 15" dia 21" dia with 24" dia inside dimension cast iron cover and frame 2 cwt. Roof in RCC 1:2.4 slab 6" thick cement concrete 1:3:6 in foundation 1" thick cement concrete 1:2.4 flooring 1/2" thick cement plaster 1:3 to all inside valve surfaces lead 2 1/2 depth 24" dia	Each	12.00	45000.0	FOURTY FIVE THOUSAND ONLY	540000.0
17	Jointing C.I / M.S flanged pipe and special flanged and inside trenches i/c supplying rubber packing of required thickness nuts and bolts with washers etc and other tools required for jointing the joints to the specified pressure etc complete. 24" dia	Each	24.00	9500.0	NINE THOUSAND FIVE HUNDRED ONLY	228000.0
18	Refilling the excavated stuff in 6" thick layers i/c watering and raming to full compaction etc complete.	P/ Cft	44175.00	2.0	TWO RUPEES ONLY	88350.0
19	Supplying and fixing 24" dia RCC pipe with sand layer. 24" dia	P/Rft	2050.00	390.0	THREE NINETY ONLY	799500.0
Total Bid Price of AC 24" DIA PIPE (the amount to entered in paragraph 1 of the form of Bid) In words TWENTY FIVE MILLION ONE HUNDRED SIXTY THREE THOUSAND EIGHT HUNDRED TWENTY ONLY						



Signature:  
Company Name:


*[Handwritten signature]*

**SCHEDULE OF PRICE**

Name of Work:- (D) SUPPLYING AND INSTALLING 60 BHP A.C ELECTRIC MOTOR FOR DISPOSAL OF STROM WATER FLOW FROM CANTT BADIN & ADJOINING AREA OF DISTRICT BADIN

**Bill No. 2) Structures**

Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	Supplying and installing in position i/e transportation to site of work at Badin Cantt: A.C electric pumping set consisting of A.C electric motor 60 BHP of 3 phase 50 cycles 400/420 volts 1450 RPM ILG4-223-4AA60 recoupled with non-collonging pump (200-315) size 8"x8" mounted as common steel frame or base plate capable of discharging 1857 gallons / minute against a head of 50 ft. i/e installation of pumping set on C.C foundation ratio 1:2:4 & 1:4:8 with Ballast with M'S nuts and bolts of 5/8" dia to be embedded in C.C foundation i/e providing and fixing on prepared board A.C 50 cycles 3 phase 12/25 ampere trips rating push button type star delta starter complete with no volts and over load release and required i/e providing and fixing on prepared board iron clad tripple pole and neutral switc fuse rewirable type fuse link carried 500 watts grade 30 ampere providing and fixing volts meter 0.500 volts and ampere 0-500 apere installed on installed board i.e providing and fixing metal board to accomodate main or sub mains control switches dressed in the wall size 3' x 2 1/2" i/e providing phase indication bulb with holder and providing internal electric wiring for mains with 3.	P/Set		2 Sets	1810000/-	one million Eight Hundred Ten Thousand only	3620000/-
Total Bid Price of 1 No. 60 BHP A.C ELECTRIC MOTOR							3620000/-
Total Bid Price of 2 No. 60 BHP A.C ELECTRIC MOTOR (the amount to entered in paragraph 1 of the form of Bid) In words							
THREE million Six Hundred Twenty Thousand only							

Signature: 


**EXECUTIVE ENGINEER**  
Drainage Division  
Badin.

**SCHEDULE OF PRICE**

Name of Work:- (E) Supplying and Fixing 200 KV Transformer, PVC Sheeted with 3.5 core copper conductor 600/1000 Size 240mm<sup>2</sup> and other electric materials to provide Electric for 50 No. Tubewells and Pump House in Badin Cantt: area.

**Bill No. 2) Structures**

Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	Supply at site, installation, testing and commissioning of Outdoor type 200 KVA, three phase, pad mounted transformer. The sheet steel enclosure shall be 10 SWG thick and painted in dark green/grey color of 250 micron film. The complete unit shall be designed, fabricated commissioned as per WAPDA's technical standards and specifications including the cost of HT cable from external WAPDA pole to transformer.	Each		1.00	800000.0	Eight Hundred Thousand only	800000.0
2	Electrification of the lighting system of the pump house and also the ventilation system.as per direction of engineer and approval.						
a	Providing and laying ( main or sub main ) PVC insulated with size 2.3/029 copper conductor in 3/4 in dia PVC conduite on surface	P /Mtr		36.00	180.0	one Hundred Eighty only	6480.0
b	Providing and laying ( main or sub main ) PVC insulated with size 2.7/029 copper conductor in 3/4 in dia PVC conduite on surface	P /Mtr		38.00	250.0	Two Hundred fifty only	9500.0
c	Providing and laying ( main or sub-main ) PVC insulated with size 2.7/036 copper conductor in 3/4 in dia PVC conduite on surface	P /Mtr		40.00	290.0	Two Hundred ninety only	11600.0



**EXECUTIVE ENGINEER**  
Drainage Division  
Badin.


d	d. Providing and fixing DP i/c Change over switch 500 volts 30 AMP on a prepared board 195-	Each		1.00	3500.0	THREE THOUSAND FIVE HUNDRED	3500.0
e	e. Providing and fixing one way SP 5 AMP switch surface type 216-	Each		4.00	50.0	FIFTY ONLY	200.0
f	f. Providing and fixing two pin 5 AMP Plug and socket 222-	Each		3.00	150.0	one Hundred FIFTY ONLY	450.0
g	g. Providing and fixing three pin 10/15 AMP Plug and socket 224-	Each		3.00	210.0	TWO HUNDRED TEN ONLY	630.0
h	h. Providing and fixing brass ( Lamp Holder Suitable for 12mm (1/2 in) Dia )	Each		6.00	110.0	one Hundred TEN ONLY	660.0
i	i. Providing and fixing brass ceiling fan 56 in ( Good Quality ) 235-	Each		2.00	4800.0	FOUR THOUSAND EIGHT HUNDRED	9600.0
3	<b>Supply, installation, testing and commissioning of Motor control panel, made out of 2mm thick powder coated steel sheet following accessories.</b>						
a	Providing and fixing BP i/c Change over switch 500 Volts 600AMP On a prepared board	Each		1.00	77000.0	SEVENTY SEVEN THOUSAND ONLY	77000.0
b	Providing and fixing Lamp for 2000( HPIT ) Watts Light @ as per site requirement and instruction of Engineer incharge . 191	Each		2.00	55000.0	FIFTY FIVE THOUSAND ONLY	110000.0
c	Providing and fixing ammeters size 96/96mm Direct 15A, 30A, 50A, 60A & 100A as required .	Each		1.00	1000.0	one THOUSAND ONLY	1000.0
d	Providing and fixing volt meter size 96/96mm 500 Volt as required & as per instruction of EI	Each		1.00	1000.0	one THOUSAND ONLY	1000.0
e	P/F Timer 500 Hours Power backup ( National ) After removing of existing burnt / Damage / Old timer after disconnection of main power supply and reconnection the same after fixing the timer as required as per instruction of EI	Each		5.00	10000.0	TEN THOUSAND ONLY	50000.0



**EXECUTIVE ENGINEER**  
Drainage Division  
Bain.

f	Providing and fixing circuit breaker 800 AMP TP setting 500 - 800 AMP ( XS -800 NJ ) on prepared board as required.	Each	1.00	90000.0	NINETY THOUSAND ONLY	90000.0
g	Providing and fixing circuit breaker 125, 150, 200 & 225 AMP TP ( XS -225 NS ) on prepared board as required.	Each	5.00	35000.0	THIRTY FIVE THOUSAND ONLY	175000.0
h	Providing and fixing Magnetic Contractor FC65N ( 110 A as required & as per instructor EI	Each	6.00	23000.0	TWENTY THREE THOUSAND ONLY	138000.0
i	Providing and fixing Over load Relays for size 11 & above model FT 300 as required & as per Instruction EI.	Each	6.00	59000.0	FIFTY NINE THOUSAND ONLY	354000.0
4	iii) Following sizes of 600/1000 volts grade, multi-core standred, PVC heated cable from transformer to main low voltage panel(LCPS) to distribution boards/motors including connections at both ends.the table shall be drawn in trenches as per drawings,specification or as approved by the engineer.					
a	Providing and laying (Main or sub Main ) PVC insulated and PVC Sheeted with three core . copper conductor 600/1000 Size 70mm2	P /Mtr	90.00	4500.0	FOUR THOUSAND FIVE HUNDREED	405000.0
b	Providing and laying (Main or sub Main ) PVC insulated and PVC Sheeted with 3.5 core copper conductor 600/1000 Size 240mm2	P /Mtr	136.00	14900.0	FOURTEEN THOUSAND NINE HUNDREED ONLY	2026400.0
Total Bid Price of EXTERNAL ELECTRIFICATION (the amount to entered in paragraph 1 of the form of Bid) In words						
FOUR MILLION TWO HUNDRED SEVENTY THOUSAND TWENTY RUPEE ONLY						

Signature:  
Company Name:



EXECUTIVE ENGINEER  
Drainage Division  
B. Adit.

**SCHEDULE OF PRICE**

Name of Work:- (F) SUPPLYING DIESEL GENERATOR ALONG CANTT: AREA @ BADIN

**Bill No. 2) Structures**

Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	Denyo 60/50 KVA DCA-ES Branch New, Made in Japan, 1500 R.P.M, 50", Sound Proof Canopy, ISUZU Engine, 3 Phase or Equivalent.	P/Set		2 Sets	3000000	THREE MILLION only	6,000,000.00
Total Bid Price of 1 No. AC 24" DIA PIPE							
Total Bid Price of 2 No. DIESEL GENERATOR (the amount to entered in paragraph 1 of the form of Bid) In words							
Six million only							
6,000,000.00							

**EXECUTIVE ENGINEER**  
Drainage Division  
Badin.

Signature:





**NON TRANSFERABLE**

**CALL DEPOSIT RECEIPT**

Hyderabad Branch  
Phone: 022-2730911-5 Fax: 022-2730911-5  
Telex: SUMBPKKA

**CDR No. 5000**

**DATE: 22-Feb-2016**

**RS. 120,000.00**  
**RECEIVED FROM**

**IN FAVOUR OF EXECUTIVE ENGINEER DRAINAGE DIVISION BADIN ON A/C OF THADANI ENTERPRISES**

**THE SUM OF RUPEES PAK RUPEE ONE MILLION ONE HUNDRED AND TWENTY THOUSAND ONLY**

As a deposit AT CALL bearing NO PROFIT subject to the general rules of the Bank with respect to such deposits.

This receipt is Non-Transferable and Payable to Beneficiary or Purchaser.

In the event that this instrument is not encashed within 6 months

of issue. The Bank reserves the right to validate the same before encashment.

Encashment of this instrument is subject to payment of withholding tax, as per applicable law.

**For Summit Bank Limited**

**AUTHORIZED SIGNATURE**

**AUTHORIZED SIGNATURE**

CDR. 00005000

⑈00005000⑈0810036⑈

⑈080⑈

# SPPRA BIDDING DOCUMENTS



## GOVERNMENT OF SINDH

Name of Department: **IRRIGATION DEPARTMENT** 3

Name of Project/Scheme: ADP NO. 648 "POCKET DRAINAGE SYSTEM FOR PART COMMAND DEHS KALHORKI, JHURKANDI, KERANDDI AND CHORHAL CANTONMENT AREA TAPO, TALUKA AND DISTRICT BADIN"

Name of Work:- **PACKAGE NO. 03: DISPOSAL CHANNEL ALONG CANTT: AREA @ BADIN.**

- Construction of Pump House,
- Construction RCC Sump /Tank 16'x8'
- Providing & laying, Jointing & Testing A.C Rising Main 24" Q dia for disposal of wet weather flow from Cantt. Badin 2050 Rft.
- Supplying & Installing 60 BHP A.C Electric Motor for disposal of storm water flow from cantt. Badin and adjoining area.
- External Electrification.
- Diesel Generator 50 KVA (02 No.) along Cantonment Area @ Badin

Name of Procuring Agency: **Executive Engineer, Drainage Division, Badin**

Document issued to: MS Haji Sajjad Ali Saadani

DR No. & Amount: 76/03 dt. 17-02-2016

*[Signature]*  
Executive Engineer  
Drainage Division  
Badin

PACKAGE NO. 03

**SUMMARY OF BID PRICE**

**CONTRACT NAME, DISPOSAL CHANNEL ALONG CANTT: AREA @ BADIN.**

Bill Nr.	Description	Amount
1	Earth Work	
2	Structures A) PUMP HOUSE B) R.C.C SUMP / TANK 16'X 8' C) PROVIDING LAYING JOINTING & TESTING AC RISING MAIN 24" DIA D) SUPPLYING & INSTALLING 60 BHP A.C ELECTRIC MOTOR E) SUPPLYING & INSTALLING 60 BHP A.C ELECTRIC MOTOR F) SUPPLYING DIESEL GENERATOR	1,357,642/- 2,037,739/- 27,317,475/- 4,000,000/- 46,04,730/- 2,000,000/-
	Total Bid Price (the amount to entered in paragraph 1 to 2 of the form of bid in words <i>four crore sixty three lac seven thousand five hundred eighty six only</i> )	46,317,586/-




Signature: *[Handwritten Signature]*  
Company Name: *[Handwritten Name]*

PACKAGE NO. 03


**SUMMARY OF BID PRICE**

**CONTRACT NAME** DISPOSAL CHANNEL ALONG CANTT: AREA @ BADIN.

Bill Nr.	Description	Amount
1	Earth Work	
2	Structures A) PUMP HOUSE B) R.C.C SUMP / TANK 16'X 8' C) PROVIDING LAYING JOINTING & TESTING AC RISING MAIN 24" DIA D) SUPPLYING & INSTALLING 60 BHP A.C ELECTRIC MOTOR E) SUPPLYING & INSTALLING 60 BHP A.C ELECTRIC MOTOR F) SUPPLYING DIESEL GENERATOR	1,357,642/2 2,037,739/2 27,317,475/2 4,000,000/2 46,54,730/2 2,000,000/2
	Total Bid Price (the amount to entered in paragraph 1 to 2 of the form of bid in words <i>four crore sixty three lac seven thousand five hundred eighty six only</i> )	46,317,586/2



Signature: *[Handwritten Signature]*  
Company Name: *[Handwritten Name]*



7	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms, moulds, lifting, shuttering, curring, rendering and finishing the exposed surface (including screening and washing of shingle). (a) R.C.C work in roof slabs beams columns, rafts, lintels and other structural members laid in situ or precast laid in position complete in all respects (i) Ratio (1:2:4) 90 lbs cement 2 Cft Sand, 4 Cft Shingle 1/8" to 1/4" gauge.	P/Cft		324.00	680	six hundred eighty only	220,320/-
8	Fabrication of mild steel reinforcement for cement concrete including cutting, bending, laying in position making joints and fastening including cost of binding wire (also includes removal of rust from bars)	P/Cwt		6.65	8200	Eight thousand Two hundred only	54,530/-
9	Cement concrete plain including placing compacting finishing and curing complete including screening and washing of stone aggregate without shuttering ratio 1:3:6.	P/Cft		128.00	300	Three hundred only	38,400/-
10	Cement Plaster 1:4 up to 20 ft height.	P/Sft		866.00	80	Eighty only	69,280/-
11	Cement plaster 1:4 upto 20' height 3/8" thick	P/Sft		866.00	70	Seventy only	60,620/-
12	Making and fixing steel grated door with 1 1/6" thick as binding i/c angle iron frame 2"x2x3/3 and 3/4" sq. bars 4" centre to centre with locking arrangement.	P/Sft		23.00	2000	Two thousand only	46,000/-
13	Cement pointing flush on stone work. (in cement mortar 1:3)	P/Sft		2500.00	50	fifty only	12,5000/-

*g. h. s.*



7	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms, moulds, lifting, shuttering, curring, rendering and finishing the exposed surface (including screening and washing of shingle). (a) R.C.C work in roof stabs beams columns, rafts, lintels and other structural members laid in situ or precast laid in position complete in all respects (i) Ratio (1:2:4) 90 lbs cement 2 Cft Sand, 4 Cft Shingle 1/8" to 1/4" gauge.	P/Cft		324.00	680	Six hundred eighty only	220,320/-
8	Fabrication of mild steel reinforcement for cement concrete including cutting, bending, laying in position making joints and fastening including cost of binding wire (also includes removal of rust from bars)	P/Cwt		6.65	8200	Eight thousand Two hundred only	54,530/-
9	Cement concrete plain including placing compacting finishing and curing complete including screening and washing of stone aggregate without shuttering ratio 1:3:6.	P/Cft		128.00	350	Three hundred only	38,400/-
10	Cement Plaster 1:4 up to 20 ft height.	P/Sft		866.00	80	Eighty only	69,280/-
11	Cement plaster 1:4 upto 20' height 3/8" thick	P/Sft		866.00	70	Seventy only	60,620/-
12	Making and fixing steel grated door with 1 1/6" thick as binding i/c angle iron frame 2"x2x3/3 and 3/4" sq. bars 4" centre to centre with locking arrangement.	P/Sft		23.00	2000	Two thousand only	46,000/-
13	Cement pointing flush on stone work. (in cement mortar 1:3)	P/Sft		2500.00	50	fifty only	12,5000/-

*gndls*

**SCHEDULE OF PRICE**

Name of Work:- (B) CONSTRUCTION OF R.C.C SUMP / TANK 16' X 8' ALONG CANTT: AREA @ BADIN.  
 Bill No. 2) Structures

Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	Excavation of well in dry upto 20' below ground level and disposal of soil within one chain 0-3' depth	P/ Cft	.	582.75	22	Twenty two only	12,821/-
2	Wet sinking of wells for depth below spring level by means of i/c all charges for shoring leading and ramming excavated material with one chain in (ordinary soil)						
i	0-5' depth	P/ Cft		389.00	18	Eighteen only	7,002/-
ii	5-10' depth	P/ Cft		971.00	35	Thirty five only	33,985/-
iii	10-15' depth	P/ Cft		971.00	40	forty only	38,840/-
iv	15-20' depth	P/ Cft		971.00	50	fifty only	48,550/-
3	Cement concrete brick or stone ballast 1 1/2" x 2" gauge in cement sand mortar ratio 1:4:8.	P/ Cft		224.00	150	one hundred fifty only	33,600/-
4	Cement concrete including washing of aggregate and ramming						
i.	Ratio 1:3:6	P/ Cft		116.25	300	Three hundred only	38,875/-
ii.	Ratio 1:2:4	P/ Cft		116.25	350	Three hundred fifty only	40,688/-

S.M.S.



**SCHEDULE OF PRICE**

Name of Work:- (B) CONSTRUCTION OF R.C.C SUMP / TANK 16' X 8' ALONG CANTT: AREA @ BADIN.  
 Bill No. 2) Structures

Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	Excavation of well in dry upto 20' below ground level and disposal of soil within one chain 0-3' depth	P/ Cft	.	582.75	22	Twenty Two only	12,821 1/2
2	Wet sinking of wells for depth below spring level by means of i/c all charges for shoring leading and ramming excavated material with one chain in (ordinary soil)						
i	0-5' depth	P/ Cft		389.00	18	Eighteen only	7,002 1/2
ii	5-10' depth	P/ Cft		971.00	35	Thirty five only	33,985 1/2
iii	10-15' depth	P/ Cft		971.00	40	forty only	38,840 1/2
iv	15-20' depth	P/ Cft		971.00	50	fifty only	48,550 1/2
3	Cement concrete brick or stone ballast 1 1/2" x 2" gauge in cement sand mortar ratio 1:4:8.	P/ Cft		224.00	150	one hundred fifty only	33,600 1/2
4	Cement concrete including washing of aggregate and ramming						
i.	Ratio 1:3:6	P/ Cft		116.25	300	Three hundred only	38,875 1/2
ii.	Ratio 1:2:4	P/ Cft		116.25	350	Three hundred fifty only	40,688 1/2

gms






**SCHEDULE OF PRICE**

**Name of Work:- (C) PROVIDING LAYING JOINTING & TESTING AC RISING MAIN 24" DIA FOR DISPOSAL OF WT WEATHER FLOW FROM CANTT. BADIN AND ADJOINING AREA DISTRICT BADIN**

**Bill No. 2) Structures**

Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	Dismantling & remaining Road metalling	P/ Cft		125.00	12	Twelve only	1500/-
2	Excavation of pipe line in trenches and pits i/e terimming and dressing side to true alignment and shape leveling of beds of trenches correct level i/e cutting joints holes and disposal of surplus earth one chain as directed by engineer in charge i/e providing fence gaurds light flag and wherever required lift upto 5 ft. and lead up to one	P/ Cft		21525.00	15	Fifteen only	322,875/-
3	Exvavation of pipe line in trenches and pits in wet soil clay or mud i/e trimming and dressing side to alignment and shape leveling of beds of trenches and where ever required lift upto 5 ft. and lead one chain (PHSI No. 14, p-66) correct level i/e cutting joint holes and disposal flag.	P/ Cft		22525.00	15	fifteen	337,875/-
4	Full Hire charges of Pumping set per day including of the wages of driver and assistant fuel or electric energy required plate form with suction and delivery pipe for pumping out water from trench i/c the cost of erection and dismantling of acopements after completion of job.	P/ day		40.00	1350	Thirteen hundred fifty only	54,000/-



*Handwritten signature*


**SCHEDULE OF PRICE**

Name of Work:- (C) PROVIDING LAYING JOINTING & TESTING AC RISING MAIN 24" DIA FOR DISPOSAL OF WT WEATHER FLOW FROM CANTT. BADIN AND ADJOINING AREA DISTRICT BADIN

Bill No. 2) Structures

Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	Dismantling & remaing Road metalling	P/ Cft		125.00	12	Twelve only	1500/-
2	Excavation of pipe line in trenches and pits i/e terimming and dressing side to true alignment and shape leveling of beds of trenches correct level i/e cutting joints holes and disposal of surplus earth one chain as directed by engineer in charge i/e providing fence gaurds light fleg and wherever required lift upto 5 ft. and lead up to one	P/ Cft		21525.00	15	Fifteen only	322,875/-
3	Exvavation of pipe line in trenches and pits in wet soil clay or mud i/e trimming and dressing side to alignment and shape leveling of beds of trenches and where ever required lift upto 5 ft. and lead one chain (PHSI No. 14, p-66) correct level i/e cutting joint holes and disposal fleg.	P/ Cft		22525.00	15	fifteen	337,875/-
4	Full Hire charges of Pumping set pet day including of the wages of driver and assistant fuel or electric energy required plate form with suction and delivery pipe for pumping out water from trench i/c the cost of erection and dismantling of acopements after completion of job.	P/ day		40.00	1350	Thirteen hundred fifty only	54,000/-

S.P.S



15	Making jointing C.I special fitting i/c laying of the required Dia meter and testing the joints along with abestos cement pressure pipe line to the specified pressure and making good all leaky joints etc. complete	Each	6.00	400	four hundred only	2400/-
16	Providing chamber 3 1/2 x 2 1/2 inside dimension 4 ft deep as apposed designed for sloc valve chamber 15" dia 21" dia with 24" dia inside dimension cast iron cover and frame 2 cwt. Roof in RCC 1:2:4 slab 6" thick cement concrete 1:3:6 in foundation 1" thick cement concrete 1:2:4 flooring 1/2" thick cement plaster 1:3 to all inside valve surfaces lead 2 1/2 depth 24" dia	Each	12.00	47000	forty seven thousand only	564,000/-
17	Jointing C.I / M.S flanged pipe and special flanged and inside trenches i/c supplying rubber packing of required thickness nuts and bolts with washers etc and other tools required for jointing the joints to the specified pressure etc complete. 24" dia	Each	24.00	10000	Ten thousand only	240,000/-
18	Refilling the excavated stuff in 6" thick layers i/c watering and raming to full compaction etc complete.	P/ Cft	44175.00	3	Three only	132,525/-
19	Supplying and fixing 24" dia RCC pipe with sand layer. 24" dia	P/Rft	2050.00	400	four hundred only	820,000/-
Total Bid Price of AC 24" DIA PIPE (the amount to entered in paragraph 1 of the form of Bid) In words						
Two crore Seventy three lac Seventeen thousand four hundred seventy five only						



Signature: *[Handwritten Signature]*  
Company Name:

15	Making jointing C.I special fitting i/c laying of the required Dia meter and testing the joints along with abestos cement pressure pipe line to the specified pressure and making good all leaky joints etc. complete.	Each	6.00	400	four hundred only	2400/-
16	Providing chamber 3 1/2 x 2 1/2 inside dimension 4 ft deep as appoced designed for sloc valve chamber 15" dia 21" dia with 24" dia inside dimension cost iron cover and frame 2 cwt. Roof in RCC 1:2:4 slab 6" thick cement concrete 1:3:6 in foundation 1" thick cement concrete 1:2:4 flooring 1/2" thick cement plaster 1:3 to all inside valve surfaces lead 2 1/2 depth 24" dia	Each	12.00	47000	forty seven thousand only	564,000/-
17	Jointing C.I / M.S flanged pipe and special flanged and inside trenches i/c supplying rubber packing of required thickness nuts and bolts with washers etc and other tools required for jointing the joints to the specified pressure etc complete. 24" dia	Each	24.00	10000	Ten thousand only	240,000/-
18	Refilling the excavated stuff in 6" thick layers i/c watering and raming to full compaction etc complete.	P/ Cft	44175.00	3	Three only	132,525/-
19	Supplying and fixing 24" dia RCC pipe with sand layer. 24" dia	P/Rft	2050.00	400	four hundred only	820,000/-
<b>Total Bid Price of AC 24" DIA PIPE (the amount to entered in paragraph 1 of the form of Bid) in words</b> Two Crore Seventy three lac Seventeen thousand four hundred seventy five only						




Signature: *[Handwritten Signature]*  
 Company Name: *[Handwritten Name]*

**SCHEDULE OF PRICE**

Name of Work:- (E) Supplying and Fixing 200 KV Transformer, PVC Sheeted with 3.5 core copper conductor 600/1000 Size 240mm<sup>2</sup> and other electric materials to provide Electric for 50 No. Tubewells and Pump House in Badin Cantt: area.

**Bill No. 2) Structures**

Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	Supply at site, installation, testing and commissioning of Outdoor type 200 KVA, three phase, pad mounted transformer. The sheet steel enclosure shall be 10 SWG thick and painted in dark green/grey color of 250 micron film. The complete unit shall be designed, fabricated commissioned as per WAPDA's technical standards and specifications including the cost of HT cable from external WAPDA pole to transformer.	Each		1.00	1000000	Ten lac only	1,000,000/-
2	<b>Electrification of the lighting system of the pump house and also the ventilation system.as per direction of engineer and approval.</b>						
a	Providing and laying ( main or sub main ) PVC insulated with size 2.3/.029 copper conductor in 3/4 in dia PVC conduite on surface	P /Mtr		36.00	200	Two hundred only	7,200/-
b	Providing and laying ( main or sub main ) PVC insulated with size 2.7/.029 copper conductor in 3/4 in dia PVC conduite on surface	P /Mtr		38.00	230	Two hundred thirty only	8,740/-
c	Providing and laying ( main or sub main ) PVC insulated with size 2.7/.036 copper conductor in 3/4 in dia PVC conduite on surface	P /Mtr		40.00	250	Two hundred fifty only	10,000/-




*Handwritten signature/initials*

**SCHEDULE OF PRICE**

Name of Work:- (E) Supplying and Fixing 200 KV Transformer, PVC Sheeted with 3.5 core copper conductor 600/1000 Size 240mm<sup>2</sup> and other electric materials to provide Electric for 50 No. Tubewells and Pump House in Badin Cantt. area.

**Bill No. 2) Structures**

Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	Supply at site, installation, testing and commissioning of Outdoor type 200 KVA, three phase, pad mounted transformer. The sheet steel enclosure shall be 10 SWG thick and painted in dark green/grey color of 250 micron film. The complete unit shall be designed, fabricated commissioned as per WAPDA's technical standards and specifications including the cost of HT cable from external WAPDA pole to transformer.	Each		1.00	1000000	Ten Lac only	1,000,000/-
2	<b>Electrification of the lighting system of the pump house and also the ventilation system.as per direction of engineer and approval.</b>						
a	Providing and laying ( main or sub main ) PVC insulated with size 2.3/.029 copper conductor in 3/4 in dia PVC conduite on surface	P /Mtr		36.00	200	Two hundred only	7,200/-
b	Providing and laying ( main or sub main ) PVC insulated with size 2.7/.029 copper conductor in 3/4 in dia PVC conduite on surface	P /Mtr		38.00	230	Two hundred thirty only	8,740/-
c	Providing and laying ( main or sub main ) PVC insulated with size 2.7/.036 copper conductor in 3/4 in dia PVC conduite on surface	P /Mtr		40.00	250	Two hundred fifty only	10,000/-



*J. N. S.*

f	Providing and fixing circuit breaker 800 AMP TP setting 500 - 800 AMP ( XS -800 NJ ) on prepared board as required.	Each	1.00	100,000	one lac only	100,000/-
g	Providing and fixing circuit breaker 125, 150, 200 & 225 AMP TP ( XS -225 NS ) on prepared board as required.	Each	5.00	40,000	forty thousand only	200,000/-
h	Providing and fixing Magnetic Contractor FC65N ( 110 A as required & as per instruction EI	Each	6.00	25,000	Twenty five thousand only	150,000/-
i	Providing and fixing Over load Relays for size 11 & above model FT 300 as required & as per Instruction EI.	Each	6.00	57,000	fifty seven thousand only	342,000/-
4	iii) Following sizes of 600/1000 volts grade, multi-core standard, PVC heated cable from transformer to main low voltage panel (LCP'S) to distribution boards/motors including connections at both ends. the table shall be drawn in trenches as per drawings, specification or as approved by the engineer.					
a	Providing and laying (Main or sub Main ) PVC insulated and PVC Sheeted with three core copper conductor 600/1000 Size 70mm <sup>2</sup>	P /Mtr	90.00	4700	four thousand seven hundred only	423,000/-
b	Providing and laying (Main or sub Main ) PVC insulated and PVC Sheeted with 3.5 core copper conductor 600/1000 Size 240mm <sup>2</sup>	P /Mtr	136.00	15500	fifteen thousand five hundred only	2108,000/-
Total Bid Price of EXTERNAL ELECTRIFICATION (the amount to entered in paragraph 1 of the form of Bid) In words						
forty six lac four thousand seven hundred thirty only						



Signature: *[Handwritten Signature]*  
 Company Name: *[Handwritten Name]*

f	Providing and fixing circuit breaker 800 AMP TP setting 500 - 800 AMP ( XS - 800 NJ ) on prepared board as required.	Each	1.00	100,000	one lac only	100,000/-
g	Providing and fixing circuit breaker 125, 150, 200 & 225 AMP TP ( XS - 225 NS ) on prepared board as required.	Each	5.00	40,000	forty thousand only	200,000/-
h	Providing and fixing Magnetic Contractor FC65N ( 110 A as required & as per instruction EI	Each	6.00	25,000	Twenty five thousand only	150,000/-
i	Providing and fixing Over load Relays for size 11 & above model FT 300 as required & as per Instruction EI.	Each	6.00	57,000	fifty seven thousand only	342,000/-
4	iii) Following sizes of 600/1000 volts grade, multi-core stranded, PVC heated cable from transformer to main low voltage panel (LCP'S) to distribution boards/motors including connections at both ends. the table shall be drawn in trenches as per drawings, specification or as approved by the engineer.					
a	Providing and laying (Main or sub Main ) PVC insulated and PVC Sheeted with three core copper conductor 600/1000 Size 70mm <sup>2</sup>	P /Mtr	90.00	4700	four thousand seven hundred only	423,000/-
b	Providing and laying (Main or sub Main ) PVC insulated and PVC Sheeted with 3.5 core copper conductor 600/1000 Size 240mm <sup>2</sup>	P /Mtr	136.00	15500	fifteen thousand five hundred only	2108,000/-
Total Bid Price of EXTERNAL ELECTRIFICATION (the amount to entered in paragraph 1 of the form of Bid) in words						
forty six lac four thousand seven hundred thirty only						



Signature: *[Handwritten Signature]*  
 Company Name: *[Handwritten Name]*



**SCHEDULE OF PRICE**

Name of Work:- (F) SUPPLYING DIESEL GENERATOR ALONG CANTT: AREA @ BADIN

**Bill No. 2) Structures**

Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words*	
1	Denyo 60/50 KVA DCA-ES Branch New, Made in Japan, 1500 R.P.M, 50", Sound Proof Canopy, ISUZU Engine, 3 Phase or Equivalent.	P/Set		2 Sets	3500000	Twenty five lac only	7000,000
Total Bid Price of 1 No. AC 24" DIA PIPE							
Total Bid Price of 2 No. DIESEL GENERATOR (the amount to entered in paragraph 1 of the form of Bid) In words <i>Seventy lac only</i>							
7000,000							



Signature: *[Handwritten Signature]*



بنك الفلاح المحدود  
BANK ALFALAH LIMITED

(0045) Main Branch Saddar Hyderabad

### Call Deposit Receipt

No. CDRHYD 0685208

Ref No: FT16053130164909

Date: 22 FEB 2016

Amount not over PKR 1,225,000.00 only

Rs.	1,225,000.00
-----	--------------

Received from M/S. HAJI SIRAJUDDIN SOOMRO

On Account EXECUTIVE ENGINEER DRAINAGE DIVISION BADIN ON A/C M/S. HAJI SIRAJUDDIN SOOMRO

Rupees ONE MILLION TWO HUNDRED TWENTY FIVE THOUSAND ONLY

as a deposit at call bearing no Interest/Profit subject to general rules of the Bank with respect to such deposits.

THIS RECEIPT IS NON TRANSFERABLE  
PAYABLE TO BENEFICIARY ONLY

Authorised Signature

Authorised Signature

# SPPRA BIDDING DOCUMENTS



## GOVERNMENT OF SINDH

Name of Department: **IRRIGATION DEPARTMENT** 3

Name of Project/Scheme: ADP NO. 648 "POCKET DRAINAGE SYSTEM FOR PART COMMAND DEHS KALHORKI, JHURKANDI, KERANDDI AND CHORHAL CANTONMENT AREA TAPO, TALUKA AND DISTRICT BADIN"

Name of Work:- **PACKAGE NO. 03: DISPOSAL CHANNEL ALONG CANTT: AREA @ BADIN.**


- Construction of Pump House,
- Construction RCC Sump /Tank 16'x8'
- Providing & laying, Jointing & Testing A.C Rising Main 24" Q dia for disposal of wet weather flow from Cantt. Badin 2050 Rft.
- Supplying & Installing 60 BHP A.C Electric Motor for disposal of storm water flow from cantt. Badin and adjoining area.
- External Electrification.
- Diesel Generator 50 KVA (02 No.) along Cantonment Area @ Badin

Name of Procuring Agency: **Executive Engineer, Drainage Division, Badin**

Document issued to: M/S Sheikh Bazz Khan & Brothers

DR No. & Amount:

78/03 At 17-02-2016

  
Executive Engineer  
Drainage Division  
Badin

PACKAGE NO. 03

**SUMMARY OF BID PRICE**

**CONTRACT NAME** DISPOSAL CHANNEL ALONG CANTT: AREA @ BADIN.

Bill Nr.	Description	Amount
1	Earth Work	—
2	Structures A) PUMP HOUSE B) R.C.C SUMP / TANK 16'X 8' C) PROVIDING LAYING JOINTING & TESTING AC RISING MAIN 24" DIA D) SUPPLYING & INSTALLING 60 BHP A.C ELECTRIC MOTOR E) SUPPLYING & INSTALLING 60 BHP A.C ELECTRIC MOTOR F) SUPPLYING DIESEL GENERATOR	1,406,450.0 2,214,221.0 30,085,630.0 4,600,000 4,626,690.0 8,000,000
	Total Bid Price (the amount to entered in paragraph 1 to 2 of the form of bid in words <i>fifty million six hundred thirty two thousand nine hundred ninety one rupees only.</i>	50,932,991.0



Signature:


Company Name:

**SCHEDULE OF PRICE**

Name of Work:- (A) CONSTRUCTION OF PUMP HOUSE  
Bill No. 2) Structures


Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	Excavation in foundation of building bridges and other structure including dabelling dressing refilling around structure with excavated earth watering and ramming lead upto 5 ft in soft soil.	P/Cft		396.00	10	Ten Rupees only	3,960.00
2	Cement concrete brick or stone ballast 1 1/2" to 2" guage Ratio 1:4:8.	P/Cft		256.00	250	Two hundred fifty Rupees only	64,000.00
3	Random rubble masonry (uncoursed) ratio 1:6.	P/Cft		223.00	380	Three hundred eighty Rupees only	84,740.00
4	Coursed Rubble Masonary including hammer dressing, cement mortar ratio 1:6.	P/Cft		624.00	400	four hundred rupees only	249,600.00
5	Damp proof course with (cement sand and shingle concrete 1:2:4 i/e 2 coats asphaltic mixture.	P/Sft		149.00	50	fifty rupees only	7,450.00
6	Pacca brick work in ground floor i/c of joints in cement sand mortar (1:6)	P/Sft		707.00	330	Three hundred thirty Rupees only	233,310.00





7	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms, moulds, lifting, shuttering, curring, rendering and finishing the exposed surface (including screening and washing of shingle). (a) R.C.C work in roof stabs beams columns, rafts, lintels and other structural members laid in situ or precast laid in position complete in all respects (i) Ratio (1:2:4) 90 lbs cement 2 Cft Sand, 4 Cft Shingle 1/8" to 1/4" guage.	P/Cft	324.00	700	Seven hundred rupees only	226,800.00
8	Fabrication of mild steel reinforcement for cement concrete including cutting, bending, laying in position making joints and fastening including cost of binding wire (also includes removal of rust from bars)	P/Cwt	6.65	9000	Nine Thousand rupees only	59,850.00
9	Cement concrete plain including placing compacting finishing and curing complete including screening and washing of stone aggregate without shuttering ratio 1:3:6.	P/Cft	128.00	270	Two hundred seventy rupees only	34,560.00
10	Cement Plaster 1:4 up to 20 ft height.	P/Sft	866.00	70	Seventy rupees only	60,620.00
11	Cement plaster 1:4 upto 20' height 3/8" thick	P/Sft	866.00	80	Eighty rupees only	69,280.00
12	Making and fixing steel grated door with 1 1/6" thick as binding i/c angle iron frame 2"x2x3/3 and 3/4" sq. bars 4" centre to centre with locking arrangement.	P/Sft	23.00	2200	Two Thousand Two hundred rupees only	50,600.00
13	Cement pointing flush on stone work. (in cement mortar 1:3)	P/Sft	2500.00	65	Sixty five rupees only	162,500.00

14	Supplying and fixing in position iron steel grill of 3/4" x 1/4" size flate iron of approved design i/c painting and 3 coats etc complete weight not to be less than 3.7 pounds / Sq. ft. of finish grill.	P/ Sft		36.00	490	four hundred twenty rupees only	17,640.00
15	Supplying and fixing windows of Z section 3/4" x 3/4" x 1/8" partly fixed partly open able i/c fixing with 2408 x z glass fitting and painting 3 coat etc complete	P/ Sft		80.00	480	four hundred fifty rupees only	36,000.00
16	White washing 3 coats	P/ Sft		1956.00	10	Ten rupees only	19,560.00
17	Colour washing 2 coats	P/ Sft		866.00	15	fifteen Rupees only	12,990.00
18	White washing 2 coats	P/ Sft		866.00	15	fifteen rupees only	12,990.00
Total Bid Price of PUMP HOUSE (the amount to entered in paragraph 1 of the form of Bid) in words one million four hundred six Thousand four hundred fifty rupees only.							1,406,480.00



Signature:  
Company Name:


**SCHEDULE OF PRICE**  
**Name of Work:- (B) CONSTRUCTION OF R.C.C SUMP / TANK 16' X 8' ALONG CANTT: AREA @ BADIN.**

Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	Excavation of well in dry upto 20' below ground level and disposal of soil within one chain 0-3' depth	P/ Cft		582.75	25	Twenty five rupees only	14,569
2	Wet sinking of wells for depth below spring level by means of i/c all charges for shoring leading and ramming excavated material with one chain in (ordinary soil)						
i	0-5' depth	P/ Cft		389.00	27	Twenty seven rupees only	10,503
ii	5-10' depth	P/ Cft		971.00	40	forty rupees only	38,840
iii	10-15' depth	P/ Cft		971.00	44	forty four rupees only	42,724
iv	15-20' depth	P/ Cft		971.00	60	Sixty rupees only.	58,260
3	Cement concrete brick or stone ballast 1 1/2" x 2" gauge in cement sand mortar ratio 1:4:8.	P/ Cft		224.00	140	one hundred forty rupees only.	31,360
4	Cement concrete including washing of aggregate and ramming						
i.	Ratio 1:3:6	P/ Cft		116.25	350	Three hundred fifty rupees only	40,687.50
ii.	Ratio 1:2:4	P/ Cft		116.25	390	Three hundred ninety rupees only.	45,337.50






5	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms, moulds, lifting, shuttering, curring, rendering and finishing the exposed surface (including screening and washing of shingle). (a) R.C.C work in roof slabs beams columns, rafts, lintels and other structural members laid in situ or precast laid in position complete in all respects (i) Ratio (1:2:4) 90 lbs cement 2 Cft Sand, 4 Cft Shingle 1/8" to 1/4" gauge.	P/Cft		1052.00	700	Seven hundred rupees only	736,400.00	
6	Fabrication of mild steel reinforcement for cement concrete including cutting, bending, laying in position making joints and fastening including cost of binding wire (also includes removal of rust from bars)	P/cwt		61.17	9000	Nine Thousand rupees only	55,536.00	
7	Providing and fixing C.C foundation 1:3:6 M.S Leader M.S angle iron 2" x 2" x 1/4" 1-0 sport with M.S bars 3/4" dia 1-0 sport i/c painting 3 coats with anticorrosive sheet paint etc complete	P/Rft		20.00	2100	Two Thousand one hundred rupees only	42,000.00	
8	Providing construction joints in concrete work of 9' wide corrugated P.V.C water stopper with bulb i/c soldering cost of material and labour	P/Rft		1224.00	390	Three hundred thirty rupees only.	477,360.00	
9	Cement Plaster 1:4 up to 20 ft height.	P/ Sft		1020.00	100	One hundred rupees only.	102,000.00	
10	Supply Hi-bond pre-packaged paymer modified mortar (DHPMM) Hi-bond (sector)	P/ Kg		215.00	110	one hundred Ten rupees only.	23,560	
Total Bid Price of R.C.C SUMP / TANK (the amount to entered in paragraph 1 of the form of Bid) in words								2,214,221.00
Two million Two hundred fourteen Thousand Two hundred Twenty one rupees only.								



Signature:  
Company Name:

**SCHEDULE OF PRICE**


Name of Work:- (C) PROVIDING LAYING JOINTING & TESTING AC RISING MAIN 24" DIA FOR DISPOSAL OF WT WEATHER FLOW FROM CANTT. BADIN AND ADJOINING AREA DISTRICT BADIN



Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	Dismantling & remaining Road metalling	P/ Cft		125.00	15	fifteen rupees only	1875
2	Excavation of pipe line in trenches and pits i/e trimming and dressing side to true alignment and shape leveling of beds of trenches correct level i/e cutting joints holes and disposal of surplus earth one chain as directed by engineer in charge i/e providing fence guards light flag and wherever required lift upto 5 ft. and lead up to one	P/ Cft		21525.00	18	eighteen rupees only	387,450
3	Excavation of pipe line in trenches and pits in wet soil clay or mud i/e trimming and dressing side to alignment and shape leveling of beds of trenches and where ever required lift upto 5 ft. and lead one chain (PHSI No. 14, p-66) correct level i/e cutting joint holes and disposal flag.	P/ Cft		22525.00	18	eighteen rupees only	405,450
4	Full Hire charges of Pumping set per day including of the wages of driver and assistant fuel or electric energy required plate form with suction and delivery pipe for pumping out water from trench i/c the cost of erection and dismantling of acopements after completion of job.	P/ day		40.00	1450	one thousand four hundred fifty rupees only	58,000



5	Providing asbestos cement pressure pipes and cement joint of class B and fixing in IC cutting fitting and jointing with rabble ring i/c testing with water to a head of 122 meter or 400 ft.	P/Rft		2050.00	12000	Twelve Thousand rupees only.	24,600,000
6	Cost Iron special for A.C pressure pipe						
	Bend 90 Deg	Each		4.00	48500	forty eight thousand five hundred rupees only.	194,000
	Bend 45 Deg	Each		4.00	48500	forty eight thousand five hundred rupees only.	194,000
7	Five Hydrant tee 24" dia	Each		4.00	26000	Twenty six thousand rupees only.	104,000
8	Air valve double acting 3" x 1" 24" dia	Each		4.00	26000	Twenty six thousand rupees only.	104,000
9	C. I short pieces) 24" dia	Each		4.00	25000	Twenty five thousand rupees only.	100,000
10	A. C Collar "B" Class 24" dia	Each		7.00	7500	Seven thousand five hundred rupees only.	52,500
11	One pair of Rubber Rings for AC pressure pipe "B" class cement joints 24" dia	Each		7.00	3050	Three thousand rupees only.	21,000
12	Manufacturing supplying Mild steel pipe 1/4" thick cutting bending etc complete. 24" dia	P/Rft		106.00	12000	Twelve Thousand rupees only.	1,272,000
13	Manufacturing supplying Mild steel flange of different dia made out of MS sheet of various thickness i/c cutting drilling holes and welding of flanges with M.S pipe etc complete (PHSM) 24" dia	Each		12.00	10000	Ten Thousand rupees only.	120,000
14	C. I bend with flanged ends with holes, i/c turning and facing of flanges for all size.	P/Cwt		36.44	12000	Twelve thousand rupees only.	437,280



15	Making jointing C.I special fitting i/c laying of the required Dia meter and testing the joints along with abestos cement pressure pipe line to the specified pressure and making good all leaky joints etc. complete.	Each	6.00	450	four hundred fifty rupees only	2700
16	Providing chamber 3 1/2 x 2 1/2 inside dimension 4 ft deep as appoced designed for sloc valve chamber 15" dia 21" dia with 24" dia inside dimension cast iron cover and frame 2 cwt. Roof in RCC 1:2.4 slag 6" thick cement concrete 1:3:6 in foundation 1" thick cement concrete 1:2:4 flooring 1/2" thick cement plaster 1:3 to all inside valve surfaces lead 2 1/2 depth 24" dia	Each	12.00	50000	fifty Thousand rupees only	600,000
17	Jointing C.I / M.S flanged pipe and special flanged and inside trenches i/c supplying rubber packing of required thickness nuts and bolts with washers etc and other tools required for jointing the joints to the specified pressure etc complete. 24" dia	Each	24.00	12000	Twelve Thousand rupees only	288,000
18	Refilling the excavated stuff in 6" thick layers i/c watering and raming to full compaction etc complete.	P/ Cft	44175.00	5	five rupees only	220,875
19	Supplying and fixing 24" dia RCC pipe with sand layer. 24" dia	P/Rft	2050.00	450	four hundred fifty rupees only	922,500
<b>Total Bid Price of AC 24" DIA PIPE (the amount to entered in paragraph 1 of the form of Bid) In words</b> <i>Thirty million eight five Thousand six hundred thirty rupees only.</i>						30085,630

Signature:  
Company Name:

**SCHEDULE OF PRICE**

**Name of Work:- (D) SUPPLYING AND INSTALLING 60 BHP A.C ELECTRIC MOTOR FOR DISPOSAL OF STROM WATER FLOW FROM CANTT BADIN & ADJOINING AREA OF DISTRICT BADIN**

**Bill No. 2) Structures**

Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	Supplying and installing in position i/e transportation to site of work at Badin Cantt. A.C electric pumping set consisting of A.C electric motor 60 BHP of 3 phase 50 cycles 400/420 volts 1450 RPM ILG4-223-4AA60 recoupled with non-colloging pump (200-315) size 8"x8" mounted as common steel frame or base plate capable of discharging 1857 gallons / minute against a head of 50 ft. i/e installation of pumping set on C.C foundation ratio 1:2.4 & 1:4:8 with Ballast with M.S nuts and bolts of 5/8" dia to be embedded in C.C foundation i/e providing and fixing on prepared board A.C 50 cycles 3 phase 12/25 ampere trips rating push button type star delta starter complete with no volts and over load release and required i/e providing and fixing on prepared board iron clad tripple pole and neutral switc fuse rewirable type fuse link carried 500 walts grade 30 ampere providing and fixing volts meter 0.500 volts and ampere 0-500 apere installed on installed board i.e providing and fixing metalled board to accomodate main or sub mains control switches dressed in the wall size 3' x 2 1/2" i/e providing phase indication bulb with holder and providing internal electric wiring for mains with 3.	P/Set		2 Sets	2300000	Two million Three hundred thousand rupees only	4,600,000
Total Bid Price of 1 No. 60 BHP A.C ELECTRIC MOTOR							
Total Bid Price of 2 No. 60 BHP A.C ELECTRIC MOTOR (the amount to entered in paragraph 1 of the form of Bid) In words							4,600,000
						four million Six hundred thousand rupees only.	



Signature: -

**SCHEDULE OF PRICE**

Name of Work:- (E) Supplying and Fixing 200 KV Transformer, PVC Sheeted with 3.5 core copper conductor 600/1000 Size 240mm<sup>2</sup> and other electric materials to provide Electric for 50 No. Tubewells and Pump House in Badin Cantt. area.

**Bill No. 2) Structures**

Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	Supply at site, installation, testing and commissioning of Outdoor type 200 KVA, three phase, pad mounted transformer. The sheet steel enclosure shall be 10 SWG thick and painted in dark green/grey color of 250 micron film. The complete unit shall be designed, fabricated commissioned as per WAPDA's technical standards and specifications including the cost of HT cable from external WAPDA pole to transformer.	Each		1.00	975000	Nine hundred seventy five Thousand rupees only.	975,000
2	<b>Electrification of the lighting system of the pump house and also the ventilation system as per direction of engineer and approval.</b>						
	a. Providing and laying ( main or sub main ) PVC insulated with size 2.3/.029 copper conductor in 3/4 in dia PVC conduit on surface	P /Mtr		36.00	180	one hundred eighty rupees only	6,480
	b. Providing and laying ( main or sub main ) PVC insulated with size 2.7/.029 copper conductor in 3/4 in dia PVC conduit on surface	P /Mtr		38.00	250	Two hundred fifty rupees only	9,500
	c. Providing and laying ( main or sub main ) PVC insulated with size 2.7/.036 copper conductor in 3/4 in dia PVC conduit on surface	P /Mtr		40.00	220	Two hundred twenty rupees only	8,800





d	d. Providing and fixing DP i/c Change over switch 500 volts 30 AMP on a prepared board 195 -	Each		1.00	3500	Three thousand five hundred rupees only.	3500
e	e. Providing and fixing one way SP 5 AMP switch surface type 216-	Each		4.00	70	seventy rupees only.	280
f	f. Providing and fixing two pin 5 AMP Plug and socket 222-	Each		3.00	250	Two hundred fifty rupees only.	750
g	g. Providing and fixing three pin 10/15 AMP Plug and socket 224-	Each		3.00	300	Three hundred rupees only.	900
h	h. Providing and fixing brass ( Lamp Holder Suitable for 12mm (1/2 in) Dia )	Each		6.00	180	one hundred eighty rupees only.	1080
i	i. Providing and fixing brass ceiling fan 56 in ( Good Quality ) 235-	Each		2.00	550	five hundred rupees only.	1100
3	<b>Supply, installation, testing and commissioning of Motor control panel, made out of 2mm thick powder coated steel sheet following accessories.</b>						
a	Providing and fixing BP i/c Change over switch 500 Volts 600AMP On a prepared board	Each		1.00	100000	one hundred thousand rupees only.	100,000
b	Providing and fixing Lamp for 2000( HPIT ) Watts Light @ as per site requirement and instruction of Engineer incharge . 191	Each		2.00	60000	sixty thousand rupees only.	120,000
c	Providing and fixing ammeters size 96/96mm Direct 15A, 30A, 50A, 60A & 100A as required .	Each		1.00	2500	Two thousand five hundred rupees only.	2500
d	Providing and fixing volt meter size 96/96mm 500 Volt as required & as per instruction of EI	Each		1.00	4000	four thousand rupees only.	4000
e	P/F Timer 500 Hours Power backup ( National ) After removing of existing burnt / Damage / Old timer after disconnection of main power supply and reconnection the same after fixing the timer as required as per instruction of EI	Each		5.00	13500	Thirteen thousand five hundred rupees only.	67,500

f	Providing and fixing circuit breaker 800 AMP TP setting 500 - 800 AMP ( XS -800 NJ ) on prepared board as required .	Each		1.00	150000	one hundred fifty thousand rupees only.	150,000	
g	Providing and fixing circuit breaker 125, 150, 200 & 225 AMP TP ( XS -225 NS ) on prepared board as required .	Each		5.00	43000	fourty three thousand rupees only.	215,000	
h	Providing and fixing Magnetic Contractor FC65N ( 110 A as required & as per instruction EI	Each		6.00	24000	Twenty four thousand rupees only	144,000	
i	Providing and fixing Over load Relays for size 11 & above model FT 300 as required & as per Instruction EI .	Each		6.00	55000	fifty five thousand rupees only.	330,000	
4	iii) Following sizes of 600/1000 volts grade, multi-core standred, PVC heated cable from transformer to main low voltage panel (LCP'S) to distribution boards/motors including connections at both ends. the table shall be drawn in trenches as per drawings, specification or as approved by the engineer.							
a	Providing and laying (Main or sub Main ) PVC a insulated and PVC Sheeted with three core copper conductor 600/1000 Size 70mm <sup>2</sup>	P /Mtr		90.00	5800	five thousand rupees only	450,000	
b	Providing and laying (Main or sub Main ) PVC b insulated and PVC Sheeted with 3.5 core copper conductor 600/1000 Size 240mm <sup>2</sup>	P /Mtr		136.00	14900	fourteen thousand nine hundred rupees only.	2,026,400	
Total Bid Price of EXTERNAL ELECTRIFICATION (the amount to entered in paragraph 1 of the form of Bid) In words								4,626,690.00
four million six hundred Twenty six thousand six hundred sixty rupees only.								



Signature:  
Company Name:



**SCHEDULE OF PRICE**

Name of Work:- (F) SUPPLYING DIESEL GENERATOR ALONG CANTT: AREA @ BADIN  
 Bill No. 2) Structures

Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	Denyo 60/50 KVA DCA-ES Branch New, Made in Japan, 1500 R.P.M, 50", Sound Proof Canopy, ISUZU Engine, 3 Phase or Equivalent.	P/Set		2 Sets	400000	four million rupees only	8,000,000
Total Bid Price of 1 No. AC 24" DIA PIPE							
Total Bid Price of 2 No. DIESEL GENERATOR (the amount to entered in paragraph 1 of the form of Bid) In words Eight million rupees only							
							8,000,000.00



Signature:



Meezan Bank

The Premier Islamic Bank

A/C PAYEE ONLY

PO.1601.1900920

P.O. No. 01900920

22/02/16

Date \_\_\_\_\_

Saddar Bazar Branch Hyderabad-Pakistan.

NOT OVER Rs. \*1,245,000.00\*

\*EXECUTIVE ENGINEER DRAINAGE DIVISION BADIN\*

Pay \_\_\_\_\_ or order

\*ONE MILLION TWO HUNDRED AND FOURTY FIVE THOUSAND ONLY\*-

Rupees \_\_\_\_\_

\*1,245,000.00\*  
Rs.

PAYABLE AT ANY MBL BRANCH

DO NOT WRITE BELOW THIS LINE

Abdul Raheem Khwaja

For Meezan Bank Ltd

PA# C-569

Authorized Signature

ABDUL WAHEED MEMON  
Authorisation Manager B-721  
Institutional Signatory

⑈01900920⑈0891601⑈1757100011601⑈020⑈

# SPPRA BIDDING DOCUMENTS



## GOVERNMENT OF SINDH

Name of Department: **IRRIGATION DEPARTMENT**

Name of Project/Scheme: ADP NO. 648 "POCKET DRAINAGE SYSTEM FOR PART COMMAND DEHS KALHORKI, JHURKANDI, KERANDDI AND CHORHAL CANTONMENT AREA TAPO, TALUKA AND DISTRICT BADIN"

Name of Work:- PACKAGE NO. 04: Construction of (13 No.) Solar Tube well (80 ft. Depth) of 1.0 Cusec Capacity along In & Out Cantonment Area @ Badin.

Name of Procuring Agency: **Executive Engineer, Drainage Division, Badin**

Document issued to:

M/S. Thadani Enterprises

DR No. & Amount:

77/04 dt: 17-02-2016

for   
Executive Engineer  
Drainage Division  
Badin

PACKAGE NO. 04

**SUMMARY OF BID PRICE**

CONTRACT NAME Construction of (13 No.) FROM TUBE WELL NO. 01 TO 13 Solar Tube well (80 ft. depth) of 1.0 Cusec. Capacity along In & Out Cantonment Area @ Badin.

Bill Nr.	Description	Amount
1	Earth Work	—
2	Structures SOLAR TUBE WELLS (80 FT. DEPTH OF 1.0 SUSEC CAPACITY	46,621,640.0
	Total Bid Price (the amount to entered in paragraph 1 to 2 of the form of bid in words FOURTY SIX MILLION SIX HUNDRED THIRTY ONE THOUSAND SIX HUNDRED FORTY ONLY	46,621,640.0

Signature:  
Company Name:

**EXECUTIVE ENGINEER**  
Drainage Division  
Badin




**SCHEDULE OF PRICE**

Name of Work:- Construction of (13 No.) from T/well No. 01 to 13 Solar Tube well (80 ft. depth) of  
 1.0 Cusec Capacity along Cantonment Area @ Badin.

**Bill No. 2) Structures**

Item Nr.	Description	Unit	Specifications Chapter No.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	LORENTZ Pump PS9k2 C-SJ30-7, LORENTZ Controller, Water Sensor, Cable Splice Kit, PV Protect & PV Disconnect. Flow = 250, 500 lit / day Head = 120 ft, Outlet = 3 inch or Equivalent	P/Set		1 Set	115000.0	one million one Hundred FIFTEEN THOUSAND only	11,50,000.0
2	Solar Panel (Canadian Solar) Poly Crystalline, 250 W	Each		40 Nos.	48400.0	FOURTY EIGHT THOUSAND FOUR HUNDRED only	19,36,000.0
3	PV Mounting Structure MS Mounting Powder Coated	Each		40 Nos.	38000.0	THREE THOUSAND EIGHT HUNDRED	15,20,000.0
4	Cables						
	i) 4 mm2, 4 core (Pump to Controller)	P/Ft.		160 Ft.	250.0	Two Hundred FIFTY only	40,000.0
	ii) 4 mm2, 1 Core (Panel Interconnection)	P/Ft.		200 Ft.	118.0	one Hundred EIGHTEEN only	23,600.0
iii)	1.5mm2, 2 core (Controller to Water Sensor)	P/Ft.		160 Ft.	98.0	NINETY EIGHT only	15,680.0
5	Combiner Box Model Steel Made	P/Set		1 Set	8000.0	EIGHT THOUSAND only	8000.0



**EXECUTIVE ENGINEER**  
 Drainage Division  
 Badin.

6	Safety Rope for Pump & accessories 6 mm GI made with Plastic Insulation	P/ Ft.	250 ft.	96.0	NINETY SIX ONLY	24000.0
7	Delivery pipe with accessories 2' / 3 mm GI Pipe	P/ Ft.	120 ft.	850.0	EIGHT HUNDRED FIFTY ONLY	102000.0
8	Installation Charges	P/ Job	1 Job	135000.0	ONE HUNDRED THIRTY FIVE THOUSAND ONLY	135000.0
Total Bid Price of 1 NO. SOLAR TUBEWELL THREE MILLION FIVE HUNDRED EIGHTY ONLY						
Total Bid Price of 13 NO. SOLAR TUBE WELLS (the amount to entered in paragraph 1 of the form of Bid) In words FOURTY SIX MILLION SIX HUNDRED TWENTY ONE THOUSAND SIX HUNDRED						
						3586280.0
						46621640.0

EXECUTIVE ENGINEER  
Drainage Division  
B.M.U.

Signature:  
Company Name:



# Summit Bank

Hyderabad Branch

Phone: 022-2730911-5 Fax: 022-2730911-5

Telex: SUMBPKKA

RS. 1,000,000.00

RECEIVED FROM

IN FAVOUR OF

EXECUTIVE ENGINEER DRAINAGE DIVISION BADIN ON A/C OF THADANI ENTERPRISES

THE SUM OF RUPEES PAK RUPEE ONE MILLION ONLY

As a deposit AT CALL bearing NO PROFIT subject to the general rules of the Bank with respect to such deposits.

This receipt is Non-Transferable and Payable to Beneficiary or Purchaser.

In the event that this instrument is not encashed within 6 months

of issue. The Bank reserves the right to validate the same before encashment.

Encashment of this instrument is subject to payment of withholding tax, as per applicable laws.

CDR. 00005001

NON TRANSFERABLE

CALL DEPOSIT RECEIPT

CDR No. 5001

DATE 22-Feb-2016

For Summit Bank Limited

AUTHORIZED SIGNATURE

AUTHORIZED SIGNATURE

⑈00005001⑈0810036⑈

⑈080⑈

# SPPRA BIDDING DOCUMENTS



## GOVERNMENT OF SINDH

Name of Department:

**IRRIGATION DEPARTMENT**

Name of Project/Scheme:

**ADP NO. 648 "POCKET DRAINAGE SYSTEM FOR PART  
COMMAND DEHS KALHORKI, JHURKANDI, KERANDDI AND  
CHORHAL CANTONMENT AREA TAPO, TALUKA AND  
DISTRICT BADIN"**

Name of Work:-

**PACKAGE NO. 04: Construction of (13 No.) Solar Tube  
well (80 ft. Depth) of 1.0 Cusec Capacity along In &  
Out Cantonment Area @ Badin.**


Name of Procuring Agency: **Executive Engineer, Drainage Division, Badin**

Document issued to:

MS Haji Sajjad Ali Soomro

DR No. & Amount:

76/04 dt. 17-02-2016

  
Executive Engineer  
Drainage Division  
Badin



PACKAGE NO. 04

**SUMMARY OF BID PRICE**

Construction of (13 No.) FROM TUBE WELL NO. 01 TO 13 Solar Tube well (80 ft. depth) of 1.0 Cusec Capacity along In & Out Cantonment Area @ Badin.

**CONTRACT NAME**

Bill Nr.	Description	Amount
1	Earth Work	
2	Structures SOLAR TUBE WELLS (80 FT. DEPTH OF 1.0 SUSEC CAPACITY	49999,560-
	Total Bid Price (the amount to entered in paragraph 1 to 2 of the form of bid in words Fourty nine million nine hundred ninety nine (thd) five hnd. sixty six (thd) only.	49999,560-



Signature:

Company Name:

**SCHEDULE OF PRICE**

Name of Work:- Construction of (13 No.) from T/well No. 01 to 13 Solar Tube well (80 ft. depth) of 1.0 Cusec Capacity along Cantonment Area @ Badin.

**Bill No. 2) Structures**

Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	LORENTZ Pump PS9K2 C-SJ30-7, LORENTZ Controller, Water Sensor, Cable Splice Kit, PV Protect & PV Disconnect. Flow = 250, 500 lit / day Head = 120 ft, Outlet = 3 inch or Equivalent	P/Set		1 Set	1000000-	One million only.	1000000-
2	Solar Panel (Canadian Solar) Poly Crystalline, 250 W or Equivalent	Each		40 Nos.	59500-	Fifty nine thousand five hundred only	2380000-
3	PV Mounting Structure MS Mounting Powder Coated	Each		40 Nos.	3385-	Three thousand three hundred eighty five only.	135400-
4	<b>Cables</b>						
i)	4 mm <sup>2</sup> , 4 core (Pump to Controller)	P/Ft.		160 Ft.	267-	Two hundred sixty seven only.	42720-
ii)	4 mm <sup>2</sup> , 1 Core (Panel Interconnection)	P/Ft.		200 Ft.	115-	one hundred fifteen only.	23000-
iii)	1.5mm <sup>2</sup> , 2 core (Controller to Water Sensor)	P/Ft.		160 Ft.	100-	One hundred only.	16000-
5	Combiner Box Model Steel Made	P/Set		1 Set	8000-	Eight thousand only.	8000-



6	Safety Rope for Pump & accessories 6 mm GI made with Plastic Insulation	P/Ft.	250 ft.	100 →	One hundred only	25000-
7	Delivery pipe with accessories 2' / 3 mm GI Pipe	P/Ft.	120 ft.	800 -	Eight hundred only	96000-
8	Installation Charges	P/Job	1 Job	120000+	One lac twenty thousand only	120000-
Total Bid Price of 1 NO. SOLAR TUBEWELL						3846170-
Total Bid Price of 13 NO. SOLAR TUBE WELLS (the amount to entered in paragraph 1 of the form of Bid) In words						49999560-
Fourty nine million nine hundred eighty nine thousand five hundred sixty only -						

Signature:  
Company Name:





بنك الفلاح المحدود  
BANK ALFALAH LIMITED

(0045) Main Branch Saddar Hyderabad

## Call Deposit Receipt

No. CDRHYD 0685209

Ref No. FT16053713529222

Date: 22 FEB 2016

Amount not over PKR 1,000,000.00 only

Rs. 1,000,000.00

Received from M/S. HAJI SIRAJUDDIN SOOMRO

On Account EXECUTIVE ENGINEER DRAINAGE DIVISION BADIN ON A/C M/S. HAJI SIRAJUDDI  
N SOOMRO

Rupees ONE MILLION ONLY

as a deposit at call bearing no Interest/Profit subject to  
general rules of the Bank with respect to such deposits.

THIS RECEIPT IS NON TRANSFERABLE  
PAYABLE TO BENEFICIARY ONLY

*[Signature]*  
13w

Authorized Signature

*[Signature]*  
9/7

Authorized Signature

# SPPRA BIDDING DOCUMENTS



## GOVERNMENT OF SINDH

Name of Department: **IRRIGATION DEPARTMENT**

Name of Project/Scheme: **ADP NO. 648 "POCKET DRAINAGE SYSTEM FOR PART COMMAND DEHS KALHORKI, JHURKANDI, KERANDDI AND CHORHAL CANTONMENT AREA TAPO, TALUKA AND DISTRICT BADIN"**

Name of Work:- **PACKAGE NO. 04: Construction of (13 No.) Solar Tube well (80 ft. Depth) of 1.0 Cusec Capacity along In & Out Cantonment Area @ Badin.**

Name of Procuring Agency: **Executive Engineer, Drainage Division, Badin**

Document issued to: **M/S Umar Jam & Company**

DR No. & Amount: **80/04 dt: 19-02-2016**

**H**

*[Signature]*  
Executive Engineer H.C.  
Drainage Division  
Badin

PACKAGE NO. 04

**SUMMARY OF BID PRICE**

Construction of (13 No.) FROM TUBE WELL NO. 01 TO 13 Solar Tube well (80 ft. depth) of 1.0 Cusec Capacity along In & Out Cantonment Area @ Badin.

**CONTRACT NAME**

Bill Nr.	Description	Amount
1	Earth Work	NIL
2	Structures SOLAR TUBE WELLS (80 FT. DEPTH OF 1.0 SUSEC CAPACITY	56,592,900.0
	Total Bid Price (the amount to entered in paragraph 1 to 2 of the form of bid in words FIFTY SIX MILLIONS FIVE HUNDRED NINETY TWO THOUSAND NINE HUNDRED ONLY	56,592,900.0

**UMER JAN & COMPANY**  
ENGINEERS & CONTRACTORS

Signature:

Company Name:

**SCHEDULE OF PRICE**

Name of Work:- Construction of (13 No.) from T/well No. 01 to 13 Solar Tube well (80 ft. depth) of 1.0 Cusec Capacity along Cantonment Area @ Badin.

Item No.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	LORENTZ Pump PS9K2 C-SJ30-7, LORENTZ Controller, Water Sensor, Cable Splice Kit, PV Protect & PV Disconnect. Flow = 250, 500 lit / day Head = 120 ft, Outlet = 3 inch or Equivalent	P/Set		1 Set	150,000.0	ELEVEN LAC FIFTY THOUSAND only	1,50,000.0
2	Solar Panel (Canadian Solar) Poly Crystalline, 250 W or Equivalent	Each		40 Nos.	65,000.0	SIXTY FIVE THOUSAND only	2,600,000.0
3	PV Mounting Structure MS Mounting Powder Coated	Each		40 Nos.	4,000.0	FOUR THOUSAND only	160,000.0
4	Cables 4 mm <sup>2</sup> , 4 core (Pump to Controller) 4 mm <sup>2</sup> , 1 Core (Panel Interconnection)	P/Ft.		160 Ft.	265.0	Two HUNDRED SIXTY FIVE only	42,400.0
						ONE HUNDRED TWENTY FIVE only	25,000.0
						ONE HUNDRED FIFTEEN only	18,400.0
5	1.5mm <sup>2</sup> , 2 core (Controller to Water Sensor) Combiner Box Model Steel Made	P/Set		1 Set	10,000.0	TEN THOUSAND only	10,000.0

6	Safety Rope for Pump & accessories 6 mm GI made with Plastic Insulation	P/Ft.	250 ft.	110.0	ONE HUNDRED TEN RUPEES ONLY	27,500.0
7	Delivery pipe with accessories 2" / 3 mm GI Pipe	P/Ft.	120 ft.	1,000.0	ONE THOUSAND ONLY	120,000.0
8	Installation Charges	P/Job	1 Job	200,000.0	TWO LAC ONLY	200,000.0
Total Bid Price of 1 NO. SOLAR TUBEWELL						435,330.0
Total Bid Price of 13 NO. SOLAR TUBE WELLS (the amount to entered in paragraph 1 of the form of Bid) In words						56,592,900.0
FIFTY SIX MILLION FIVE HUNDRED NINETY TWO THOUSAND NINE HUNDRED ONLY						

Signature:  
Company Name:





**First Women Bank Ltd.** Sukkur Branch.

*Not over Rs. 1000000/-*

No. FWDC 0327364

# DEPOSIT AT CALL

22 - 02 - 2016

Received from Executive Engineer Drainage Division Badin

Rupees One million only

as a Deposit repayable at call. m/s M/s Jai Etc.

For First Women Bank Limited

NON TRANSFERABLE

Rs. 1000000/-

Authorised Signature

Authorised Signature

This receipt must be returned to the Bank duly discharged by the depositor.

Do not write below this line

⑈032736⑈0⑈70009⑈0000000000⑈080⑈0

D-4  
H-2

# SPPRA BIDDING DOCUMENTS



## GOVERNMENT OF SINDH

Name of Department:

**IRRIGATION DEPARTMENT**

Name of Project/Scheme:

ADP NO. 648 "POCKET DRAINAGE SYSTEM FOR PART COMMAND DEHS KALHORKI, JHURKANDI, KERANDDI AND CHORHAL CANTONMENT AREA TAPO, TALUKA AND DISTRICT BADIN"

Name of Work:-

PACKAGE NO. 05: Construction of (13 No.) Solar Tube well (80 ft. Depth) of 1.0 Cusec Capacity along In & Out Cantonment Area @ Badin.


Name of Procuring Agency: **Executive Engineer, Drainage Division, Badin**

Document issued to:

M/S Haji Saqajuddin Soomro

DR No. & Amount:

76/05 dt. 17-02-2015

  
Executive Engineer  
Drainage Division  
Badin

PACKAGE NO. 05

**SUMMARY OF BID PRICE**

Construction of (13 No.) FROM TUBE WELL NO. 14 TO 26 Solar Tube well (80 ft. depth) of 1.0 Cusec Capacity along In & Out Cantonment Area @ Badin.

**CONTRACT NAME**

Bill Nr.	Description	Amount
1	Earth Work	
2	Structures SOLAR TUBE WELLS (80 FT. DEPTH OF 1.0 SUSEC CAPACITY	46,635,940 -
	Total Bid Price (the amount to entered in paragraph 1 to 2 of the form of bid in words Forty six Million six hundred thirty five thousand nine hundred forty only	46,635,940 -



Signature: *NKS*  
Company Name:

**EXECUTIVE ENGINEER**  
Drainage Division  
Badin.


**SCHEDULE OF PRICE**

Name of Work:- Construction of (13 No.) from T/well No. 14 to 26 Solar Tube well (80 ft. depth) of 1.0 Cusec Capacity along Cantonment Area @ Badin.

**Bill No. 2) Structures**

Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					* Figure	Words	
1	LORENTZ Pump PS9k2 C-SJ30-7, LORENTZ Controller, Water Sensor, Cable Splice Kit, PV Protect & PV Disconnect. Flow = 250, 500 lit / day Head = 120 ft, Outlet = 3 inch or Equivalent	P/Set		1 Set	99,500	Nine lac fifty five thousands	99,500-
2	Solar Panel (Canadian Solar) Poly Crystalline, 250 W or Equivalent	Each		40 Nos.	53,500	Fifty three thousand five hundred	2,140,000-
3	PV Mounting Structure MS Mounting Powder Coated	Each		40 Nos.	3000-	Three Thousand only	1,20,000 -
4	<b>Cables</b>						
i)	4 mm <sup>2</sup> , 4 core (Pump to Controller)	P/Ft.		160 Ft.	210 -	Two hundred Ten Rupees only	33,600 -
ii)	4 mm <sup>2</sup> , 1 Core (Panel Interconnection)	P/Ft.		200 Ft.	118 -	one hundred eighteen only	23,600
iii)	1.5mm <sup>2</sup> , 2 core (Controller to Water Sensor)	P/Ft.		160 Ft.	98 -	Ninety eight only	15,680
5	Combiner Box Model Steel Made	P/Set		1 Set	8000-	Eight thousand only	8,000-



  
 EXECUTIVE ENGINEER  
 Training Division  
 Badin

6	Safety Rope for Pump & accessories 6 mm GI made with Plastic Insulation	P/ Ft.	250 ft.	98.-	Ninty Eight Rupees only	24,500.-
7	Delivery pipe with accessories 2' / 3 mm GI Pipe	P/ Ft.	120 ft.	850.-	Eight hundred Fifty only	102,000.-
8	Installation Charges	P/ Job	1 Job	125,000.-	one lac twenty five thousand only	125,000
Total Bid Price of 1 NO. SOLAR TUBEWELL						
Total Bid Price of 13 NO. SOLAR TUBE WELLS (the amount to entered in paragraph 1 of the form of Bid) In words Forty six Million six hundred Twenty five thousand nine hundred forty only						
46,635,940.-						



Signature: *[Handwritten Signature]*  
Company Name: *[Handwritten Name]*

**EXECUTIVE ENGINEER**  
**Drainage Division**  
**Badin.**



بنك الفلاح المحدود  
BANK ALFALAH LIMITED

(0045) Main Branch Saddar Hyderabad

## Call Deposit Receipt

No. CDRHYD 0685210

Ref No: FT16053255364800

Date: 22 FEB 2016

Amount not over PKR 1,000,000.00 only

BANK ALFALAH JA JAH B BANK ALFALAH JA JAH B BANK ALFALAH JA JAH B  
Rs. 1,000,000.00

Received from M/S. HAJI SIRAJUDDIN SOOMRO

On Account EXECUTIVE ENGINEER DRAINAGE DIVISION BADIN ON A/C M/S. HAJI SIRAJUDDI  
N SOOMRO

Rupees ONE MILLION ONLY

as a deposit at call bearing no Interest/Profit subject to  
general rules of the Bank with respect to such deposits.

THIS RECEIPT IS NON TRANSFERABLE  
PAYABLE TO BENEFICIARY ONLY

*[Handwritten Signature]*  
13w

Authorized Signature

*[Handwritten Signature]*

Authorized Signature

# SPPRA BIDDING DOCUMENTS



## GOVERNMENT OF SINDH

Name of Department: **IRRIGATION DEPARTMENT**

Name of Project/Scheme: ADP NO. 648 "POCKET DRAINAGE SYSTEM FOR PART COMMAND DEHS KALHORKI, JHURKANDI, KERANDDI AND CHORHAL CANTONMENT AREA TAPO, TALUKA AND DISTRICT BADIN"

Name of Work:- PACKAGE NO. 05: Construction of (13 No.) Solar Tube well (80 ft. Depth) of 1.0 Cusec Capacity along In & Out Cantonment Area @ Badin.

Name of Procuring Agency: **Executive Engineer, Drainage Division, Badin**

Document issued to:

MS Thadani Enterprises

DR No. & Amount:

77/05 dt: 17-02-2016

*[Signature]*  
Executive Engineer  
Drainage Division  
Badin

PACKAGE NO. 05

**SUMMARY OF BID PRICE**

**CONTRACT NAME:** Construction of (13 No.) FROM TUBE WELL NO. 14 TO 26 Solar Tube well (80 ft. depth) of 1.0 Cusec Capacity along In & Out Cantonment Area @ Badin.

Bill Nr.	Description	Amount
1	Earth Work	—
2	Structures SOLAR TUBE WELLS (80 FT. DEPTH OF 1.0 SUSEC CAPACITY	49,999,560/-
	Total Bid Price (the amount to entered in paragraph 1 to 2 of the form of bid in words <i>Forty nine million nine hundred Ninety nine Thousand Five Hundred Sixty only</i>	49,999,560/-

Signature:

Company Name:





**SCHEDULE OF PRICE**

Name of Work:- Construction of (13 No.) from T/well No. 14 to 26 Solar Tube well (80 ft. depth) of 1.0 Cusec Capacity along Cantonment Area @ Badin.


**Bill No. 2) Structures**

Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	LORENTZ Pump PS9K2 C-SJ30-7, LORENTZ Controller, Water Sensor, Cable Splice Kit, PV Protect & PV Disconnect. Flow = 250, 500 lit / day Head = 120 ft, Outlet = 3 inch or Equivalent	P/Set		1 Set	1000000/-	One Million only	1,000,000/-
2	Solar Panel (Canadian Solar) Poly Crystalline, 250 W or Equivalent	Each		40 Nos.	59,500/-	Fifty nine Thousand Five Hundred only	2,380,000/-
3	PV Mounting Structure MS Mounting Powder Coated	Each		40 Nos.	3,385/-	Three Thousand Three Hundred Eighty Five only	1,35,400/-
4	<b>Cables</b>						
i)	4 mm <sup>2</sup> , 4 core (Pump to Controller)	P/ Ft.		160 Ft.	267/-	Two Hundred Sixty Seven only	42,720/-
ii)	4 mm <sup>2</sup> , 1 Core (Panel Interconnection)	P/ Ft.		200 Ft.	115/-	one hundred Fifteen only	23,000/-
iii)	1.5mm <sup>2</sup> , 2 core (Controller to Water Sensor)	P/ Ft.		160 Ft.	100/-	one hundred only	16,000/-
5	Combiner Box Model Steel Made	P/Set		1 Set	8000/-	Eight Thousand only	8,000/-



6	Safety Rope for Pump & accessories 6 mm GI made with Plastic Insulation	P/ Ft.	250 ft.	100%	One Hundred only	25,000/-
7	Delivery pipe with accessories 2" / 3 mm GI Pipe	P/ Ft.	120 ft.	80%	Eight Hundred only	96,000/-
8	Installation Charges	P/ Job	1 Job	120,000%	One Hundred Twenty Thousand only	120,000/-
Total Bid Price of 1 NO. SOLAR TUBEWELL						
Total Bid Price of 13 NO. SOLAR TUBE WELLS (the amount to entered in paragraph 1 of the form of Bid) In words Forty Nine Million Nine Hundred Ninety Nine Thousand Five Hundred Sixty only						

Signature:  
Company Name:





**NON TRANSFERABLE**

**CALL DEPOSIT RECEIPT**

Hyderabad Branch

Phone: 022-2730911-5 Fax: 022-2730911-5

Telex: SUMBPKKA

**CDR No. 5002**

**DATE: 22-Feb-2016**

**RS. 1,000,000.00**

**RECEIVED FROM**

**IN FAVOUR OF EXECUTIVE ENGINEER DRAINAGE DIVISION BADIN ON A/C OF THADANI ENTERPRISES**

**THE SUM OF RUPEES PAK RUPEE ONE MILLION ONLY**

As a deposit AT CALL bearing NO PROFIT subject to the general rules of the Bank with respect to such deposits.

This receipt in Non-Transferable and Payable to Beneficiary or Purchaser.

In the event that this instrument is not encashed within 6 months

of issue. The Bank reserves the right to validate the same before encashment.

Encashment of this instrument is subject to payment of withholding tax, as per applicable law.

CDR. 00005002

AUTHORIZED SIGNATURE

AUTHORIZED SIGNATURE

⑈00005002⑈0810036⑈

⑈080⑈

# SPPRA BIDDING DOCUMENTS



## GOVERNMENT OF SINDH

Name of Department:

**IRRIGATION DEPARTMENT**

Name of Project/Scheme:

**ADP NO. 648 "POCKET DRAINAGE SYSTEM FOR PART COMMAND DEHS KALHORKI, JHURKANDI, KERANDDI AND CHORHAL CANTONMENT AREA TAPO, TALUKA AND DISTRICT BADIN"**

Name of Work:-

**PACKAGE NO. 05: Construction of (13 No.) Solar Tube well (80 ft. Depth) of 1.0 Cusec Capacity along In & Out Cantonment Area @ Badin.**

Name of Procuring Agency: **Executive Engineer, Drainage Division, Badin**

Document issued to:

**M/S Umar Jam and Company**

DR No. & Amount:

**80/05 dt: 19-02-2016**

**H**

**for [Signature]**  
Executive Engineer  
Drainage Division  
Badin

PACKAGE NO. 05

**SUMMARY OF BID PRICE**

Construction of (13 No.) FROM TUBE WELL NO. 14 TO 26 Solar Tube well (80-ft. depth) of 1.0 Cusec Capacity along In & Out Cantonment Area @ Badin.

**CONTRACT NAME**

Bill Nr.	Description	Amount
1	Earth Work	NIL
2	Structures SOLAR TUBE WELLS (80 FT. DEPTH OF 1.0 SUSEC CAPACITY	56,592,900.0
	Total Bid Price (the amount to entered in paragraph 1 to 2 of the form of bid in words FIFTY SIX MILLIONS FIVE HUNDRED NINETY TWO THOUSAND NINE HUNDRED ONLY	56,592,900.0

**UMER JAN & COMPANY**  
Engineers & Contractors

Signature:  
Company Name:

**SCHEDULE OF PRICE**

Name of Work:- Construction of (13 No.) from T/well No. 14 to 26 Solar Tube well (80 ft. depth) of 1.0 Cusec Capacity along Cantonment Area @ Badin.

**Bill No. 2) Structures**

Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	LORENTZ Pump PS9k2 C-SJ30-7, LORENTZ Controller, Water Sensor, Cable Splice Kit, PV Protect & PV Disconnect. Flow = 250, 500 lit / day Head = 120 ft, Outlet = 3 inch or Equivalent	P/Set		1 Set	115000.0	ELEVEN LAC FIFTY THOUSAND only	11,50,000.0
2	Solar Panel (Canadian Solar) Poly Crystalline, 250 W or Equivalent	Each		40 Nos.	65000.0	SIXTY FIVE THOUSAND only	26,00,000.0
3	PV Mounting Structure MS Mounting Powder Coated	Each		40 Nos.	4000.0	FOUR THOUSAND only	1,60,000.0
4	<b>Cables</b>						
i)	4 mm <sup>2</sup> , 4 core (Pump to Controller)	P/ Ft.		160 Ft.	265.0	TWO HUNDRED SIXTY FIVE only	42,400.0
ii)	4 mm <sup>2</sup> , 1 Core (Panel Interconnection)	P/ Ft.		200 Ft.	125.0	ONE HUNDRED TWENTY FIVE only	25,000.0
iii)	1.5mm <sup>2</sup> , 2 core (Controller to Water Sensor)	P/ Ft.		160 Ft.	115.0	ONE HUNDRED FIFTEEN only	18,400.0
5	Combiner Box Model Steel Made	P/Set		1 Set	10000.0	TEN THOUSAND only	10,000.0

**UMER JAN & COMPANY**  
ENGINEERS & CONTRACTORS

6	Safety Rope for Pump & accessories 6 mm GI made with Plastic Insulation	P/Ft.	250 ft.	110.0	one HUNDRED TEN RUPEES only	27,500.0
7	Delivery pipe with accessories 2" / 3 mm GI Pipe	P/Ft.	120 ft.	1000	one THOUSAND only	120,000.0
8	Installation Charges	P/Job	1 Job	200,000.0	Two LAC only	200,000.0
Total Bid Price of 1 NO. SOLAR TUBEWELL						4,35,330.0
Total Bid Price of 13 NO. SOLAR TUBE WELLS (the amount to entered in paragraph 1 of the form of Bid) In words						56,59,290.0
FIFTY SIX MILLION FIVE HUNDRED NINETY TWO THOUSAND NINE HUNDRED only						

Signature:  
Company Name:

**UMER JAN & COMPANY**  
Engineers & Contractors



First Women Bank Ltd. Sukkur Branch.

*Not over Rs. 1000,000/-*

No. FWDC 0327361

*P.S  
H-2*

### DEPOSIT AT CALL

22-02 2016

Received from *Executive Engineer Drainage Division Badin*

Rupees *One Million only*

as a Deposit repayable at call. *M/S Umar Jain & Co.*

For First Women Bank Limited

NOT TRANSFERABLE

Rs. 1000000/-

Authorised Signature

Authorised Signature

This receipt must be returned to the Bank duly discharged by the depositor.

Do not write below this line.

⑈0327361⑈0470009⑈000000000000⑈080⑈0



# SPRA BIDDING DOCUMENTS



## GOVERNMENT OF SINDH

Name of Department:

**IRRIGATION DEPARTMENT**

Name of Project/Scheme:

**ADP NO. 648 "POCKET DRAINAGE SYSTEM FOR PART  
COMMAND DEHS KALHORKI, JHURKANDI, KERANDDI AND  
CHORHAL CANTONMENT AREA TAPO, TALUKA AND  
DISTRICT BADIN"**

Name of Work:-

**PACKAGE NO. 06: Construction of (12 No.) Solar Tube  
well (80 ft. Depth) of 1.0 Cusec Capacity along In &  
Out Cantonment Area @ Badin.**

Name of Procuring Agency: **Executive Engineer, Drainage Division, Badin**

Document issued to:

*MS Haji Sajiduddin Soomro*

DR No. & Amount:

*76/06 dt. 17-02-2016*

*[Signature]*  
Executive Engineer  
Drainage Division  
Badin

PACKAGE NO. 06

**SUMMARY OF BID PRICE**

Construction of (12 No.) FROM TUBE WELL NO. 27 TO 38 Solar Tube well (80 ft. depth) of 1.0 Cusec Capacity along In & Out Cantonment Area @ Badin.

**CONTRACT NAME**

Bill Nr.	Description	Amount
1	Earth Work	-
2	Structures SOLAR TUBE WELLS (80 FT. DEPTH OF 1.0 SUSEC CAPACITY	43,048,560 -
	Total Bid Price (the amount to entered in paragraph 1 to 2 of the form of bid in words Fourty three Million fourty eight thousand five hundred sixty only	43,048,560 -



Signature: *[Signature]*  
Company Name:

**EXECUTIVE ENGINEER**  
Drainage Division  
Badin.

SCHEDULE OF PRICE

Name of Work:- Construction of (12 No.) from T/well No. 27 to 38 Solar Tube well (80 ft. depth) of 1.0 Cusec Capacity along Cantonment Area @ Badin.

Bill No. 2) Structures

Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	LORENTZ Pump PS9k2 C-SJ30-7, LORENTZ Controller, Water Sensor, Cable Splice Kit, PV Protect & PV Disconnect. Flow = 250, 500 lit / day Head = 120 ft, Outlet = 3 inch or Equivalent	P/Set		1 Set	99,500-	Nine lac Ninety five thousands only	99,500-
2	Solar Panel (Canadian Solar) Poly Crystalline, 250 W or Equivalent	Each		40 Nos.	53,500-	Fifty three thousand five hundred only	2,140,000-
3	PV Mounting Structure MS Mounting Powder Coated	Each		40 Nos.	3,000-	Three thousand only	1,20,000-
4	<b>Cables</b>						
i)	4 mm2, 4 core (Pump to Controller)	P/Ft.		160 Ft.	210-	Two hundred Ten only	33,600-
ii)	4 mm2, 1 Core (Panel Interconnection)	P/Ft.		200 Ft.	118-	one hundred eighteen only	23,600-
iii)	1.5mm2, 2 core (Controller to Water Sensor)	P/Ft.		160 Ft.	98-	Ninety eight only	15,680-
5	Combiner Box Model Steel Made	P/Set		1 Set	8,000-	Eight thousand only	8,000-



**EXECUTIVE ENGINEER**  
Drainage Division  
Badin.

6	Safety Rope for Pump & accessories 6 mm GI made with Plastic Insulation	P/ Ft.		250 ft.	98	Twenty Eight Rupees only	24,500 -
7	Delivery pipe with accessories 2' / 3 mm GI Pipe	P/ Ft.		120 ft.	850-	Eight hundred fifty only	102,000 -
8	Installation Charges	P/ Job		1 Job	125,000-	one lac Twenty five thousand only	125,000 -
Total Bid Price of 1 NO. SOLAR TUBEWELL							
Total Bid Price of 12 NO. SOLAR TUBE WELLS (the amount to entered in paragraph 1 of the form of Bid) In words Forty three Million forty eight thousand five hundred sixty only							



Signature: *[Handwritten Signature]*  
Company Name: *[Handwritten Name]*

**EXECUTIVE ENGINEER**  
Drainage Division  
Badin



بنك الفلاح المحدود  
BANK ALFALAH LIMITED

(0045) Main Branch Saddar Hyderabad

# Call Deposit Receipt

No. CDRHYD 0685211

Ref No: FT16053886053495

Date: 22 FEB 2016

Amount not over PKR 915,000.00 only

Rs. 915,000.00
----------------

Received from M/S. HAJI SIRAJUDDIN, SOOMRO

On Account EXECUTIVE ENGINEER DRAINAGE DIVISION BADIN ON A/C M/S. HAJI SIRAJUDDIN SOOMRO

Rupees NINE HUNDRED FIFTEEN THOUSAND ONLY

as a deposit at call bearing no Interest/Profit subject to general rules of the Bank with respect to such deposits.

THIS RECEIPT IS NON TRANSFERABLE  
PAYABLE TO BENEFICIARY ONLY.

13w

Authorized Signature

917  
Authorized Signature

# SPPRA BIDDING DOCUMENTS



## GOVERNMENT OF SINDH

Name of Department: **IRRIGATION DEPARTMENT**

Name of Project/Scheme: **ADP NO. 648 "POCKET DRAINAGE SYSTEM FOR PART COMMAND DEHS KALHORKI, JHURKANDI, KERANDDI AND CHORHAL CANTONMENT AREA TAPO, TALUKA AND DISTRICT BADIN"**

Name of Work:- **PACKAGE NO. 06: Construction of (12 No.) Solar Tube well (80 ft. Depth) of 1.0 Cusec Capacity along In & Out Cantonment Area @ Badin.**


Name of Procuring Agency: **Executive Engineer, Drainage Division, Badin**

Document issued to:

MS Thadani Enterprises

DR No. & Amount:

77/06 H-17-02-2016

  
Executive Engineer  
Drainage Division  
Badin

PACKAGE NO. 06

**SUMMARY OF BID PRICE**

Construction of (12 No.) FROM TUBE WELL NO. 27 TO 38 Solar Tube well (80 ft. depth) of 1.0 Cusec Capacity along In & Out Cantonment Area @ Badin.

**CONTRACT NAME**

Bill Nr.	Description	Amount
1	Earth Work	—
2	Structures SOLAR TUBE WELLS (80 FT. DEPTH OF 1.0 SUSEC CAPACITY	46,153,440/-
	Total Bid Price (the amount to entered in paragraph 1 to 2 of the form of bid in words <i>Forty Six Million one hundred Fifty Three Thousand Four Hundred forty only</i>	46,153,440/-



Signature:


Company Name:

**SCHEDULE OF PRICE**

Name of Work:- Construction of (12 No.) from T/well No. 27 to 38 Solar Tube well (80 ft. depth) of 1.0 Cusec Capacity along Cantonment Area @ Badin.

**Bill No. 2) Structures**

Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	LORENTZ Pump PS9K2 C-SJ30-7, LORENTZ Controller, Water Sensor, Cable Splice Kit, PV Protect & PV Disconnect. Flow = 250, 500 lit / day Head = 120 ft, Outlet = 3 inch or Equivalent	P/Set		1 Set	1000000	One Million only	1,000,000/-
2	Solar Panel (Canadian Solar) Poly Crystalline, 250 W or Equivalent	Each		40 Nos.	59,500/-	Fifty Nine Thousand Five Hundred only	2,380,000/-
3	PV Mounting Structure MS Mounting Powder Coated	Each		40 Nos.	3385/-	Three Thousand Three Hundred Eighty Five only	135,400/-
4	<b>Cables</b>						
i)	4 mm <sup>2</sup> , 4 core (Pump to Controller)	P/ Ft.		160 Ft.	267/-	Two Hundred Sixty Seven only	42,720/-
ii)	4 mm <sup>2</sup> , 1 Core (Panel Interconnection)	P/ Ft.		200 Ft.	115/-	one Hundred Fifteen only	23,000/-
iii)	1.5mm <sup>2</sup> , 2 core (Controller to Water Sensor)	P/ Ft.		160 Ft.	100/-	one Hundred only	16,000/-
5	Combiner Box Model Steel Made	P/Set		1 Set	8000/-	Eight Thousand only	8,000/-






6	Safety Rope for Pump & accessories 6 mm GI made with Plastic Insulation	P/ Ft.	250 ft.	100/-	One Hundred only	25,000/-
7	Delivery pipe with accessories 2' / 3 mm GI Pipe	P/ Ft.	120 ft.	800/-	Eight Hundred only	96,000/-
8	Installation Charges	P/ Job	1 Job	120,000/-	One Hundred Twenty Thousand only	120,000/-
Total Bid Price of 1 NO. SOLAR TUBEWELL						
Total Bid Price of 12 NO. SOLAR TUBE WELLS (the amount to entered in paragraph 1 of the form of Bid) In words Fourty Six Million one hundred fifty Three Thousand Four Hundred forty only						
						3,846,120/-
						46,153,440/-

Signature:

Company Name:





**NON TRANSFERABLE**

**CALL DEPOSIT RECEIPT**

Hyderabad Branch

Phone: 022-2730911-5 Fax: 022-2730911-5

Telex: SUMBPKKA

RS. 925,000.00

RECEIVED FROM

IN FAVOUR OF

EXECUTIVE ENGINEER DRAINAGE DIVISION BADIN ON A/C OF THADANI ENTERPRISES

THE SUM OF RUPEES PAK RUPEE NINE HUNDRED AND TWENTY FIVE THOUSAND ONLY

As a deposit AT CALL bearing NO PROFIT subject to the general rules of the Bank with respect to such deposits.

This receipt is Non-Transferable and Payable to Beneficiary or Purchaser.

In the event that this instrument is not encashed within 6 months

of issue. The Bank reserves the right to validate the same before encashment.

Encashment of this instrument is subject to payment of withholding tax, as per applicable laws.

CDR: 00005003

CDR No: 5003

DATE: 22-Feb-2016

For Summit Bank Limited

AUTHORIZED SIGNATURE

AUTHORIZED SIGNATURE

⑈00005003⑈0810036⑈

⑈080⑈

# SPPRA BIDDING DOCUMENTS



## GOVERNMENT OF SINDH

Name of Department: **IRRIGATION DEPARTMENT**

Name of Project/Scheme: ADP NO. 648 "POCKET DRAINAGE SYSTEM FOR PART COMMAND DEHS KALHORKI, JHURKANDI, KERANDDI AND CHORHAL CANTONMENT AREA TAPO, TALUKA AND DISTRICT BADIN"

Name of Work:- PACKAGE NO. 06: Construction of (12 No.) Solar Tube well (80 ft. Depth) of 1.0 Cusec Capacity along In & Out Cantonment Area @ Badin.

Name of Procuring Agency: **Executive Engineer, Drainage Division, Badin**

Document issued to: M/S Ummax Jam & Company

DR No. & Amount: 80/03 H-19-02-2015  
06

*H*

*[Signature]*  
Executive Engineer  
Drainage Division  
Badin

PACKAGE NO. 06

**SUMMARY OF BID PRICE.**

**CONTRACT NAME**

Construction of (12 No.) FROM TUBE WELL NO. 27 TO 38 Solar Tube well (80 ft. depth) of 1.0 Cusec Capacity along In & Out Cantonment Area @ Badin.

Bill Nr.	Description	Amount
1	Earth Work	NIL
2	Structures SOLAR TUBE WELLS (80 FT. DEPTH OF 1.0 SUSEC CAPACITY	52,239,600.0
	Total Bid Price (the amount to entered in paragraph 1 to 2 of the form of bid in words FIFTY TWO MILLION TWO HUNDRED THIRTY AND THOUSAND SIX HUNDRED ONLY	52,239,600.0

**UMER JAN & COMPANY**  
Engineers & Contractors

Signature:

Company Name:

**SCHEDULE OF PRICE**

Name of Work:- Construction of (12 No.) from T/well No. 39 to 50 Solar Tube well (80 ft. depth) of 1.0 Cusec Capacity along Cantonment Area @ Badin.

**Bill No. 2) Structures**

Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	LORENTZ Pump PS9K2 C-SJ30-7, LORENTZ Controller, Water Sensor, Cable Splice Kit, PV Protect & PV Disconnect. Flow = 250, 500 lit / day Head = 120 ft, Outlet = 3 inch or Equivalent	P/Set		1 Set	115,000.00	ELEVEN LAC FIFTY THOUSEND only	11,50,000.00
2	Solar Panel (Canadian Solar) Poly Crystalline, 250 W or Equivalent	Each		40 Nos.	65,000.00	SIXTY FIVE THOUSEND only	2,60,000.00
3	PV Mounting Structure MS Mounting Powder Coated	Each		40 Nos.	4,000.00	FOUR THOUSEND only	1,60,000.00
4	<b>Cables</b>						
i)	4 mm <sup>2</sup> , 4 core (Pump to Controller)	P/Ft.		160 Ft.	265.00	TWO HUNDRED SIXTY FIVE only	42,400.00
ii)	4 mm <sup>2</sup> , 1 Core (Panel Interconnection)	P/Ft.		200 Ft.	125.00	ONE HUNDRED TWENTY FIVE only	25,000.00
iii)	1.5mm <sup>2</sup> , 2 core (Controller to Water Sensor)	P/Ft.		160 Ft.	115.00	ONE HUNDRED FIFTEEN only	18,400.00
5	Combiner Box Model Steel Made	P/Set		1 Set	10,000.00	TEN THOUSEND only	10,000.00

**UMER JAN & COMPANY**  
Engineers & Contractors

6	Safety Rope for Pump & accessories 6 mm GI made with Plastic Insulation	P/Ft.	250 ft.	110.0	one HUNDRED TEN Rupees only	27500.0
7	Delivery pipe with accessories 2' / 3 mm GI Pipe	P/Ft.	120 ft.	1000.0	one THOUSAND only	120,000.0
8	Installation Charges	P/Job	1 Job	200,000.0	Two LAC only	200,000.0
Total Bid Price of 1 NO. SOLAR TUBEWELL						
Total Bid Price of 12 NO. SOLAR TUBE WELLS (the amount to entered in paragraph 1 of the form of Bid) In words						
FIFTY TWO MILLION TWO HUNDRED THIRTY NINE THOUSAND SIX HUNDRED only						
						4,353,300.0
						52,239,600.0

Signature:

Company Name:

UMER JAN & COMPANY  
Engineers & Contractors



First Women Bank Ltd. Sukkur Branch.

Not over Rs. 1000,000/-

No. FWDC 0327362

# DEPOSIT AT CALL

Received from Executive Engineer Drainage Division Buden 22-02-2016

Rupees One million only

as a Deposit repayable at call. M/s Umar Sam & Co.

For First Women Bank Limited

Rs. 1000,000/-

Authorised Signature

Authorised Signature

This receipt must be returned to the Bank duly discharged by the depositor.

Do not write below this line.

⑈0327362⑈0470009⑈000000000000⑈080⑈0

NON NEGOTIABLE

P-6  
4-2

# SPPRA BIDDING DOCUMENTS



## GOVERNMENT OF SINDH

Name of Department:

**IRRIGATION DEPARTMENT**

Name of Project/Scheme:

**ADP NO. 648 "POCKET DRAINAGE SYSTEM FOR PART COMMAND DEHS KALHORKI, JHURKANDI, KERANDDI AND CHORHAL CANTONMENT AREA TAPO, TALUKA AND DISTRICT BADIN"**

Name of Work:-

**PACKAGE NO. 07: Construction of (12 No.) Solar Tube well (80 ft. Depth) of 1.0 Cusec Capacity along In & Out Cantonment Area @ Badin.**

Name of Procuring Agency: **Executive Engineer, Drainage Division, Badin**

Document issued to:

*M/S Haji Sajjad Ali Soomro*

DR No. & Amount:

*76/07 dt. 17-02-2016.*

*[Signature]*  
Executive Engineer  
Drainage Division  
Badin



PACKAGE NO. 07

**SUMMARY OF BID PRICE**

Construction of (12 No.) FROM TUBE WELL NO. 39 TO 50 Solar Tube well (80 ft. depth) of 1.0 Cusec Capacity along In & Out Cantonment Area @ Badin.

**CONTRACT NAME**

Bill Nr.	Description	Amount
1	Earth Work	
2	Structures SOLAR TUBE WELLS (80 FT. DEPTH OF 1.0 SUSEC CAPACITY	43,048,560-
	Total Bid Price (the amount to entered in paragraph 1 to 2 of the form of bid in words <i>fourty three Million forty-eight thousand five hundred sixty only</i>	43,048,560-



Signature: *H.S.*  
Company Name:

**EXECUTIVE ENGINEER**  
Drainage Division  
Badin.

**SCHEDULE OF PRICE**

Name of Work:- Construction of (12 No.) from T/well No. 39 to 50 Solar Tube well (80 ft. depth) of 1.0 Cusec Capacity along Cantonment Area @ Badin.

**Bill No. 2) Structures**

Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	LORENTZ Pump PS9k2 C-SJ30-7, LORENTZ Controller, Water Sensor, Cable Splice Kit, PV Protect & PV Disconnect. Flow = 250, 500 lit / day Head = 120 ft, Outlet = 3 inch or Equivalent	P/Set		1 Set	995000-	Nine Lacs Ninety Five Thousand only	995000-
2	Solar Panel (Canadian Solar) Poly Crystalline, 250 W or Equivalent	Each		40 Nos.	53500-	Fifty three thousand five hundred only	21401000
3	PV Mounting Structure MS Mounting Powder Coated	Each		40 Nos.	3000-	Three thousand only	120000-
4	<b>Cables</b>						
i)	4 mm2, 4 core (Pump to Controller)	P/Ft.		160 Ft.	210-	Two hundred Ten only	33600-
ii)	4 mm2, 1 Core (Panel Interconnection)	P/Ft.		200 Ft.	118-	one hundred eighteen only	23600-
iii)	1.5mm2, 2 core (Controller to Water Sensor)	P/Ft.		160 Ft.	98-	Ninety eight only	15680-
5	Combiner Box Model Steel Made	P/Set		1 Set	8000-	Eight thousand only	8000-



**EXECUTIVE ENGINEER**  
Drainage Division  
Badin

6	Safety Rope for Pump & accessories 6 mm GI made with Plastic Insulation	P/Ft.	250 ft.	98-	Nintye eight only	24,500-
7	Delivery pipe with accessories 2' / 3 mm GI Pipe	P/Ft.	120 ft.	850-	Eight hundred fifty only	102,000-
8	Installation Charges	P/Job	1 Job	125000	one lac Twenty five thousand only	125,000-
Total Bid Price of 1 NO. SOLAR TUBEWELL						
Total Bid Price of 12 NO. SOLAR TUBE WELLS (the amount to entered in paragraph 1 of the form of Bid) in words						
forty three Million forty eight thousand five hundred sixty only						
43,48,560						



Signature: *[Handwritten Signature]*  
Company Name:

*[Handwritten Signature]*

PROPERTY OFFICER  
District Office



بنك الفلاح المحدود  
BANK ALFALAH LIMITED

(0045) Main Branch Saddar Hyderabad

### Call Deposit Receipt

No. CDRHYD 0685212

Ref. No. FTI6053909966438

Date: 22 FEB 2016

Amount not over PKR 915,000.00 only

Rs.	915,000.00
-----	------------

Received from M/S. HAJI SIRAJUDDIN SOOMRO

On Account EXECUTIVE ENGINEER DRAINAGE DIVISION BADIN ON A/C M/S. HAJI SIRAJUDDIN SOOMRO

Rupees NINE HUNDRED FIFTEEN THOUSAND ONLY

as a deposit at call bearing no Interest/Profit subject to general rules of the Bank with respect to such deposits.

THIS RECEIPT IS NON TRANSFERABLE  
PAYABLE TO BENEFICIARY ONLY

*[Handwritten Signature]*  
13/2

Authorized Signature

*[Handwritten Signature]*  
8/17

Authorized Signature

# SPPRA BIDDING DOCUMENTS



## GOVERNMENT OF SINDH

Name of Department: **IRRIGATION DEPARTMENT**

Name of Project/Scheme: ADP NO. 648 "POCKET DRAINAGE SYSTEM FOR PART COMMAND DEHS KALHORKI, JHURKANDI, KERANDDI AND CHORHAL CANTONMENT AREA TAPO, TALUKA AND DISTRICT BADIN"

Name of Work:- PACKAGE NO. 07: Construction of (12 No.) Solar Tube well (80 ft. Depth) of 1.0 Cusec Capacity along In & Out Cantonment Area @ Badin.

Name of Procuring Agency: **Executive Engineer, Drainage Division, Badin**

Document issued to:

MS Thadani Enterprises

DR No. & Amount:

77/07 H: 17-02-2016.

*[Signature]*  
Executive Engineer  
Drainage Division  
Badin

H

PACKAGE NO. 07

**SUMMARY OF BID PRICE**

**CONTRACT NAME**

Construction of (12 No.) FROM TUBE WELL NO. 39 TO 50 Solar Tube well (80 ft. depth) of 1.0 Cusec Capacity along In & Out Cantonment Area @ Badin.

Bill Nr.	Description	Amount
1	Earth Work	-
2	Structures SOLAR TUBE WELLS (80 FT. DEPTH OF 1.0 SUSEC CAPACITY	46,153,440/-
	Total Bid Price (the amount to entered in paragraph 1 to 2 of the form of bid in words <i>Forty Six Million One Hundred Fifty Three Thousand four Hundred forty only</i>	46,153,440/-



Signature:  
Company Name:

**SCHEDULE OF PRICE**

Name of Work:- Construction of (12 No.) from T/well No. 39 to 50 Solar Tube well (80 ft. depth) of 1.0 Cusec Capacity along Cantonment Area @ Badin.

**Bill No. 2) Structures**

Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.)
					Figure	Words	
1	LORENTZ Pump PS9K2 C-SJ30-7, LORENTZ Controller, Water Sensor, Cable Splice Kit, PV Protect & PV Disconnect. Flow = 250, 500 lit / day Head = 120 ft, Outlet = 3 inch or Equivalent	P/Set		1 Set	1000000/-	One Million only	1,000,000/-
2	Solar Panel (Canadian Solar) Poly Crystalline, 250 W or Equivalent	Each		40 Nos.	59,500/-	Fifty Nine Thousand Five Hundred only	2,380,000/-
3	PV Mounting Structure MS Mounting Powder Coated	Each		40 Nos.	3385/-	Three Thousand Three Hundred Eighty Five only	135,400/-
4	<b>Cables</b>						
i)	4 mm2, 4 core (Pump to Controller)	P/Ft.		160 Ft.	267/-	Two Hundred Sixty Seven only	42,720/-
ii)	4 mm2, 1 Core (Panel Interconnection)	P/Ft.		200 Ft.	115/-	one Hundred fifteen only	23,000/-
iii)	1.5mm2, 2 core (Controller to Water Sensor)	P/Ft.		160 Ft.	100/-	one Hundred only	16,000/-
5	Combiner Box Model Steel Made	P/Set		1 Set	8000/-	Eight Thousand only	8,000/-



6	Safety Rope for Pump & accessories 6 mm GI made with Plastic Insulation	P/ Ft.	250 ft.	100/2	One Hundred only	25,000/-
7	Delivery pipe with accessories 2' / 3 mm GI Pipe	P/ Ft.	120 ft.	800/-	Eight Hundred only	96,000/-
8	Installation Charges	P/ Job	1 Job	120,000/-	One Hundred Twenty Thousand only	120,000/-
Total Bid Price of 1 NO. SOLAR TUBEWELL						
Total Bid Price of 12 NO. SOLAR TUBE WELLS (the amount to entered in paragraph 1 of the form of Bid) in words						
Forty Six Million One Hundred Fifty Three Thousand Four Hundred forty only.						

Signature:  
Company Name:







Hyderabad Branch  
Phone: 022-2730911-5 Fax: 022-2730911-5  
Tele: SUMBPKKA

**NON TRANSFERABLE**

**CALL DEPOSIT RECEIPT**

RS. 925,000.00  
RECEIVED FROM ---

CDR No. 5004  
DATE: 22-Feb-2016

IN FAVOUR OF EXECUTIVE ENGINEER DRAINAGE DIVISION BADIN ON A/C OF THADANI ENTERPRISES

THE SUM OF RUPEES PAK RUPEE NINE HUNDRED AND TWENTY FIVE THOUSAND ONLY

As a deposit AT CALL bearing NO PROFIT subject to the general rules of the Bank with respect to such deposits.  
This receipt in Non-Transferable and Payable to Beneficiary or Purchaser.  
In the event that this instrument is not encashed within 6 months of issue. The Bank reserves the right to validate the same before encashment.  
Encashment of this instrument is subject to payment of withholding tax, as per applicable laws.

*(Handwritten Signature)*  
For Summit Bank Limited  
AUTHORIZED SIGNATURE

CDR. 00005004

⑈00005004⑈0810036⑈

⑈080⑈

Hyderabad Branch

# SPPRA BIDDING DOCUMENTS



## GOVERNMENT OF SINDH

Name of Department: **IRRIGATION DEPARTMENT**

Name of Project/Scheme: ADP NO. 648 "POCKET DRAINAGE SYSTEM FOR PART COMMAND DEHS KALHORKI, JHURKANDI, KERANDDI AND CHORHAL CANTONMENT AREA TAPO, TALUKA AND DISTRICT BADIN"

Name of Work:- PACKAGE NO. 07: Construction of (12 No.) Solar Tube well (80 ft. Depth) of 1.0 Cusec Capacity along In & Out Cantonment Area @ Badin.

H

Name of Procuring Agency: **Executive Engineer, Drainage Division, Badin**

Document issued to:

M/S Thomas Jan & Company

DR No. & Amount:

80 / ~~01~~ H.C. 19-02-2015  
07

*for [Signature] H.C.*  
Executive Engineer,  
Drainage Division  
Badin

PACKAGE NO. 07

**SUMMARY OF BID PRICE**

**CONTRACT NAME**

Construction of (12 No.) FROM TUBE WELL NO. 39 TO 50 Solar Tube well (80 ft. depth) of 1.0 Cusec Capacity along In & Out Cantonment Area @ Badin.

Bill Nr.	Description	Amount
1	Earth Work	NIL
2	Structures SOLAR TUBE WELLS (80 FT. DEPTH OF 1.0 SUSEC CAPACITY	52,239,600.0
	Total Bid Price (the amount to entered in paragraph 1 to 2 of the form of bid in words FIFTY TWO MILLION TWO HUNDRED THIRTY NINE THOUSAND SIX HUNDRED ONLY	52,239,600.0

**UMER JAVR COMPANY**  
Engineers & Contractors

Signature:


Company Name:

**SCHEDULE OF PRICE**

Name of Work:- Construction of (12 No.) from T/well No. 27 to 38 Solar Tube well (80 ft. depth) of 1.0 Cusec Capacity along Cantonment Area @ Badin.

**Bill No. 2) Structures**

Item Nr.	Description	Unit	Specifications Chapter Nr.	Quantity	Rate (Rs.)		Amount (Rs.) *
					Figure	Words	
1	LORENTZ Pump PS9K2 C-SJ30-7, LORENTZ Controller, Water Sensor, Cable Splice Kit, PV Protect & PV Disconnect. Flow = 250, 500 lit / day Head = 120 ft, Outlet = 3 inch or Equivalent	P/Set		1 Set	150000.0	ELEVEN LAC FIFTY THOUSEND only	1,50,000.0
2	Solar Panel (Canadian Solar) Poly Crystalline, 250 W or Equivalent	Each		40 Nos.	65000.0	SIXTY FIVE THOUSEND only	2,600,000.0
3	PV Mounting Structure MS Mounting Powder Coated	Each		40 Nos.	4000.0	FOUR THOUSEND only	1,60,000.0
4	<b>Cables</b>						
i)	4 mm <sup>2</sup> , 4 core (Pump to Controller)	P/ Ft.		160 Ft.	265.0	TWO HUNDRED SIXTY FIVE only	42,400.0
ii)	4 mm <sup>2</sup> , 1 Core (Panel Interconnection)	P/ Ft.		200 Ft.	125.0	ONE HUNDRED TWENTY FIVE only	25,000.0
iii)	1.5mm <sup>2</sup> , 2 core (Controller to Water Sensor)	P/ Ft.		160 Ft.	115.0	ONE HUNDRED FIFTEEN only	18,400.0
5	Combiner Box Model Steel Made	P/Set		1 Set	10000.0	TEN THOUSEND only	10,000.0

  
**TMR M & C COMPANY**  
 CONTRACTORS

6	Safety Rope for Pump & accessories 6 mm GI made with Plastic Insulation	P/Ft.		250 ft	110-0	one HUNDRED TEN RUPEES only	27,500.0
7	Delivery pipe with accessories 2' / 3 mm GI Pipe	P/Ft.		120 ft	1000-0	one THOUSAND only	120,000.0
8	Installation Charges	P/Job		1 Job	200000-0	Two LAC only	200,000.0
Total Bid Price of 1 NO. SOLAR TUBEWELL							
Total Bid Price of 12 NO. SOLAR TUBE WELLS (the amount to entered in paragraph 1 of the form of Bid) In words							
FIFTY TWO MILLION TWO HUNDRED THIRTY NINE THOUSAND SIX HUNDRED only							
							4,353,300.0
							52,23,960.0

Signature:  
Company Name:

**UMER JAN & COMPANY**  
Engineers & Contractors



First Women Bank Ltd. Sukkur Branch.

Net over Rs. 10,00,000/-

No. FWDC 0327363

### DEPOSIT AT CALL

*Executive*

22 02 2016

Received from Engineer Engineer Drainage Division Balloch  
Rupees One million only

as a Deposit repayable at call. M/s Law & Co.  
For First Women Bank Limited

NOT TRANSFERABLE

Rs. 10,00,000/-

Authorised Signature

Authorised Signature

P-7  
H-2

This receipt must be returned to the Bank duly discharged by the depositor.

Do not write below this line

⑈0327363⑈0470009⑈000000000000⑈080⑈0



# OFFICE OF THE EXECUTIVE ENGINEER DRAINAGE DIVISION, BADIN

E-mail : drainagedivisionbadin@gmail.com

Off: No. 022-9210347

No. TC/ G-148/DD/ 64 of 2016

Badin, Dated: 18 / 02 / 2016

To,

The Director (A&F)  
Sindh Public Procurement Regulatory Authority (SPPRA)  
Karachi.

Subject: CO-OPTED MEMBERS IN BIDDING PROCESS.

As per recommendations by the Procuring Committee the following persons are hereby accepted as a co-opted members in procure committee consited for the ADP No. 648 "POCKET DRAINAGE SYSTEM FOR PART COMMAND DEHS KALHORKI, JHURKANDI, KERANDDI AND CHORHAL CANTONMENT AREA TAPO, TALUKA AND DISTRICT BADIN"

1. Major  
Iftikhar  
Head Quarter 206 Brigade  
Badin Cantonment.
2. Syed Aijaz Ali  
Executive Engineer  
Akram Wah Division, Badin.

  
(Fawad Ahmed Memon)  
EXECUTIVE ENGINEER  
DRAINAGE DIVISION  
BADIN