



# KARACHI WATER & SEWERAGE BOARD

## OFFICE OF THE DIRECTOR (DESIGN & ESTIMATE)

### BID EVALUATION REPORT


1	Name of Procuring Agency:	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No:	SPPRA Serial No.35047 I.D.No. _____
3	Tender Description/Name of Work/Item:	<b>REPLACEMENT OF 12" DIA &amp; 8" DIA RCC SEWERAGE PIPE LINE I/C PROVIDING &amp; FIXING RCC RING SLABS OF MANHOLE COVERS AND CONSTRUCTION OF INTERMEDIATE MANHOLES IN DIFFERENT AREAS OF UC-15 &amp; UC-16 OF LANDHI TOWN</b>
4	Method of Procurement:	Single Stage (One Envelop)
5	Tender Published:	Through SPPRA Web Site
6	Total Bid Documents Sold:	2 Nos
7	Total Bid Received:	2 Nos
8	Technical Bid Opening Date (if applicable):	N/A
9	No. of Bid Technically Qualified (if applicable)	N/A
10	Bid (s) Rejected:	<del>Nil</del> Nil
11	Financial Bid Opening Date:	21-11-2017

### 12 BID EVALUATION REPORT

S#	Name of Firm / Bidder	COST OFFERED BY THE BIDDER	RANKING IN TERMS OF COST	COMPARISON WITH ESTIMATED COST	REASON FOR ACCEPTANCE / REJECTION	REMARKS
1	M/s. Shan Builders	Rs.9,59,797/-	1 <sup>st</sup> Lowest	@0.155% Below	Pay Order and required documents are available. P.O # 17317759 dt:20-11-2017 Rs.20,000/-from HBL Paposh Nagar Branch Karachi	Substantially Responsive
2	M/s.Sadiq & Co.	Rs.9,61,785/-	2 <sup>nd</sup> Lowest	@0.051% Above	Pay Order and required documents are available. P.O # 11510554 dt:25-10-2017 Rs.20,000/-from HMBL Paposh Nagar Branch Karachi	Substantially Responsive


The all concerned bidders are being informed accordingly.


The E.E Concerned for compliance of Rule-45 of SPPRA 2010 **M/s. Shan Builders** declared as the lowest responsive bidder by the Committee and recommended for sanction from Competent Authority.

  
(Nadeem Ahmed Khan)  
D.A.O (Dist. Korangi)  
Member / Secretary

  
(Saif-ul-Haque)  
Additional Director Internal  
Audit – KMC Member

  
(Maqsood Ahmed Shaikh)  
Superintending Engineer  
(KMC)  
Member

  
(Wajid Iqbal Siddiqui)  
S.E. (Dist. Korangi)

  
(Saifuddin) 22-11-17  
Director (Design & Estimate)  
Director Design & Estimate

## COMPARATIVE STATEMENT

**Name of Work: REPLACEMENT OF 12" DIA & 8" DIA RCC SEWERAGE PIPE LINE I/C PROVIDING & FIXING RCC RING SLABS OF MANHOLE COVERS AND CONSTRUCTION OF INTERMEDIATE MANHOLES IN DIFFERENT AREAS OF UC-15 & UC-16 OF LANDHI TOWN**


Item No	Description of Work	Estimated Cost				M/s.Shan Builders		M/s.Sadiq & Co.		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
1	Scarifying the existing road surface	2580.00	Sft	116.16	%Sft	2,996.93	115.00	2,967.00	116.25	2,999.25
2	Excavation for pipe line in trenches and pits in all kind of soils of murum i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by Engineer Incharge providing fence guards, lights, flags sand temporary crossing for non-vehicular traffic wherever required lift upto 5 ft (1.52 m) and lead upto one chain (30.5m). Lift 0' to 5' ft	7740.00	Cft	4650.00	%0Cft	35,991.00	4650.00	35,991.00	4650.00	35,991.00
3	Excavation for pipe line in trenches, pits in wet silt clay or mud i/c trimming and dressing sides to true alignment and shape, leveling of beds of trenches to correct level and grade, cutting joint holes and disposal of surplus earth within one chain as directed by Engineering Incharge. Providing fence guard, light, flags and temporary crossing for non vehicular traffic where ever required lift upto 5' ft and lead upto one chain. Lift upto 05' - 08' ft	4565.00	Cft	5400.00	%0Cft	24,651.00	5400.00	24,651.00	5400.00	24,651.00
	Upto 5' - 8' ft	4320.00	Cft	5950.00	%0Cft	25,704.00	5900.00	25,488.00	6000.00	25,920.00
4	Full hire charges of pumping set per day i/c of wages of driver and assistant fuel or electric energy platform for placing the pump etc at lower depth with suction and delivery pipes for pumping out water found at various depth from trenches including the cost of erection and dismantling after completion of the job. Hire charges of pumping set upto 10 HP pumping out water from 20 ft deep trench	14.00	Days	1500.00	P/Day	21,000.00	1500.00	21,000.00	1500.00	21,000.00
5	Providing, & Laying of RCC Pipes with Rubber Ring Joint and fitting in trench including cutting, fitting, jointing with rubber ring i/c testing with water to specified pressure. 12" Dia	580.00	Rft	367.00	P/Rft	212,860.00	366.00	212,280.00	367.00	212,860.00
	08" Dia	336.00	Rft	206.00	P/Rft	69,216.00	205.00	68,880.00	207.00	69,552.00

**Name of Work: REPLACEMENT OF 12" DIA & 8" DIA RCC SEWERAGE PIPE LINE I/C PROVIDING & FIXING RCC RING SLABS OF MANHOLE COVERS AND CONSTRUCTION OF INTERMEDIATE MANHOLES IN DIFFERENT AREAS OF UC-15 & UC-16 OF LANDHI TOWN**


Item No	Description of Work	Estimated Cost				M/s.Shan Builders		M/s.Sadiq & Co.		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
6	Providing Manhole 4' feet internal dia without RCC cover with C.I Frame 15 Kg and 5 feet clear depth 1:2:4 cast in situ with in 9" thick wall, 1:4:8: C.C in 6ft dia and 6" inch thick in foundation 1:2:4 C.C in benching 1/2" thick cement plaster with 1:3 cement mortar on all inside wall surfaces of channel and benching i/c making required nos of main and branch channels, 3/4" dia M.S Foot rest @12" c/c i/c cost of excavation in all kinds of soil, backfilling and disposal of excavated stuff etc complete as per design and instruction of Engineer Incharge.	22.00	Nos	14529.29	Each	319,644.38	14529.00	319,638.00	14530.00	319,660.00
7	Add or deduct for extra depth per ft.	20.00	(+)Ft	2538.62	P/ft	50,772.40	2538.50	50,770.00	2539.00	50,780.00
8	Manufacturing and supplying of 21 inch diameter RCC Manhole Covers cast in 1:2:4 cement concrete ratio 3" inch deep at centre rein-forced with 1/2" dia M.S tor bars with 4" c/c welded to a 3/16" thick 2" wide M.S Flat and tow hook of 3/8" dia tor bars including compacting, curing and trnsportation within 10 miles etc. 21" dia	60.00	Nos	913.63	Each	54,817.80	912.00	54,720.00	914.00	54,840.00
9	Manufacturing and supplying of RCC Ring Slab of 21" dia (inside) and 36" dia outside 7.5" width and 6" thick i/c 3/8" dia tor steel bars two concentric rings with 3/8" dia 8 Nos cross linked bars welded and two sunk type hooks, casted in 1:1 1/2" 3 concrete with embedded 15 Kg C.I Frame in perfect position i/c transportation charges for an average lead of 20 Km per trip from casting yard to town office. (A minimum of 25 slabs per trip will be transported.	40.00	Nos	1906.60	Each	76,264.00	1906.00	76,240.00	1907.00	76,280.00
10	Shifting to the site and fixing 36" dia ring slab in perfect position on damaged manhole i/c cutting of the position of damaged mnahole in proper shape laying in layer of C.M in 2" thickness and disposal of the debris.	40.00	Nos	563.09	Each	22,523.60	562.00	22,480.00	563.00	22,520.00


**Name of Work: REPLACEMENT OF 12" DIA & 8" DIA RCC SEWERAGE PIPE LINE I/C PROVIDING & FIXING RCC RING SLABS OF MANHOLE COVERS AND CONSTRUCTION OF INTERMEDIATE MANHOLES IN DIFFERENT AREAS OF UC-15 & UC-16 OF LANDHI TOWN**


Item No	Description of Work	Estimated Cost				M/s.Shan Builders		M/s.Sadiq & Co.		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
11	Making connection with the existing manhole including the cost of cutting hole in wall, making them good in C.C 1:2:4 and making the required channel etc. complete	8.00	Nos	180.00	Each	1,440.00	180.00	1,440.00	185.00	1,480.00
12	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete.	15728.00	Cft	2760.00	%0Cft	43,409.28	2750.00	43,252.00	2750.00	43,252.00
<b>TOTAL QUOTED / CORRECTED COST</b>						<b>961,290</b>		<b>959,797</b>		<b>961,785</b>

  
 (Nadeem Ahmed Khan)  
 D.A.O (Dist.Korangi)  
 Member / Secretary

  
 (Saif-ul-Haque)  
 Addl. Director Internal  
 Audit KMC - Member

  
 (Maqsod Ahmed Shaikh)  
 Superintending Engineer (K.M.C)  
 Member

  
 (Wajid Iqbal Siddiqui)  
 S.E (Dist. Korangi)  
 Member

  
 (Saifuddin)  
 Director (Design & Estimate)  
 Convener  
 22.11.17

Method of Procurement: Single Stage Single Envelope.

Name of Work: REPLACEMENT OF 12" DIA & 8" DIA RCC SEWERAGE PIPE LINE /C PROVIDING & FIXING RCC RING SLABS OF MANHOLE COVERS AND CONSTRUCTION OF INTERMEDIATE MANHOLES IN DIFFERENT AREAS OF UC-15 & UC-16 OF LANDHI TOWN

MINUTES OF BID OPENING MEETING.

A meeting of the procurement committee of this department was held on 21-11-2017 for opening the bids received in respect of subject NIT till deadlines of submission. The meeting was attended by all / following members of the procurement committee and the representative of bidders.

(Attendance sheet is enclosed).

2. Two bidders submitted their bids till the deadline of submission.

- i. M/s. Shan Builders
- ii. M/s. Sadiq & Co.


3. The bids were opened at 2:30 P.M in the presence of the above mentioned participants and the rates quoted by bidders were read aloud and encircled by Chairman of the Procurement Committee.

S. No	Name of Firm	Quoted Price	Amount of Bid Security	Pay Order No. / Date
01	M/s. Shan Builders	Rs.9,59,797/-	Rs.20,000/-	P.O # 17317759 dt:20-11-2017 from HBL Paposh Nagar Branch Karachi
02	M/s. Sadiq & Co.	Rs.9,61,745/-	Rs.20,000/-	P.O # 11510554 dt:25-10-2017 from HMBL Paposh Nagar Branch Karachi


4. The bids do not contain any cutting or over-writing.


5. The committee shall examine all the bids as per the qualification / eligibility criteria provided in the bidding document and verify the documents and bid security submitted by the bidders (if required).


The meeting ended with the vote of thanks to and from the chair.

  
(Nadeem Ahmed Khan)  
D.A.O (Dist. Korangi)  
Member / Secretary

  
(Saif-ul-Haque)  
Additional Director Internal  
Audit – KMC Member

  
(Maqsood Ahmed Shaikh)  
Superintending Engineer (KMC)  
Member

  
(Wajid Iqbal Siddiqui)  
S.E (Dist. Korangi)  
Member

  
(Saifuddin)  
Director (Design & Estimate)  
Convener  
21.11.17

Method and procedure of procurement: Open Competitive Bidding (National/ International Competitive Bidding) (Single Stage-One Envelope)


Description of work: REPLACEMENT OF 12" DIA & 8" DIA RCC SEWERAGE PIPE LINE I/C PROVIDING & FIXING RCC RING SLABS OF MANHOLE COVERS AND CONSTRUCTION OF INTERMEDIATE MANHOLES IN DIFFERENT AREAS OF UC-15 & UC-16 OF LANDHI TOWN


Date of Opening: 21-11-2017


**BIDDERS' ELIGIBILITY/ QUALIFICATION REPORT**


Eligibility/ Qualification Criteria:

S. No.	Eligibility / Qualification Criteria	Bidders' Name	
		M/s. Shan Builders	M/s. Sadiq & Co.
1.	NTN	Yes	Yes
2.	Registration with Sindh Revenue Board (SRB)	Yes	Yes
	<b>Qualification Criteria:</b>		
3.	Minimum three years' experience of relevant field.	Yes	Yes
4.	Turnover of at least last three years	Yes	Yes
5.	Required Bid Security is attached.	Yes	Yes
6.	Bid is signed, named and stamped by the authorized person of the firm along with Authorization letter.	Yes	Yes
7.	Qualified/ disqualified	Qualified	Qualified

  
(Nadeem Ahmed Khan)  
D.A.O (Dist. Korangi)  
Member / Secretary

  
(Saif-ul-Haque)  
Additional Director Internal  
Audit – KMC Member

  
(Maqsood Ahmed Shaikh)  
Superintending Engineer (KMC)  
Member

  
(Wajid Iqbal Siddiqui)  
S.E (Dist. Korangi)  
Member

  
(Saifuddin)  
Director (Design & Estimate)  
Convener

