

SINDH PUBLIC PROCUREMENT REGULATORY AUTHORITY

CONTRACT EVALUATION FORM

**TO BE FILLED IN BY ALL PROCURING AGENCIES FOR PUBLIC CONTRACTS OF
WORKS, SERVICES & GOODS
KW&SB/Liaquatabad Town Sewerage.**

- 1) NAME OF THE ORGANIZATION / DEPT. Local Govt KW&SB.
- 2) PROVINCIAL / LOCAL GOVT / OTHER Local Government / K.S.B.
- 3) TITLE OF CONTRACT Statement regarding the repair of sewer / lifted manholes at
- 4) TENDER NUMBER Muzaffargarh District Area in Liaquatabad Town
(sewage)
- 5) BRIEF DESCRIPTION OF CONTRACT Improvement of sewerage system.
- 6) FORUM THAT APPROVED THE SCHEME Director, K.S.B.
- 7) TENDER ESTIMATED VALUE 8,26,215/-
- 8) ENGINEER'S ESTIMATE 8,24,457/-
(For civil works only)
- 9) ESTIMATED COMPLETION PERIOD (AS PER CONTRACT) 1-4-2014
- 10) TENDER OPENED ON (DATE & TIME) 1-4-2014 3.00 p.m.
- 11) NUMBER OF TENDER DOCUMENTS SOLD 03
(Attach list of buyers)
- 12) NUMBER OF BIDS RECEIVED 03
- 13) NUMBER OF BIDDERS PRESENT AT THE TIME OF OPENING OF BIDS _____
- 14) BID EVALUATION REPORT All ready sent.
(Enclose a copy)
- 15) NAME AND ADDRESS OF THE SUCCESSFUL BIDDER M/s. Gul Sawab & Co
1/C 134 Fajani Colony
Muzaffargarh Dist. K.S.B.
- 16) CONTRACT AWARD PRICE 8,24,457
- 17) RANKING OF SUCCESSFUL BIDDER IN EVALUATION REPORT 1. M/s. Gul Sawab & Co.
(i.e. 1st, 2nd, 3rd EVALUATION BID). 2. M/s. Nawab & Co.
3. M/s. Swab Moor Khan Bros.
- 18) METHOD OF PROCUREMENT USED :- (Tick one)

a)	SINGLE STAGE – ONE ENVELOPE PROCEDURE <input checked="" type="checkbox"/>	Domestic/ Local
b)	SINGLE STAGE – TWO ENVELOPE PROCEDURE _____	
c)	TWO STAGE BIDDING PROCEDURE _____	
d)	TWO STAGE – TWO ENVELOPE BIDDING PROCEDURE _____	

PLEASE SPECIFY IF ANY OTHER METHOD OF PROCUREMENT WAS ADOPTED i.e. EMERGENCY, DIRECT CONTRACTING ETC. WITH BRIEF REASONS:

19) APPROVING AUTHORITY FOR AWARD OF CONTRACT Managing Director, A.S.S.D.

20) WHETHER THE PROCUREMENT WAS INCLUDED IN ANNUAL PROCUREMENT PLAN?

Yes	<input type="checkbox"/>	No	<input type="checkbox"/>
-----	--------------------------	----	--------------------------

21) ADVERTISEMENT :

i) SPPRA Website
(If yes, give date and SPPRA Identification No.)

Yes	SP.No. 1342 L.D	2014
No		

ii) News Papers
(If yes, give names of newspapers and dates)

Yes	
No	

22) NATURE OF CONTRACT

Domestic/ Local	<input checked="" type="checkbox"/>	Int.	<input type="checkbox"/>
--------------------	-------------------------------------	------	--------------------------

23) WHETHER QUALIFICATION CRITERIA
WAS INCLUDED IN BIDDING / TENDER DOCUMENTS?
(If yes, enclose a copy)

Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
-----	--------------------------	----	-------------------------------------

24) WHETHER BID EVALUATION CRITERIA
WAS INCLUDED IN BIDDING / TENDER DOCUMENTS?
(If yes, enclose a copy)

Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
-----	--------------------------	----	-------------------------------------

25) WHETHER APPROVAL OF COMPETENT AUTHORITY WAS OBTAINED FOR USING A
METHOD OTHER THAN OPEN COMPETITIVE BIDDING?

Yes	<input type="checkbox"/>	No	<input type="checkbox"/>
-----	--------------------------	----	--------------------------

26) WAS BID SECURITY OBTAINED FROM ALL THE BIDDERS?

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

27) WHETHER THE SUCCESSFUL BID WAS LOWEST EVALUATED
BID / BEST EVALUATED BID (in case of Consultancies)

Yes	<input type="checkbox"/>	No	<input type="checkbox"/>
-----	--------------------------	----	--------------------------

28) WHETHER THE SUCCESSFUL BIDDER WAS TECHNICALLY
COMPLIANT?

Yes	<input type="checkbox"/>	No	<input type="checkbox"/>
-----	--------------------------	----	--------------------------

29) WHETHER NAMES OF THE BIDDERS AND THEIR QUOTED PRICES WERE READ OUT AT
THE TIME OF OPENING OF BIDS?

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

30) WHETHER EVALUATION REPORT GIVEN TO BIDDERS BEFORE THE AWARD OF
CONTRACT?

(Attach copy of the bid evaluation report)

Yes	<input type="checkbox"/>	No	<input type="checkbox"/>
-----	--------------------------	----	--------------------------

31) ANY COMPLAINTS RECEIVED
(If yes, result thereof)

Yes	
No	<input checked="" type="checkbox"/>

32) ANY DEVIATION FROM SPECIFICATIONS GIVEN IN THE TENDER NOTICE / DOCUMENTS
(If yes, give details)

Yes	
No	<input checked="" type="checkbox"/>

33) WAS THE EXTENSION MADE IN RESPONSE TIME?
(If yes, give reasons)

Yes	
No	<input checked="" type="checkbox"/>

34) DEVIATION FROM QUALIFICATION CRITERIA
(If yes, give detailed reasons.)

Yes	
No	

35) WAS IT ASSURED BY THE PROCURING AGENCY THAT THE SELECTED FIRM IS NOT
BLACK LISTED?

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

36) WAS A VISIT MADE BY ANY OFFICER/OFFICIAL OF THE PROCURING AGENCY TO THE
SUPPLIER'S PREMISES IN CONNECTION WITH THE PROCUREMENT? IF SO, DETAILS TO
BE ASCERTAINED REGARDING FINANCING OF VISIT, IF ABROAD:
(If yes, enclose a copy)

Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
-----	--------------------------	----	-------------------------------------

37) WERE PROPER SAFEGUARDS PROVIDED ON MOBILIZATION ADVANCE PAYMENT IN
THE CONTRACT (BANK GUARANTEE ETC.)?


Yes	<input type="checkbox"/>	No	<input type="checkbox"/>
-----	--------------------------	----	--------------------------

38) SPECIAL CONDITIONS, IF ANY
(If yes, give Brief Description)

Yes	
No	<input checked="" type="checkbox"/>

39) Date of Award of Contract

Signature & Official Stamp of
Authorized Officer


ZAFAR MALIK
Executive Engineer (SF W)
Liaquatabad Town
Karachi Water & Sewerage Board

FOR OFFICE USE ONLY

SPPRA, Block. No.8, Sindh Secretariat No.4-A, Court Road, Karachi
Tele: 021-9205356; 021-9205369 & Fax: 021-9206291

Print

Save

Reset

OFFICE OF THE EXECUTIVE ENGINEER (SEW)
LIAQUATABAD ZONE, K.W.&S.B

No: EE /LQT/Sew/2014/ 35

Dated: 19-5-2014

M/S Gul Sawab & Co,
M.C 134 Mujahid Colony
Nazimabad No.4
Karachi

LETTER OF COMMENCEMENT /WORK ORDER

**SUBJECT:- EMERGENT REPAIRING OF BROKEN / SETTLED MANHOLES AT
NAZIMABAD & GULBEHAR AREA IN LIAQUATABAD ZONE
(SEWERAGE).**

Consequent upon the condition of Contract and letter of acceptance vide No.KW&SB/CE/Central/2014/70 Dated 16-5-2014 and subsequent you are hereby directed to commence the works in strict accordance with the contract with the expedition and diligence the date of commencement of work shall be reckoned from the 14 day of the received of the letter.


Please be noted that M/s.Gul Sawab & Co shall act as the engineer on this project through their authorized representative, the names and designation of the personnel's deputed will be communicated to you accordingly.

Therefore, you are advised to attend the office of the undersigned to obtain necessary instruction to carry out the work assigned to your firm and get it complete the same within (15) days positively, failing which penalty of Rs.500 per days will be charged.

Please note that the work would be carried out on war footing basis / day and night strictly according to the specification and will be completed within the stipulated period.

The expenditure will be charge under BG No.O-023-16 for year 2013-14 amounting to Rs. 8,24,457/- Eight Lacs Twenty Four Thousand Four Hundred Fifty Seven only.

Please acknowledge the receipt of this letter by signing in the space provided below.


EXECUTIVE ENGINEER
LIAQUATABAD TOWN (Sew)

- 1.The C.E,(Central),KWSB
- 2.S.E. Liaquatabad Zone
- 3.A.E.E. Liaquatbad Zone Sew.
- 4.Office Copy.

With directive to communicate the names along-with the
Designation of the personnel's engaged for the works.
Received the latter.

Signature _____
Designation. _____



**OFFICE OF THE EXECUTIVE ENGINEER (SEW) LIAQUATABAD ZONE
KARACHI WATER & SEWERAGE BOARD
ABSTRACT OF COST**

Name of Work: Emergent Repairing of Broken / Settled manholes at Nazimabad & Gulbhar Area in Liaquatabad Zone.

S.No	Ref No	DESCRIPTION	QUANTITY	RATE	PER	AMOUNT
1	pub-53 P-62 ITM-5	Excavation for pipe line in trenches, and pits in all kind of soils of murum i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade, cutting joint holes and disposal of surplus earth within a one chain as directed by engineer In charge, Providing fence guards, lights, flags and temporary crossing for non vehicular traffic where ever required lift up to 5 ft. (1.52m) and lead up to one chain (30.5m).	916.3 Cft	4650/-	%0Cft	Rs. 4260.79/=
2	pub-53 P-76 ITM-23	Full hire charges of the pumping per day inclusive of wage of driver & Assistant, fuel or Electric. Energy plate from required for placing pumps etc. at lower depth with suction and delivery pipes for pumping out water found at various depths from trenches i/c the cost of erection and dismantling after completion of the job.	12 days	1500	P/Day	Rs. 18000/=
3	Pub-52 P-16 ITM-(1)	Cement concrete plain including placing compacting, finishing and curing and complete. (i/c screening and washing at stone aggregate) Ratio 1:2:4	1876.12 Cft	14429.25	% Cft	Rs. 270710/=
4	Based on Sch-2012	Steel Shuttering for construction of Manhole (Circular) at site i/c its erection in proper position and removal after concrete i/c transportation complete etc	192.5 P/Rft	99.00	P/Rft	Rs. 19057.5/=
5	Based on sch 2012	C.I Frame	420 Kg	70/=	P/Kg	Rs. 29400/=
6	pub-53 P-77 ITM-24	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc. complete.	916.3 Cft	2760.00	%0Cft	Rs. 2528.98/=
7	pub-54 P-31 ITM-1	Manufacturing and supplying of 21" R.C.C. manhole cover cast in 1:2:4 concrete ratio 3 inch deep at center, reinforced with 1/2 inch dia to steel bars at 4" c/c welded to 3/16" thick 2" wide M.S plate two hook of 3/8" dia tor bar including compacting i/c curing, and transportation with in 10 miles.	200 Nos 50 Nos	913.63 1051.25	Each Each	Rs. 182726/= Rs. 52562.5/=
8	pub-54 P-31 ITM-2	Manufacturing and Supplying RCC ring slabs of 21" inside 36" dia outside 7.5" width and 6" thick i/c 3/8" dia tor steel bars two concentric rings with 3/8" dia 8 Nos cross linked bars welded and two sunk type hooks casted in a 1:1-1/2:3 concrete with embedded 15 kg C.I frame in perfect position i/c transportation charges for an average lead of 20 km per trip from casting yard to town offices (A minimum of 25 slabs per trip will be transported.	100 Nos	1906.60	Each	Rs. 190660/=
9	pub-54 P-31 ITM-4	Shifting to the site and fixing of 36" dia ring slab in perfect position on damaged manholes including cutting of damaged portion of manhole in proper shape and laying of cement mortar of 2" thickness and disposal of debris	100 Nos	563.09	Each	Rs. 56309/=
TOTAL						Rs. 826214.77/=

S. Faheem Akhter Zaidi
Chief Engineer (Central)
KW & SB

Estimated Technically Section for annual Reg
20 RS 8, 26, 215/-

Sub-Engineer (Sew) Assistant Ex-Engineer (Sew) Executive Engineer (Sew)
Liaquatabad Zone KW&SB Liaquatabad Zone, KW&SB Liaquatabad Zone, KW&SB

11/2/14 11/2/14 11/2/14 11/2/14

ZAFAR MALI
Executive Engineer (SF)
Liaquatabad Town,
Karachi Water & Sewerage B



KARACHI WATER & SEWERAGE BOARD
OFFICE OF THE EXECUTIVE ENGINEER (SEW)
ST-7 KDA BUILDING LIAQUATABAD ZONE

(30)

Estimate on item rate basis
Time Limit 15 Days
Penalty Rs.500/ Per Day
Tender Cost Rs.1000/-
Earnest Money 2% of Total Bid
Date of Receiving 1-4-2014 at 2.00 P.M
Date of opening 1-4-2014 at 3.00 P.m.

M/s Gulzarab & Co.
Pay order No. 58 Dt 21-03-2014
Bank/Br. _____
Amount' _____ B/No _____ Dt _____
(Signature)

Name of Work: - Emergent Repairing of Broken / settled Manholes at Nazimabad-5 & Gulbehar Area in Liaquatabad Zone

SR No	DESCRIPTION	QUANTITY	RATE in Rupees / in Figer	PER	AMOUNT
1	Excavation for pipe line in trenches, and pits in all kind of soils of murum i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade, cutting joint holes and disposal of surplus earth within a one chain as directed by engineer In charge, Providing fence guards, lights, flags and temporary crossing for non vehicular traffic where ever required lift up to 5 ft. (1.52m) and lead up to one chain (30.5m).	916.3 cft	Four thousand six hundred Fifty (4650)	%0cft	4260.15
2	Full hire charges of the pumping per day inclusive of wage of driver & Assistant, fuel or Electric. Energy plate from required for placing pumps etc. at lower depth with suction and delivery pipes for pumping out water found at various depths from trenches i/c the cost of erection and dismantling after completion of the job. Hire charges pumping set of up to 10 HP pumping out water from 10 ft deep trench.	12 day	One thousand Four hundred (1400)	Each	16800
3	Cement concrete plain i/c placing compacting finishing and curing and complete i/c screening and washing at stone aggregate ratio 1:2:4	1876.12 cft	Fourteen thousand Four hundred Twenty Nine and Paise (Twenty Five) 14429-25	%cft	2706710
4	Steel shuttering for construction of Manholes (Circular) at site i/c its erection in proper position and removal after concrete i/c transportation complete etc.	192.5 P/ft	(99) Ninety Nine	P/ft	19052.5
5	C.I Frame	420 Kg	70 Seventy	P/Kg	29400
6	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc. complete.	916.3 Cft	2760 Twenty seven hundred sixty	%0Cft	2528518

A.T.C
(Signature)
ZAFAR MALIK
Executive Engineer (SEW)
Liaquatabad Town,
Karachi Water & Sewerage Board

(Signatures)

7	Manufacturing and supplying of 21" dia RCC manhole covers cast in 1:2:4 concrete raion 3 inch deep at centre, reinforced with 1/2" inch dia to steel bars at 4" c/c welded to 3/16" thick 2" wide M.SW plate two hook of 3/8" dia tor bar including compacting i/c curing, and transportation with in 10 miles	21" dia	200 Nos	Nine hundred Thirt- (913)	Each	182,000
		24" dia	50 Nos	(2050) one Thousand Fift-ty.	Each	5,200
8	Manufacturing and supplying of RCC ring slabs of 21" inside 36" dia outside 7.5" width and 6" thick i/c 3/8" dia tor steel bars two hook concentric rings with 3/8" dia 8 Nos cross linked bars welded and two sunk type hooks casted in 1:1:-1/2:3 concrete with embedded 15 kg C.I frame in perfect position i/c transportation charges for an average lead of 20 km per trip from casting yard to Town office (A minimum of 25 slabs per trip will be transported.		100 Nos	One thousand Nine Hundred Six. (1906)	Each	190,600
9	Shifting to the site and fixing of 36" dia ring slab in perfect position on damaged manholes i/c cutting of damaged portion of manholes in proper shape and laying of cement mortar of 2" thickness and disposal of debris.		100 Nos	Five hundred Sixty. (560)	Each	56,000



A.T.G
ZAFAR BAKIK
 Executive Engineer (Sewerage)
 Liaquatabad Town
 Karachi Water & Sewerage Board

[Signature]
 Executive Engineer
 Liaquatabad Zone (Sew)

Note: Participant /Contractor shall be bound to compliance all instruction / rule of SPPRA, 2010 /PEC as well as KW&SB.

I/we hereby quoted (Rs 8,24,457.77) Eight Lacs twenty four thousand four hundred fifty seven Rupees
[Signature]
 Contractor Signature

[Signature]
 Jafar Twenty



REHAN AKHTAR Stamp Vendor
Licence No.129 Shop No.16,Block-14,
Karim Plaza, Gulshan-e-Iqbal, Karachi
S.NO.

097682

17 MAY 2014

ISSUED TO WITH ADDRESS
THROUGH WITH ADDRESS
PURPOSE
VALUE IN
STAMP VALUE IN QUANTITY

Zahid Mehmood
Advocate

payments to be made by the Employer to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the Employer to execute and complete the Works and remedy defects therein in conformity and in all respects within the provisions of the Contract.

4. The Employer hereby covenants to pay the Contractor, in consideration of the execution and completion of the Works as per provisions of the Contract, the Contract Price or such other sum as may become payable under the provisions of the Contract at the times and in the manner prescribed by the Contract.

IN WITNESS WHEREOF the parties hereto have caused this Contract Agreement to be executed on the day, month and year first before written in accordance with their respective laws

Signature of the Contractor

M/s. Gul Sawab & Co
Proprietor

Signature of the Employer

CHIEF ENGINEER, CENTRAL
KW&SB

A.F.C

ZAFAR MALIK
Executive Engineer (SF W)
Liaquatabad Town,
Karachi Water & Sewerage Board

Witness:

1. M. SHARIFA & Brothers

2. Waris & Sons


Witness:

SUPERINTENDING ENGINEER
LIAQUATABAD TOWN
KW&SB

EXECUTIVE ENGINEER SEW
LIAQUATABAD TOWN
KW&SB



80



REHAN AKHTAR Stamp Vendor
Licence No. 125- Shop No. 16, Block-14,
Karum Plaza, Gulshan-e-Iqbal, Karachi
S.NO

097681

CONTRACT AGREEMENT

ISSUED TO WITH ADDRESS
THROUGH WITH ADDRESS
PURPOSE
VALUE RS

Zahid Mehmood
Advocate

Sanction Amount Rs. 824,457/-

THIS CONTRACT AGREEMENT (hereinafter called the "Agreement") made on the 16th day of MAY, 2014 between The Karachi Water & Sewerage Board represented by it's **The Chief Engineer (Central), KW&SB** (hereinafter called the "Employer") of the one part and **M/s. Gul Sawab & Co.** (hereinafter called the "Contractor") of the other part.

WHEREAS the Employer is desirous that certain Works, viz **EMERGENT REPAIRING OF BROKEN / SETTLED MANHOLES AT NAZIMABAD & GULBEHAR AREA IN LIAQUATABAD ZONE SEWERAGE**, Should be executed by the Contractor and has accepted a Bid by the Contractor for the execution and completion of such Works and the remedying of any defects therein.


NOW This Agreement witness as follows:-

1. In this Agreement words and expressions shall have the same meanings as are respectively assigned to them in the Conditions of Contract hereinafter referred to.
2. The following documents after incorporating addenda, if any except those parts relating to Instructions to Bidders, shall be deemed to form and be read and construed as part of this Agreement, viz:
 - a. The Letter of Sanction;
 - b. The completed Form of Bid along with Schedules to Bid;
 - c. Conditions of Contract & Contract Data;
 - d. The priced Schedule of Prices;
 - e. The Specifications; and
 - f. The Drawings.

A.F.C
Zafar Malik
ZAFAR MALIK
Executive Engineer (SE.W)
Liaquatbad Town,
Karachi Water & Sewerage Board

Zahid Mehmood
Zahid Mehmood
Advocate

B555666



100 Rupees



AGENCY STAMP VENDOR
 License No. 04, Shop No. 16, Block-14,
 Cantonment, Gulshan-e-Iqbal, Karachi
 Date of Issue: 03 MAY 2014
 NO. 108642 DATE
 ISSUED TO WRITE TO: ZAHID MEHMOOD
 THROUGH WITH ADDRESS: Advocate
 PURPOSE _____
 SIGNATURES _____
 VENDOR'S SIGNATURE _____

**EMERGENT REPAIRING OF BROKEN / SETTLED
 MANHOLES AT NAZIMABAD & GULBEHAR AREA
 IN LIAQUATABAD ZONE SEWERAGE**

BY
M/s. Gul Sawab & Co
Rs. 824,457/-

A.T.K

ZAFAR MALIK
 Executive Engineer (SF/W)
 Liaquatnbad Town,
 Karachi Water & Sewerage Board



KARACHI WATER & SEWERAGE BOARD

OFFICE OF THE CHIEF ENGINEER (IP&D)

BID EVALUATION REPORT

(B)

1	Name of Procuring Agency	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No	SPPRA Serial No.19342 I D No. /2014
3	Tender Description/Name of Work/Item	EMERGENT REPAIRING OF BROKEN / SETTLED MANHOLES AT NAZIMABAD & GULBEHAR AREA IN LIAQUATABAD ZONE SEWERAGE
4	Method of Procurement	Single Stage (One Envelop)
5	Tender Published	Through Web Site
6	Total Bid Documents Sold	03 Nos
7	Total Bid Received	03 Nos
8	Technical Bid Opening Date (if applicable)	N/A
9	No. of Bid Technically Qualified (if applicable)	N/A
10	Bid (s) rejected	Two
11	Financial Bid Opening Date	1/4/2014

12 Bid Evaluation Report

#	NAME OF FIRM OR BIDDER	COST OFFERED BY THE BIDDERS	RANKING IN TERMS OF COST	COMPARISON WITH ESTIMATED COST	REASON FOR ACCEPTANCE/ REJECTION	REMARKS
1	M/s Gul Sawab & Co	Rs. 824,457/-	1st Lowest	@ 0.2127% Below	Substantially Responsive	P.O # AAA 11135733 Dt: 26-03-2014 Rs. 18,000/- Allied Papoh Nagar Br
2	M/s Nawab & Co	Rs. 829,114/-	2nd Lowest	@ 0.3508% Above	Un Responsive bid due to unqualified	P.O # AAA 11135728 Dt: 25-03-2014 Rs. 17,000/- Allied Papoh Nagar Br
3	M/s Sawab Noor Khan & Brothers	Rs. 841,514/-	3rd Lowest	@ 1.8517% Above	Un Responsive bid due to unqualified	P.O # AAA 11135732 Dt: 26-03-2014 Rs. 17,500/- Allied Papoh Nagar Br

he all concerned bidder are being informed accordingly.

he E.F. Concerned for compliance of rule 45 of SPPRA 2010 M/s. Gul Sawab & Co. declared as the lowest responsive bidder
the Committee and recommended for Sanction from Competent Authority.

(Abdul Jabbar Shaikh)
Accounts Officer (Central)
Member/Secretary

(Saif-ul-Haque)
Additional Director Internal
Audit - KMC Member

(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member

(Syed Fahim Akhtar Zaidi)
Chief Engineer (Central)
Member

(Abdul Rahim Khattai)
Chief Engineer (IPD),
(Convener)

(A. J. C.)
SAFAR MALIK
Executive Engineer (SE-AD)
Liaquatabad Town,
Karachi Water & Sewerage Board

45

COMPARATIVE STATEMENT

NAME OF WORK: EMERGENT REPAIRING OF BROKEN / SETTLED MANHOLES AT NAZIMABAD & GULBEHAR AREA IN LIAQJATABAD ZONE SEWERAGE

S.No	Description of Work	Engineer's Estimate			M/s. Gul Sawab & Co		M/s. Nawab & Co.		M/s. Sawab Noor Khan & Brothers		
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount	Rate	Amount
1	Excavation for pipe line in trenches, and pits in all kind of soils of murum i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade, cutting joint holes and disposal of surplus earth within a one chain as directed by engineer in charge, Providing fence guards, lights, flags and temporary crossing for non vehicular traffic where ever required lift up to 5 ft. (1.52m) and lead up to one chain (30.5m)	916.3	4,550.00	% 0 Cft	4,250.80	4,550.00	4,250.30	4,550.00	4,250.00	4,550.00	4,250.00
2	Full hire charges of the pumping per day inclusive of wage of driver & Assistant fuel or Electric. Energy plate from required for placing pumps e/c at lower depth with suction and delivery pipes for pumping out water found at various depths from trenches i/c the cost of erection and dismantling after completion of the job. Hire charges pumping set of up to 10 HP pumping out water from 10 ft deep trench	12	1,500.00	P/Day	13,000.00	1,450.00	15,350.00	1,500.00	18,200.00	1,500.00	21,600.00
3	Cement concrete plain i/c placing compacting finishing and curing and complete i/c screening and washing at stone aggregate ratio 1:2:4	1876.12	14,429.25	% Cft	270,710.05	14,429.25	270,710.05	14,430.00	270,724.12	14,430.00	270,724.12

Zafar Malik
ZAFAR MALIK
 Executive Engineer (SF/W)
 Liaquatabad Town,
 Karachi Water & Sewerage Board

[Signature]

[Signature]


[Signature]

[Signature]

NAME OF WORK: EMERGENT REPAIRING OF BROKEN / SETTLED MANHOLES AT NAZIMABAD & GULBEHAR AREA IN LIAQUATABAD ZONE SEWERAGE

413

S.No	Description of Work	Engineer's Estimate			M/s. Gul Sawab & Co		M/s. Nawab & Co.		M/s. Sawab Noor Khan & Brothers		
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount	Rate	Amount
4	Steel shuttering for construction of Manholes (Circular) at site i/c its erection in proper position and removal after concrete i/c transportation complete etc	192.5	Rft	99.00	19,057.50	99.00	19,057.50	100.00	19,250.00	100.00	19,250.00
5	C.I. Frame.	420	Kg	70.00	29,400.00	70.00	29,400.00	70.00	29,400.00	70.00	29,400.00
6	Refilling the excavated stuff in trenches 3" thick layer i/c watering ramming to full compaction etc complete	913.3	Cft	2,760.00	2,523.99	2,760.00	2,523.99	2,760.00	2,523.99	2,760.00	2,523.99
7	Manufacturing and supplying of 21" dia RCC Manhole cover in cast 1:2:4 concrete ratio 3" deep at centre reinforced with 1/2" dia to steel bars 4" c/c welded to 3/16" thick 2" wide M.S plat and two hook of 3/8" dia for bars i/c compacting, curing & transportation within 10 miles. 21" Dia	200	Nos	913.63	182,726.00	913	182,800	915	183,000	915	183,000
	24" Dia	50	Nos	1,051.25	52,562.50	1,050	52,500	1,055	52,750	1,055	52,750
8	Manufacturing and supplying RCC ring slabs of 21" inside diameter 36" outside diameter 7.5" width and 6" thick i/c 3/8" dia for steel bars two concentric rings with 3/8" dia 8 Nos cross linked bars welded and two sunk type hooks casted in 1:1-1/2:3 concrete with embedded 15 Kg C.I. frame in perfect position i/c transportation charges for an average lead of 20 Km per trip from casting yard to town office (A minimum of 25 slabs per trip will be transported)	100	Nos	1,905.60	190,560.00	1,905	190,500	1,910	191,000	1,910	191,000




M/s. Sawab Noor Khan & Brothers





M/s. Gul Sawab & Co



ZAFAR IQBAL
 Executive Engineer (SE W)
 Liaquatabad Town,
 Karachi Water & Sewerage Board

NAME OF WORK: EMERGENT REPAIRING OF BROKEN / SETTLED MANHOLES AT NAZIMABAD & GULBEHAR AREA IN LIAQUATABAD ZONE SEWERAGE

S.No	Description of Work	Engineer's Estimate			M/s. Gul Sawab & Co		M/s. Nawab & Co.		M/s. Sawab Noor Khan & Brothers		
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount	Rate	Amount
9	Shifting to the site and fixing of 36" dia Ring slab in perfect position on damaged Manhole i/c cutting of damaged portion in proper shape and laying of cement mortar of 2" thickness and disposal of debris.	100	Nos	563.09	Each	56309.00	560	57000	57000	570	67000
	Total Quoted / Corrected Cost					826,214.83		829,113.90			841,513.90
	Say					826,215		824,457			841,514

(Abdul Jabbar Shaikh)
Accounts Officer (Central)
Member/Secretary

(Saif-ul-Haque)
Additional Director Internal
Audit - KMC Member

(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member

(Syed Fahim Akhtar Zaidi)
Chief Engineer (Central)
Member

(Abdul Rahim Khattar)
Chief Engineer (IPD) (Convener)

(Syed Farid Malik)
Executive Engineer (SFW)
Liaquatnabad Town
Karachi Water & Sewerage Board

BIDDERS QUALIFICATION REPORT

43

Rule-46(i) (a) Single Stage One Envelope Procedure

Opening Date: 01-04-2014

Name of Work: **EMERGENT REPAIRING OF BROKEN / SETTLED MANHOLES AT NAZIMABAD & GULBEHAR AREA IN LIAQUATABAD ZONE SEWERAGE.**

Name of Bidder **M/s. Gul Sawab & Co.**


S.No	Eligibility	Yes	No
1	Relevant experience	✓	✗
2	Turnover Statement	✓	✗
3	Registration with Income Tax	✓	✗
4	Registration with Sales Tax where applicable.	—	—


Name of Bidder **M/s. Nawab & Co.**


S.No	Eligibility	Yes	No
1	Relevant experience	—	✓
2	Turnover Statement	—	✓
3	Registration with Income Tax	—	✓
4	Registration with Sales Tax where applicable.	—	—


Name of Bidder **M/s. Sawab Noor Khan & Brothers**

S.No	Eligibility	Yes	No
1	Relevant experience	—	✓
2	Turnover Statement	—	✓
3	Registration with Income Tax	—	✓
4	Registration with Sales Tax where applicable.	—	—


(Abdul Jabbar Shaikh)
Accounts Officer (Central)
Member / Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit – KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Syed Fahim Akhtar Zaidi)
Chief Engineer (Central)
Member


(Abdul Raheem Khan)
Chief Engineer (IPD)
Convener

Method of Procurement: Single Stage Single Envelope.

Name of Work: EMERGENT REPAIRING OF BROKEN / SETTLED MANHOLES AT NAZIMABAD & GULBEHAR AREA IN LIAQUATABAD ZONE SEWERAGE.

MINUTES OF BID OPENING MEETING.

A meeting of the procurement committee of this department was held on 01-04-2014 for opening the bids received in respect of subject NIT till deadlines of submission. The meeting was attended by all / following members of the procurement committee and the representative of bidders. (Attendance sheet is enclosed).

2. Three bidders submitted their bids till the deadline of submission.

- i. M/s. Gul Sawab & Co.
- ii. M/s. Nawab & Co.
- iii. M/s. Sawab Noor Khan & Brothers


3. The bids were opened at 02:30 P.M in the presence of the above mentioned participants and the rates quoted by bidders were read aloud and encircled by Chairman of the Procurement Committee.

S. No	Name of Firm	Quoted Price	Amount of Bid Security	Pay Order No. / Date
01	M/s. Gul Sawab & Co	Rs. 824,457/27	Rs.18,000/-	P.O # AAA 11135733 Dt: 26-03-2014 Allied Papoh Nagar Br
02	M/s. Nawab & Co	Rs. 829,115/33	Rs.17,000/-	P.O # AAA 11135728 Dt: 25-03-2014 Allied Papoh Nagar Br
02	M/s. Sawab Noor Khan & Brothers	Rs. 841,515/33	Rs.17,500/-	P.O # AAA 11135732 Dt: 26-03-2014 Allied Papoh Nagar Br


4. The bids do not contain any over-writing or cutting.


5. The committee shall examine all the bids as per the qualification / eligibility criteria provided in the bidding document and verify the documents and bid security submitted by the bidders (if required).

The meeting ended with the note of thanks to and from the chair.


(Abdul Jabbar Shaikh)
Accounts Officer (Central)
Member / Secretary


(Saif-ul-Maque)
Additional Director Internal
Audit - KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Syed Fahim Akhtar Zaidi)
Chief Engineer (Central)
Member


(Abdul Raheem Khattai)
Chief Engineer (IPD)
Convener



KARACHI WATER & SEWERAGE BOARD

OFFICE OF THE CHIEF ENGINEER (IP&D)

BID EVALUATION REPORT


1	Name of Procuring Agency	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No	SPPRA Serial No.19342 I.D No. /2014
3	Tender Description/Name of Work/Item	EMERGENT REPAIRING OF BROKEN / SETTLED MANHOLES AT NAZIMABAD & GULBEHAR AREA IN LIAQUATABAD ZONE SEWERAGE
4	Method of Procurement	Single Stage (One Envelop)
5	Tender Published	Through Web Site
6	Total Bid Documents Sold	03 Nos
7	Total Bid Received	03 Nos
8	Technical Bid Opening Date (if applicable)	N/A .
9	No. of Bid Technically Qualified (if applicable)	N/A .
10	Bid (s) rejected	Two
11	Financial Bid Opening Date	1/4/2014

12 Bid Evaluation Report

S #	NAME OF FIRM OR BIDDER	COST OFFERED BY THE BIDDERS	RANKING IN TERMS OF COST	COMPARISON WITH ESTIMATED COST	REASON FOR ACCEPTANCE/ REJECTION	REMARKS
1	M/s. Gul Sawab & Co	Rs. 824,457/-	1st Lowest	@ 0.2127% Below	Substantially Responsive	P.O # AAA 11135733 Dt: 26-03-2014 Rs.18,000/- Allied Papoh Nagar Br
2	M/s. Nawab & Co.	Rs. 829,114/-	2nd Lowest	@ 0.3508% Above	Un Responsive bid due to unqualified	P.O # AAA 11135728 Dt: 25-03-2014 Rs.17,000/- Allied Papoh Nagar Br
3	M/s. Sawab Noor Khan & Brothers	Rs. 841,514/-	3rd Lowest	@ 1.8517% Above	Un Responsive bid due to unqualified	P.O # AAA 11135732 Dt: 26-03-2014 Rs.17,500/- Allied Papoh Nagar Br

The all concerned bidder are being informed accordingly.

The E.E Concerned for compliance of rule 45 of SPPRA 2010 M/s. Gul Sawab & Co. declared as the lowest responsive bidder by the Committee and recommended for Sanction from Competent Authority.


(Abdul Jabbar Shaikh)
Accounts Officer (Central)
Member/Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit - KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Syed Fahim Akhtar Zaidi)
Chief Engineer (Central)
Member


(Abdul Rahim Khattai)
Chief Engineer (IPD),
(Convener)





KARACHI WATER & SEWERAGE BOARD

ATTENDANCE SHEET

FIRMS / CONTRACTORS

Name Of Work:- EMERGENT REPAIRING OF BROKEN / SETTLED
MANHOLES AT NAZIMABAD & GULBEHAR AREA IN
LIAQUATABAD ZONE SEWERAGE

Date of Opening: 01-04-2014
Time of Receiving: 02:00 P.M
Time of Opening: 03:00 PM

S.No	Name of Contractor	Name of Firms	Signature
		M/s Gul Sewab & co	
	Amir Khan	M/s Amir & co	
	Sulwab abou	M/s Sewab Noor Khan & co.	

119

COMPARATIVE STATEMENT

NAME OF WORK: EMERGENT REPAIRING OF BROKEN / SETTLED MANHOLES AT NAZIMABAD & GULBEHAR AREA IN LIAQUATABAD ZONE SEWERAGE


S.No	Description of Work	Engineer's Estimate			M/s. Gul Sawab & Co		M/s. Nawab & Co.		M/s. Sawab Noor Khan & Brothers	
		Quantity	Rate	Unit	Rate	Amount	Rate	Amount	Rate	Amount
1	Excavation for pipe line in trenches, and pits in all kind of soils of murum i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade, cutting joint holes and disposal of surplus earth within a one chain as directed by engineer in charge. Providing fence guards, lights, flags and temporary crossing for non vehicular traffic where ever required lift up to 5 ft. (1.52m) and lead up to one chain (30.5m)	916.3	Cft	4,650.00	% 0 Cft	4,260.80	4,650.00	4,260.80	4,650.00	4,260.80
2	Full hire charges of the pumping per day inclusive of wage of driver & Assistant, fuel or Electric. Energy plate from required for placing pumps etc. at lower depth with suction and delivery pipes for pumping out water found at various depths from trenches i/c the cost of erection and dismantling after completion of the job. Hire charges pumping set of up to 10 HP pumping out water from 10 ft deep trench	12	Day	1,500.00	P/Day	18,000.00	1,400.00	16,800.00	1,600.00	19,200.00
3	Cement concrete plain i/c placing compacting finishing and curing and complete i/c screening and washing aggregate ratio 1:2:4	1876.12	Cft	14,429.25	% Cft	270,710.05	14,429.25	270,710.05	14,430.00	270,724.12
						270,710.05	14,430.00	270,724.12	14,430.00	270,724.12


Handwritten signatures and initials are present on the right side of the page, including a large signature and the initials 'MB'.


(98)

NAME OF WORK: EMERGENT REPAIRING OF BROKEN / SETTLED MANHOLES AT NAZIMABAD & GULBEHAR AREA IN LIAQUATABAD ZONE SEWERAGE

S.No	Description of Work	Engineer's Estimate			M/s. Gul Sawab & Co		M/s. Nawab & Co.		M/s. Sawab Noor Khan & Brothers		
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount	Rate	Amount
4	Steel shuttering for construction of Manholes (Circular) at site i/c its erection in proper position and removal after concrete i/c transportation complete etc	192.5	99.00	P/Rft	19,057.50	99.00	19,057.50	100.00	19,250.00	100.00	19,250.00
5	C.I.Frame.	420	70.00	P/Kg	29,400.00	70.00	29,400.00	70.00	29,400.00	70.00	29,400.00
6	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc. complete	916.3	2,760.00	% 0 Cft	2,528.99	2,760.00	2,528.99	2,760.00	2,528.99	2,760.00	2,528.99
7	Manufacturing and supplying of 21" dia RCC Manhole cover in cast 1:2:4 concrete ratio 3" deep at centre reinforced with 1/2" dia to steel bars 4" c/c welded to 3/16" thick 2" wide M.S plat and two hook of 3/8" dia tor bars i/c compacting, curing & transportation within 10 miles. 21" Dia	200	913.63	Nos	182,726.00	913	182,600	915	183,000	915	183,000
		50	1,051.25	Nos	52,562.50	1050	52,500	1055	52,750	1055	52,750
8	Manufacturing and supplying RCC ring slabs of 21" inside diameter 36" outside diameter 7.5" width and 6" thick i/c 3/8" dia tor steel bars two concentric rings with 3/8" dia 8 Nos. cross linked bars welded and two sunk type hooks casted in 1:1-1/2:3 concrete with embedded 15 Kg C.I frame in perfect position i/c transportation charges for an average lead of 20 Km per trip from casting yard to town office (A minimum of 25 slabs per trip will be transported)	100	1,906.60	Each	190,660.00	1906	190,600	1910	191,000	1910	191,000











NAME OF WORK: EMERGENT REPAIRING OF BROKEN / SETTLED MANHOLES AT NAZIMABAD & GULBEHAR AREA IN LIAQUATABAD ZONE SEWERAGE


S.No	Description of Work	Engineer's Estimate			M/s. Gul Sawab & Co		M/s. Nawab & Co.		M/s. Sawab Noor Khan & Brothers	
		Quantity	Rate	Unit	Rate	Amount	Rate	Amount	Rate	Amount
9	Shifting to the site and fixing of 36" dia Ring slab in perfect position on damaged Manhole i/c cutting of damaged portion in proper shape and laying of cement mortar of 2" thickness and disposal of debris.	100	563.09	Each	560	56000	570	57000	670	67000
	Total Quoted / Corrected Cost					824,457.33		829,113.90		841,513.90
	Say					824,457		829,114		841,514


 (Abdul Jabbar Shaikh)
 Accounts Officer Central
 Member/Secretary


 (Saif-ul-Haque)
 Additional Director Internal
 Audit - KMC Member


 (Maqsood Ahmed Shaikh)
 Superintending Engineer (KMC)
 Member


 (Syed Fahim Akhtar Zaidi)
 Chief Engineer (Central)
 Member


 (Abdul Rahim Khattar)
 Chief Engineer (IPD) (Govt. Member)