



SHAHEED BENAZIR BHUTTO HOUSING CELL



M-01, Beaumont Plaza,
Behind PIDC House, Karachi
Phone No. 9204178-9- Fax 5680117

LETTER OF COMMENCEMENT

No. BHC/DIR-T/F-43B/2012/3139-A
Karachi dt. 29th May, 2012

To,

M/s Kazmi Construction Company- Al-Dost Constructors. (JV)

CONTRACT PRICE (234.633) MILLION

Subject: **INFRASTRUCTURE DEVELOPMENT WORKS INCLUDING WATER SUPPLY, SEWERAGE, DRAINAGE AND ROADS OF BENAZIR COLONY AT DEH LUQMAN KHAIRPUR, SINDH.**


This has reference to this office Bid acceptance, letter no. SBBHC/DIR-T/F-43B/2012/3123 Dt. 11th May 2012. You are required to please commence the work within Fourteen Days (14) from the date of issue of this letter and complete the same within stipulated time as defined in bidding documents.

In case you failed to commence the work within (14) fourteen days from the date of issue of this letter, necessary action under the relevant clauses of the contract agreement shall be initiated against you.


(SYED MANZAR ABBAS)
CHAIRMAN-BHC

C.C.

- M/s Osmani & Company for taking further appropriate steps for commencing of work at site
- P.S to Minister Housing
- Deputy Director Engineering-BHC
- Office Record-BHC



Kazmi Const Co. JV Al-Dost Constructors.
 National Identity Card No. 42501-1426 735-9-
 V.P. No. 16 District 18 Sindh
 on Exhibit in Opation 112/09 Dated 18/5/12
 E. No. 16 Dated 18/5/12

[Signature]
 18/5/12

CONTRACT AGREEMENT

THIS CONTRACT AGREEMENT (hereinafter called the "Agreement") made on the Tuesday 22nd of May 2012 between Shaheed Benazir Bhutto Housing Cell (hereafter called the "Employer") of the one part and Kazmi Construction Company (JV) Al Dost Constructors (hereafter called the "Contractor") of the other part.

WHEREAS the Employer is desirous that certain Works, viz INFRASTRUCTURE DEVELOPMENT INCLUDING WATER SUPPLY, SEWERAGE AND ROADS OF BENAZIR COLONY AT DEH LUQMAN, KHAIRPUR SINDH, should be executed by the Contractor and has accepted a Bid by the Contractor for the execution and completion of such Works and the remedying of any defects therein.


NOW, this Agreement witnesses as follows:

1. In this Agreement words and expressions shall have the same meanings as are respectively assigned to them in the Conditions of Contract hereinafter referred to.
2. The following documents after incorporating addenda / Clarification as agreed or otherwise, if any, except those parts relating to Instructions to Bidders shall be deemed to form and be read and construed as part of this Contract, viz:
 - a) The Contract Agreement (If Completed)
 - b) The Letter of Acceptance;
 - c) The complete Form of Bid;

JOINT VENTURE

Kazmi Const Co., Al-Dost Constructors

[Signature] A. Sami

**STAMP OFFICE CITY COURTS KARACHI**issued to Kazmi Construction Co. Pvt. Ltd. Constructer.M.C. / Company Card No. 92501-1436735-2.M.C. D.S.R. No. 6 dated 15/12/12in Behalf of Challan No. 4 dated 15/12/12S. No. 6 dated 15/12/12


(Signature)
15/12/12

- d) Special Stipulations (Appendix-A to Bid);
 - e) The particular Conditions of Contract – Part II;
 - f) The General Conditions – Part I;
 - g) The priced Bill of Quantities (Appendix-D to Bid)
 - h) The completed Appendices to Bid (B,C,E to O)
 - i) The drawings;
 - j) Specifications – Technical Provisions
 - k) Addendum "A" (any other)
3. In, consideration of the payments to be made by the Employers to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the Employer to execute and complete the Works and remedy defects therein conformity and in all respects with the provisions of the Contract.
4. The Employer hereby covenants to pay the Contractor, in consideration of the execution and completion of the Works as per provisions of the Contract, the Contract Price or such other sum as may become payable under the provisions of the Contract at the times and in the manner prescribed by the Contract.

JOINT VENTURE

Kazmi Const Co., At-Dost Constructors

(Signature)
A. Samad



GRAND BAZAR CITY COURTS KARACHI

Contractor: Kazmi Const. Co. J/v AL-Dost Constructors
 P.O. / Company Cert. No. 42501-1936735-9
 W.P.D. No. 16 dated 15/5/12
 Certificate of Completion No. 204 dated 16/5/12
 B. No. 11 dated 15/5/12

[Handwritten signature]

IN WITNESS WHEREOF the parties hereto have caused this Agreement to be executed on the day, month year first before written in accordance with their respective laws.

Signature of the Contractor

Signature of Employer

[Handwritten signature]

(Seal) **JOINT VENTURE**

Kazmi Const Co., AL-Dost Constructors

[Handwritten signatures]
 A. Samad

(Seal)

Signed, Sealed and Delivered in the presence of:

Witness:


[Handwritten signature]
Ashique Ali

(Name, Title and Address)

Witness

[Handwritten signature]
M. Shajiq Begum

(Name, Title and Address)



OFFICE CITY COURTS KARACHI

and to (Name) Amt. to J/V Al-Dost Contractor


Company Card No. 42501-1424735-9


D.S.R. No. 16 Dated 18/11/11

Behalf of Challan No. 204 Dated 18/11/11

No. 16 Dated 18/11/11

City Courts Karachi
18/11/11





STATE ENGINE CITY COURTS KARACHI


Issued to Kamari Const. Co. JV AL-Dost Contractors


HC / Company Card No. 42501-1436735-S


Under D.S.P. No. 16 Dated 15/5/52

On Behalf of Chattan Waley Dated 18/5/52

Sl. No. 16 Dated 15/5/52


15/5/52







STAMP OFFICE CITY COURTS KARACHI

Issued to Khazmi Const- Co. J/V At-Dost Constructn.
 NIC/ Company Card No. 42501-1436725-5.
 Vite D.S.R. No. 16 Dated 18.5.72
 on Behalf of Challan No. 204 Dated 18.5.72
 E. No. 16 Dated 18.5.72


[Handwritten signature]
18/5/72






Khanji Construction Co S/V Al-Dast Contractor
 Company Card No. 92501-143673T-P
 No. 16 Dated 18/5/12
 Serial of Cheque No. 204 Dated 18/5/12
 No. 16 Dated 18/5/12

[Handwritten Signature]
 18/5/12





STATE OFFICE CITY COURTS KARACHI

Case No. Khairi, Govt. Co. S/N 91- Dist. Contractor.

Company Card No. 42501-14 86735-5.


Dist. C.R. No. 16 Dated 18/5/72

Dist. C.R. No. 204 Dated 18/5/72

No. 16 Dated 18/5/72

Sec. Office of Justice
18/5/72





STATE CITY COURTS KARACHI

Case No. Gazmi Cont 6. J/v At-Dost Constructw.


Company Card No. 42501-1436735-9


Order No. 16 Dated 15/6/11

Challan No. 204 Dated 15/6/11

Ex. No. 16 Dated 15/6/11

Dr. J. I. Khan
 15/6/11





STAMPED BY ICE CITY COURTS KARACHI

Issued to Karmi Const. Co. J/V Al-Dast Construction


NIC / Company Card No. 42501-1436935-9

Vide D.S.R. No. 16 Dated 18/5/72

on Behalf of Challan No. 24 Dated 18/5/72

E. No. 16 Dated 18/5/72

Signature
 18/5/72



PAK OFFICE CITY COURTS KARACHI

Issued to Karim Anot. & S/V AL-Dost Contractor.

C/Company Card No. 42501-1434735-9.


Ch. D.S.P. No. 16 Dated 15/5/72

Receipt of Challan No. 204 Dated 15/5/72

No. 16 Dated 15/5/72

(Signature)
 15/5/72





LAND OFFICE CITY COURTS KARACHI

Issued to KAZMI Const. Co. S/o AL-DOST Construct.


Company Card No. 42501-1426735-5.

To D.S.R. No. 16 Dated 15/5/12

Behalf of Chaitan No. 204 Dated 15/5/12

No. 16 Dated 15/5/12

Office Vendor
12/5/12



TAMP OFFICE CITY COURTS KARACHI

Used to: Kazmi Enforcement & S/v Al-Dast Contractor.


C / Company Card No. 42801-1436785-5.

No. S.R. No. 16 Date 15/5/11

Rehall of Challan No. 204 Dated 15/5/11

No. 16 Dated 15/5/11

[Signature]
15/5/11



STAMP OFFICE CITY COURTS KARACHI


Issued to Kazmi Const. Co. J/v Al-Dast Constructr


M/C/ Company Card No. 42501-1434735-9.

File D.S.R. No. 16 Dated 18/5/74

In Behalf of Challan No. 204 Dated 18/5/74

No. 16 Dated 18/5/74


 18/5/74



CHIEF OFFICE CITY COURTS KARACHI

Drawn to: Kazmi Const. Co. Pvt. Ltd. Constructr -


MC. Agency Car. No. 42501-1436735-3


Vol. D.S. No. 16 Dated 18/8/72

on Behalf of Shri. P. S. D. S. D. Dated 18/8/72

P. No. 16 Dated 18/8/72

E. H. Khan
18/8/72





STAMP OFFICE CITY COURTS KARACHI

Issued to Karim, Const. & J/V Al-Dast Constructor.


VIC / Company Card No. 42501-1436735-2

vide D.S.R. No. 16 Dated 15/8/12

in Behalf of Challan No. 204 Dated 15/8/12

R. No. 16 Dated 15/8/12

Encl. Officer Karachi
15/8/12



BILL OF QUANTITIES

A. Preamble

1. The Bill of Quantities shall be read in conjunction with the Conditions of Contract, Specifications and Drawings.
2. The quantities given in the Bill of Quantities are estimated and provisional, and are given to provide a common basis for bidding. The basis of payment will be the actual quantities of work executed and measured by the Contractor and verified by the Engineer and valued at the rates and prices entered in the priced Bill of Quantities, where applicable, and otherwise at such rates and prices as the Engineer may fix in accordance with provisions of the Contract.
3. The rates and prices entered in the priced Bill of Quantities shall, except insofar as it is otherwise provided under the Contract include all costs of Contractor's plant, labour, supervision, materials, execution, insurance, profit, taxes and duties, together with all general risks, liabilities and obligations set out or implied in the Contract. Furthermore all duties, taxes and other levies payable by the Contractor under the Contract, or for any other cause, as on the date 28 days prior to deadline for submission of Bids, shall be included in the rates and prices and the total Bid Price submitted by the Bidder.
4. A rate or price shall be entered against each item in the priced Bill of Quantities, whether quantities are stated or not. The cost of items against which the Contractor will have failed to enter a rate or price shall be deemed to be covered by other rates and prices entered in the Bill of Quantities.
5. The whole cost of complying with the provisions of the Contract shall be included in the items provided in the priced Bill of Quantities, and where no items are provided, the cost shall be deemed to be distributed among the rates and prices entered for the related items of the Works.
6. General directions and description of work and materials are not necessarily repeated nor summarised in the Bill of Quantities. References to the relevant sections of the Bidding Documents shall be made before entering prices against each item in the priced Bill of Quantities.
7. Provisional sums included and so designated in the Bill of Quantities shall be expended in whole or in part at the direction and discretion of the Engineer in accordance with Sub-Clause 58.2 of Part I, General Conditions of Contract.

JOINT VENTURE
Osmani & Co. (Pvt.) Ltd. & M. Mostafa & Co.

BILL OF QUANTITIES
GRAND SUMMARY

Client / Owner : Shaheed Benazir Bhutto Housing Cell, Government of Sindh
 Name Of Project : Infrastructure Development i/c. Water Supply, Sewerage, Drainage and Roads of Benazir Colony at Deh Luqman, Khairpur, Sindh
 Location : Khairpur, Sindh
 Contract No. : BCK-001

Sr. No.	Particulars	Amount (Rs.)
1	Construction of Roads & Storm Water Drain	193,168,179
2	Laying of Water Supply Network	86,064,86
3	Laying of Sewer lines	63,354,140
265,128,805 Sub Total Rs.		265,132,967.00
Add: Provisional Sum Rs.		10,000,000
275,128,805 Grand Total Rs.		275,132,967.00

(Rupees Two hundred seventy five million One hundred thirty two thousand nine hundred sixty seven only. In Words)

JOINT VENTURE
Nazmi Const Co., Al-Dest Constructors

Contractor

Excluding Provisional Sum of Rs. 10 million

Sub Total Rs. 265,128,805/-
 Net off 30,489,83/-
 Rebate 11.5% Rs. 30,490,291/-

Rs. 2,34,64,267.00

2/14 10,000,000/-

Two hundred thirty four million six hundred forty-two thousand six hundred seventy six only.

Abdul

Handwritten signatures and stamps, including a circular stamp with text and a date 2/14/11.

CONSTRUCTION OF ROADS &
STORM WATER DRAINS

JOINT VENTURE
K&L Const Co., AL-Duct Construction

BILL OF QUANTITIES SUMMARY - ROAD WORKS

Client / Owner : Shaheed Benazir Bhutto Housing Cell, Government of Sindh
Name Of Project : Infrastructure Development i/c. Water Supply, Sewerage, Drainage and Roads of
Benazir Colony at Deh Luqman, Khairpur, Sindh
Location : Khairpur, Sindh
Contract No. : BCK-001

Sr. No.	Particulars	Amount (Rs.)
1	Construction of 25' Wide Road alongwith SW Drain	98,905,252
2	Construction of 30' Wide Road alongwith SW Drain	37,261,035
3	Construction of 40' Wide Road alongwith SW Drain	57,001,892
Total of Road & SW Drain Works Rs.		1,93,166,179

Amount in Rupees One hundred ninety three million One hundred Sixty Eight thousand One hundred Seventy nine only
In Words

JOINT VENTURE
Kazim Const Co., AL-Dost Constructors

Contractor

JOINT VENTURE
Kazim Const Co., AL-Dost Constructors

CONSTRUCTION OF 25FT WIDE
ROAD

APPROVED
DATE

11

BILL OF QUANTITIES

Client / Owner : Shahèed Benazir Bhutto Housing Cell, Government of Sindh
Name Of Project : Infrastructure Development i/c. Water Supply, Sewerage, Drainage and Roads of Benazir Colony at Deh Luqman, Khairpur, Sindh
Job-Head : Construction of Road - 25ft Wide
Location : Khairpur, Sindh
Contract No. : BKC-001

Sr. No.	Particulars	Amount (Rs.)
1	Construction of 25' Wide Road	84,776,751-00
2	Storm Water Drain along Road	14,128,501-00
Total Amount of 25' wide Road Rs.		98,905,252-00

Amount in Rupees Eighty eight million nine hundred five thousand two hundred fifty two only
In Words

JOINT VENTURE
Kazmi Const. Co., AL-Dost Constructors

Contractor

JOINT VENTURE
Kazmi Const. Co., AL-Dost Constructors

5

BILL OF QUANTITIES

Client / Owner : Shaheed Benazir Bhutto Housing Cell, Government of Sindh
 Name Of Project : Infrastructure Development i/c. Water Supply, Sewerage, Drainage and Roads of Benazir Colony at Deh Luqman, Khairpur, Sindh
 Job-Head : Construction of Road - 25ft Wide
 Location : Khairpur, Sindh
 Contract No. : BKC-001

Sl. No.	Particulars	Qty.	Unit	Rate (Rs)		Amount (Rs.)
				In Figure	In Words	
Road Work						
1	Natural Ground Compaction upto an average depth of 6", by sheep-foot roller and power roller with optimum moisture content to achieve minimum 90% modified A.A.S.H.T.O. density.	765,322	Sft.	1/5	One.	765,322
2	Earth work for embankment from borrow pits including laying in 6 inch layers, clod breaking, ramming, dressing & compaction by sheep foot / power roller with optimum moisture content to 95-100% of modified A.A.S.H.T.O dry density complete, upto an average lead of 5 miles and lift upto 5ft (Rate deemed to include Preparation of Sub grade to proper Camber & Grade).	1,820,093	Cft.	17/5	Seventeen	30941581
3	Earth work excavation upto required level in ordinary soil and using the excavated earth in embankment including all lift and 1000ft lead (Avg.), dressing, leveling of earth to design section and location, compaction by sheep-foot / power roller with optimum moisture content to a minimum 95% of modified A.A.S.H.T.O. dry density complete as per the instructions of the Engineer. (Surplus unsuitable earth to be disposed off within 1000ft lead as per the directions of the Engineer).	40,596	Cft.	9/5	Nine	365,364
4	Preparing sub-grade including earth excavation or filling to an average depth of 9 inches dressing to camber and consolidation with power roller. (In cut areas only).	46,177	Sft.	1/5	One.	46,177
5	Laying burnt brick on end edging including supplying 9"X4-1/2"X 3" first class burnt bricks, excavation for having edging with small size parallel to the road complete as per the instructions of the Engineer.	24,677	Rft.	35/5	Thirty five.	863,695
6	Providing, laying and spreading in layers not more than 6 inches loose thickness graded granular sub-base material upto any thickness in sub-base course in required grade and camber and compacted to the required density by approved mechanical means (vibratory roller, road packer and smooth wheel rollers, etc) as per design and specifications including watering, including all lead and lift, etc complete (actual compacted depth shall be considered for payment.)	340,159	Cft.	48/5	Forty eight.	16327632

JOINT VENTURE
 Kazim Const Co., Al-Dost Constructors

No.	Particulars	Qty.	Unit	Rate (Rs)		Amount (Rs.)
				In Figure	In Words	
7.	Preparing Base Course i/c supplying and spreading stone metal of approved quality properly graded maximum size of 1-1/2" in required thickness to proper camber and grade i/c supplying and spreading 15 Cft: screenings and non plastic quarry fines, filling depressions with stone metal after initial rolling including watering and compaction the same so as to achieve 100% density as per modified A.A.S.H.T.O specifications. (Total compacted thickness 9" in two layers 4-1/2" each) compacted thickness will be considered for payment.	297,594	Cft.	55/-	fifty five.	16,367,670.
8.	Providing 3 coat surface treatment (T.S.T) in new or existing surface with 25 lbs bitumen and 2.75cft crushed bajri 1/2" and down gauge in 1st coat, 25 lbs bitumen and 2.75 cft crushed bajri 3/8" size and down gauge in 2nd coat and 18lbs of bitumen and 1.5 cft crushed bajri 1/4" size in 3rd coat with including cleaning the road surface before applying bitumen and rolling after spreading crushed bajri (uniformly) in each coat.	444,170	Sft.	43/-	forty three	19,099,310.
Total of Road Rs.						84,976,751.

Rupees Eighty Four million seven hundred seventy six thousand seven hundred fifty one only. (In Words)

JOINT VENTURE
Kazmi Const. Co., Al-Dosa Constructors
CONTRACTOR

JOINT VENTURE
Kazmi Const. Co., Al-Dosa Constructors

BILL OF QUANTITIES

/ Owner : Shaheed Benazir Bhutto Housing Cell, Government of Sindh
 Of Project : Infrastructure Development i/c. Water Supply, Sewerage, Drainage and Roads of Benazir Colony at Deh Luqman, Khairpur, Sindh
 Head : Construction of Road - SW Drain along 25ft Wide
 Location : Khairpur, Sindh
 Contract No. : BKC-001

Particulars	Qty.	Unit	Rate (Rs)		Amount (Rs.)
			In Figure	In Words	
STORM WATER DRAIN					
Excavation in foundation of building, bridges and other structures including dagbelling dressing refilling around structure with excavated earth watering and ramming lead upto 5ft.	17,766	Cft.	1/-	One.	17,766.00
Pacca brick work in foundation and plinth in (1:3 cement sand mortar).	97,470	Cft.	20/3	Twenty	1,949,400.00
Cement concrete plain including placing, compacting, finishing and curing, complete (including screening and washing of stone aggregate without shuttering). Ratio 1:2:4	3,208	Cft.	120/5	One hundred Twenty	384,960.00
Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rates also includes all kind of form moulds; lifting shuttering curing rendering and finishing the exposed surface, complete (including screening and washing of stone aggregate). Ration 1:1 1/2:3 (Perforated Hole 3" Dia @ 6" Spacing.)	30,845	Cft.	195/5	One Hundred ninety Five	6,014,775.00
Fabrication of mild steel reinforcement for cement concrete including cutting, bending, laying in position. Making joints and fastenings including cost of binding wire (also includes removal of rust from bars).	1,377	Cwt	3000/5	Three thousand	41,310.00
Cement pointing struks joints on walls. (Ratio 1:3)	117,459	Sft.	5/5	Five	587,295.00
Bitumen coating to plastered or or cement concrete surface	117,459	Sft.	3/5	Three	352,377.00
Cement plaster 1:3 upto 20' height (1/2" thick)	98,704	Sft.	7/5	Seven	690,928.00
Total of Storm Water Drain Rs.					14,128,501.00

Rupees FOURTEEN Million One hundred Twenty eight thousand Five hundred One Only
 (In Words)

JOINT VENTURE
 Contractors
 CONTRACTOR

JOINT VENTURE
 Kazim Const Co., Al-Dost Contractors

CONSTRUCTION OF 30FT WIDE
ROAD

JOINT VENTURE
Kazmi Const Co., Al-Dost Constructors

BILL OF QUANTITIES

Client / Owner : Sifaheed Benazir Bhutto Housing Cell, Government of Sindh
Name Of Project : Infrastructure Development i/c. Water Supply, Sewerage, Drainage and Roads of Benazir Colony at Deh Luqman, Khairpur, Sindh
Project Head : Construction of Road - 30ft Wide
Location : Khairpur, Sindh
Contract No. : BCK-001

Sr. No.	Particulars	Amount (Rs.)
1	Construction of 30' Wide Road	32,171,039.00
2	Storm Water Drain along Road	5,089,996.00
Total Amount of 30' wide Road Rs.		37,261,035.00

Words Thirty Seven million two hundred seventy one thousand thirty five only
In Words

Kazmi
JOINT VENTURE
Constructors

JOINT VENTURE
Kazmi Const Co., AL-Dost Constructors

Contractor

BILL OF QUANTITIES

Client / Owner : Shaheed Benazir Bhutto Housing Cell, Government of Sindh
 Name Of Project : Infrastructure Development i/c. Water Supply, Sewerage, Drainage and Roads of Benazir Colony at Deh
 Location : Luqman, Khairpur, Sindh
 Job-Head : Construction of Road - 30ft Wide
 Location : Khairpur, Sindh
 Contract No. : BCK-001

Particulars	Qty.	Unit	Rate (Rs)		Amount (Rs.)
			In Figure	In Words	
Road Work					
Natural Ground Compaction upto an average depth of 6", by sheep-foot roller and power roller with optimum moisture content to achieve minimum 90% modified A.A.S.H.T.O. density.	329,968	Sft.	1/-	One	329,968.00
Earth work for embankment from borrow pits including laying in 6 inch layers, clod breaking, ramming, dressing & compaction by sheep foot / power roller with optimum moisture content to 95-100% of modified A.A.S.H.T.O dry density complete, upto an average lead of 5 miles and lift upto 5ft (Rate deemed to include Preparation of Sub grade to proper Camber & Grade).	654,837	Cft.	17/-	Seventeen	11,132,229.00
Earth work excavation upto required level in ordinary soil and using the excavated earth in embankment including all lift and 1000ft lead (Avg.), dressing, leveling of earth to design section and location, compaction by sheep-foot / power roller with optimum moisture content to a minimum 95% of modified A.A.S.H.T.O. dry density complete as per the instructions of the Engineer. (Surplus unsuitable earth to be disposed off within 1000ft lead as per the directions of the Engineer).	9,902	Cft.	9/-	nine	89,118.00
Preparing sub-grade including earth excavation or filling to an average depth of 9 inches dressing to camber and consolidation with power roller. (In cut areas only).	12,759	Sft.	1/-	One	12,759.00
Laying burnt brick on end edging including supplying 9"X4-1/2"X 3" first class burnt bricks, excavation for having edging with small size parallel to the road complete as per the instructions of the Engineer.	8,883	Rft.	35/-	Thirty Five	310,905.00
Providing, laying and spreading in layers not more than 6 inches loose thickness graded granular sub-base material upto any thickness in sub-base course in required grade and camber and compacted to the required density by approved mechanical means (vibratory roller, road packer and smooth wheel rollers, etc) as per design and specifications including watering, including all lead and lift, etc complete (actual compacted depth shall be considered for payment.)	135,776	Cft.	45/-	Forty Five	6,109,920.00

JOINT VENTURE
 Kazim Const Co., AL-Dest Contractors

Particulars	Qty.	Unit	Rate (Rs)		Amount (Rs.)
			In Figure	In Words	
Preparing Base Course i/c supplying and spreading stone metal of approved quality properly graded maximum size of 1-1/2" in required thickness to proper camber and grade i/c supplying and spreading 15 Cft: screenings and non plastic quarry fines, filling depressions with stone metal after initial rolling including watering and compaction the same so as to achieve 100% density as per modified A.A.S.H.T.O specifications. (Total compacted thickness 9" in two layers 4-1/2" each) compacted thickness will be considered for payment.	119,032	Cft.	55/-	fifty five	6,546,760
Providing 3 coat surface treatment (T.S.T) in new or existing surface with 25 lbs bitumen and 2.75cft crushed bajri 1/2" and down gauge in 1st coat, 25 lbs bitumen and 2.75 cft crushed bajri 3/8" size and down gauge in 2nd coat and 18lbs of bitumen and 1.5 cft crushed bajri 1/4" size in 3rd coat with including cleaning the road surface before applying bitumen and rolling after spreading crushed bajri (uniformly) in each coat.	177,660	Sft.	43/-	forty three	7,639,380
Total of Road Rs.					32,171,039

pees Thirty two million One hundred Seventy One thousand thirty nine only
(In Words)

JOINT VENTURE
Kazmi Const Co., AL-Dosri Constructors
CONTRACTOR

JOINT VENTURE
Kazmi Const Co., AL-Dosri Constructors

BILL OF QUANTITIES

Owner : Shaheed Benazir Bhutto Housing Cell, Government of Sindh
 Of Project : Infrastructure Development i/c. Water Supply, Sewerage, Drainage and Roads of Benazir Colony at Deh
 Luqman, Khairpur, Sindh
 Head : Construction of Road - SW Drain along 30ft Wide
 Location : Khairpur, Sindh
 Contract No. : BCK-001

Particulars	Qty..	Unit	Rate (Rs)		Amount (Rs.)
			In Figure	In Words	
STORM WATER DRAIN					
Excavation in foundation of building, bridges and other structures including dagbelling dressing refilling around structure with excavated earth watering and ramming lead upto 5ft.	6,395	Cft.	1/-	One	6,395.00
Pacca brick work in foundation and plinth in (1:3 cement sand mortar).	35,087	Cft.	20/-	Twenty	7,01,740.00
Cement concrete plain including placing, compacting, finishing and curing, complete (including screening and washing of stone aggregate without shuttering). Ratio 1:2:4	1,155	Cft.	120/-	{One hundred} {Twenty}	1,38,600.00
Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rates also includes all kind of form moulds: lifting shuttering curing rendering and finishing the exposed surface, complete (including screening and washing of stone aggregate). Ration 1:1 1/2:3 (Perforated Hole 3" Dia @ 6" Spacing.)	11,104	Cft.	195/-	{One hundred} {Ninety Five}	2,16,52,80.00
Fabrication of mild steel reinforcement for cement concrete including cutting, bending, laying in position. Making joints and fastenings including cost of binding wire (also includes removal of rust from bars).	497	Cwt	3000/-	{Three thousand} {Only}	14,91,000.00
Cement pointing struks joints on walls. (Ratio 1:3)	42,283	Sft.	5/-	Five	2,11,415.00
Bitumen coating to plastered or or cement concrete surface	42,283	Sft.	3/-	Three	1,26,849.00
Cement plaster 1:3 upto 20' height (1/2" thick)	35,531	Sft.	7/-	Seven	2,48,717.00
Total of Storm Water Drain Rs.					5,08,996.00

pees Five million Eighty nine thousand nine hundred ninety six Only
 (In Words)

JOINT VENTURE
 Kazmi Const Co., AL-Dost Constructors
 CONTRACTOR

JOINT VENTURE
 Kazmi Const Co., AL-Dost Constructors

CONSTRUCTION OF 40FT WIDE
ROAD

JOINT VENTURE
Kazmi Const Co., Al-Dost Constructors

BILL OF QUANTITIES

Client / Owner : Shaheed Benazir Bhutto Housing Cell, Government of Sindh
Name Of Project : Infrastructure Development i/c. Water Supply, Sewerage, Drainage and Roads of
Benazir Colony at Deh Luqman, Khairpur, Sindh
Project-Head : Construction of Road - 40ft Wide
Location : Khairpur, Sindh
Contract No. : BCK-001

Sr. No.	Particulars	Amount (Rs.)
1	Construction of 40' Wide Road	46,028,500
2	Storm Water Drain along Road	10,973,392
Total Amount of 40' wide Road Rs.		57,001,892

Words Fifty seven million one thousand eight hundred ninety two
- only -
In Words

JOINT VENTURE
Kazmi Const Co., AL-Dost Constructors

Contractor

BILL OF QUANTITIES

Client / Owner : Shaheed Benazir Bhutto Housing Cell, Government of Sindh
 Name Of Project : Infrastructure Development i/c. Water Supply, Sewerage, Drainage and Roads of Benazir Colony at Delh
 Luqman, Khairpur, Sindh
 Sub-Head : Construction of Road - 40ft Wide
 Location : Khairpur, Sindh
 Contract No. : BCK-001

Sr. No.	Particulars	Qty.	Unit	Rate (Rs)		Amount (Rs.)
				In Figure	In Words	
A. Road Work						
1	Natural Ground Compaction upto an average depth of 6", by sheep-foot roller and power roller with optimum moisture content to achieve minimum 90% modified A.A.S.H.T.O. density.	388,488	Sft.	1/=-	One	388,488.00
2	Earth work for embankment from borrow pits including laying in 6 inch layers, clod breaking, ramming, dressing & compaction by sheep foot / power roller with optimum moisture content to 95-100% of modified A.A.S.H.T.O dry density complete, upto an average lead of 5 miles and lift upto 5ft (Rate deemed to include Preparation of Sub grade to proper Camber & Grade).	1,132,922	Cft.	17/0	Seventeen	19,259,676.00
3	Earth work excavation upto required level in ordinary soil and using the excavated earth in embankment including all lift and 1000ft lead (Avg.), dressing, leveling of earth to design section and location, compaction by sheep-foot / power roller with optimum moisture content to a minimum 95% of modified A.A.S.H.T.O. dry density complete as per the instructions of the Engineer. (Surplus unsuitable earth to be disposed off within 1000ft lead -as per the	70,742	Cft.	9/=-	nine	6,36,678.00
4	Preparing sub-grade including earth excavation or filling to an average depth of 9 inches dressing to camber and consolidation with power roller. (In cut areas only).	36,452	Sft.	1/=-	One	36,452.00
5	Providing, laying and spreading in layers not more than 6 inches loose thickness graded granular sub-base material upto any thickness in sub-base course in required grade and camber and compacted to the required density by approved mechanical means (vibratory roller, road packer and smooth wheel rollers, etc) as per design and specifications including watering, including all lead and lift, etc complete (actual compacted depth shall be considered for payment.)	169,722	Cft.	45/=-	Forty Five	7,63,749.00
6	Preparing Base Course i/c supplying and spreading stone metal of approved quality properly graded maximum size of 1-1/2" in required thickness to proper camber and grade i/c supplying and spreading 15 Cft. screenings and non plastic quarry fines, filling depressions with stone metal after initial rolling including watering and compaction the same so as to achieve 100% density as per modified A.A.S.H.T.O specifications. (Total compacted thickness 9" in two layers 4-1/2", each) compacted thickness will be considered for payment.	151,618	Cft.	55/2	Fifty Five	8,338,990.00

JOINT VENTURE
 Kazi Const Co. Al-Dest Contractors

Sr. No.	Particulars	Qty.	Unit	Rate (Rs)		Amount (Rs.)
				In Figure	In Words	
7	Providing 3 coat surface treatment (T.S.T) in new or existing surface with 25 lbs bitumen and 2.75cft crushed bajri 1/2" and down gauge in 1st coat, 25 lbs bitumen and 2.75 cft crushed bajri 3/8" size and down gauge in 2nd coat and 18lbs of bitumen and 1.5 cft crushed bajri 1/4" size in 3rd coat with including cleaning the road surface before applying bitumen and rolling after spreading crushed bajri (uniformly) in each coat.	226,296	Sft.	43/2	forty three	9730728
Total of Road Rs.						46028500

Rupees forty six million twenty eight thousand five hundred only
 (In Words)

CONTRACTOR

JOINT VENTURE
 Kazmi Const Co., AL-Dost Constructors

BILL OF QUANTITIES

Owner : Shaheed Benazir Bhutto Housing Cell, Government of Sindh
 Of Project : Infrastructure Development i/c. Water Supply, Sewerage, Drainage and Roads of Benazir Colony at Deh Luqman, Khairpur, Sindh
 Head : Construction of Road - SW Drain along 40ft Wide
 Location : Khairpur, Sindh
 Contract No. : BCK-001

Particulars	Qty.	Unit	Rate (Rs)		Amount (Rs.)
			In Figure	In Words	
FORM WATER DRAIN					
Excavation in foundation of building, bridges and other structures including dagbelling dressing refilling around structure with excavated earth watering and ramming lead upto 5ft.	6,788	Cft.	1/-	One	6,788.00
Pacca brick work in foundation and plinth in: (1:3 cement sand mortar).	74,489	Cft.	20/-	Twenty	1,489,780.00
Cement concrete plain including placing, compacting, finishing and curing, complete (including screening and washing of stone aggregate without shuttering). Ratio 1:2:4	2,452	Cft.	195/-	One hundred and ninety five	478,140.00
Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rates also includes all kind of form moulds: lifting shuttering curing rendering and finishing the exposed surface, complete (including screening and washing of stone aggregate). Ration 1:1	23,572	Cft.	195/-	One hundred and ninety five	4,596,540.00
Fabrication of mild steel reinforcement for cement concrete including cutting, bending, laying in position. Making joints and fastenings including cost of binding wire (also includes removal of rust	1,052	Cwt	3000/-	Three thousand	3,156,000.00
Cement pointing struks joints on walls. (Ratio 1:3)	89,765	Sft.	5/-	Five	448,825.00
Bitumen coating to plastered or or cement concrete surface	89,765	Sft.	3/-	Three	269,295.00
Cement plaster 1:3 upto 20' height (1/2" thick)	75,432	Sft.	7/-	Seven	528,024.00
Total of Storm Water Drain Rs.					10,973,392.00

TEN Million nine hundred seventy three thousand three hundred ninety two Two Only (In Words)

JOINT VENTURE
Kazmi Const Co., AL-Dost Contractors

CONTRACTOR

LAYING OF WATER SUPPLY
NETWORK

JOINT VENTURE
Kazmi Const Co., Al-Dost Constructors

BILL OF QUANTITIES
SUMMARY - WATER SUPPLY WORKS

Client / Owner : Shaheed Benazir Bhutto Housing Cell, Government of Sindh
 Name Of Project : Infrastructure Development i/c. Water Supply, Sewerage, Drainage and Roads of Benazir Colony at Deh Luqman, Khairpur, Sindh
 Project Head : Laying Water Supply Network including Overhead Tank, Pump Room and Tubewell
 Location : Khairpur, Sindh
 Contract No. : BCK-001

No.	Description	Amount (Rs.)
1	Laying of Water Supply Network	569,6706.00
2	Construction of Over Head Tank 2146444	2,150,606.00
3	Installation of Tubewell	233,120.00
4	Construction of Pump Room for Tubewell - Civil Works	403,316.00
5	Construction of Pump Room for Tubewell - Electrical Works	126,900.00
Total Water Supply Works Rs.		8610648.00

860648

Words Eight million six hundred ten thousand six hundred forty eight

In Words

Contractor

JOINT VENTURE
 Project Co. Ltd. BCK

BILL OF QUANTITIES

Owner : Shaheed Benazir Bhutto Housing Cell, Government of Sindh
 Of Project : Infrastructure Development i/c. Water Supply, Sewerage, Drainage and Roads of Benazir Colony
 at Deh Luqman, Khairpur, Sindh
 Head : Laying Water Supply Network including Overhead Tank, Pump Room and Tubewell
 Location : Khairpur, Sindh
 Contract No. : BCK-001

Particulars	Qty.	Unit	Rate		Amount (Rs.)
			In Figure	In Words	
Excavation for pipe lines in trenches, and pits in soft soils i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade, cutting joint holes and disposal of surplus earth within one chain as directed by Engineer, providing fence guard, lights, flags and temporary crossings for non vehicular traffic where ever required lift upto 5 ft and lead up to one chain.	272,511	Cft.	1/-	One	272,511.00
Providing PVC pipes of Class "D". fixing in trench i/c cutting, fitting and jointing with solvent cement i/c testing with water to a head of 122 meters or 400 ft.					
PVC pipe dia 3" Class "D"	28,392	Rft.	60/-	single	1703520
PVC pipe dia 6" Class "D"	4,335	Rft.	150/-	one hundred fifty	650250
PVC pipe dia 10" Class "D"	8,702	Rft.	225/-	two hundred twenty five	1957750
Refilling the excavated stuff in trenches 6" thick layers including watering, ramming to full compaction, etc. complete	221,965	Cft	2/-	TWO.	443930
Providing R.C.C chamber 3'x3' ft (inside dimensions) x upto 4.50' ft deep as per approved section for Sluice Valves 3 inches to 12 inches dia with 18 x 18 inches inside size cast iron cover and frame (w = 1 cwt. or 50 kg) fixed in R.C.C 1:2:4 slab 6 inches thick (with 5 lbs of steel per Cft) 9 inches thick brick masonry walls set in 1:6 C.M R.C.C 1:2:4 9" thick in foundation, 1 inch thick CC 1:2:4 flooring, 1/2 inch thick cement plaster 1:3 to all inside wall surfaces and to top including providing and fixing foot rest at every one foot beyond 2-1/2 feet depth, curing, excavation, backfilling and disposal of surplus earth etc complete. (including cost of steel reinforcement).	9	Nos.	3000/-	Three thousand	27000/-
Supplying, stacking and filling sand (River Sand) of approved quality from outside sources in bedding and around pipe as shown in drawings, including dressing, watering and consolidation by ramming in layers not exceeding 9" inch (229mm) in depth to full compaction.	43,605	Cft	3/-	Three	130815.00

JOINT VENTURE
 Kazmi Const Co., AL-Dost Constructors

Particulars	Qty.	Unit	Rate		Amount (Rs.)
			In Figure	In Words	
Providing and fixing Cast Iron Sluice Valves of approved quality (local made) with flanged ends & short pieces if required to each valve, of approved quality and make, complete with bolts and nuts, including the cost of insertion rubber washers, valves to stand specified test pressure etc. complete as directed by the Engineer. For 10" dia pipe	2	Nos.	2000/-	Two thousand	4,000/-
Supply & fixing double action 4" dia cast iron Air valve (local made) on 10" dia uPVC pipe line, fixing in position, testing and commissioning in manhole / chambers as per design, drawing & as per direction of the Engineer etc., complete (Cost of chamber to be paid separately) For 10" dia	7	Nos.	2000/-	Two thousand	14,000/-
Providing & fixing uPVC Equal Tee all end turned. Dia 3"x3"x3"	61	Nos.	250/-	Two hundred fifty	15,250/-
Dia 6"x6"x6"	4	Nos.	450/-	Four hundred fifty	1,800/-
Dia 10"x10"x10"	6	Nos.	600/-	Six hundred	3,600/-
Providing & fixing uPVC unequal Tee all end turned. Dia 6" X 6"x 3"	42	Nos.	350/-	Three hundred fifty	14,700/-
Dia 10" X 10"x 6"	6	Nos.	650/-	Six hundred fifty	3,900/-
Dia 10" X 10"x 3"	29	Nos.	600/-	Six hundred	17,400/-
Providing & fixing uPVC elbows all end turned. Dia 10" x 10", 90°	4	Nos.	600/-	Six hundred	2,400/-
Dia 10" x 10", 45°	2	Nos.	400/-	four hundred	800/-
Dia 6" x 6", 90°	4	Nos.	400/-	four hundred	1,600/-
Dia 6" x 6", 45°	2	Nos.	400/-	four hundred	800/-
Dia 3" x 3", 90°	6	Nos.	400/-	four hundred	2,400/-
Dia 3" x 3", 45°	1	No.	400/-	four hundred	400/-
Service Connection					
Making 1/2" dia service connection from uPVC pipe line with and including cost of PP male threaded adopter with end cap for 1/2" dia service connection, PP saddle clamp suitable for uPVC pressure pipe, with and i/c the cost of excavation, providing and fixing G.I plug to plug the connection, back filling the trench with suitable granular material as per the directions of the Engineer.					
Service Connection form 3" dia pipe line	799	Nos.	200/-	Two hundred	159,800/-
Service Connection from 6" dia pipe line	116	Nos.	250/-	two hundred fifty	29,000/-

Particulars	Qty.	Unit	Rate		Amount (Rs.)
			In Figure	In Words	
Providing & Laying in trenches 3/4" dia (20 mm) Polyethylene water pipe line including cutting, fitting, jointing, connecting with adopter for making connection at one end & plugging at other end as per the directions of the Engineer.	11,944	Rft.	20/-	Twenty	238,880
Total Amount Rs.					5696706

pees *Five million six hundred ninty six thousand seven hundred six only*
 In Words

Contractor

JOINT VENTURE
 Kazmi Const Co., AL-Dost Constructors

BILL OF QUANTITIES

Owner : Shaheed Benazir Bhutto Housing Cell, Government of Sindh
 Of Project : Infrastructure Development i/c. Water Supply, Sewerage, Drainage and Roads of Benazir Colony
 at Deh Luqman, Khairpur, Sindh
 Lead : Laying Water Supply Network including Overhead Tank, Pump Room and Tubewell
 on : Khairpur, Sindh
 Contract No. : BCK-001

Particulars	Qty.	Unit	Rate		Amount (Rs.)
			In Figure	In Words	
<p>S.R Cement is to be used in all items of cement concrete in contact with earth. Extra cost for using S.R Cement to be paid separately. Steel form work is to be used for fair face.</p> <p>Excavation in ordinary soil, foundation of building, bridges and other structures including bagbellling, dressing, refilling around structures with excavated earth, watering and ramming lead upto one chain and lift upto 5 feet, etc complete</p>	10,381	Cft	1/2	One	10381
<p>Providing and laying PCC (1:4:8) using crushed graded boulders 2" down gauge in foundation, basement and plinth including, compacting, curing etc, complete (Minimum cylindrical strength of 1000psi @ 28 days</p>	799	Cft	50/-	fifty	39950
<p>White Washing Two coats</p>	15,413	Sft	0.30 0.03	Point Three	4,624
<p>Providing & fixing C.I Manhole Cover with frame (cost of material etc. (2 Nos.)</p>	3	Cwt	3000/-	Three thousand	9,000
<p>Bitumen coating to plastered or cement concrete surface</p>	1,405	Sft	3/2	three	4,215
<p>Reinforced cement concrete work including all labour and material in beams, columns, footings upto ground level (Using S.R Cement) etc. except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also included all kinds of forms, moulds, lifting of shuttering, curing, rendering and finishing the exposed surface with all leads and lift complete in all respect. (having minimum cylindrical strength of 3000 Psi @ 28 days but not leaner than 1:1-1/2:3 in foundation, column & beams etc. complete.</p>	4,055	Cft	195/-	One ninety five	790,725
<p>Reinforced cement concrete work including all labour and material in beams, columns, footings etc. except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also included all kinds of forms, moulds, lifting of shuttering, curing, rendering and finishing the exposed surface with all leads and lift complete in all respect. (having minimum cylindrical strength of 3000 Psi @ 28 days but not leaner than 1:1-1/2:3 in foundation, column & beams etc. of OH Tank upto the height of 50ft</p>	2,049	Cft	195/-	One ninety five	399,555

JOINT VENTURE
 CONSULTANTS & CONTRACTORS

Particulars	Qty.	Unit	Rate		Amount (Rs.)
			In Figure	In Words	
Reinforced cement concrete work including all labour and material in walls & slab etc. except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also included all kinds of forms, moulds, lifting of shuttering, curing, rendering and finishing the exposed surface with all leads and lift, also cost of admixture etc., complete in all respect. (having minimum cylindrical strength of 4000 Psi @ 28 days (but not leaner than 1:1-1/2:3) in wall, bottom slab & top slab (OH Tank) including approved water proofing material added in cement as per the specifications of the manufacturer & directions of the Engineer.etc., Complete.	2,599	Cft	195/2	One ninety five	506,805
Fabrication of deformed bars conforming to ASTM A-615 Grade 60. having yield strength of 60,000 PSI reinforcement for cement concrete, with & i/c. the cost of cutting, bending, making joints, fastening and laying in position, including cost of steel bars but excluding such overlaps as are not shown on drawings, binding wire and removal of rust from bars etc complete in all respects (O/H Tank upto height of 50ft.)	125	Cwt	3000/2	Three thousand	375000
Providing and laying Stone soling 6" in layers under foundation including packing with spawls and chips & consolidating.	1,597	Cft	3/2	three	4791
Providing and fixing in proper position at construction Joints 25mm x 19mm water stopper R-X conforming to AASNI / NSF-61 made by "GETO COLLIOD Environment Company ILLINOIS USA". All as per the specification of Manufacturer.	139	Rft.	40/2	fourty	5560
Total Amount Rs.					2150106

2140000

Two million One hundred Fifty thousand Six hundred Sixty Only.
 In Words

Contractor

JOINT VENTURE
 Kazmi Const Co., Al-Dost Contractors

BILL OF QUANTITIES

Owner : Shaheed Benazir Bhutto Housing Cell, Government of Sindh
 Of Project : Infrastructure Development i/c. Water Supply, Sewerage, Drainage and Roads of Benazir Colony
 at Deh Luqman, Khairpur, Sindh
 Head : Laying Water Supply Network including Overhead Tank, Pump Room and Tubewell
 on : Khairpur, Sindh
 Contract No. : BCK-001

Particulars	Qty.	Unit	Rate		Amount (Rs.)
			In Figure	In Words	
<p>Payment of trial boring will only be made if the site/location, after initial boring and study of strata is not found prospective to yield the required quantity of water and is decided to be abandoned. Quantities are Provisional. The tubewells will be located minimum 200ft apart. The rates of boring shall include all costs pertaining to mobilization of plant and equipment, shifting of plant & equipment from one location to the other and demobilization of plant and equipment, maintenance of temporary site facilities, etc.</p> <p>Electric resistivity survey for location of suitable site of tubewells (2 packages for each tubewells).</p>	4	Each	2000/-	Two thousand	8,000/-
<p>Trial bore 12" dia including all kinds of strata such as shingle gravel clay etc for 1 No. tubewell, each 250 ft deep.</p>	500	Rft	100/-	One hundred	50,000/-
<p>Direct rotary/ reverse rotary drilling of bore hole for tube well in all kinds of soil (15"-18" dia). a) From ground level to 250' below ground level</p>	500	Rft	100/-	One hundred	50,000/-
<p>Providing strong substantially built box of deodar wood 4' x 2-1/2' x 9" with compartments lock and locking arrangement for preserving samples of strata from bore hole.</p>	2	Job	2500/-	Two thousand five hundred only	5,000/-
<p>Providing and installing brass strainer in tube well bore hole including sockets. specials sockets, studs etc; complete. 10" dia, 6mm (1/4") wall thickness. (60 x 2)</p>	120	Rft	40/-	Forty	4,800/-
<p>Providing and installing MS bail plug in tubewells borehole (10" dia 5 ft long each).</p>	2	Each	1500/-	One thousand five hundred	3,000/-
<p>Providing and installing MS blind pipe socket welded joint MS reducer (where necessary) in tubewells borehole i/c. jointing welding with strainer etc. 10" dia 1/4" thick. (15 x 2)</p>	30	Rft	1000/-	One thousand	30,000/-
<p>Shrouding with graded pea gravel 3/8" to 1/8" (10-3 mm) around tube well in bore hole.</p>	432	Cft	10/-	Ten	4,320/-
<p>Development washing of Tubewells upto depth with air compressor complete at each level of strainer aquifer taping i/c bail plug for not less than 72 hours or till cleaning of water which level is more to be the entire satisfaction of Engineer-in-charge</p>	2	Job	20,000/-	Twenty thousand	40,000/-

JOINT VENTURE
 Nazmi Const Co., AL-Dest Constructors
 Twenty thousand

Particulars	Qty.	Unit	Rate		Amount (Rs.)
			In Figure	In Words	
Testing of Tubewells @1.5 time of designed discharge and measuring safe yield, spring level drawdown etc. at the designed discharge and safe yield with submersible pump continuously pumping for 48 hours i/c cost of hire charges of submersible pump, generator etc. and other related T&P i/c P.O.L charges, labour etc. complete in all respect to the entire satisfaction of Engineer-in-charge.	2	Job	3000/-	Three thousand	6,000.00
Providing fixing in position M.S suspension clamp (2" x 1/2") flat iron with nut & bolts in R.C.C (1:2:4) size (4' x 4' x 3') for 12" dia pipe i/c all cost of labour and material charges etc; complete.	2	Each	2000/-	Two thousand	4,000.00
Testing of water samples from laboratory & collection from bore of tube well complete with all charges.	4	Each	1000/-	One thousand	4,000.00
Provision made for Electric Tubewells Logging not done from competent/ expert department/ engineer and providing water boring and conversion chart safe yield table, draw down detection in 4 at tamps, One copy of strata chart with other data shall be framed and hanging in pump house and one copy framed and hanging at each pumping unit.	2	Each	2000/-	Two thousand	4,000.00
Providing and fixing in position KSB deep well turbine for one cusec discharge upto 250 ft head coupled with Siemens motor complete with control panel, transportation installation with and including all accessories to complete the job as per the direction of the Engineer.	2	Nos	10,000	Ten thousand	20,000.00
Total Amount Rs.					233,120.00

Two hundred thirty three thousand One hundred twenty only
 In Words

JOINT VENTURE
 Kazz Const Co., Al-Dort Constructors

Contractor

BILL OF QUANTITIES

Owner : Shaheed Benazir Bhutto Housing Cell, Government of Sindh
 Of Project : Infrastructure Development i/c. Water Supply, Sewerage, Drainage and Roads of Benazir Colony
 at Deh Luqman, Khairpur, Sindh
 Head : Construction of Pump Room 12' x 10' - Civil Works (For 02 Nos. Tube well)
 Location : Khairpur, Sindh
 Contract No. : BCK-001

Particulars	Qty.	Unit	Rate		Amount (Rs.)
			In Figure	In Words	
<i>S.R Cement is to be used in all items of cement concrete Extra cost for using S.R Cement to be paid separately.</i>					
Excavation in ordinary soil, foundation of building, bridges and other structures including dagbelling, dressing, refilling around structures with excavated earth, watering and ramming lead upto one chain and lift upto 5 feet, etc	466	Cft	1/-	one	466.00
Providing and laying PCC (1:4:8) using crushed graded boulders 2" down gauge in foundation, basement and plinth including, compacting, curing etc, complete	64	Cft	40/-	forty	2560.00
Providing and laying PCC (1:3:6) using crushed graded boulders 2" down gauge in foundation, basement and plinth including, compacting, curing etc, complete	554	Cft	50/-	fifty	27700.00
Erection and Removal of centering for R.C.C or plain cement concrete works of Deodar Wood (2nd Class)	1,362	Sft	30/-	thirty	40860.00
Provide & lay damp proof course 2" thick with cement sand and shingle concrete 1:2:4) including 2 coats of asphaltic mixture including form work, with all leads and lifts etc complete in all respects.	150	Sft	15/-	fifteen	2250.00
Filling, watering and ramming earth, under floor with new earth excavated from outside lead upto one chain and lift upto 5 feet	126	Cft	2/-	two	252.00
Providing & laying first class solid burnt brick masonry set in c.m. (1:6) in straight or curved walls including scaffolding, raking out joints and curing etc. complete.	768	Cft	30/-	thirty	23040.00
Providing and laying 4" thick topping / Flooring cement concrete (1:2:4) including surface finishing and dividing into panels.	252	Sft	30/-	thirty	7560.00
Reinforced cement concrete (1:2:4) work including all labour and material in roof slab, beams, columns, rafts, lintels etc. except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also included all kinds of forms, moulds, lifting of shuttering, curing, rendering and finishing the exposed surface with all leads and lift complete in all respect.	308	Cft	195/-	One ninety five	60240.00

JOINT VENTURE
 Kazmi Const Co., Al-Dock Constructors

Particulars	Qty.	Unit	Rate		Amount (Rs.)
			In Figure	In Words	
Fabrication of Tor steel reinforcement for cement concrete, cutting, bending, making joints, fastening and laying in position, including cost of steel bars, binding wire and removal of rust from bars etc complete in all respects	14	Gwt.	3000/-	Three thousand	42,000/-
Providing and fixing ornamental cement jalli 2" thick (1:2:4) without steel.	26	Sft.	30/-	Thirty	780/-
Two coats of bitumen laid hot using 34 lbs for % sft over roof and blinded with sand at one Cft. Per % Sft.	440	Sft	10/-	Ten	4,400/-
Providing weather proof screed average 2" thick cement concrete (1:2:4) providing slopes to the rain water spouts including surface finishing, in panels, form work and it's removal with all leads & lifts etc. complete in all respects	440	Sft	30/-	Thirty	13,200/-
Providing and fixing in position doors, windows and ventilators of 1st Class deodar wood frames (3" x 4-1/2"), and 1-1/2" thick teak wood ply shutters of 2nd class deodar wood skeleton (solid) styles and rails core of partal wood and teak ply wood (3-ply) on both sides i/c hold fasts, hinges, iron tower bolts, handles and cleats with cord etc. complete.	190	Sft	150/-	one fifty	28,500/-
Making & fixing steel grated doors with 1/16" thick sheeting including angle iron frame 2" x 2" 3/8 and 3/4" square bars 4" centre to centre with locking arrangement.	44	Sft	400/-	Four hundred	17,600/-
Provide and laying cement plaster in c.m. (1:4), 3/4" thick smooth finishing, curing as specified including scaffolding form work and it's removal with all leads & lifts etc complete in all respects. (Inner surface)	2,338	Sft	7/-	Seven	16,366/-
Cement Pointing struck joints on walls. Ratio.1:3 (For Outer Surface)	1,086	Sft	7/-	Seven	7,602/-
White Washing Two coats (Inner Side)	1,148	Sft	5/-	Fine	5,740/-
Colour Washing two coats (Outer Side)	1,036	Sft	5/-	Fine	5,180/-
Painting doors and windows any type (Two coat).	240	Sft	10/-	Ten	2,400/-
Providing, laying and spreading graded granular sub-base material (Under the Floor) upto any thickness, leveling & compacting with vibratory Hand Roller including watering with all lead and lift, etc complete as directed by the Engineer.	190	Cft	12/-	Twelve	2,280/-

JOINT VENTURE
 Kazim Const Co., Al-Dost Constructors

Particulars	Qty.	Unit	Rate		Amount (Rs.)
			In Figure	In Words	
Providing, and fixing access cover 2'-8" x 2'-8" comprising on M.S angle iron frame 4" x 4" x 1/4" thick embaded in cement concrete with M.S nuts and bolts, cover of 1/4" thick M.S sheet with required hinges, M.s Handle 3/4" dia of mild steel rod and 2" x 1/2" steel Plate with slot locking Bar 1/4" dia locking bar required welding/Errecting etc. complete with all necessary accessories as per Drawing / Design and as per direction of the Engineer.	2	Nos.	2000/-	Two thousand	4000/-
Providing, and fixing M.S Hoist Beam, sizes.3" wide at Top, depth 6" and 12" wide at Bottom fixed with 1/2" dia and 8" long Nut & Bolts embaded in Cement concrete, necessary welding / Errection etc. complete as per Drawing / Design and as per direction of the Engineer.	864	Kg.	75/-	Seventy five	64800/-
Providing & Fixing 160mm dia (6" dia) PN-8 Polyethylene water pipe line with flanged including cutting, fitting, jointing, connecting all complete as per Drawing / Design and as per directions of the Engineer.	42	Rft.	20/-	Twenty	840/-
Providing & Fixing Flanged Reducer 6" x 4" dia (160mm x 110mm) connecting with Polyethylene water pipe line all complete as per Drawing / Design and as per directions of the Engineer.	2	Each	1000/-	One thousand	2,000/-
Providing & Fixing C.I Flanged Non-Return Valve 6" dia (160mm) connecting with Polyethylene water pipe line all complete as per Drawing / Design and as per directions of the Engineer.	2	Nos.	1000/-	One thousand	2,000/-
Supply & fixing Single Orifice cast iron Air valve (2" Dia local made) on 6" dia polyethylene pipe line, fixing in position, testing and commissioning in manhole / chambers as per design, drawing & as per direction of the Engineer etc., complete (Cost of chamber to be paid separately but including cost of Tee)	2	Nos.	1000/-	One thousand	2,000/-
Providing and fixing 6" dia Cast Iron Sluice Valves of approved quality (local made) with flanged ends & short pieces if required to each valve, of approved quality and make, complete with bolts and nuts, including the cost of insertion rubber washers, valves to stand specified test pressure-etc. complete as directed by the Engineer.	2	Nos.	1500/-	One thousand Five hundred	3000/-
Providing and fixing 6" x 6" x 6" (160mm x 160mm x 160mm) dia equal Tee fixing of 6" dia polyethylene pipe line as per Drawing / Design and as per direction of the Engineer	2	Nos.	1000/-	One thousand	2000/-

Particulars	Qty.	Unit	Rate		Amount (Rs.)
			In Figure	In Words	
Providing and fixing 6" dia (160mm) dia 90° bend on polyethylene pipe line as per Drawing / Design and as per direction of the Engineer	2	Nos.	1000/-	One thousand	2000/-
Providing and fixing 6" dia (160mm) dia flexible coupling on polyethylene pipe line as per Drawing / Design and as per direction of the Engineer	2	Nos.	1000/-	One thousand	2000/-
Providing and fixing 1/2" dia uPVC Pipe including the cost of necessary fittings etc. complete as per Drawing / Design and as per direction of the Engineer	22	Rft.	40/-	Forty	880/-
Providing and using Sulphate Resistance cement instead of Ordinary Portland Cement complete as directed by the Engineer.	280	Bags	25/-	Twenty five	7000/-
Total Amount Rs.					403316/-

Four lac three thousand three hundred sixteen only.

In Words

Factor

JOINT VENTURE
 Kazmi Const Co., AL-Dost Contractors

BILL OF QUANTITIES

Owner : Shaheed Benazir Bhutto Housing Cell, Government of Sindh
 Of Project : Infrastructure Development i/c. Water Supply, Sewerage, Drainage and Roads of
 Benazir Colony at Deh Luqman, Khairpur, Sindh
 Head : Construction of Pump Room 12' x 10' - Electrical Works (For 02 Nos. Tube well)
 Location : Khairpur, Sindh
 Project No. : BCK-001

Particulars	Qty.	Unit	Rate		Amount (Rs.)
			In Figure	In Words	
Providing and wiring of light, fan point to switch wired with 2 x 1.5mm ² single core PVC insulated (Pakistan cable or equivalent) laid in 20mm dia PVC conduit recessed in the wall column as required complete with all accessories.	12	Nos.	300/-	Three hundred	3600/-
Providing and wiring of 5A-3ping outlet wired with 3 x 1.5mm ² single core PVC insulated (Pakistan cable or equivalent) laid in 20mm dia PVC conduit recessed in the wall column as required complete with all accessories.	6	Nos.	200/-	Two hundred	1200/-
Providing and wiring of circuit wire wired with 3 x 2.5 mm ² single core PVC insulated (Pakistan cable or equivalent) laid in 20mm dia PVC conduit recessed in the wall, floor column as required from DB to switch board complete with all accessories.	2	Ckts.	2000/-	Two thousand	4000/-
Same as item no 3 but wiring of main supply with 3 x 4 mmsq PVC cable in 25mm dia PVC conduit from MDB to main switch board complete with all accessories.	100	Mtr	250/-	Two hundred fifty	25000/-
Providing, installing and connecting of 10A gang switch approved quality of switch in 16 SWG sheet steel box (Hussain or equivalent) flush in the wall complete with all accessories.	12	Nos.	250/-	Two hundred fifty	3000/-
Providing, installing, connecting and testing of fluorescent putty fitting 1 x 40 W light fixtures as approved type, Philips or equivalent complete with tube rod, starter, blast and other accessories.	4	Nos.	400/-	Four hundred	1600/-
Providing, installing, connecting and testing of bulk head weather proof light fixtures as approved type, Philips or equivalent complete with bulb, holder, cover and other accessories.	4	Nos.	1000/-	One thousand	4000/-

Particulars	Qty.	Unit	Rate		Amount (Rs.)
			In Figure	In Words	
Providing, installing, connecting and testing of 3pin 5amps outlet approved quality of outlet in 16 SWG sheet steel box (Hussain or equivalent) flush in the wall complete with all accessories.	6	Nos.	1000/-	One thousand	6000/-
Providing, installing, connecting and testing of 56" sweep ceiling fan as approved type pak, milat, cliemax fan or equivalent complete with fan dimmer flexible wire and other accessories.	2	Nos.	3000/-	Three thousand	6000/-
PVC conduit 50 mm dia complete with all bends, tees, boxes, saddles etc for concealed wiring, supply and fixing.	50	Mtr	30/-	thirty	1500/-
Wiring in conduit concealed with single core PVC insulated cable installed and connected, complete (exclusive of conduit) one single core cable 16mm ² , supply and fixing.	80	Mtr	100/-	One hundred	8000/-
Cable electric LT,600/1000 volts, insulated overall stranded copper conductor 25 mmsq 3.5 core unarmoured cable laid in PVC pipe, (exclusive of cost of pipe) , supply and fixing.	70	Mtr	500/-	five hundred	35000/-
Providing installing connecting and testing of Earthing sets of 24" x 24" x 1/4" thick copper plate buried at 15 ft. deep in the ground or to the depth of water level which over is more work to include digging of earth pit and refilling with sand, complete with necessary salt and shora 50 Kg. each to make the specified results according to IEE regulation, and latest B.S. standards. Complete with all accessories, like brass nut-bolts and washer etc. as per Engineer approval. The earth pit should be at 8 feet away from the building foundation.	2	Nos.	3000/-	three thousand	6000/-
Providing , laying and connecting 1 x 3/0 SWG hard drawing bare copper leads from Earthing plates to panels (MDB's) as shown on the drawing or as directed by the Engineer. The copper leads to be laid in suitable size of G. I. Pipe complete with all G. I. pipe and other accessories.	50	Mtr	200/-	Two hundred	10000/-

Particulars	Qty.	Unit	Rate		Amount (Rs.)
			In Figure	In Words	
DISTRIBUTION BOARDS					
Providing, installing, connecting, testing and commissioning distribution board wall/floor mounted housed in 16 SWG sheet steel housing, dust proof, hinged door/lock, suitable for. 500 volts, 3 phase, 4 wires and earth terminal AC system as approved by the Engineer. The panel comprises of:-					
DISTRIBUTION BOARD - MAIN					
<u>Incoming</u>					
1-125 A TP Mccb 13KA					
3-Indication lamps					
1-Voltmeter scaled-0-500 V					
1-Volt selector switch					
1-Ammeter scaled-0-100A					
1-Amps selector switch					
3-current transfer scaled-5-100A					
<u>Outgoing</u>					
1-100 A TP Mccb 10KA (for DB-P)					
1-15 A TP Mcb 7.5KA					
3-10 A SP Mcb-6 KA					
3-15A SP Mcb-6KA					
	2	Job.	6000/-	Six thousand	12000/-
Total Amount Rs.					126,900/-

One Lac Twenty Six thousand nine hundred only

In Words

JOINT VENTURE
 Kazim Const Co., Al-Dost Constructors

Contractor

LAYING OF SEWER LINES

JOINT VENTURE
Kaz Const Co., AL-Dest Contractors

71

BILL OF QUANTITIES

Owner : Shaheed Benazir Bhutto Housing Cell, Government of Sindh
 Of Project : Infrastructure Development i/c. Water Supply, Sewerage, Drainage and Roads of Benazir Colony
 at Deh Luqman, Khairpur, Sindh
 Lead : Laying Sewer Line
 on : Khairpur, Sindh
 ct No. : BCK-001

Particulars	Qty.	Unit	Rate		Amount (Rs.)
			In Figure	In Words	
Cement Concrete in contact with earth to be carried out with S.R. Cement surface steel formwork is to be used in all the items of P.C.C.					
Excavation for pipe lines in trenches, and pits in soft soils i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade, cutting joint holes and disposal of surplus earth within one chain as directed by Engineer, providing fence guard, lights, flags and temporary crossings for non vehicular traffic where ever required lift upto 5ft and lead up to one chain.	579,056	Cft.	15 1/2	fifteen	8,685,840
Excavation for pipe lines in trenches, and pits in soft soils i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade, cutting joint holes and disposal of surplus earth within one chain as directed by Engineer, providing fence guard, lights, flags and temporary crossings for non vehicular traffic where ever required lift 5ft to 8ft and lead up to one chain.	64,328	Cft.	20 1/2	Twenty	12,86,560
Excavation for pipe lines in trenches, and pits in soft soils i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade, cutting joint holes and disposal of surplus earth within one chain as directed by Engineer, providing fence guard, lights, flags and temporary crossings for non vehicular traffic where ever required lift 8ft to 11ft and lead up to one chain.	420	Cft.	25 1/2	Twenty five	10,500
Excavation for pipe lines in trenches, and pits in soft soils i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade, cutting joint holes and disposal of surplus earth within one chain as directed by Engineer, providing fence guard, lights, flags and temporary crossings for non vehicular traffic where ever required lift 11ft to 14ft and lead up to one chain.	38	Cft.	30 1/2	Thirty	11,400
Drilling or pumping out subsoil water during excavation, concreting, cast in situ concrete or masonry work in foundation etc. For pipe line trench volume under water to be measured first time for excavation, second time for cast in situ concrete (bedding pipe line) and third time for pipe laying	194,360	Cft.	3 1/2	Three	5,83,080

JOINT VENTURE
 Kazim Const Co., Al-Doslik Contractors

Particulars	Qty.	Unit	Rate		Amount (Rs.)
			In Figure	In Words	
Providing PVC Pipes of Class "B" fixing in trench ic cutting fitting and jointing with solvent cement ic testing with water to head of 61 meter or 200ft.					
10" Dia Pipe	30,009	Rft.	1000/-	One thousand	30,009,000
12" Dia Pipe	5,507	Rft.	1400/-	{One thousand four hundred}	77,09,800
Refilling the excavated stuff in trenches in 6" thick layer including watering, ramming, to full compaction etc complete.	416,127	Cft.	8/-	Eight	3,329,016
Cement concrete plain including placing compacting, finishing and curing, complete including screening and washing of stone aggregate without shuttering. Ratio 1:2:4. (For Manhole Base)	5,767	Cft.	195/-	One hundred ninety Five	1,124,565
Pacca brick in foundation and plinth in cement sand mortar 1:4. (Manhole Walls)	19,760	Cft.	150/-	One hundred fifty	2,964,000
Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms, moulds, lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle). (Manhole Roof Slab) Ratio 1:2:4	3,144	Cft.	195/-	{One hundred ninety Five}	6,13,080
Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds, lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle). Precast reinforced cement concrete in columns, beams lintels stair cases, shelves, etc. (Precast Manhole Cover) Ratio 1:2:4	742	Cft.	195/-	One hundred ninety Five	144,690
Erecting and fixing in position precast cement concrete or stone slab in roofs, lintels, end of pipe sleeves, etc lift upto 20 feet including all charges. (For Precast Manhole Cover)	742	Cft.	250/-	Two hundred fifty	185,500
Fabrication & supplying of mild steel reinforcement for cement concrete including cutting, bending, laying in position, making joints and fastenings including cost of binding wire also includes removal of rust from bars, laps not shown in the drawings will not be paid) (For Manhole slab & Manhole Cover)	177	Cwt.	10,000/-	Ten thousand	1,770,000
Deformed/Tor Bar					
Cement plaster 1:4, 3/4" thick upto 20ft height Walls of Manholes)	96,873	Sft.	30/-	Thirty	2,906,190

JOINT VENTURE
 Kaim Const Co., AL-DOA Constructors

Particulars	Qty.	Unit	Rate		Amount (Rs.)
			In Figure	In Words	
Bitumen coating to plastered or cement concrete surface. (Outer surface of Manhole Walls in contact with earth)	77,513	Sft.	3/-	Three	232,539
Supplying, stacking and filling sand (River Sand) of approved quality from outside sources in bedding and around pipe as shown in drawings, including dressing, watering and consolidation by ramming in layers not exceeding 9" inch (229mm) in depth to full compaction.	43,975	Cft.	35/2	Thirty Five	1539,125
Providing & laying stone soling 6" in layers under foundation including packing with spawls and chips & consolidating.	5,767	Cft.	45/2	Forty Five	259,515
Total Sewer lines Rs.					63354140

Sixty three million three hundred fifty four thousand one hundred forty only
 In Words

Factor

JOINT VENTURE
 Kazmi Const Co., Al-Dust Constructors

(INTEGRITY PACT)

DECLARATION OF FEES, COMMISSION AND BROKERAGE ETC.
PAYABLE BY THE SUPPLIERS OF GOODS, SERVICES & WORKS IN
CONTRACTS WORTH RS. 10.00 MILLION OR MORE

Contract No. BCK-001 Dated 24th March 2012

Contract Value: Rs. 234.638 Million

Contract Title: INFRASTRUCTURE DEVELOPMENT INCLUDING WATER SUPPLY, SEWERAGE
DRAINAGE & ROAD OF BENAZIR QUNY, SEH LURMAN, KHORRUA,

M/S KAZMI CONSTRUCTION
AL-DOST CONSTRUCTORS (PVT) [name of Supplier] hereby declares that it has not obtained or induced the procurement of any contract, right, interest, privilege or other obligation or benefit from Government of Pakistan (GoP) or any administrative subdivision or agency thereof or any other entity owned or controlled by GoP through any corrupt business practice.

Without limiting the generality of the foregoing, [name of Supplier] represents and warrants that it has fully declared the brokerage, commission, fees etc. paid or payable to anyone and not given or agreed to give and shall not give or agree to give to anyone within or outside Pakistan either directly or indirectly through any natural or juridical person, including its affiliate, agent, associate, broker, consultant, director, promoter, shareholder, sponsor or subsidiary, any commission, gratification, bribe, finder's fee or kickback, whether described as consultation fee or otherwise, with the object of obtaining or inducing the procurement of a contract, right, interest, privilege or other obligation or benefit in whatsoever form from GoP, except that which has been expressly declared pursuant hereto.

[name of Supplier] certifies that it has made and will make full disclosure of all agreements and arrangements with all persons in respect of or related to the transaction with GoP and has not taken any action or will not take any action to circumvent the above declaration, representation or warranty.

[name of Supplier] accepts full responsibility and strict liability for making any false declaration, not making full disclosure, misrepresenting facts or taking any action likely to defeat the purpose of this declaration, representation and warranty. It agrees that any contract, right, interest, privilege or other obligation or benefit obtained or procured as aforesaid shall, without prejudice to any other rights and remedies available to GoP under any law, contract or other instrument, be voidable at the option of GoP.

Notwithstanding any rights and remedies exercised by GoP in this regard, [name of Supplier] agrees to indemnify GoP for any loss or damage incurred by it on account of its corrupt business practices and further pay compensation to GoP in an amount equivalent to ten times the sum of any commission, gratification, bribe, finder's fee or kickback given by [name of Supplier] as aforesaid for the purpose of obtaining or inducing the procurement of any contract, right, interest, privilege or other obligation or benefit in whatsoever form from GoP.

Name of Buyer:

Signature: CHAIRMAN
[Seal]

Name of Seller/Supplier:

Signature:
[Seal]

JOINT VENTURE
Kazmi Const Co., AL-Dost Constructors

SINDH PUBLIC PROCUREMENT REGULATORY AUTHORITY

CONTRACT EVALUATION FORM

TO BE FILLED IN BY ALL PROCURING AGENCIES FOR PUBLIC CONTRACTS OF WORKS, SERVICES & GOODS

- 1) NAME OF THE ORGANIZATION / DEPTT. SHAHEED BENAZIR BHUTTO HOUSING CELL
- 2) PROVINCIAL / LOCAL GOVT./ OTHER PROVINCIAL
- 3) TITLE OF CONTRACT INFRASTRUCTURE DEVELOPMENT INCLUDING WATER SUPPLY, SEWERAGE, DRAINAGE & ROAD OF BENAZIR COLONY, DEH LUQMAN, KHAIRPUR
- 4) TENDER NUMBER INF | KRY-946 | 2012
- 5) BRIEF DESCRIPTION OF CONTRACT INFRASTRUCTURE DEVELOPMENT, DEH LUQMAN KHAIRPUR.
- 6) FORUM THAT APPROVED THE SCHEME STEERING COMMITTEE, BHC.
- 7) TENDER ESTIMATED VALUE Rs. 234, 642, 676 /=-
- 8) ENGINEER'S ESTIMATE Rs. 239, 739, 487 /=-
(For civil works only)
- 9) ESTIMATED COMPLETION PERIOD (AS PER CONTRACT) 10 MONTHS.
- 10) TENDER OPENED ON (DATE & TIME) 24.3.2012; 3:00 P.M (Tech.Prop.), 21.4.2012; 3:00 P.M (FINANCIAL PROPOSAL)
- 11) NUMBER OF TENDER DOCUMENTS SOLD 08 Nos.
(Attach list of buyers)
- 12) NUMBER OF BIDS RECEIVED 05 Nos.
- 13) NUMBER OF BIDDERS PRESENT AT THE TIME OF OPENING OF BIDS 02 Nos.
- 14) BID EVALUATION REPORT ATTACHED
(Enclose a copy)
- 15) NAME AND ADDRESS OF THE SUCCESSFUL BIDDER M/S KAZMI CONSTRUCTION - AL. DOST CONSTRUCTOR ROOM #7 (G-4) 2nd FLOOR, SNOW WHITE, COMMERCIAL BLOCK- 7& 8 KUCHS, KARACHI
- 16) CONTRACT AWARD PRICE Rs. 234.638 MILLION
- 17) RANKING OF SUCCESSFUL BIDDER IN EVALUATION REPORT (i.e. 1st, 2nd, 3rd EVALUATION BID) M/S KAZMI CONSTRUCTION - AL. DOST CONSTRUCTOR (JV)
M/S MUMTAZ & COMPANY
M/S NIAZ MUHAMMAD KHAN & BROS.
- 18) METHOD OF PROCUREMENT USED : - (Tick one)
- a) SINGLE STAGE – ONE ENVELOPE PROCEDURE _____ Domestic/ Local
- b) SINGLE STAGE – TWO ENVELOPE PROCEDURE _____ DOMESTIC
- c) TWO STAGE BIDDING PROCEDURE _____
- d) TWO STAGE – TWO ENVELOPE BIDDING PROCEDURE _____

PLEASE SPECIFY IF ANY OTHER METHOD OF PROCUREMENT WAS ADOPTED i.e. EMERGENCY, DIRECT CONTRACTING ETC. WITH BRIEF REASONS:

19) APPROVING AUTHORITY FOR AWARD OF CONTRACT MINISTER HOUSING

20) WHETHER THE PROCUREMENT WAS INCLUDED IN ANNUAL PROCUREMENT PLAN?

Yes	<input type="checkbox"/>	No	<input type="checkbox"/>	N.A
-----	--------------------------	----	--------------------------	-----

21) ADVERTISEMENT :

i) SPPRA Website
(If yes, give date and SPPRA Identification No.)

Yes	YES. Sr# 11436, 5D. 7051/2012
No	

ii) News Papers
(If yes, give names of newspapers and dates)

Yes	YES. IBRAT, EXPRESS, THE NATION 06.03.2012
No	

22) NATURE OF CONTRACT

Domestic/ Local	<input checked="" type="checkbox"/>	Int.	<input type="checkbox"/>
--------------------	-------------------------------------	------	--------------------------

23) WHETHER QUALIFICATION CRITERIA
WAS INCLUDED IN BIDDING / TENDER DOCUMENTS?
(If yes, enclose a copy)

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

24) WHETHER BID EVALUATION CRITERIA
WAS INCLUDED IN BIDDING / TENDER DOCUMENTS?
(If yes, enclose a copy)

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

25) WHETHER APPROVAL OF COMPETENT AUTHORITY WAS OBTAINED FOR USING A
METHOD OTHER THAN OPEN COMPETITIVE BIDDING?

Yes	<input type="checkbox"/>	No	<input type="checkbox"/>	N.A.
-----	--------------------------	----	--------------------------	------

26) WAS BID SECURITY OBTAINED FROM ALL THE BIDDERS?

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

27) WHETHER THE SUCCESSFUL BID WAS LOWEST EVALUATED
BID / BEST EVALUATED BID (in case of Consultancies)

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

28) WHETHER THE SUCCESSFUL BIDDER WAS TECHNICALLY
COMPLIANT?

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

29) WHETHER NAMES OF THE BIDDERS AND THEIR QUOTED PRICES WERE READ OUT AT
THE TIME OF OPENING OF BIDS?

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

30) WHETHER EVALUATION REPORT GIVEN TO BIDDERS BEFORE THE AWARD OF
CONTRACT?

(Attach copy of the bid evaluation report)

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

31) ANY COMPLAINTS RECEIVED
(If yes, result thereof)

Yes	
No	No

32) ANY DEVIATION FROM SPECIFICATIONS GIVEN IN THE TENDER NOTICE / DOCUMENTS
(If yes, give details)

Yes	
No	No

33) WAS THE EXTENSION MADE IN RESPONSE TIME?
(If yes, give reasons)

Yes	YES. HOLIDAY AT 23RD MARCH 2012 CORRIGENDUM ISSUED
No	

34) DEVIATION FROM QUALIFICATION CRITERIA
(If yes, give detailed reasons.)

Yes	
No	No

35) WAS IT ASSURED BY THE PROCURING AGENCY THAT THE SELECTED FIRM IS NOT
BLACK LISTED?

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

36) WAS A VISIT MADE BY ANY OFFICER/OFFICIAL OF THE PROCURING AGENCY TO THE
SUPPLIER'S PREMISES IN CONNECTION WITH THE PROCUREMENT? IF SO, DETAILS TO
BE ASCERTAINED REGARDING FINANCING OF VISIT, IF ABROAD:
(If yes, enclose a copy)

Yes	<input type="checkbox"/>	No	<input type="checkbox"/>
-----	--------------------------	----	--------------------------

N.A

37) WERE PROPER SAFEGUARDS PROVIDED ON MOBILIZATION ADVANCE PAYMENT IN
THE CONTRACT (BANK GUARANTEE ETC.)?

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

38) SPECIAL CONDITIONS, IF ANY
(If yes, give Brief Description)

Yes	
No	No

39) Date of Award of Contract: 29.05.2012

Signature & Official Stamp of
Authorized Officer

Director (Technical)
People's Housing Cell
Government of Sindh

FOR OFFICE USE ONLY

SPPRA, Block. No.8, Sindh Secretariat No.4-A, Court Road, Karachi
Tele: 021-9205356; 021-9205369 & Fax: 021-9206291

Print

Save

Reset

BID EVALUATION REPORT

Name of Procuring Agency: Shaheed Benazir Bhutto Housing Cell, Govt. of Sindh

Tender Reference No: INF / KRY 946/2012

Tender Description / Name of work/item: Infra Structure Development including Water Supply, Sewerage, Drainage and Roads of Benazir Colony at Deh Luqman, Khairpur Sindh

Method of Procurement: Single Stage, Two Envelope

Tender Published: Ibrat, Express & The Nation, 6th March 2012 SPPRA Sr#. 11436. ID-7051/2012

Total Bid Documents Sold: 08 Nos. (Annexure A).

Total Bids Received: 05 Nos. (Annexure B)

Technical Bid Opening date: 24th March 2012 (Annexure C-D).

No. of Bid Technically qualified: 03 Nos.

Bids Rejected: 02 Nos.

Financial Bids Opening date: 21st April 2012 (Annexure E).

BID EVALUATION REPORT:

Sr. #	Name of Firm or Bidder	Cost offered by the Bidder	Ranking in terms of Cost	Comparison with Estimated Cost	Reasons for Acceptance / Rejection	Remarks
9	1	2	3	4	5	6
1	M/s Kazmi Construction – Al-Dost Constructor (JV)	Rs: 2,34,642,676/-	1 st	2.12% Below	Lowest One	
2	M/s Mumtaz & Company	Rs: 3,27,205,197/-	2 nd	36.48% Above	--	
3	M/s Niaz Muhammad Khan and Brothers	Rs: 4,11,536,445/-	3 rd	71.65% Above	--	

ADA
 DD(A/P)
 A.E (BMC)
 Conv. A.S. (BMC)

M-1, Beaumont Plaza
Behind PIDC House
Karachi.
Tel. 99204178-9
Fax. 35680117

12 (b) Name and Number of the Contract

**INFRASTRUCTURE DEVELOPMENT INCLUDING WATER SUPPLY SEWERAGE,
DRAINAGE AND ROADS OF BENAZIR COLONY AT DEH LUQMAN, KHAIRPUR,
SINDH.
CONTRACT NO. BCK-001**

20.1 (a) Deadline for submission of bids

2:00pm on July 23, 2011

23.1 Venue, time, and date of Bid opening

Opening of Technical Proposals:

Venue : Office of the Employer
M-1, Beaumont Plaza
Behind PIDC House
Karachi
Tel. 99204178-9
Fax. 35680117

Time : 3:00pm

Date : July 23, 2011

Opening of Financial Proposals:

Venue : Office of the Employer
M-1, Beaumont Plaza
Behind PIDC House
Karachi
Tel. 99204178-9
Fax. 35680117

Time : To be announced after Evaluation of Technical Bids

Date : To be announced after Evaluation of Technical Bids

28.5 Evaluation and Comparison of Bids

(a) Technical Evaluation

I. Mandatory Requirements

For consideration of the Technical Proposals submitted by the bidders following are the mandatory requirements:

- i) License of the bidder with Pakistan Engineering Council in Category C3 or above and having specialization code of CE-01 and CE-09, valid for the year 2011.

- ii) Bid Security as mentioned in Instruction to Bidders Clause IB-15
- iii) Documentary evidence of the year of establishment of the bidding firm.
- iv) Affidavit on the stamp paper duly notarized that the bidding firm is not black listed by any Government Department / Semi-Government / Autonomous Body / any other Client
- vii) List of any present or past litigation of the Bidding Firm with any Organization, Govt. Dept. or private concern (If "No" write "Nil" and submit an affidavit on Stamp Paper in this regard).
- viii) Documentary evidence of the bidders having requisite experience.

Further evaluation of only those bidders will be done who have cleared the all the Mandatory requirements.

II. Qualification Requirements

Following documents shall be evaluated (only for those Bidders who clear all mandatory requirements) on the basis of points as detailed below (Financial proposal of only those bidders shall be opened whose Technical Proposal gets a minimum of 60 qualifying points out of 100 maximum points.):-

1. Documentary proof of all the requirements laid down in Clause IB-9 as under: -

- **Experience** **Max. Point 30**
 - List of overall experience of the firm with details of works in past five years (one point for each project of Rs. 100 million or above) Max. Point. 5
 - No. of projects completed in time in last ten years (one point for each project of Rs. 50 million or above) Max. Point. 5
 - Experience of similar works in last 10 years (one point for each project of Rs. 50 million or above subject to a maximum of 3 projects in a specific field i.e. Roads, Drains, Water Supply & Sewerage) Max. Point. 10
 - List of similar works in hand (one point for each project of Rs. 50 million or above subject to a maximum of 3 projects in a specific field i.e. Roads, Drains, Water Supply & Sewerage) Max. Point. 10
- **Pre-qualification with different organizations/ departments for similar works with documentary proof (one point for each similar Pre-Qualification done in past 5 years).** **Max. Point 10**
- **List of machinery and equipment intended to be used on the project with proof of ownership (Form BG-01)** **Max. Point 10**
 - List of Machinery & Equipment Max. Point. 05
 - Proof of Ownership Max. Point. 05
- **List of qualified Engineers with their qualification** **Max. Point 15**
 - CV of the proposed Project Manager with 15 years overall experience and 10 years experience in related works. Max. Point. 10

- List of Engineers on role for One Year with the bidder and their qualification (with documentary proof and PEC Registration Number) (Half Point for each engineer) Max. Point. 05
- 2. Proposed Construction Schedule, Method Statement, & Organization Chart** Max. Point 10
 - Proposed Construction Schedule (Form BE-1) Max. Point. 04
 - Method of Performing Work (Form BF-01) Max. Point. 03
 - Organization Chart (Form BK-1) Max. Point. 03
- 3. Documentary evidence of Financial Soundness** Max. Point 25
 - Financial Soundness Certificate from the Bank issued in last one year Max. Point. 07
 - Audited Reports of the firm for last 03 years Max. Point. 06
 - Banks Statement for the last 12 months Max. Point. 02
 - Average Annual Turnover of last 03 years Max. Point. 10
 - o Less than Rs. 75 million - 0 Points
 - o Rs. 075 million to Rs. 100 million - 02 Points
 - o Rs. 100 million to Rs. 125 million - 04 Points
 - o Rs. 125 million to Rs. 150 million - 06 Points
 - o Rs. 150 million to Rs. 175 million - 08 Points
 - o Rs. 175 million or above - 10 Points

Total of Max. Point 100

(d) Commercial Evaluation

It will be examined in detail whether the Bids comply with the commercial/contractual conditions of the Bid Documents. It is expected that no major deviation/ stipulation shall be taken by the Bidders

(e) Evaluated Bid Price

In evaluating the Bids, the Employer will determine for each Bid in addition to the Bid Price, the following factors (adjustments) in the manner and to the extent indicated below to determine the Evaluated Bid Price:

- (i) Making any correction for errors pursuant to Sub-Clause 24.2 hereof.
- (ii) Excluding Provisional Sums, if any, but including priced Daywork.
- (iii) Making an appropriate adjustment for any other acceptable variation or deviation.

32.1 Standard form and amount of Performance Security acceptable to the Employer

Amount of Performance Security shall be per Clause 10.1 of Part II-Conditions of Particulars Application.



SHAHEED BENAZIR BHUTTO HOUSING CELL



M-01, Beaumont Plaza,
Behind PIDC House, Karachi
Phone No. 9204178-9- Fax 5680117

No. BHC/DIR-T/F-43-B/2012/ 3136
Karachi dt. 22nd May, 2012

To,

The Manager CB,
Sindh Public Procurement Regularity Authority,
Government of Sindh,
Karachi.

Subject: **BID EVALUATION REPORT**

I am directed to refer to your letter no. Dir (CB-1364)/SPPRA/3-1(SBBHC)/11-12/6890 dt. 18th May 2012, on the subject noted above.

The original Bid Evaluation Report is enclosed as desire please. You are requested to hoist the above one on SPPRA website.


21.5.2012
(AGHA ZARAR KHAN)
DEPUTY DIRECTOR ENG.

BID EVALUATION REPORT

- 1 **Name of Procuring Agency:** Shaheed Benazir Bhutto Housing Cell, Govt: of Sindh A.
- 2 **Tender Reference No:** INF / KRY 946/2012
- 3 **Tender Description / Name of work/item:** Infra Structure Development including Water Supply, Sewerage, Drainage and Roads of Benazir Colony at Deh Luqman, Khairpur Sindh
- 4 **Method of Procurement:** Single Stage, Two Envelope
- 5 **Tender Published** Ibrat, Express & The Nation, 6th March 2012 SPPRA Sr#. 11436. ID-7051/2012
- 6 **Total Bid Documents Sold:** 08 Nos. (Annex-A)
- 7 **Total Bids Received:** 05 Nos. (Annex-B)
- 8 **Technical Bid Opening date:** 24th March 2012 (Annex-B1)
- 9 **No. of Bid Technically qualified** 03 Nos.
- 10 **Bids Rejected:** 02 Nos.
- 11 **Financial Bids Opening date:** 21st April 2012 (Annex-C)

12 BID EVALUATION REPORT:

Sr. #	Name of Firm or Bidder	Cost offered by the Bidder	Ranking in terms of Cost	Comparison with Estimated Cost	Reasons for Acceptance / Rejection	Remarks
0	1	2	3	4	5	6
1	M/s Kazmi Construction – Al-Dost Constructor (JV)	Rs: 2,34,642,676/-	1 st	2.12% Below	Lowest One	
2	M/s Mumtaz & Company	Rs: 3,27,205,197/-	2 nd	36.48% Above	--	
3	M/s Niaz Muhammad Khan and Brothers	Rs: 4,11,536,445/-	3 rd	71.65% Above	--	

ADA
 DD(A/P)
 21/4/2012
 22/4/2012

LIST OF CONTRACTORS FOR DELI LUQMAN KHAIPIR

ANNEXURE - A

Sr. No.	Contractor/ Investors	Key Person	Phone/ Fax/ Email	Bank Name / Branch	Address:
1	M/S NIJZ MUHAMMAD KHAN AND BROTHERS	Mr. Amir	022-2782359 022-2728031 022-2780383	MCB PO# 3963756/RS. 3000 Add: Karachi PUDC House-0915	Sheh Maki Road, Karcha Orla, Hyderabad
2	M/S MAQBOOL AHMED & CO.	Mr. Maqbool	021-37740033 021-34305070	Summit Bank PO# 50600800/RS. 3000 Add: Latifabad#7 Branch Hyderabad	59, Ground Floor, Block-III, D.C.H.S, Off. Shahheed-e- Millet Road, Karachi
3	M/S MUMTAZ & COMPANY GOVERNMENT CONTRACTORS	Shafiqe Ahmed	022-2653196 22-2650885	Summit Bank PO# 50600799/RS. 3000 Add: Latifabad#7 Branch Hyderabad	Bungalow# C-11 Prince Town Phase-4I Qasimabad Hyderabad
4	MUHANDASEEN (PVT) LTD ENGINEERS BUILDERS DEVELOPERS		92-21-34688202 92-21-34688206	BankIslami Pakistan Limited PO# DRA/411125312357/RS. 3000/- Add: Rashid Minhas Road, Karachi	A-118, Block-C, Gulshan-e- Iqbal Karachi
5	AL-DOST-KAZMI CONSTRUCTORS (JV)	Mr. Abdul Samad	021-34979147 0332-3639508	Soneri Bank Limited PO# 00122367/RS. 3000/- Add: Gulshan-e-Iqbal Karachi (0034)	R-13, Shanti Nagar, Sindhi Society, Block-19 Gushan Iqbal Karachi
6	KHAKI CONSTRUCTION COMPANY	Ali Dad Khaki	75651	NBP PO# 640345/RS. 3000/- Add: Kumb Branch	Ranipur Taluka Sobodero PO Ranipur District Khairpur
7	COURAGE DEVELOPMENT FOUNDATION	Javed Balouch	021-38629288	MCB PO# 3994477/RS. 3000 Add: Karachi Shaikh Sultan Trust-0842	PLOT# 190 Japwa House Sector 6-A Cawsway Road Mehran Town Karachi
8	G.O.S CONSTRUCTION	Mr. Faiz Shaikh	0300-2139984	HBL PC# 6980063/RS. 3000/- SMHS Blok-A Sub Block-B	F#204 Plot#103/1 Zaitgi Arcad Sindhi Muslims Housing Society Karachi

TECHNICAL PROPOSAL OPENING STATEMENT

24th March 2012

Sr.#	Name of Bidder	Bid Security Amount (Rs.)	Form & Detail of Bid Security	Technical Proposal each page Signed (Y/N)	Sealed Financial Proposal (Y/N)	Remarks
1	M/s MUMTAZ & COMPANY	R. 35,000,000/-	Jubilee General Insurance Company Limited Call Deposit NBD. CNR. A - 115917, Kungs Bazaar MCB, CNR. 602462, TML (R) Bazar Jubilee General Insurance Company Limited ABL; box no. 4371641 HBL; PO NO. 6843008 SONERI BANK LTD. 20112422	Y	Y	
2	M/s KHAKI CONSTRUCTION Co.	R. 33,000,000/-		Y	Y	
3	M/s G.O.S CONTRACTORS	R. 45,000,000/-		Y	Y	
4	M/s N/AZ MUHAMMAD KHAN & BROTHERS	R. 35,000,000/-		Y	Y	
5	M/s KAZMI & AL-DOST CONSTRUCTION (PVT)	R. 15,000,000/- R. 8,500,000/- R. 10,000,000/-		Y	Y	
6						
7						

NAME: M. Shafiqur Raza

NAME: Agha Zahoor

NAME: Akbar Ali

Position: Assistant Engineer (B&H)

Position: D. D. F.

Position: ADD (K.I.S.I.)

Sign: [Signature]
24.3.2012







Sign: [Signature]

Sign: [Signature]

LIST OF PARTICIPANTS

TECHNICAL COMMITTEE MEETING

24th March, 2012

No.	Name:	Name of Org.	Phone/Cell	Signature
	S. Haidel Abbas	OSmas & Co	0300 9261500	
	M/S N.K.B Ghulam Mustafa		0331 3640474 0332-3639508	 
	AL Doost Constnctn J/V Kazimce			
	M/S Munir & Company (Solely AL)		0300-3798101	
	M/S G.O.S Contvet.v's		0300-2139984	
	M.S. Bazmi	BHAC	99204178	
	Agha Zauar Khan	BHAC	99204170	
	Aamir Ali	BHAC	0300-3104272	

LIST OF PARTICIPANTS

... COMMITTEE MEETING: 23rd April 2012.

Name of Officer	Name of Org.	Phone / Cell	Signature
Bluf. J. Ahmed M/S Mumbaz & Company	M/S Mumbaz & Company	022-2653196 03003798101	
Abdul Samad Kazim Const. Co. JV ALD Const	KAZIMI Const/JVAI PEAST	0330-3635509	
Maj (R) Ansan Siddiq Geo GM (P&CA)	Osmari & Company	03222777714	
G. A. Baloch	BHC	03832332522	
Amjad Hussain	AD. Admn BHC	03002206087	
Vasim Khan	D.D.E	0300 877222	
Fazal Mangi	XEN(H) KLP	0345-3900900	
Hakim Ali Jamali	PE Insp KLP	0300-3403839	
M. Shafiqur Rahman	A.E BHC	021-9921718	

**COMPARATIVE STATEMENT
GRAND SUMMARY**

ANNEXURE - A

Client / Owner : Shaheed Benazir Bhutto Housing Cell, Government of Sindh
 Name of Project : Infrastructure Development i/c. Water Supply, Sewerage, Drainage and Roads of Benazir Colony at Deh Lujman, Khairpur, Sindh
 Location : Khairpur, Sindh
 Contract No. : BCK-001

Sr. No.	Particulars	Engineer's Estimate		M/s. Kazmi Construction		M/s. Niaz Muhammad Khan		M/s. Murtaz & Co.	
		Amount (Rs.)		Amount (Rs.)	Difference %	Amount (Rs.)	Difference %	Amount (Rs.)	Difference %
1	Construction of Roads & Storm Water Drain	167,003,716		193,168,179	15.67%	309,574,580	85.37%	264,332,676	58.58%
2	Laying of Water Supply Network	37,171,735		8,606,486	-76.85%	52,714,884	41.81%	30,169,994	-18.84%
3	Laying of Sewer lines	39,207,127		63,354,140	61.59%	49,326,991	25.81%	43,011,713	9.70%
	Sub Total Rs.	243,382,578		265,128,805	8.93%	411,616,455	69.12%	338,014,383	38.88%
	Less Rebate			-30,489,813			3.25%	-10,985,467	
	Sub Total Rs.	243,382,578		234,638,992	-3.59%	411,616,455	69.12%	327,028,916	34.37%
	Add: Provisional Sum Rs.	10,000,000		10,000,000		10,000,000		10,000,000	
	Grand Total Rs.	253,382,578		244,638,992	-3.45%	421,616,455	66.40%	337,028,916	33.01%

[Handwritten Signature]

Annexure C, X