



KARACHI WATER & SEWERAGE BOARD

OFFICE OF THE CHIEF ENGINEER (IP&D)

BID EVALUATION REPORT

1	Name of Procuring Agency	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No	KWSB/DPR/2014/32 Published in i) The Nation ii) Daily Awani Awaz on dated:16-02-2014 iii) Daily Express on dated: 15-02-2014 SPPRA Serial No.19022 I.D No. /2014
3	Tender Description/Name of Work/Item	REPLACEMENT OF WORN OUT / DAMAGED 12" DIA SEWERAGE LINE BY PROVIDING AND LAYING 12" DIA RCC SEWER PIPE LINE ADJACENT MASJID-E- UMAR BLOCK-20 GULBERG.
4	Method of Procurement	Single Stage (One Envelop)
5	Tender Published	Through Web Site / Press
6	Total Bid Documents Sold	02 Nos
7	Total Bid Received	02 Nos
8	Technical Bid Opening Date (if applicable)	N/A .
9	No. of Bid Technically Qualified (if applicable)	N/A .
10	Bid (s) rejected	Nil
11	Financial Bid Opening Date	11/3/2014
12	Bid Evaluation Report	

S #	NAME OF FIRM OR BIDDER	COST OFFERED BY THE BIDDERS	RANKING IN TERMS OF COST	COMPARISON WITH ESTIMATED COST	REASON FOR ACCEPTANCE/ REJECTION	REMARKS
1	M/s. RS Enterprises	Rs. 2,118,084/-	1st Lowest	@ 0.0071% Below	Substantially Responsive	P.O # 6274553 Dt:06-03-2014 Rs.43,000/- Bank Al Habib Karimabad Br
2	M/s. Nabih & co.	Rs.2,131,734/-	2nd Lowest	@ 0.6372% Above	Substantially Responsive	P.O # 284457 Dt:06-03-2014 Rs.43,000/- Summit Bank Karimabad Br karachi

The all concerned bidder are being informed accordingly.
The E.E Concerned for compliance of rule 45 of SPPRA 2010 M/s. RS Enterprises. declared as the lowest responsive bidder by the Committee and recommended for Sanction from Competent Authority.

(Abdul Jabbar Shaikh)
Accounts Officer (Central)
Member/Secretary

(Saif-ul-Haque)
Additional Director Internal
Audit - KMC Member

(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member

(Syed Fahim Akhtar Zaidi)
Chief Engineer (Central)
Member

(Abdul Rahim Khattai)
Chief Engineer (IPD),
(Convener)

NAME OF WORK: REPLACEMENT OF WORN OUT / DAMAGED 12" DIA SEWERAGE LINE BY PROVIDING AND LAYING 12" DIA RCC SEWER PIPE LINE ADJACENT MASJID-E- UMAR BLOCK-20 GULBERG.


COMPARATIVE STATEMENT


S.No	Description of Work	Engineer's Estimate				M/s. RS Enterprises		M/s. Nabiha & Co.	
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount
1	Dismantling & removing road mantling Excavation for pipe line in trenches, and pits in all kind of soils of murum i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade, cutting joint holes and disposal of surplus earth within a one chain as directed by engineer in charge, Providing fence guards, lights, flags and temporary crossing for non vehicular traffic where ever required lift up to 5 ft. (1.52m) and lead up to one chain (30.5m)	8100	605.00	% Cft	49,005.00	605.00	49,005.00	605.00	49,005.00
2	Add for additional lift of every three ft or part there of in item No.1 to 15 (A&B) excavation for pipe lines and storage tanks trenches and pits. 5 to 8 ft	40500	4,650.00	% 0 Cft	188,325.00	4,650.00	188,325.00	4,650.00	188,325.00
3	Full hire charges of the pumping per day inclusive of wage of driver & Assistant, fuel or Electric. Energy plate from required for placing pumps etc. at lower depth with suction and delivery pipes for pumping out water found at various depths from trenches i/c the cost of erection and dismantling after completion of the job. Hire charges pumping set of up to 10 HP pumping out water from 10 ft deep trench	56 Day	1,500.00	P/Day	84,000.00	1,500.00	84,000.00	1,600.00	89,600.00


(Handwritten signatures and initials)


NAME OF WORK: REPLACEMENT OF WORN OUT / DAMAGED 12" DIA SEWERAGE LINE BY PROVIDING AND LAYING 12" DIA RCC SEWER PIPE LINE ADJACENT MASJID-E- UMAR BLOCK-20 GULBERG.

S.No	Description of Work	Engineer's Estimate				M/s. RS Enterprises		M/s. Nabiha & Co.	
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount
4	Providing, Laying RCC pipes with Rubber Ring Joint and fitting in trench i/c cutting rubber ring i/c testing with water to specified pressure. 12" dia	2700	367.00	P/Rft	990,900.00	368.00	993,600.00	370.00	999,000.00
5	Providing Manhole 4 feet internal diameter without RCC manhole cover with C.I frame (15 kg) and 5 feet clear depth cast in situ 1:2.4 g" thick wall 1:4 :8 cement concrete in 6ft dia and 6 inch thick in foundation. 1:2;4, 1:2;4 CC in benching Vz" cement plaster 1:3 cement mortar on inside wall and surface of channel and benching to top Including making required number of main and branches channels%" dia abrs M.S rest at 12" C/C kind of soil back filling and disposal of excavated stuff etc complete, as per design and instruction of the engineer in charge								
6	Extra for depth beyond 5' depth, if less than 5, deduction will be made at the same rate	28 Nos	14,529.29	Each	406,820.12	14,500.00	406,000.00	14,500.00	406,000.00
7	Making connections with the existing manholes i/c cost of cutting holes in walls, making them good in cement concrete 1:2;4 and making the required channel etc com lete	27 Rft	2,538.62	P/Rft	68,542.74	2,538.62	68,542.74	2,538.62	68,542.74
8	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc. complete	50 Nos	180.00	Each	9,000.00	175.00	8,750.00	200.00	10,000.00
		61486 Cft	2,760.00	% 0 Cft	169,701.36	2,760.00	169,701.36	2,760.00	169,701.36













NAME OF WORK: REPLACEMENT OF WORN OUT / DAMAGED 12" DIA SEWER AND LAYING 12" DIA RCC SEWER PIPE LINE ADJACENT MASJID-E-UMAR B

S. No.	Description of Work	Engineer's Estimate			M/s. Nabiha & Co.	
		Quantity	Rate	Unit	Rate	Amount
9	Manufacturing and supplying of 21" RCC Manhole cover cast in situ 1:2.4 concrete ratio 3" deep at centre reinforced with 1/2" dia for steel bar at 4" c/c welded to 3/16" thick 2" wide M.S plate and two hook of 3/8" dia for bars i/c compacting, i/c curing & transportation within 10 miles.	28 Nos	913.63	Each	900.00	25,200.00
	Total Quoted / Corrected Cost					2,131,734.10
	Say					2,131,734


 (Abdul Jabbar Shaikh)
 Accounts Officer (Central)
 Member/Secretary


 (Saif-ul-Haque)
 Additional Director Internal
 Audit - KMC Member


 (Ahmed Shaikh)
 Chief Engineer (KMC)
 Member


 (Syed Fahim Akhtar Zaidi)
 Chief Engineer (Central)
 Member


 (Abdul Raheem)
 Chief Engineer (Central)