SINDH PUBLIC PROCUREMENT REGULATORY AUTHORITY



CONTRACT EVALUATION FORM

TO BE FILLED IN BY ALL PROCURING AGENCIES FOR PUBLIC CONTRACTS OF WORKS, SERVICES & GOODS

| 1) | NAME OF THE ORGANIZATION / DEPTT. Works & Sowices Depart min |
|----------|---|
| 2) | PROVINCIAL GLOCAL CONTLICTURE Dictaint Government. |
| 3) | Cart to of Road |
| 4) | TENDER NUMBER NIT NO 230 dated 03.12.2010 Hal mos Rombat Pinkhil |
| 3) 5) | BRIEF DESCRIPTION OF CONTRACT Construction of Road Hyd. MPS Road at Pinkhill 2/1-3/2 |
| 6) | FORUM THAT APPROVED THE SCHEME Local Government of Sindh |
| 7) | TENDER ESTIMATED VALUE Rs: 10.000/260) |
| 2010 | ENGINEER'S ESTIMATE RS: 9. 990/=(m1 |
| 8) | (For civil works only) |
| 9) | ESTIMATED COMPLETION PERIOD (AS PER CONTRACT) & Month |
| | TENDER OPENED ON (DATE & TIME) 04-07-20/0 at 2:00 Pm |
| | NUMBER OF TENDER DOCUMENTS SOLD 03 Nos (Attach list of buyers) |
| 12 | NUMBER OF BIDS RECEIVED 03 NOS |
| 13 | NUMBER OF BIDDERS PRESENT AT THE TIME OF OPENING OF BIDS 03 NOS |
| 14 |) BID EVALUATION REPORT (Enclose a copy) NAME AND ADDRESS OF THE SUCCESSFUL BIDDER M/L Muyamil Suy Services 1. 87 80 202 |
| 15 | NAME AND ADDRESS OF THE SUCCESSFUL BIDDER M/L MINGOUNT SWY |
| | CONTRACT AWARD PRICE R: 97.98203 /= |
| | |
| 17 |) RANKING OF SUCCESSFUL BIDDER IN EVALUATION REPORT 1st Nos (i.e. 1 st , 2 nd , 3 rd EVALUATION BID). |
| | |
| | |
| | |
| 18 | 8) METHOD OF PROCUREMENT USED : - (Tick one) |
| | a) SINGLE STAGE - ONE ENVELOPE PROCEDURE Demostic/ Local |
| | |
| | b) SINGLE STAGE - TWO ENVELOPE PROCEDURE |
| | |

To.

M/S Muzamil Engineering Services, Government Contractor, Tando Allahyar.

SUBJECT: CONSTRUCTION OF ROAD FROM HYDERABAD MIRPURKHAS ROAD @ PIR KATHI DHINGANO BOZDAR ROAD DEH REECHAL VIA DEHS, GUJJO DARRO, KUBBI, DHANDH SHAH MILE 2/1-3/2.

REFERENCE: Your B-I tender dated 04-01-2011.

Your quoted rate premium i.e. Part "A" @ 10.45% Above (Ten Point Four Five % Above) for Road work, Part "B" @ 34.90% Above (Thirty Four Point bline Zero % Above) for culverts the tender being the lowest is hereby approved.

You are accordingly informed to please start the aforesaid work within 7 (Seven) days from the date of issue of this work order under the supervision of the Beputy District Officer (Roads) Tando Aliahyar and note that the work is to be completed with in a period of (06) Months.

You are also requested to please execute the whole and every part of the work exactly full in accordance with the specification, design, drawings and instructions in writing relating to the work duly singed by the undersigned and lodged in my office. You are cruitled to have access to the same for the purpose of inspection during office hours. If required to make or cause to be made copies of the same specifications and all with Design. Drawings and instruction as aforesaid. The extra conditions as per insecutive District Officer (W&S) Department Tando Allahyar letter No. quoted above, is also given below for your information and strict compliance.

- No premiums shall be allowed on non-schedule nems.
- ii) No separate payment for carriage of materials shall be made. Premium quoted by the contractor covers the cost of carriage of materials involved.
- All materials required for construction shall be procured and brought at site by contractor at his own cost from approved sources/quarries.
- iv) No payment of extra item shall be made unless written order is given to contractor by the District Officer for execution of such extra items and approved by the competent authority.
- Income Tax shall be deducted from the bill on the value of work degree of paid for as per latest orders of competent authority in this regard



- vi) Contractor shall arrange bitumen from the National Refinery only and payment on account of bitumens item / work done shall be made on production of such certificate by the contractor from the National Refinery.
- vii) Work will be carried out strictly as per PWD specification.
- viii) All requisite codal formalities will be observed before start of work.
- ix) Water charges and all leads and lifts of material arc included in the item of work.
- x) If any omission and error found in schedule "B" which will be jointly initialed by the Contractor and District Officer before issuance of work order.
- xi) Item of earth work 95% compaction shall not be executed without use of vibratory road roller.
- xii) No escalation whatever will be allowed the work is continued is next year for want of requisite funds.

The photo-state copies of Schedule-B, (Part A & B) duly attested by the undersigned also enclosed herewith for your information & guidance.

You should give in writing the name of your authorized agent who would receive instructions at the site of work during the course of its execution and also attend this office for signing the agreement.

DISTRICT OFFICER (ROADS)
TANDO ALLAHYAR

Copy forwarded to the Deputy District Officer (Roads) Tando Allahyar for information and necessary action. The copies of Schedule-B (Part A & B) are enclosed herewith for his record and carrying out the work accordingly. The work should strongly be carried out as per P.W.D. specifications. The date of start of work should also be reported to this office for record.

DISTRICT OFFICER (ROADS)
TANDO ALL HYAR

OFFICE OF THE DISTRICT OFFICER (ROADS) TANDO ALLAHYAR

COMPARATIVE STATEMENT

B.I

Date of issue

04-01-2011

Date of opening

04-01-2011

NAME OF WORK:

Construction of road from Hyderabad Mirpurkhas road @ Pir Kathi Dhingano Bozdar road Deh Reechal via Dehs, Gujjo Darro,

Kubbi, Dhandh Shah mile 2/1-3/2

| | S.No | Name of Contractor Whom Tender issued | Road Work Part (A) Construction | Road Work Part (B) Culverts | M. Structure (1) (2) (3) |
|---|------|--|---------------------------------------|-----------------------------------|---|
| | 01 | 02 | 03 | 0,4 | 05 |
| | 1, | M/s Muzmil | 10.45% | 34.907 | |
|) | | Ergy: Sorrices | abaire | abare. | |
| - | | | | | |
| | >/- | W. Runtag Ali | 11.30% | 36.409 | |
| | | av: Rumboz Ali' Prozenda | Work | 36.40 % | |
| | | | | - 1/ | |
| | 37- | W Abdul Hales | n 11.854 | 37.107 | 77 11 11 14 1 - 14 10 10 10 10 10 10 10 10 10 10 10 10 10 |
| | / | Timojo | Naha | abake. | |

Certified that the tenders have been opened before us.

DIVISIONAL ACCOUNTS OFFICER DISTRICT OFFICER (ROADS)

TANDO ALLAHYAR

DISTRICT OFFICER (ROADS)

Opened in my Persence

EXECUTIVE DISTRICT OFFICER
WORKS & SERVICES DEPARTMENT

WORKS & SERVICES DEPARTMENT E.D.O. WORKS & SERVICES TANDO ALLAHYAR D.O. ROADS & TRANSPORT TANDO ALLAHYAR

Issued to Mr./Messrs. Muzamil Engy Services

And charged Rs: 3000 =

D.R. No. 10 | 33 dt. 0411

N.I.T. No. TC/G-55/DOR/230

Dated: 03-12-2010

DISTRICT OFFICER ROADS TANDO ALLAHYAR

B-1 TENDER FOR WORKS

I/ We hereby tender for the execution, for the Governor of Sindh, (hereinbefore) and hereinafter referred to as "Government"), of the work specified in the under written memorandum within the time specified in such memorandum at (Part "A" 11-45 % Above) Belew Part "B34-90% Above/Below, Part "C"———— % Above/Below & Part "D"——— % Above/Below the estimated rates entered in Schedule 'B' (memorandum showing items of work to be carried cut and in accordance in all respects with the specifications, designs, drawings and instructions in writing referred to in Rule here of and in Clause-12 of the annexed conditions of contract and agree that when materials for the work are provided by the Government such materials and the rates to be paid for them shall be as provided in Schedule 'A' hereto.

MEMORANDUM

1. General Description

Construction of road from Hyderabad Mirpurkhas road @ Pir Kathi Dhingano Bozdar road Deh Reechal via Dehs, Gujjo Darro, Kubbi, Dhandh Shah mile 2/1-3/2

Opened in my Persence

E.D.O

(a) Estimated Cost

Rs. 10000000 /=

(b) Earnest Money 2% Rs. 200000 /=

Security Deposit (i/c E/Money) 5% (:

Rs.

Percentage, if any, to be deducted (d)

500000 /=

from bills 3%

Rs. 300000 /=

(e) Time allowed for the work from date of written order to commence.

(06) Months

Should this tender be accepted. I/We hereby agree to abide by any fulfill all the terms and provisions of the conditions of contract annexed here to so far as applicable, and in default there of to forfeit and ay to Government the sum of money mentioned in the said conditions

Receipt / Call Deposit No. 0000319 dated 21-12-2010 from Manyan bank limital at Tando Multyr in respect of the sum of Rs. 200000/2 is herewith forwarded representing the earnest money (a) the full

value of which is to be absolutely forfeited to government should 1 / We not deposit the full amount of security deposit specified in the above memorandum, in accordance with Clause@1 (A) of the said conditions, otherwise the said sum of Rs. ________________ shall be retained by Government on account of such security deposit as aforesaid, or (b) the full value of which shall be retained by the Government on account of the security deposit specified in Clause-(B) of the conditions.

FFICER (ROADS)

NAME OF WORK:- CONSTRUCTION

OF ROAD FROM MIRPURKHAS ROAD @ PIR KATHI DHINGANO BOZDAR ROAD DEH REECHAL VIA DEHS, GUJJO DARRO, KUBBI,

DHANDH SHAH MILE 2/1-3/2 = 1.80 KM (PART-A)

S.NO QTY ITEM OF WORK RATE UNIT AMOUNT

1-EARTH WORK

Earth work for road embankment by bulldozers including ploughing, mixing, clod breaking, dressing with optimum moisture content, lead up to 100 ft and lift up to 5 ft in all types of soil except rock. (If earthwork is done by other than departmental agency).

85 % Density

623500 Cft W/O Lead 396400 Cft With Lead

@ Rs. 2515.39 %0 Cft @ Rs. 4408.53 %0 Cft Rs. 1568346.00

95%to 100% Density

Rs. 1747341.00

38069 Cft W/O Lead

@ Rs. 3660.67 %0 Cft

Rs. 139358.00

47586 Cft With Lead

@ Rs. 5377.55 %0 Cft

Rs. 255896.00

Preparing SUB-BASE COURSE by supplying and spreading stone metal approved quality form approved quarry properly graded to maximum size 1 1/2" required thickness of proper camber and spreading 15 cft screening and non plastic quarry fines filling depression with stone metal after initial rolling watering and compacting the same so as to achieve 100% density as per modified AASHO specifications Rate i/cs providing and using templates, camber, plates screens farm and directed, rate i/cs all cost of materials t&P carriage upto site of work.

36709 Cft

?(

@ Rs. 3422.90 % Cft

Rs. 1256512.00

3-BRICK ON EDGING Laying of including supplying of 9" x4 1/2" x 3" 1st class burnt bricks excavation for laying edging with small side parallel to the road. Rate including all cost of material T&P and carriage upto 3 chains.

11880 Rft

@ Rs. 827.05% Rft

Rs. 98254.00

4-BASE COURSE Preparing by supplying and spreading stone metal approved quality form approved quarry properly graded to maximum size 1 1/2" required thickness of proper camber and spreading 15 cft screening and non plastic quarry fines filling depression with stone metal after initial rolling watering and compacting the same so as to achieve 100% density as per modified AASHO specifications Rate i/cs providing and using templates, camber, plates screens (1) **(1)** (1) (1) farm and directed, rate i/cs all cost of materials t&P carriage upto site of work.

36709 Cft

@ Rs. 3596.46% Cft

Rs. 1320225.00

THREE COAT Providing Three Coat of surface dressing on new or existing surface with 40 + 5-25 +14 = 79 lbs of bitumen 80/100 penetration and 5.50 + 2.75 + 1.5 = 9.75 cft bajri of 3/4" x 1/2" gauge for first coat, 1/2" - 3/8" gauge for 2nd Coat, 3/8" - 1/4" for 3rd Coat i/c cleaning the road surface before lying each coat and rolling with power roller laying each coat separately. Rate includes all cost of materials T&P and carriage up to site of work.

73418 Sft

@ Rs. 997.89 Sft

Rs. 732631.00

EARTH WORK for embankment form B.Pits i/c laying in 6" layer clod breaking dressing 6etc. complete load upt 100cft and lift up to 5.0 ft. (in ordinary soil).

40703 Cft W/O Lead

@ Rs. 970.40 % Rft

39498.00

50878 Cft With Lead

@ Rs. 3854.80 % Rft

Rs. 196195.00

TOTAL

Rs. 7354386.00

Add: Diff: Cost Bitumen 25.79 Tons @ Rs. 50035.07 =

Rs. 1295408.00

G. TOTAL

Rs. 8649094.00

I/We undertake to accept any change in quantities rates and amount as per Technically, Sanctioned Estimates.

2. I/We shall not claim any change in the quoted premium.

NAME OF WORK:- CONSTRUCTION OF ROAD FROM HYDERABAD MIRPURKHAS ROAD @ PIR KATHI DHINGANO BOZDAR ROAD DEH REECHAL VIA DEHS, GUJJO DARRO, KUBBI, DHANDH SHAH MILE 2/1-3/2 = 1.80 KM 3' SPAN RCC SLAP CULVERT (PART-B)

QTY S.NO ITEM OF WORK RATE **AMOUNT** UNIT 1. Excavation in foundation of building bridges and other structure i/c dag belling dressing refilling around structure with excavated stuff watering ramming lead upto 100" and lift upto 5 feet (in ordinary soil). 1190 Cft @ Rs. 1306/80 per %0 cft. Rs. 1555.00 Cement concrete brick on stone metal ballast Ratio 1:4:8 245 Cft @ Rs. 3584/10 per %0 Cft. Rs. 8781.00 3. Pucca brick work ratio 1:4 work in foundation and plinth in cement sand mortar Ratio 1:4. 597 Cft @ Rs. 4150.30 per %0 Cft. Rs. 24777.00 4. Cement concrete plain i/c compacting finishing & curing etc complete (i/c screening of aggregate w/o shuttering) ratio 1:2:4 84 Cft @ Rs. 5941/10 per % cft. Rs. 4991.00 5. Fabrication of mild steel reinforcement for cement concrete i/c cutting bending binding laying in position making joints & festering i/c cost of binding wire also i/c removal of rust form bars. 5.67 Cwt. @ Rs. 2651/55 per Cwt Rs. 15034.00 6. R.C.C work i/c all labour & material except the cost of steel reinf: and its labor for binding and remning which will be paid separately rate including all kinds of forms A COMMENT OF moulds lighting shuttering curing rendering and finishing surface i/c screaming and finishing pre-cast laid in position complete in all respect ration 1:2:4. 81 Cft @ Rs. 114/00 per % cft. Rs. 9234.00 7. Brick on edge flooring laid in 1:6 cement Mortar over a bed of 3/4" thick cement mortar 1:7 Bed flooring. 79 Rft @ Rs. 1736/13 per % Sft. Rs. 1372.00 Cement Plaster 1:3 upto 20.0' height 1/2 " thick. 361 Sft @ Rs. 604/18 per % Sft. Rs. 2181.00 Erection and removal of cetentering for cement concrete (Plan). 107 Sft @ Rs. 1405/75 per % Sft. Rs. 1504.00 **Grand Total** Rs. 69429.00

> I/We undertake to accept any change in quantities rates and amount as per Technically, Sanctioned Estimates.

I/We shall not claim any change in the quoted premium.

CONTRACTOR,

DISTRICT OFFICER (ROADS)
TANDO ALLAHYAR

WORKS & SERVICES DEPARTMENT E.D.O. Issued to Mr./Messrs. Mumbers Alice WORKS & SERVICES TANDO ALLAHYAR D.O. ROADS & TRANSPORT TANDO ALLAHYAR

Pizzaila Government Bortseter And charged Rs: 300) =

D.R. No. 10 38 dt. 04 11 2011

N.I.T, No. TC/G-55/DOR/230

Dated: 03-12-2010

ROADS TANDO ALLAHYAR

B-1 TENDER FOR WORKS

I/ We hereby tender for the execution, for the Governor of Sindh, (hereinbefore) and hereinafter referred to as "Government"), of the work specified in the under written memorandum within the time specified in such memorandum at Part "A" 11.30 % Above/Below Part "B" 30 % Above/Below & Part "D" 4% Above/Below the estimated rates entered in Schedule 'B' (memorandum showing dems of work to be carried and in accordance in all respects with the appears of work to be carried out and in accordance in all respects with the specifications, designs, drawings and instructions in writing referred to in Rule-I here of and in Clause-12 of the annexed conditions of contract and agree that when materials for the work are provided by the Government such materials and the rates to be paid for them shall be as provided in Schedule 'A' hereto.

MEMORANDUM

General Description 1.

: Construction of road from Hyderabad Mirpurkhas road @ Pir Kathi Dhingano Bozdar road Deh Reechal via Dehs, Gujjo Darro, Kubbi, Dhandh Shah mile 2/1-3/2

Opened in my Persence

(a) Estimated Cost

Rs. 100000000 /=

E.D.O

(b) Earnest Money 2% Rs. 200000 /=

... Security Deposit (i/c E/Money) 5%

Rs. 500000 /=

Percentage, if any, to be deducted (d)

from bills 3%-

Rs. 300000 /=

Time allowed for the work from (e) date of written order to commence.

(06) Months

Should this tender be accepted. I/We hereby agree to abide by any fulfill all the terms and provisions of the conditions of contract annexed here to so far as applicable, and in default there of to forfeit and ay to Government the sum of money mentioned in the said conditions.

Receipt / Call Deposit No. 2278035 dated 22-12-200 from United Bank LMCH BK at Hyderestad in respect of the sum of Rs. 2000/2 is herewith forwarded representing the earnest money (a) the full

value of which is to be absolutely forfeited to government should 1 / We not deposit the full amount of security deposit specified in the above memorandum, in accordance with Clause01 (A) of the said conditions, otherwise the said sum of Rs. 2000/2 shall be retained by Government on account of such security deposit as aforesaid, or (b) the full value of which shall be retained by the Government on account of the security deposit specified in Clause-1 (B) of the conditions.

CONTRACTOR

NAME OF WORK:- CONSTRUCTION OF ROAD FROM HYDERABAD MIRPURKHAS ROAD @ PIR KATHI DHINGANO BOZDAR ROAD DEH REECHAL VIA DEHS, GUJO DARRO, KUBBI,

DHANDH SHAH MILE 2/1-3/2 = 1.80 KM (PART-A)

QTY S.NO ITEM OF WORK RATE UNIT AMOUNT

1- EARTH WORK

Earth work for road embankment by bulldozers including ploughing, mixing, clod breaking, dressing with optimum moisture content, lead up to 100 ft and lift up to 5 ft in all types of soil except rock. (If earthwork is done by other than departmental agency).

85 % Density

623500 Cft **W/O Lead** @ Rs. 2515.39 %0 Cft 396400 Cft **With Lead** @ Rs. 4408.53 %0 Cft

Rs. 1568346.00 Rs. 1747**5**41.00

95%to 100% Density

38069 Cft W/O Lead 47586 Cft With Lead @ Rs. 3660.67 %0 Cft @ Rs. 5377.55 %0 Cft Rs. 139358.00

Rs. 2558 6.00

Preparing SUB-BASE COURSE by supplying and spreading stone metal approved quality form approved quarry properly graded to maximum size 1 ½" required thickness of proper camber and spreading 15 cft screening and non plastic quarry fines filling depression with stone metal after initial rolling watering and compacting the same so as to achieve 100% density as per modified AASHO specifications Rate i/cs providing and using templates, camber, plates screens farm and directed, rate i/cs all cost of materials t&P carriage upto site of work.

36709 Cft

@ Rs. 3422.90 % Cft

Rs. 1256512.00

3- BRICK ON EDGING Laying of including supplying of 9" x4 ½" x 3" 1st class burnt bricks excavation for laying edging with small side parallel to the road. Rate including all cost of material T&P and carriage upto 3 chains.

11880 Rft

@ Rs. 827.05% Rft

Rs. 98254.00

4- BASE COURSE Preparing by supplying and spreading stone metal approved quality form approved quarry properly graded to maximum size 1 ½" required thickness of proper camber and spreading 15 cft screening and non plastic quarry fines filling depression with stone metal after initial rolling watering and compacting the same so as to achieve 100% density as per modified AASHO specifications Rate i/cs providing and using templates, camber, plates screens farm and directed, rate i/cs all cost of materials t&P carriage upto site of work.

36709 Cft

@ Rs. 3596.46% Cft

Rs. 1320225.00

5- THREE COAT Providing Three Coat of surface dressing on new or existing surface with 40 + 25 +14 = 79 lbs of bitumen 80/100 penetration and 5.50 + 2.75 + 1.5 = 9.75 cft bajri of 3/4" x 1/3" gauge for first coat, 1/2" – 3/8" gauge for 2nd Coat, 3/8" – 1/4" for 3rd Coat i/c cleaning the road surface before lying each coat and rolling with power roller laying each coat separately. Rate includes all cost of materials T&P and carriage up to site of work.

73418 Sft

@ Rs. 997.89 Sft

Rs. 732631.00

6- EARTH WORK for embankment form B.Pits i/c laying in 6" layer clod breaking dressing etc. complete load upt 100cft and lift up to 5.0 ft. (in ordinary soil).

40703 Cft W/O Lead

@ Rs. 970.40 % Rft

Rs. 39498.00

50878 Cft With Lead

@ Rs. 3854.80 % Rft

Rs. 196124.00

TOTAL

Rs. 7354386.00

Add: Diff: Cost Bitumen 25.79 Tons @ Rs. 50035.07 =

Rs. 1295408.00

G. TOTAL

Rs. 8649004.00

 I/We undertake to accept any change in quantities rates and amount as per Technically, Sanctioned Estimates.

2. I/We shall not claim any change in the quoted premium.

CONTRACTOR

NAME OF WORK:- CONSTRUCTION OF ROAD FROM HYDERABAD MIRPURKHAS ROAD @ PIR KATHI DHINGANO BOZDAR ROAD DEH REECHAL VIA DEHS, GUJJO DARRO, KUBBI, DHANDH SHAH MILE 2/1-3/2 = 1.80 KM 3' SPAN RCC SLAP CULVERT (PART-B)

QTY S.NO ITEM OF WORK RATE UNIT **AMOUNT** 1. Excavation in foundation of building bridges and other structure i/c dag belling dressing refilling around structure with excavated stuff watering ramming lead upto 100" and lift upto 5 feet (in ordinary soil). 1190 Cft @ Rs. 1306/80 per %0 cft. Rs. 1555.00 2. Cement concrete brick on stone metal ballast Ratio 1:4:8 245 Cft @ Rs. 3584/10 per %0 Cft. Rs. 8781.00 3. Pucca brick work ratio 1:4 work in foundation and plinth in cement sand mortar Ratio 1:4. 597 Cft @ Rs. 4150.30 per %0 Cft. Rs. 24777.00 4. Cement concrete plain i/c compacting finishing & curing etc complete (i/c screening of aggregate w/o shuttering) ratio 1:2:4 84 Cft @ Rs. 5941/10 per % cft. Rs. 4991.00

> Fabrication of mild steel reinforcement for cement concrete i/c cutting bending binding laying in position making joints & festering i/c cost of binding wire also i/c removal of rust form bars.

> > 5.67 Cwt.

@ Rs. 2651/55

per Cwt

Rs. 15034.00

 R.C.C work i/c all labour & material except the cost of steel reinf: and its labor for binding and remning which will be paid separately rate including all kinds of forms moulds lighting shuttering curing rendering and finishing surface i/c screaming and finishing pre-cast laid in position complete in all respect ration 1:2:4.

81 Cft

ROCCOS AND TO

@ Rs. 114/00

per % cft.

Rs. 9234.00

 Brick on edge flooring laid in 1:6 cement Mortar over a bed of ¾" thick cement mortar 1:7 Bed flooring.

79 Rft

@ Rs. 1736/13

per % Sft.

Rs. 1372.00

8. Cement Plaster 1:3 upto 20.0' height 1/2 " thick.

361 Sft

@ Rs. 604/18

per % Sft.

Rs. 2181.00

9. Erection and removal of cetentering for cement concrete (Plan).

107 Sft

@ Rs. 1405/75

per % Sft.

Rs. 1504.00

Grand Total

Rs. 69429.00

 I/We undertake to accept any change in quantities rates and amount as per Technically, Sanctioned Estimates.

I/We shall not claim any change in the quoted premium

CONTRACTOR

WORKS & SERVICES TANDO ALLAHYAR D.O. ROADS & TRANSPORT TANDO ALLAHYAR

WORKS & SERVICES DEPARTMENT E.D.O. Issued to Mr./Messrs. Abolul Hoale Turejo Loverment Contral

And charged Rs: 3000

D.R. No. 10139

N.I.T. No. TC/G-55/DOR/230 Dated: 03-12-2010

DISTRICT OFFICER ROADS TANDO ALLAHYAR

B-1 TENDER FOR WORKS

I/ We hereby tender for the execution, for the Governor of Sindh, (hereinbefore) and hereinafter referred to as "Government"), of the work specified in the under written the estimated rates entered in Schedule 'B' (memorandum showing items of work to be carried out and accordance in all respects with the specifications, designs, drawings and -structions in writing referred to in Rule-I here of and in Clause-12 of the annexed conditions of contract and agree that when materials for the work are provided by the Government such materials and the rates to be paid for them shall be as provided in Schedule 'A' hereto.

MEMORANDUM

General Description

Construction of road from Hyderabad Mirpurkhas road (a) Pir Kathi Dhingano Bozdar road Deh Reechal via Dehs, Gujjo Darro, Kubbi, Dhandh Shah mile 2/1-3/2

Opened in my Persence

E.D.O

(a) Estimated Cost Rs. 10000000 /=

Earnest Money 2% (b)

Rs. 200000 /=

Security Deposit (i/c E/Money) 5% (0)

Rs. 500000 /=

Percentage, if any, to be deducted (d)

300000 /= Rs.

from bills 3%

(06) Months

Time allowed for the work from (e) date of written order to commence.

Should this tender be accepted. I/We hereby agree to abide by any fulfill all the terms and provisions of the conditions of contract annexed here to so far as applicable, and in default there of to forfeit and ay to Government the sum of money mentioned in the said conditions

Receipt / Call Deposit No. 2240926 dated 29-12-200 from Unifeel but Bit. Racel Br Hydrabad in respect of the sum of Rs. 2000/2 is herewith forwarded representing the earnest money (a) the full

value of which is to be absolutely forfeited to government should I / We not deposit the full amount of security deposit specified in the above memorandum, in accordance with Clause01 (A) of the said conditions, otherwise the said sum of Rs. 200000 shall be retained by Government on account of such security deposit as aforesaid, or (b) the full value of which shall be retained by the Government on account of the security deposit specified in Clause-1 (B) of the conditions.

DISTRICT OFFICER (ROADS) TANDO ALLAHYAR

NAME OF WORK:- CONSTRUCTION OF ROAD FROM HYDERABAD MIRPURKHAS ROAD @ PIR KATHI DHINGANO BOZDAR ROAD DEH REECHAL VIA DEHS, GUJJO DARRO, KUBBI, DHANDH SHAH MILE 2/1-3/2 = 1.80 KM (PART-A)

| QTY S.NO | ITEM OF WORK | RATE | UNIT | AMOUNT |
|----------|--------------|------|------|--------|
|----------|--------------|------|------|--------|

1- EARTH WORK

Earth work for road embankment by bulldozers including ploughing, mixing, clod breaking, dressing with optimum moisture content, lead up to 100 ft and lift up to 5 ft in all types of soil except rock. (If earthwork is done by other than departmental agency).

85 % Density

38069 Cft W/O Lead @ Rs. 3660.67 %0 Cft 47586 Cft With Lead @ Rs. 5377.55 %0 Cft

%0 Cft Rs. 139358.00 %0 Cft Rs. 255836.00

Preparing SUB-BASE COURSE by supplying and spreading stone metal approved quality form approved quarry properly graded to maximum size 1 ½" required thickness of proper camber and spreading 15 cft screening and non plastic quarry fines filling depression with stone metal after initial rolling watering and compacting the same so as to achieve 100% density as per modified AASHO specifications Rate i/cs providing and using templates, camber, plates screens farm and directed, rate i/cs all cost of materials t&P carriage upto site of work.

36709 Cft

@ Rs. 3422.90 % Cft

Rs. 1256512.00

3- BRICK ON EDGING Laying of including supplying of 9" x4 ½" x 3" 1st class burnt bricks excavation for laying edging with small side parallel to the road. Rate including all cost of material T&P and carriage upto 3 chains.

11880 Rft

@ Rs. 827.05% Rft

Rs. 98254.00

4- BASE COURSE Preparing by supplying and spreading stone metal approved quality form approved quarry properly graded to maximum size 1 ½" required thickness of proper camber and spreading 15 cft screening and non plastic quarry fines filling depression with stone metal after initial rolling watering and compacting the same so as to achieve 100% density as per modified AASHO specifications Rate i/cs providing and using templates, camber, plates screens farm and directed, rate i/cs all cost of materials t&P carriage upto site of work.

36709 Cft

@ Rs. 3596.46% Cft

Rs. 1320225.00

5- THREE COAT Providing Three Coat of surface dressing on new or existing surface with 40+ 25+14=79 lbs of bitumen 80/100 penetration and 5.50 + 2.75 + 1.5 = 9.75 cft bajri of 3/4" x 1/2" gauge for first coat, 1/2" – 3/8" gauge for 2nd Coat, 3/8" – 1/4" for 3rd Coat i/c cleaning the road surface before lying each coat and rolling with power roller laying each coat separately. Rate includes all cost of materials T&P and carriage up to site of work.

73418 Sft

@ Rs. 997.89 Sft

Rs. 732631.00

6- EARTH WORK for embankment form B.Pits i/c laying in 6" layer clod breaking dressing etc. complete load upt 100cft and lift up to 5.0 ft. (in ordinary soil).

40703 Cft W/O Lead

@ Rs. 970.40 % Rft

Rs. 39498.00

50878 Cft With Lead

@ Rs. 3854.80 % Rft

Rs. 196109.00

TOTAL

Rs. 7354\$86.00

Add: Diff: Cost Bitumen 25.79 Tons @ Rs. 50035.07 =

Rs. 1295408.00

G. TOTAL

Rs. 8649694.00

 I/We undertake to accept any change in quantities rates and amount as per Technically, Sanctioned Estimates.

2. I/We shall not claim any change in the quoted premium.

CONTRACTOR

NAME OF WORK:- CONSTRUCTION OF ROAD FROM HYDERABAD MIRPURKHAS ROAD @ PIR KATHI DHINGANO BOZDAR ROAD DEH REECHAL VIA DEHS, GUJJO DARRO, KUBBL DHANDH SHAH MILE 2/1-3/2 = 1.80 KM 3' SPAN RCC SLAP CULVERT (PART P)

| | | | DHANDH SHAH MI CULVERT (PART-B) | $\frac{\text{AL VIA DEI}}{\text{LE } 2/1-3/2} = 1$ | IS, GUJJO DARRO, KUBI .80 KM 3' SPAN RCC SLA | BI, AP |
|---------|----|---|---|--|---|------------|
| | Q | TY S.NO ITEM | OF WORK | RATE | UNIT AMOUNT | j |
| | 1 | Excavation in found refilling around stru upto 5 feet (in ordin | cture with excavated s | es and other str tuff watering ra | ructure i/c dag belling dressir imming lead upto 100" and i | ng lift |
| | | 1190 Cft | @ Rs. 1306/80 | per %0 cft. | Rs. 1555.00 | |
| | 2. | Cement concrete br | ick on stone metal balla | ast Ratio 1:4:8 | | |
| | | 245 Cft | @ Rs. 3584/10 | per %0 Cft. | Rs. 8781.00 | |
| | 3. | Pucca brick work Ratio 1:4. | ratio 1:4 work in four | ndation and pl | linth in cement sand morta | аг |
| | | 597 Cft | @ Rs. 4150.30 | per %0 Cft. | Rs. 24777.00 | |
| | 4. | Cement concrete pl aggregate w/o shutte | ain i/c compacting finis ering) ratio 1:2:4 | hing & curing e | etc complete (i/c screening o | of |
| | | 84 Cft | @ Rs. 5941/10 | per % cft. | Rs. 4991.00 | |
| | 5. | Fabrication of mild s laying in position ma form bars. | steel reinforcement for king joints & festering in | cement concre c cost of bindin | ete i/c cutting bending bindin ng wire also i/c removal of rus | g st |
| | | 5.67 Cwt. | @ Rs. 2651/55 | per Cwt | Rs. 15034.00 | |
| <i></i> | 6. | moulds lighting shut | g which will be paid s | eparately rate and finishing | steel reinf: and its labor fo including all kinds of forms surface i/c screaming and ion 1:2:4 | 0 |
| | | 81 Cft | @ Rs. 114/00 | per % cft. | Rs. 9234.00 | |
| | 7. | Brick on edge flooring 1:7 Bed flooring. | ig laid in 1:6 cement M | ortar over a be | ed of ¾" thick cement mortar | ja s |
| | | 79 Rft | @ Rs. 1736/13 | per % Sft. | Rs. 1372.00 | |
| | 8. | Cement Plaster 1:3 u | pto 20.0' height 1/2 " th | ick, | | |
| | | 361 Sft | @ Rs. 604/18 | per % Sft. | Rs. 2181.00 | |
| | 9. | Erection and remova | of cetentering for ceme | ent concrete (P | lan). | |
| | | 107 Sft | @ Rs. 1405/75 | per % Sft. | Rs. 1504.00 | |
| | | | | | | |
| | | | C | T 1 | | |

 I/We undertake to accept any change in quantities rates and amount as per Technically, Sanctioned Estimates.

Grand Total

I/We shall not claim any change in the quoted premium.

CONTRACTOR

DISTRICT OFFICER (ROADS)
TANDO ALLAHYAR

Rs. 69429.00

Name of Agenery: Mk Muzamil Early Services

Vand of No. 105-11-94-50,000 L.F. of 8 is each,

SGP (Klip.) D. No. 105-11-94-50,000 L.F. of 8 is each,

G. R. P. W. D. Nos. 7938 of 6-435

Both General Construction of Seach Deh Reach (WA)

86-1 of 8-6-36, 1958-W of 27-9-37, G.C.M.P. DEHS Fuljo Dazzo Kubbi Dhoudh Sharl

and M. Depit. No. 383-1/37 of 9-11-37

(P. W. D.) No. 8-173, 2-W of 22-2-30, PUBLIC WORKS DEPARTMENT

G. Rs (P. W. D.) No. 1038-1 of 22-2-37

12-10-44 and 2-5-44 654-W of 22-2-39

12-10-44, and 2-5-44, 05-W 1038/13-1 of

28-3-49, 36-47-W 2 of 12-12-50.

DIVISION CIRCLE LA BUO ALLAHYAR Estimate Section to G. 9,9900 (m) DIVISION TANDO ALLAHYAR VIde NO- F.DO (NES) /DR/TS/506. Dated 16-02-2010 Percentage Rate Tender and Contract for works 5-1-2011 General Rules and Directions for the Guidance of Contractors 1. All work proposed to be executed by contract shall be notified in a form of invitation to tender posted on a board hung up in the office of the Executive Engineer and signed by the Executive Engineer. This form will state the work to be carried out, as well as the date for submitting and opening tenders, and the time allowed for carrying out the work; also the amount of earnest money to be deposited with the tender, and the amount of the security deposit to be deposited by the successful tenderers and the percentage, if any to be deducted from bills. It will also state whether a refund of quarry fees, royalities, oetrol dues and ground rents will be granted. Copies of the specificatons designs and awings and estimated rates schedule rates and any other documents required by connection with the work shall be signed by the Excuring and shall also be open for PAKISTAN PAKIST PAKISTAN 2. In the event of the ter بزرومير signed separately by each partner any partner, it shall be signed on attorney authorizing him to do : 3. Receipts for garments : by a firm, shall also be signed tors and described in their reput be signed in the name of the persons having authority to have ADHESIVE 0 4. Any poison who count stating at what percentage bove memorandum showing items of PAKKARY PAKIST PARISPAN PAKISTA der take the work. Only one kill be framed. Tenders, which pro the said form of invitation to te the work, or which contain any No printed form of tender shall contain the printed form of tender shall contain any but if contractors wish to tender separate tender for each. Tend work to which they refer written SPECIAL SPECIAL SPECIAL 5. The Executive Enginee ADHESIVE ADHESIVE tenders, in the presence of contractors who have submitted tenders or their representatives who may be present at the time, and he will enter the amounts of the several tenders in a comparative statement in a suitable form. In the comparative statement in a suitable form. ned in Rule 1. In the event of a tender being rejected the Divisional Officer shall authorize the Treasury Officer concerned to refund the amount of the earnest money for deposited to the contractor making the tender, on his giving a receipt for the returnof the money. 6. The Officer competent to dispose of the tenders shall have right rejecting all or any of the tenders. DISTRICT OFFICER (ROADS) TANDO ALLAHYAR.

so tar as applicable, and in default thereof to forfeit and pay to Government the sums of money mentioned in the said conditions.

Receipt No. 0000319 dated 31-12-274 on Government Treasury or sub-Treasury at Many Back Tails Akhplus Josepho sum of Rs. 200005 is herewith forwarded representing the earnest money [10] the full value of

*Amount to be *pecified in words and figures

which is to be absolutely forfeited to Covernment should - not deposit

Strike out (a) is no the becomity deposit is to be taken.

the full amount of security deposit specified in the above memorandum, in accordance with Clause 1 (A) of the said conditions, otherwise the said sum of Rs.....shall be retained by Goevrnment on account of such security deposite as aforesaid J. or (b) the full value of which shall be retained by the Government on account of the security deposit specified in clause I (B) of the conditions I. ** CONTE

**Strike out (b) ty denosit la to be teken.

Witnesses ***, Templir southwar pro-99900000 - "Signature of contractor before supplied of tender Witnesses ***, Templir southwar pro-999000000 - "Signature of contractor before supplied of tender Witnesses ***, Temply Mme Maintenance of witness to contractor is algorithm. Dated the (Occupation) VICTE EDG (UUTE) DB 170 SOF OF

Rignature of the officers by

The above tender is hereby accepted by me on behalf of Sind.

DISTRICT CHICER (ROADS) Division (or his wife authorized Assistant)

the Covernor

Deitel the

day of

Condition of Contract

ecutivy deposits.

Person whose tender may be accepted (herrinafter called Clause 1 .- The-Persons

the contractor) shall (A) [(within one day for a contract of Rs. 1,000 or. oss, or two days for a contract of more than Rs. 1,000 upto Rs. 2,000 and o on, upto a limit of ten days, for a contract of Rs. 10,000 or more of the receipt by him of the notification of the acceptance of his tender) deposit with the Executive Ingineer in cash or Govi: Securities endorsed to Executive Engineer (if denosited for more then twelve months) a sum sufficient with the amount of the carnest money deposited by him with his tender to make up the full security deposit specified in the tender), or (B) (perhit Government at the time of making any payment to him for work done under the contracts to deduct such sum as well (With the earnest money deposited by him.) amount more percent of all moneys so payable: such deduction to be held by Government by way of security deposit): Provided always that in the event of the contract of depositing a Lump sum by way of security deposit as a contemplated at (A) above, then and in such case, if the sum so depositing that not amount to percent of the total estimated cost of the work it shall be lawful for Government at the time of making any payment to the contractor for work done under the contract to make up the full amount of percent by deducting a sufficient sum from every such payment as last aferesaid. All compensation other sums of money payble by the contractor to Government under the terms of his contract may be deducted from, or paid by the sale of a sufficient part of his security deposit, or from the interest arising therefrom, or from any is due or may be one due sums which to the contractor under and in the event of his security this contract deposit being reduced by reason of any such deduction or sale as aforesaid the contractor shall within ten days thereafter, make good in cash or with Government securities endorsed as aforesaid any sum or sums which may have been deducted from, or raised by sale of his security deposit or any part thereof. The security, deposit referred to, when said in cash, may, at the cost of the depositor, be converted into interest-bearing securities provided that the deposited has or pressly desired this in writing.

DISTRICT OFFICER (ROADS SANDO ALLAHYAR.

- (a). To rescind the contract (of which rescision notice in writen to the contractor under the band of the Executive Engideer shall be conclusive evidence) and in that case the security deposit of the contra7tor shall stand forfeated and be absolutely at the disposal of the Government.
- (b) To employ iabour paid by the Public Work Department and to the supply materials to carry out the work, or any part of the work, debiting the contractor with the cost of the lahour and the price of the materials (as to the correctness of which cost and, price the certificate of the Executive Engineer shall be final and conclusive against the contractor) and crediting him with the value of the work done, to all respects in the same manner and at the same rates as if it had been carried out by the contractor under the terms of his contract; and in that case the certificate of the Executive Engineer, as to the value of the work done shall be final and conclusive against the contractor.
- (c) To measure up the work of the contractor and to take such part thereof as shall be unexecuted out of the hands, and to give it to another contractor to complete in which case any expenses which may be incurred to excess of the sum which would have been paid to the original contractor if the whole work had been executed by him (as to the amount of which excess expenses the certificates in writing of the Executive Engineer shall be final and conclusive) shall be borne and paid by the original contractor and shall to deducted from any money due to him by the Government under the contract or otherwise or from him security deposit or the proceeds of sale thereof, or a sufficient part thereof.

In the event of any of the above courses being adopted by the lixecutive lingineer, the contractor shall have no claim to compensation for any loss sustained by him by reason of his having purchased or procured any materials, or entered into any engagements, or made any advances on account of, or with a view to the execution of the work of the performance of the contract. And in case the contract shall be rescinded under the provision (aforesaid, the contractor shall hot be entitled to recover or to be paid any sum or any work therefore actually performed by him under this contract unless and until the Executive Engineer shall have certified in writing the performance of such work and the amount payable in respect thereof, and he shall only be entitled to be paid the amount to certified.

Clause 4,—If the progress of any particular portion of the work is unsatisfactory Executive Engineer shall, notwithstanding that all the general propress of the work is in accordance with the conditions mentioned in clause 2, be entitled to take action under clause 3 (b) after giving the continuit 10 day's notice in writing. The contractor will have no claim for compensation, for any loss sustained by him owing to such action.

Action when the progress of any particular position of the work to unsatisfactors.

Clause 5.—In any case in which any of the powers conferred upon the Executive Engineer by the clause 3 and 4 thereof shall have become exercise. able and the same shall not have been exercised, the non-exercise thereof shall not constitute a waiver of any of the conditions hereof and such powers shall notwithstanding be exerciseable in the event of any future case of default by the contractor for which under any clause or clauses bereof he is declared liable to pay compensation amounting to the whole of his security deposit and the liability of the contractor for past and future compensation shall remain unaffected. In the event of the Executive Engineer taking action under sub-clause (a) or (c) of clause 3, he may, if he so destres, take possession of sub-clause (a) or (c) of clause 3, he may, it he so desires, take possession of all or any tools, plant, materials and stores in or upon the works, or the site thereof or belonging to the contractor, or procured by him and intended to be used for the execution of the work or any part thereof, paying or allowing for the same in account at the contract rates, or in the case of contract not being applicable, at current market rates, to be certified by the Executive Engineer whose certificate thereof shall be final. In the afternative the Executive Engineer may after giving notice in writing to the contract of the engineer may after giving notice in writing to the contract of the engineer may after giving notice in writing to the contract of the engineer may after giving notice in writing to the contract of the engineer may after giving notice in writing to the contract of the engineer may after giving notice in writing to the contract of the engineer may after giving notice in writing to the contract of the engineer may after giving notice in writing to the contract of the engineer may after giving notice in writing to the contract of the engineer may after giving notice in writing to the contract of the engineer may after giving notice in writing to the contract of the engineer may after giving notice in writing to the contract of the engineer may after giving notice in writing to the contract of the engineer may after giving notice in writing to the engineer may after giving notice in writing to the engineer may after giving notice in writing to the engineer may after giving notice in writing to the engineer may after giving notice in writing to the engineer may after giving notice in writing to the engineer may after giving notice in writing to the engineer may after giving notice in writing to the engineer may after giving notice in writing to the engineer may after giving notice in writing to the engineer may after giving notice in writing to the engineer may after giving notice in writing to the engineer may native the Executive Engineer may, after giving notice in writing to the contractor or his clerk of the works, foreman or other authorized agent require him to remove such tools, plant, materials, us stores from the premises within a time to be specified in such notice, and in the event of the contractor failing to comply with any such requisition, the Executive Engineer them at the contractor's expense or sale thus by suction or pri secount of the contractor and at his risk is all respects, and the secount of the Executive Engineer as to the expense of any such remains amuont of the proceeds any expense of and such sale shall be fived clusive against the contract. DISTRICT OFFICER (ROADS TANDO ALLAHYAR.

Contractor reinsins liable topay compensation of action not taken ender clause 3 and 4.

Power to take possession of control of or sell, contractor's plant,

against the final payment only and not as payments for work ctually done and completed, and shall not preclude the Engineer-in-charge from requiring any bad, unsound, imperfect or unskilful work to be removed or taken away and re-constructed, or re-erected nor snall any such payment be considered as an admission of the due performance of the contract or any part thereof in any respect of the accruning of any claim; nor shall it conclude, determine; or effect in any other way the course of the lagineer-in-charge as to the final settlement and adjustment of the sections or otherwise, or in any way vary or effect the contract. The final Bill shall be submitted by the contractor within one month of the date tixed for the completion of the ork otherwise Engineer-in-charge's certificate of the measurements and of the total amount payable for the works shall be final and binding on all parties.

Clause 9 .- The rates for several items of works estimated to cost more 1,000 agreed to within, shall be valid only when the item concerned is accepted as having been completed full in accordance with the sanctioned specifications. In cases where the items of work are not accepted as so completed the Engineer-in-charge may make payment on account of such items at such reduced rates as he may consider reasonable in the preparation of llinator on account bills.

aced tates on account of item of work not accepted as completed to be st. the direction of the Enginee-in-

Chase 10.—A bill shall be submitted by the contractor as frequently as the progress of the work may justify for all work executed and not ince ded in any previous bill and the Engineer-in-charge shall take or cause to be taken the requisite measurements for the purpose of having the same verified and the claim, as for as admisisble, adjusted, if possible before the expiry of ten days from the presentation of the bill, at any time depute a subordinate to measure up the said work in the presence of the contractor or his authorised agent, whose countersignature to the measurement list will be sufficient warrant and the Engineer-in-charge may prepare a bill from such list which shall be binding on the contractor in all respects.

Bill to be submitted mentally.

Clause 11.-The contractor shall submit all bills on the printed forms to be had on application at the office of the Engineer- in charge. charges to be made in the bills shall always be entered at the rates specified The in the tender or in the case of any extra work ordered in pursuance of these conditions, and not mentioned or provided for in the tender at the rates heremafter provided for such work.

Itills to be on pri-

the use of any special description of materials to be supplied from the store of the P.W.D or it is required that the contractor, shall use certain stores to be provided by the Engineer-in-charge (such meterial and stores, and the prices to be charged therefore as heremafter mentioned being so far as practicable for the convenience of the contractor but not so as in any way to convol the meaning or effect of this contract specified in the schedule or, memorandum hereto annexed) the contractor shall be supplied with such materials and stores as may be required from time to time to be used by him for the purposes of the contract only and the value of the full quantity of the materials and stores so supplied shall be set off or deducted contract, or otherwise, or from the security deposits, or the preceeds of sale thereof, if the security deposits is held in Government securities, the same or a sufficient portion thereof shall in that case be sold for the purpose. All materials supplied to the contractor shall remain the absolute property of Government and shall on no account be removed from the sire of the work, and shall at all times be open to inspection by the Engineer-in-charge. Any such materials unused and in perfectly good condition at the time of completion or determination of the contract shall be, refunded to the P.W.D. store, if the Engineer-in-charge so requires by a motice in writing under his hand, but the contractor shall not be entitled to return any such materials except with the consent of the Engineer-in charge and he shall have no claim for compensation on account of any such material supplied to him as aforesaid but remaining unused by him or for, any wastage in or damage to any such materials.

CONT:

Clause 13. -The contractor shall execute the whole and every part of the work in the most substantial and work-man-like manner and both as regards material; and all other matters in strict accordance with the specifiation lodged in the office of the Executive Engineer and initialled by the parties the said specification being a part of the contract. The contractor shall its

Warks to be ers-sured in Accordaoco włodatych ce-Godin, grewioga

DISTRICT OFFICER (ROADS CONTRACTOR WYANDO ALLANYAR.

that any materials or articles provided by him for the execution of the work are unsound, or of a quality inferior to that contracted for, or are otherwise not in accordance with the contract, it shall be lawful for the Engineer-incharge to intimate this fact in writing to the contractor and then not with standing the fact that the work, materials or articles complained of may have been inady-ertently passed, certified and paid for, the contractor shall be bound forthwith to rectify or remove and reconstruct the work so specified in whole or in part, as the case may require, or it so required, shall remove the materials or articles so charge and cost; and in the event of his failing to do so within a period to be specified and provide other proper & suitable materials or articles at his own proper by the Engineer-in-charge in the writing intimation aforesaid, the contractor shall be liable to pay compensation at the rate of one percent. On the amount of the estimate for not exceeding ten days, during which the failur eso continues, and in the case of any such failure the Engineer-in-charge may rectify or remove, and reexecute the work or remove and replace the materials or articles complained of as the case may be at the risk and expense in all respects of the contractor. Should the Engineer-in-charge consider that any such inferior work or materials as described above may be accepted or made use of; it shall be within his discretion to accept the same at such reduced rates as he may the therefore.

Clause 18.—All works under or in course of execution executed in works to be opported and and times be open to the inspection and supervision of the Engineer-in-charge and his subordinates, and the contract-or shall at all times during the usual working hours, and at all other than the at which reasonable notice of the intention of the Engineer-in-charge or his subordinate to visit the work shall have been given to the contractor, cither hiraself be present to receive orders and instructions, or have a respossible agent duly accredited in writing present for that purpose, Orders given to the contractor's duly authorised agent shall be considered to have the same force an effect as if they had been given to the contractor himself.

responsible agent to be present.

Clause 19.—The contractor shall give not less than five days notice in writing to the Engineer-in-charge or his subordinate-in-charge of the work before covering up or otherwise placing beyond the reach of measurement any work in order that the same may be measured, and correct dimensions thereof taken before the same is so covered up or placed beyond the reach of measurement, and shall not cover up or place beyond the reach of measurement. rement any work without the consent in writing of the Engineer- in -charge or his subordinate-in-charge of the work; and if any work shall be covered up or placed beyond the reach of measurement without such notice having been given to consent obtained, the same shall be uncovered at the contractor's expense, and in default thereof no payment or allowance shall be made. for such work, or for the materials with which the same was excepted.

Notice to be given before work is covered up.

Clause 20.-If the contractor or his workmen, or servents shall break, deface, injure, or destroy any part of a building in which they may be working, or any building, road, fence, enclosure of grass land of cultivated ground continuous to the premises on which the work or any part thereof is being executed, or if any damage shall be done to the work, while it is in progress from any cause whatever or if any imperfections become apparent in it within three months of the grant of a certificate of completion, final or otherwise, by the Engineer-in-charge, the contractor snall make good the same at his own expense, or in default the Engineer-in-charge may cause the same to be made good by other workmen, and deduct the expenses of (which the certificate of the Engineer-in-charge shall be final) from any sums that may then be due or may thereafter become due to the contractor, or from his security deposits or the proceeds of sale thereof, or of a suffi cient portion thereof.

te for doos, and for huperfections

Clause 21.—The contractor shall supply at his own cost all material contractor to supplied such special material, if any, as may, in accordance with the polyphan, ladder contract, be supplied from the P.W.D. Stores), plant, tools, appliances, implements, ladders, cordage, tackle, scaffolding and temporary work requisite or proper for the execution of the work, whether in the original, altered or substituted form, and whether included in the specifications, of other documeats, forming part of the contract of referred to in these conditions or not, and which may be necessary for the purpose of satisfying or comparing with the requirements of the Engineer-in-charge as to any matters as

poly pinat, laiders, scaffoldings, etc.



thereupon stand forfeited and be absolutely at the disposal of Government and the same consequences shall ensure as if the contract had been rescinded under clause 3 thereof and in addition the contractor shall not be entitled to recover or be paid for any work therefore actually performed under the contract.

led

CC.

be

Inno

ne or

or

If,

:C-

nd

Dr

9. es

10 id

3.

17 y

d

Clause 27.—All sums payable by a contractor by way of compensation under any of these conditions shall be considered as a reasonable compensation to be applied to the use of Government without reference to the actual loss or damage sustained, and whether any damage has or has not been sustained.

Sum payable to way of compensadered as reasonable compensation with out reference sctus! loss.

Clause 28,--In the case of a tender by partners any change in the constitution of a firm shall be forthwith notified by the contractor to the Engineer-in-charge for his information,

Changes in the constitution of firm to be notified

Clause 29.—All works to be executed under the contract shall be executed under the direction and subject to the approval in all respects of the Superintending Engineer of the circle for the time being, who shall be entitled to direct at what point or points and in what manner they are to be commenced and from time to time carried on,

Works to be un-Superintending

Clause 30.—Except where otherwise specified in the contract and subject to ne powers delegated to him by Government under the Code rules then in force, the decision of the Superintending Engineer of the circle for the time being shall be final, conclusive and binding on all parties to the contract upon all questions relating to the meaning of the specifications, designs drawings, and instructions hereinbefore mentioned and as to the quality of workmanship, or materials used on the work or as to any other question, claim, right, matter, or thing whatsoever in any way arising out of, or relating to the contract design, drawings, specifications, estimates, instructions, orders or these conditions or otherwise concerning the works, or the execution, or failure to execute the same, whether arising, during the progress of the work. or after the completion or abandonment thereof.

Decision of Supdig: Engince


Clause 31.—The contractor shall obtain from the P.W.D. stores all stores and articles of European or American manufacture which may be required for the work, or any part thereof or in making up any articles required therefor or in connection therewith, unless he has obtained permission in writing from the Engineer-in-charge to obtain such stores and articles elsewhere. The value of such stores and articles as may be supplied to the contractor by the Engineer-in-charge will be debited the contractor in his account at the rates shown in the schedule in form "A" attached to the contract and if they are not entered in the said schedule, they shall be debited to him at cost price which for the purpose of the contract shall include the cost of carriage and all other expenses whatsoever, which shall have been incurred in obtaining delivery of the same at the stores aforesaid.

CONTSIPICE edn of &merican manufacture to be obtained from Government,

Clause 32.—When the estimate on which a tender is made includes lump soms in respect of part of the work, the contractor shall be entitled to payment in respect of the items of work involved or the part or the work in question at the same rates as are payable under this contract for such items, or if the part of the work in question is not in the opinion of the Engineerin-charge capable of measurement, the Engineer-in-charge may at his discretion pay the lump sum autofint entered in the estimate, and the certificate in writing of the Engineer-in-charge shall be final and conclusive against the contractor with regard to any sum payable to him under the provisions of this clause.

Lump sums hi estimateroryo cynicat keys or enimals.

Clause 33.—In the case of any class of work for which there is no such speci-Action where no lication as is mentioned in Rule 1 such work shall be carried out in accordance appetite attention. with the Divisional specification, and in the event of there being no Divisional specification, then in such case the work shall be carried out in all respects in ascordance with the instructions and requirements of the Engineer-in Marge.



DISTRICT OFFICER (ROADS TANDO ALLAHYAR.

Clause 45.— If any materials, such as stones metal, bajri, sand etc. are required to be conveyed by rail, the contractors will be granted certificates by the Engineer-in-charge of the work to the effect that the materials are required for Government or semi Government works thereby enabling them to have the benefit of concessionary freight charges from the ranway. In case, however, such a concession is withdrawn by the railway at any time during the currency of the contract, no claim shall be preferable against Government on this account.

Certificate concessionary fro abi charges form. the Rallway.

Clause 46 .- When tendered rates are the same preference will be given at the discretion of the accepting authority to those who tender for the carting of materials by vehicles having penumatic tyres.

Procedure acceptance of tendets when tendered rates sio samo.

Clause 47.—Any sum due to the Government by the contractor shall be liable for recovery as arrears of Land Revenue.

Recovery of duety from contractor as-Revenue Of Land

Clause 48 —Certified that no member of Legislative Assembly is in partnership with me and that Government will have the right to terminate the contract at any stage if it is discovered that a member of Legislative Assembly is a partner in the contract

Parenerah M L A'S bidden. for

Clause 49-1/We hold myself/ourselves responsible to pay the Sales Tax as livied in accordance with Pakistan General Sales Tax Act. 1948, or any other law for the time being in force.

Payment of Sale

Clause 50.—Certified that no Government servant has directly or indirectly a share or interest in the work.

Interest or sharp Government ervent in the World

Clause - 51. The contractor will not be allowed to withdraw his and ask for the return of ernest money before expiry of the period shown as under, commencing from the date of opening of the tender and that if it is withdrawn in violation of this condition earnest money shall be forfieted.

When the sanctioning authority for the tender is:-

Executive Engineer

One month.

Superintending Engineer

Two months.

Chief Engineer

Three months.

Government .

Six months,

Clause 52."If any question, difference or objection whatsoever shall arise in any way contracted with or arising out of this instrument or the meaning or obje on of any part thereof, the rights, duties or liabilities of either party, then save in so far as the decision of any such matter is here in before provided for as has been so decided, every such matter including whether its decision has been otherwise provided for any or regards the right of and obligations of the parties as the result of such termination shall be referred for arbitration to such person as may be appointed in this behall by Chief Engineer, (Irrigation), Department and his decision shall be final and binding and where the matter involves a claim for or the payment recovery or deduction of money, only the amount, if any awarded in score arbitration shall be recoverable in respect of the matters so referred;"

Certified that the Tender has been executed under my personal supervision and I am satisfied that it has been correctly prepared in accordance. with the orders issued vide Government P. W. D. circular Memo No. 1015 W dated 14th September, 1937, and subsequent orders issued in this connection.

Certified that I have noted the content of Government P. W. Circular Memorandum No. 1006-1 dated 21st February, 1950, wherein the responsibility of getting the tender checked efficiently is placed on me

Contractor

ixecultive (fin) incer, DISTRICT OFFICER (ROADS)

SCHEDULE, B.

Memorandum Showing Items of Work To be Carried out

| | Quantities | ÷4. | Te | enders | rates | | - Total | |
|-------------|---|--------------|------------|---------|----------|-----------|--|--|
| Item No. | Quantities estimated but may be more or less | Item of week | In figures | | In words | Unit | amount according to estimated quantities | |
| * : * | | | Rs. | Ps. | | | | |
| | | | | 1001 | | | | |
| | | 972 11 | | Company | | | | |
| | 1 | | | | | | . / | |
| | 77.00 | | | | | | | |
| | | | | | | | | |
| | | | | | | Moine | | |
| | | | 45 1 B | | | , Vic | | |
| f | | | | - 1 | . / (A | Thr. | . / | |
| 19 R | | | | | / | | / | |
| , P 16 | | | 1 1 | 1 | · \. | | | |
| | | | | | رورا | | | |
| | | | /- | 10 | | | | |
| CHARLES | | n solita | / . | | - / | | | |
| | | 1 Skin | 0. | | | | | |
| | | /-/- | 24 | ļ | / / / | | | |
| | | 1 | • | | | 90 | To the second | |
| 100 | | : of | | / | | e company | | |
| ANCHES AN | / | 10 | · | | | C.C. | | |
| | 2 20 20 | | | ļ | , e | | | |
| | | | | - | | - | | |
| u . | | | 9 | | V. 19 | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | 35.03 | |
| | | | 100 | | | | | |
| | | | 9 0 | | | | Teges to | |
| | | | | - | | | | |
| | 8.37 | | ., | | | | i + 1 + 4 | |
| - [| | 3000 | | | · /- 8 | | | |
| | - | | | - | | | | |
| 1 | | N. Company | | | | | | |
| | | 3. | - 1 | | 1 | | | |

Note: 1—All work shall be carried out as per Public works Departments Head-book and other specifications of the Division or as directed.

Note 2—All the columns in the Schedule should be filled in, in ink and the total of the entries in the last column should be struck by the contracter under his signature.

Note 3-Rates quoted include clearance of site (prior to commencement of Work and at its close) in all respects and hold good work under all conditions. Site moisture. Weather, etc.

Signature of Configetor)

BUNTARETOR

Signature of Assistant Engines

V- -To be Satioused on additional sheets if found necessary

SINDH PUBLIC PROCUREMENT REGULATORY AUTHORITY



CONTRACT EVALUATION FORM

TO BE FILLED IN BY ALL PROCURING AGENCIES FOR PUBLIC CONTRACTS OF WORKS, SERVICES & GOODS

| 1) | NAME OF THE ORGANIZATION / DEPTT. Works & Sorvices Deport ment |
|-----|---|
| 2) | PROVINCIAL/LOCAL GOVT/OTHER District Government |
| 3) | TITLE OF CONTRACT Constitution of Road |
| 4) | TENDER NUMBER NITNO 230 dated 3-12-2010 |
| 5) | BRIEF DESCRIPTION OF CONTRACT Construction of Road Hyd. MR Road at P. |
| 6) | FORUM THAT APPROVED THE SCHEME Local Governut of Sinda 10- |
| 7) | TENDER ESTIMATED VALUE Rs : (0.000 (m) |
| 8) | ENGINEER'S ESTIMATE (For civil works only) Rs.: 9.736 (m) |
| 9) | ESTIMATED COMPLETION PERIOD (AS PER CONTRACT) (06) Month |
| 10) | TENDER OPENED ON (DATE & TIME) 04.01.2010 at - 2:00 Pm |
| 11) | NUMBER OF TENDER DOCUMENTS SOLD 03 · NOS (Attach list of buyers) |
| 12) | NUMBER OF BIDS RECEIVED 03 NOS |
| 13) | NUMBER OF BIDDERS PRESENT AT THE TIME OF OPENING OF BIDS 03 NOC |
| 14) | BID EVALUATION REPORT (Enclose a copy) |
| 15) | NAME AND ADDRESS OF THE SUCCESSFUL BIDDER Mk Zaheer Abass Pitafi |
| 16) | CONTRACT AWARD PRICE Rs. 95.60714 /= |
| 17) | RANKING OF SUCCESSFUL BIDDER IN EVALUATION REPORT 1 St NOS |
| | |
| | |
| 18) | METHOD OF PROCUREMENT USED : - (Tick one) |
| | a) SINGLE STAGE - ONE ENVELOPE PROCEDURE Demostical total |
| | b) SINGLE STAGE - TWO ENVELOPE PROCEDURE |
| | |

| | | OF CONFE | ACT | E.O.O (W&S) |
|------------|--|--|------------|-------------------------------|
| 9) APPRO | OVING AUTHORITY I | OR AWARD OF CONTE | MCI_ | |
| 20) WHE | THER THE PROCURE | MENT WAS INCLUDED | IN ANN | UAL PROCUREMENT PLAN? Yes No |
| 21) ADVE | ERTISEMENT: | | | |
| 21) 211011 | | 1121 | Yes | 3-12.2010 |
| i) | SPPRA Website | contract Identification No. | | |
| | (If yes, give date and | SPPRA Identification No. | No | |
| | | | | National News 11-12-2018 |
| ii) | News Papers (If yes, give names o | f newspapers and dates) | Yes | Sprat daded 11-12-2011 |
| | | | No | Spran v = 1 |
| | | A | 100 | |
| 22) NAT | URE OF CONTRACT | | | Int. |
| 22) NAT | ORE OF CONTROL | | | |
| 23) WHE | THER QUALIFICATION | ON CRITERIA | 'NITO') | |
| | INCLUDED IN BIDD! es, enclose a copy) | NG / TENDER DOCUME | NIO: | Yes No |
| (II ye | ss, effetose a copyy | | | |
| 24) WHI | ETHER BID EVALUAT | TON CRITERIA | | Yes I No I |
| WAS | S INCLUDED IN BIDD | ING / TENDER DOCUM | ENTS? | |
| (If ye | es, enclose a copy) | A STATE OF THE STA | No. | |
| 26) WILD | CTUED ADDROVALO | COMPETENT AUTHOR | RITY W | AS OBTAINED FOR USING A |
| MET | THOD OTHER THAN | PEN COMPETITIVE BI | DDING? | Yes No |
| | | | 100 | |
| 26) WA | S BID SECURITY OBT | AINED FROM ALL THE | BIDDE | RS? Yes No |
| | | | | |
| 27) WH | ETHER THE SUCCESS | SFUL BID WAS LOWES | EVAL | UATED Yes No |
| BID | / BEST ÉVALUATED | BID (in case of Consultan | cies) | |
| | | SELL DIDDED WAS TEA | HNICA | IIIY Yes No V |
| | ETHER THE SUCCES MPLIANT? | SFUL BIDDER WAS TEC | -44171C/21 | |
| CO | WIT LATER TO | | | |
| | | | | |

| 31) ANY COMPLAINTS RECEIVED (If yes, result thereof) | Yes | 2 |
|--|--|--|
| | No | V |
| | | NAME AND ADDRESS OF TAXABLE ADDR |
| 32) ANY DEVIATION FROM SPECIFICATIONS GIVEN | IN THE TER | NDER NOTICE / DOCUMENTS |
| (If yes, give details) | Yes | 1 |
| | No | |
| 33) WAS THE EXTENSION MADE IN RESPONSE TIME | ? | |
| (If yes, give reasons) | Yes | |
| | No | V |
| 34) DEVIATION FROM QUALIFICATION CRITERIA | | |
| (If yes, give detailed reasons-) | Yes | |
| | No | 1 |
| | | |
| | CN THAT | THE CELECTED FIRM IS NOT |
| 35) WAS IT ASSURED BY THE PROCURING AGEN BLACK LISTED? | CY THAT | THE SELECTED FIRM IS NOT Yes No |
| BLACK LISTED? | | Yes No |
| BLACK LISTED? 36) WAS A VISIT MADE BY ANY OFFICER/OFFICIA SUPPLIED'S PREMISES IN CONNECTION WITH I | L OF THE | PROCURING AGENCY TO THE UREMENT? IF SO, DETAILS TO |
| BLACK LISTED? | L OF THE | PROCURING AGENCY TO THE UREMENT? IF SO, DETAILS TO |
| BLACK LISTED? 36) WAS A VISIT MADE BY ANY OFFICER/OFFICIA SUPPLIER'S PREMISES IN CONNECTION WITH IT BE ASCERTAINED REGARDING FINANCING OF (If yes, enclose a copy) | L OF THE I THE PROCU VISIT, IF AF | PROCURING AGENCY TO THE UREMENT? IF SO, DETAILS TO BROAD: |
| BLACK LISTED? 36) WAS A VISIT MADE BY ANY OFFICER/OFFICIA SUPPLIER'S PREMISES IN CONNECTION WITH A BE ASCERTAINED REGARDING FINANCING OF A (If yes, enclose a copy) 37) WERE PROPER SAFEGUARDS PROVIDED ON SECOND AND ADDRESS OF A COPY OF | L OF THE I THE PROCU VISIT, IF AF | PROCURING AGENCY TO THE UREMENT? IF SO, DETAILS TO BROAD: Yes No VERNO |
| BLACK LISTED? 36) WAS A VISIT MADE BY ANY OFFICER/OFFICIA SUPPLIER'S PREMISES IN CONNECTION WITH IT BE ASCERTAINED REGARDING FINANCING OF (If yes, enclose a copy) | L OF THE I THE PROCU VISIT, IF AF | PROCURING AGENCY TO THE DREMENT? IF SO, DETAILS TO BROAD: Yes No VERNO |
| 36) WAS A VISIT MADE BY ANY OFFICER/OFFICIA SUPPLIER'S PREMISES IN CONNECTION WITH IT BE ASCERTAINED REGARDING FINANCING OF A (If yes, enclose a copy) 37) WERE PROPER SAFEGUARDS PROVIDED ON THE CONTRACT (BANK GUARANTEE ETC.)? | L OF THE PROCU ME PROCU MISIT, IF AF | PROCURING AGENCY TO THE UREMENT? IF SO, DETAILS TO BROAD: Yes No VERNO |
| BLACK LISTED? 36) WAS A VISIT MADE BY ANY OFFICER/OFFICIA SUPPLIER'S PREMISES IN CONNECTION WITH IT BE ASCERTAINED REGARDING FINANCING OF VIOLENCE (If yes, enclose a copy) 37) WERE PROPER SAFEGUARDS PROVIDED ON THE CONTRACT (BANK GUARANTEE ETC.)? | L OF THE I THE PROCU VISIT, IF AF | PROCURING AGENCY TO THE UREMENT? IF SO, DETAILS TO BROAD: Yes No VERNO |
| 36) WAS A VISIT MADE BY ANY OFFICER/OFFICIA SUPPLIER'S PREMISES IN CONNECTION WITH IT BE ASCERTAINED REGARDING FINANCING OF A (If yes, enclose a copy) 37) WERE PROPER SAFEGUARDS PROVIDED ON THE CONTRACT (BANK GUARANTEE ETC.)? | L OF THE PROCU ME PROCU MISIT, IF AF | PROCURING AGENCY TO THE UREMENT? IF SO, DETAILS TO BROAD: Yes No VERNO |
| 36) WAS A VISIT MADE BY ANY OFFICER/OFFICIA SUPPLIER'S PREMISES IN CONNECTION WITH IT BE ASCERTAINED REGARDING FINANCING OF (If yes, enclose a copy) 37) WERE PROPER SAFEGUARDS PROVIDED ON THE CONTRACT (BANK GUARANTEE ETC.)? | L OF THE PROCE WISIT, IF AF | PROCURING AGENCY TO THE UREMENT? IF SO, DETAILS TO BROAD: Yes No VERNO |
| BLACK LISTED? 36) WAS A VISIT MADE BY ANY OFFICER/OFFICIA SUPPLIER'S PREMISES IN CONNECTION WITH IT BE ASCERTAINED REGARDING FINANCING OF IT (If yes, enclose a copy) 37) WERE PROPER SAFEGUARDS PROVIDED ON PROPERTY. | L OF THE PROCU VISIT, IF AF MOBILIZA I | PROCURING AGENCY TO THE UREMENT? IF SO, DETAILS TO BROAD: Yes No VERNO |
| BLACK LISTED? 36) WAS A VISIT MADE BY ANY OFFICER/OFFICIA SUPPLIER'S PREMISES IN CONNECTION WITH IT BE ASCERTAINED REGARDING FINANCING OF IT (If yes, enclose a copy) 37) WERE PROPER SAFEGUARDS PROVIDED ON PROPERTY. | L OF THE PROCU VISIT, IF AF MOBILIZA I | PROCURING AGENCY TO THE DREMENT? IF SO, DETAILS TO BROAD: Yes No |
| BLACK LISTED? 36) WAS A VISIT MADE BY ANY OFFICER OFFICIA SUPPLIER'S PREMISES IN CONNECTION WITH IT BE ASCERTAINED REGARDING FINANCING OF IT (If yes, enclose a copy) 37) WERE PROPER SAFEGUARDS PROVIDED ON THE CONTRACT (BANK GUARANTEE ETC.)? 38) SPECIAL CONDITIONS, IF ANY (If yes, give Brief Description) 39) Date of Award of Contract: | L OF THE PROCU VISIT, IF AF MOBILIZA I | PROCURING AGENCY TO THE DREMENT? IF SO, DETAILS TO BROAD: Yes No |
| BLACK LISTED? 36) WAS A VISIT MADE BY ANY OFFICER/OFFICIA SUPPLIER'S PREMISES IN CONNECTION WITH IT BE ASCERTAINED REGARDING FINANCING OF IT (If yes, enclose a copy) 37) WERE PROPER SAFEGUARDS PROVIDED ON THE CONTRACT (BANK GUARANTEE ETC.)? 38) SPECIAL CONDITIONS, IF ANY (If yes, give Brief Description) | L OF THE PROCU VISIT, IF AF MOBILIZA I | PROCURING AGENCY TO THE UREMENT? IF SO, DETAILS TO BROAD: Yes No VERNO |

To,

Mr. Zaheer Abbas Pitafi, Government Contractor, Hyderabad.

SUBJECT:

CONSTRUCTION OF ROAD FROM HYDERABAD MIRPURKHAS ROAD @ PIR KATHI DHINGANO BOZDAR ROAD DEIL REECHAL VIA DEHS, GUJJO DARRO, KUBBI, DHANDII SHAH MILE 1/0-2/1.

REFERENCE: Your B-I tender dated 04-01-2011.

Your quoted rate premium i.e. Part "A" @ 10.65% Above (Ten Point Six Five % Above) for Road work., Part "B" @ 34.85% Above (Thirty Four Point Eight Five % Above) for culverts the tender being the lowest is hereby approved.

You are accordingly informed to please start the aforesaid work within ? (Seven) days from the date of issue of this work order under the supervision of the Deputy District Officer (Roads) Tando Allahyar and note that the work is to be completed with in a period of (06) Months.

You are also requested to please execute the whole and every part of the work exactly full in accordance with the specification, design, drawings and instructions in writing relating to the work duly singed by the undersigned and lodged in my office. You are entitled to have access to the same for the purpose of inspection during office hours. If required to make or cause to be made copies of the same specifications and all such Design, Drawings and instruction as aforesaid. The extra conditions as per lixecutive District Officer (W&S) Department Tando Allahyar letter No. quoted above, is also given below for your information and strict compliance.

- No premiums shall be allowed on non-schedule items.
- No separate payment for carriage of materials shall be made. Premium quoted by the contractor covers the cost of carriage of materials involved.
- All materials required for construction shall be procured and brought at site by contractor at his own cost from approved sources/quarries.
- iv) No payment of extra item shall be made unless written order is given to contractor by the District Officer for execution of such extra items and approved by the competent authority
- Income Tax shall be deducted from the bill on the value of work done and paid for as per latest orders of competent authority in this regard.

50,46.

Contd., P/2

- vi) Contractor shall arrange bitumen from the National Refinery only and payment on account of bitumens item / work done shall be made on production of such certificate by the contractor from the National Refinery.
- vii) Work will be carried out strictly as per PWD specification.
- viii) All requisite codal formalities will be observed before start of work.
- Water charges and all leads and lifts of material are included in the item of work.
- x) If any omission and error found in schedule "B" which will be jointly initialed by the Contractor and District Officer before issuance of work order.
- xi) Item of earth work 95% compaction shall not be executed without use of vibratory road roller.
- xii) No escalation whatever will be allowed the work is continued is next year for want of requisite funds.

The photo-state copies of Schedule-B. (Part A & B) duly attested by the undersigned also enclosed herewith for your information & guidance.

You should give in writing the name of your authorized agent who would receive instructions at the site of work during the course of its execution and also attend this office for signing the agreement.

DISTRICT OFFICER (ROADS)
TANDO ALLAHYAR

Copy forwarded to the Deputy District Officer (Roads) Tando Allahyar for information and necessary action. The copies of Schedule-B (Part A & B) are enclosed herewith for his record and carrying out the work accordingly. The work should strongly be carried out as per P.W.D. specifications. The date of start of work should also be reported to this office for record.

ref

CONTRACTOR SOMETHING

are and are

OFFICE OF THE DISTRICT OFFICER (ROADS) TANDO ALLAHYAR

COMPARATIVE STATEMENT

B.I

Date of issue

04-01-2011

Date of opening

04-01-2011

NAME OF WORK:

Construction of road from Hyderabad Mirpurkhas road @ Pir Kathi Dhingano Bozdar road Deh Reechal via Dehs, Gujjo Darro,

Kubbi, Dhandh Shah mile 1/0-2/1

| S.No | Name of Contractor Whom Tender issued | Road Work Part (A) Construction | Road Work Part (B) Culverts | M. Structure (1) (2) (3) |
|------|--|--|-----------------------------------|-----------------------------|
| 01 | 02 | 03 | 04 | 05 |
| | | 1.20 | | - |
| 0 | Mr. Zaheer Showed | 10.65% | 34.85% | |
| | Refafi | Dbore | Alove | |
| | | | 1 | - |
| 2 | M/s Raman. Hyder | 11.80% | 36.10% | |
| | £ co. | Store | Phove | |
| | | | | |
| 3 | M/s Ghulam Mustafe | 12-10% | 37.70% | |
| | Shaikh | Store | Alove | |
| | | | | |
| | 1 | The second secon | | |

Certified that the tenders have been opened before us.

DIVISIONAL ACCOUNTS OFFICER

DISTRICT OFFICER (ROADS)

TANDO ALLAHYAR

Opened in my Persence

DISTRICT OFFICER (ROADS)

TANDO ALLAHYAR

EXECUTIVE DISTRICT OFFICER
WORKS & SERVICES DEPARTMENT

WORKS & SERVICES TANDO ALLAHYAR D.O. ROADS & TRANSPORT TANDO ALLAHYAR

WORKS & SERVICES DEPARTMENT E.D.O. Issued to Mr./Messrs. Mr. Zahees Albert Petafi Goverment Contactor And charged Rs: 3000 =

D.R. No. 10 140

dt. 04111 2011

N.I.T. No. TC/G-55/DOR/230 Dated: 03-12-2010

OFFICER ROADS TANDO ALLAHYAR

B-1 TENDER FOR WORKS

I/ We hereby tender for the execution, for the Governor of Sindh, (hereinbefore) and hereinafter referred to as "Government"), of the work specified in the under written memorandum within the time specified in such memorandum at Part "A"10.65% Above/Below Part "B" 34.85% Above/Below, Part "C" ____ % Above/Below & Part "D" ____ % Above/Below the estimated rates entered in Schedule B' (memorandum showing items of work to be carried and in accordance in all respects with the specifications, designs, drawings and instructions in writing referred to in Rule-I here of and in Clause-12 of the annexed conditions of contract and agree that when materials for the work are provided by the Government such materials and the rates to be paid for them shall be as provided in Schedule 'A' hereto

MEMORANDUM'

General Description

Construction of road from Hyderabad Mingagl. And road @ Pir Kathi Dhingano Bozdar road Den Recchai vi.) Dehs, Gujjo Darro. Kubbi, Dhandh Shah mile 1/0-2/1

Estimated Cost Rs 10000000 /=. (a)

(b) Earnest Money 2% Rs. 200000 /=

Security Deposit (i/c E/Money) 5% Rs. 500000 /= (c)

Percentage, if any, to be deducted ((1)) Rs. 300000 /=

from bills 3%

Time allowed for the work from (06) Months date of written order to commence

Should this tender be accepted. I/We hereby agree to abide by any fulfill all the key and and provisions of the conditions of contract annexed here to so far as applicable, and in default there of to forfeit and ay to Government the sum of money mentioned in the said conditions.

is herewith forwarded representing the earnest money (a) the fall

value of which is to be absolutely forfeited to government should 17 We not deposit the felt amount of security deposit specified in the above memorandum, in accordance with Clauser of (A) of the said conditions, otherwise the said sum of Rs _______ about be returned to Government on account of such security deposit as aforesaid, or (6) the full value of which shall be retained by the Government on account of the security deposit specified in Course (B) of the conditions.

CONTRACTOR

OPFICERARCADE: TANDO ALLAHVAP

NAME OF WORK:- CONSTRUCTION

ROAD FROM HYDERABAD OF MIRPURKHAS ROAD @ PIR KATHI DHINGANO BOZDAR ROAD DEH REECHAL VIA DEHS, GUJJO DARRO, KUBBI,

| | | | DHAN | NDH SHAH MILE 1/ | 1-2/1 = 1.80 KM | 1 (PAR | <u>(T-A)</u> |
|--|-----|---|--|--|---|---|--|
| | QTY | S.NO | ITEM | OF WORK | RATE | UNI | T AMOUNT |
| | 1- | dressing with o | road emba | pisture content, lead up is done by other than o | to 100 ft and I | ift up to | mixing, clod breaking, 5 ft in all types of soil |
| | | 490000 Cft W 362400 Cft W | | 85 % Density @ Rs. 2515.39 %0 @ Rs. 4408.53 %0 | | | 232541.00 597 64 4.00 |
| | | 85655 Cft | | 95%to 100% Densi @ Rs. 5377.55 %0 | | Rs. | 460€€ 000 |
| The same of the sa | 2- | approved quarry and spreading 15 after initial rolling modified AASHO | properly g cft screen watering specification | raded to maximum size ning and non plastic quand compacting the s | ze 1 ½" require uarry fines filling ame so as to a gand using temp P carriage upto | d thickr g depre achieve plates, o site of v | l approved quality form ness of proper camber ession with stone metal 100% density as per camber, plates screens work. 245749.00 |
| | 3- | excavation for | aying edgi | ng of including supplying with small side para e upto 3 chains. @ Rs. 827.05% Rf | allel to the road. | 3" 1 st ç Rate in Rs. | class burnt bricks cluding all cost of 98254.00 |
| No. 1 | 4- | approved quarry and spreading 1 after initial rolling modified AASHO farm and directed 36709 Cft | properly g 5 cft scree g watering specificati d, rate i/cs | graded to maximum sining and non plastic quant and compacting the sions Rate i/cs providing all cost of materials t& | ze 1 ½" require juarry fines fillin ame so as to g and using tem P carriage upto Cft | ed thicking depression achieve plates, or site of version Rs. 1 | 309087.00 |
| | 5- | 25 +14 = 79 lbs gauge for first co surface before l | of bitumen bat, 1/2" – ving each | 80/100 penetration ar 3/8" gauge for 2 nd Coa | nd 5.50 + 2.75 + at, 3/8" – 1/4" fo power roller layi | + 1.5 = 9 or 3 rd Co ng each | sting surface with 40 ÷ 9.75 cft bajri of ¾" x ½" pat i/c cleaning the road in coat separately. Rate |
| | 6- | etc. complete le 91581 Cft | for emba | ankment form B.Pits 00cft and lift up to 5.0 @ Rs. 3854.80 % |) ft. (in ordinar | iayer c y soil). Rs . | lod breaking dressing 3 5849 0.00 |

TOTAL

Rs. 7001699.00

Add: Diff: Cost Bitumen 25.89Tons @ Rs. 50035.07 =

Rs. 1295424.00

G. TOTAL

Rs. 8297123.00

I/We undertake to accept any change in quantities rates and amount as per Technically, Sanctioned Estimates.

I/We shall not claim any change in the quoted premium. 2.

DISTRICT OFFICER (ROADS) TANDO ALLAHYAR

NAME OF WORK:- CONSTRUCTION OF ROAD FROM HYDERABAD MIRPURKHAS ROAD @ PIR KATHI DHINGANO BOZDAR ROAD DEH REECHAL VIA DEHS, GUJJO DARRO, KUBBI, DHANDH SHAH MILE 1/1/2/1 = (1.80 KM) 3' SPAN RCC SLAP CULVERT (PART-B)

| | | <u>0</u> | CULVERT (PART-B) | | | |
|--------------|------------|--|---|--|--|------------|
| 1 | QTY | S.NO ITEM C | OF WORK | RATE | UNIT AMOUNT | 21-21 |
| 7 | | Excavation in founda refilling around struct upto 5 feet (in ordina | ture with excavated s | es and other stru tuff watering ran | icture i/c dag belling dres nming lead upto 100" ar | ssir nd |
| | | 1190 Cft | @ Rs. 1306/80 | per %0 cft. | Rs. 1555.00 | |
| | 2. | Cement concrete brid | ck on stone metal ball | ast Ratio 1:4:8 | | |
| | | 245 Cft | @ Rs. 3584/10 | per %0 Cft. | Rs. 8781.00 | |
| Target Toler | 3. | Pucca brick work r Ratio 1:4. | atio 1:4 work in fou | ındation and pl | inth in cement sand n | nor |
| | | 597 Cft | @ Rs. 4150.30 | per %0 Cft. | Rs. 24777.00 | |
| | 4. | Cement concrete pla aggregate w/o shutte | ain i/c compacting fin ering) ratio 1:2:4 | ishing & curing | etc complete (i/c screen | ing |
| | | 84 Cft | @ Rs. 5941/10 | per % cft. | Rs. 4991.00 | |
| | 5. | Fabrication of mild | steel reinforcement fo | or cement concre | ete i/c cutting bending b ng wire also i/c removal o | inc |
| | | form bars. | iking joints & lestering | 1 1/C COSt Of Birial | | 01 |
| | | | @ Rs. 2651/55 | | Rs. 15034.00 | _ |
| | | form bars. 5.67 Cwt. R.C.C work i/c all binding and remnir | @ Rs. 2651/56 labour & material exign which will be paid | per Cwt cept the cost of separately rate | Rs. 15034.00 f steel reinf: and its labe including all kinds of g surface i/c screamin | oor fo |
| | | form bars. 5.67 Cwt. R.C.C work i/c all binding and remnir | @ Rs. 2651/55 | per Cwt cept the cost of separately rate ing and finishing in all respect ra | Rs. 15034.00 f steel reinf: and its labe including all kinds of g surface i/c screamin | oor fo |
| | 444 | form bars. 5.67 Cwt. R.C.C work i/c all binding and remnir moulds lighting shu finishing pre-cast late 81 Cft Brick on edge floor | @ Rs. 2651/56 labour & material exing which will be paid attering curing render id in position complete @ Rs. 114/00 | per Cwt cept the cost of separately rate ing and finishin in all respect ra per % cft. | Rs. 15034.00 f steel reinf: and its labe including all kinds of g surface i/c screamination 1:2:4. | oor fo |
| | 444 | form bars. 5.67 Cwt. R.C.C work i/c all binding and remnir moulds lighting shu finishing pre-cast laid | @ Rs. 2651/56 labour & material exing which will be paid attering curing render id in position complete @ Rs. 114/00 | cept the cost of separately rate in all respect rate per % cft. | Rs. 15034.00 f steel reinf: and its labe including all kinds of g surface i/c screamination 1:2:4. Rs. 9234.00 | oor fo |
| | ~~ij 7. | form bars. 5.67 Cwt. R.C.C work i/c all binding and remnir moulds lighting shu finishing pre-cast lai 81 Cft Brick on edge floor 1:7 Bed flooring. 79 Rft | @ Rs. 2651/56 labour & material exing which will be paid ittering curing render id in position complete @ Rs. 114/00 ing laid in 1:6 cement | cept the cost of separately rate ing and finishing in all respect raper % cft. t Mortar over a per % Sft. | Rs. 15034.00 If steel reinf: and its labe including all kinds of g surface i/c screamination 1:2:4. Rs. 9234.00 bed of 3/4" thick cement | oor fo |
| | ~~ij 7. | form bars. 5.67 Cwt. R.C.C work i/c all binding and remnir moulds lighting shu finishing pre-cast lai 81 Cft Brick on edge floor 1:7 Bed flooring. 79 Rft | @ Rs. 2651/56 labour & material exi ing which will be paid attering curing render id in position complete @ Rs. 114/00 ing laid in 1:6 cemen | cept the cost of separately rate ing and finishing in all respect raper % cft. t Mortar over a ger % Sft. t thick. | Rs. 15034.00 If steel reinf: and its labe including all kinds of g surface i/c screamination 1:2:4. Rs. 9234.00 bed of 3/4" thick cement | oor fo |
| | 7. 8. | form bars. 5.67 Cwt. R.C.C work i/c all binding and remnir moulds lighting shu finishing pre-cast lai 81 Cft Brick on edge floor 1:7 Bed flooring. 79 Rft Cement Plaster 1:3 361 Sft | @ Rs. 2651/56 labour & material exiting which will be paid attering curing render id in position complete @ Rs. 114/00 ing laid in 1:6 cement @ Rs. 1736/1 upto 20.0' height 1/2 @ Rs. 604/18 | cept the cost of separately rate ing and finishing in all respect raper % cft. t Mortar over a ger % Sft. t thick. per % Sft. | Rs. 15034.00 f steel reinf: and its labe including all kinds of g surface i/c screamination 1:2:4. Rs. 9234.00 bed of ¾" thick cement Rs. 1372.00 Rs. 2181.00 | oor fo |
| | 7. 8. | form bars. 5.67 Cwt. R.C.C work i/c all binding and remnir moulds lighting shu finishing pre-cast lai 81 Cft Brick on edge floor 1:7 Bed flooring. 79 Rft Cement Plaster 1:3 361 Sft | @ Rs. 2651/56 labour & material exing which will be paid ittering curing render id in position complete @ Rs. 114/00 ing laid in 1:6 cement @ Rs. 1736/1 upto 20.0' height 1/2 | cept the cost of separately rate ing and finishing in all respect raper % cft. t Mortar over a ger % Sft. "thick. per % Sft. | Rs. 15034.00 f steel reinf: and its labe including all kinds of g surface i/c screamination 1:2:4. Rs. 9234.00 bed of ¾" thick cement Rs. 1372.00 Rs. 2181.00 | oor fo |
| | 7. 8. | form bars. 5.67 Cwt. R.C.C work i/c all binding and remnir moulds lighting shu finishing pre-cast lai 81 Cft. Brick on edge floor 1:7 Bed flooring. 79 Rft. Cement Plaster 1:3 361 Sft. | @ Rs. 2651/56 labour & material exing which will be paid ittering curing render id in position complete @ Rs. 114/00 ing laid in 1:6 cement @ Rs. 1736/1 upto 20.0' height 1/2 @ Rs. 604/18 val of cetentering for co | cept the cost of separately rate ing and finishing in all respect raper % cft. t Mortar over a ger % Sft. "thick. per % Sft. | Rs. 15034.00 If steel reinf: and its labe including all kinds of g surface i/c screamination 1:2:4. Rs. 9234.00 bed of ¾" thick cement Rs. 1372.00 Rs. 2181.00 (Plan). | oor for |

 I/We undertake to accept any change in quantities rates and amount as per Technically, Sanctioned Estimates.

2. I/We shall not claim any change in the quoted premium

CONTRACTOR

DISTRICT OFFICER (ROADS)
TANDO ALLAHYAR

WORKS & SERVICES TANDO ALLAHYAR D.O. ROADS & TRANSPORT TANDO ALLAHYAR

WORKS & SERVICES DEPARTMENT E.D.O. Issued to Mr./Messrs. M/s Kameaus Hyden & Co.

And charged Rs: 3000 =

D.R. No. 10/37 dt. 04/11/2010

N.I.T. No. TC/G-55/DOR/230

Dated: 03-12-2010

DISTRICT OFFICER ROADS TANDO ALLAHYAR

B-1 TENDER FOR WORKS

I/ We hereby tender for the execution, for the Governor of Sindh, (hereinbefore) and hereinafter referred to as "Government"), of the work specified in the under written memorandum within the time specified in such memorandum at Part "A" 11.20% Above/Below Part "B"36.10% Above/Below, Part "C" ____ % Above/Below & Part "D" ___ % Above/Below the estimated rates entered in Schedule 'B' (memorandum showing items of work to be carried and in accordance in all respects with the specifications designs advanings and instructions in writing referred to in Rule-I here of and in Clause-12 of the annexed conditions of contract and agree that when materials for the work are provided by the Government such materials and the rates to be paid for them shall be as provided in Schedule 'A' hereto.

MEMORANDUM WILL SOIL.

1. General Description

Construction of road from Hyderabad Mirpurkhas road @ Pir Kathi Dhingano Bozdar road Deh Recchal via Dehs, Gujjo Darro, Kubbi, Dhandh Shah mile 1/0-2/1

500000 /=

Estimated Cost (a) 10000000 /= Earnest Money 2% (b)

200000 /= Security Deposit (i/c E/Money) 5% Rs.

Percentage, if any, to be deducted Rs. 300000 /= from bills 3%

Time allowed for the work from (e) (06) Months date of written order to commence.

Should this tender be accepted. I/We hereby agree to abide by any fulfill all the terms and provisions of the conditions of contract annexed here to so far as applicable, and in default there of to forfeit and ay to Government the sum of money mentioned in the said conditions.

Receipt / Call Deposit No. 001492755 dated 21-12-800 from M.C.B Bomk of Pakisland Touclo Malitm in respect of the sum of ___ is herewith forwarded representing the earnest money (a) the full

value of which is to be absolutely forfeited to government should I / We not deposit the full amount of security deposit specified in the above memorandum, in accordance with Clause01 (A) of the said conditions, otherwise the said sum of Rs. 20000 shall be retained by Government on account of such security deposit as aforesaid, or (b) the full value of which shall be retained by the Government on account of the security deposit specified in Clause-1 (B) of the conditions.

OFFICER (ROADS) TANDO ALLAHYAR

NAME OF WORK:- CONSTRUCTION OF ROAD FROM HYDERABAD MIRPURKHAS ROAD @ PIR KATHI DHINGANO BOZDAR ROAD DEH REECHAL VIA DEHS, GUJJO DARRO, KUBBI, DHANDH SHAH MILE 1/0-2/1 = 1.80 KM (PART-A)

DHANDH SHAH MILE 1/0-2/1 = 1.80 KM (PART-A)ITEM OF WORK S.NO UNIT AMOUNT QTY RATE EARTH WORK 1-Earth work for road embankment by bulldozers including ploughing, mixing, clod breaking. dressing with optimum moisture content, lead up to 100 ft and lift up to 5 ft in all types of soil except rock. (If earthwork is done by other than departmental agency). 85 % Density 490000 Cft W/O Lead @ Rs. 2515.39 %0 Cft Rs. 1232541.00 Rs. 1597651.00 362400 Cft With Lead @ Rs. 4408.53 %0 Cft 95%to 100% Density 85655 Cft @ Rs. 5377.55 %0 Cft Rs. 460614.00 2-, Preparing SUB-BASE COURSE by supplying and spreading stone metal approved quality form approved quarry properly graded to maximum size 1 1/2" required thickness of proper camber and spreading 15 cft screening and non plastic quarry fines filling depression with stone metal after initial rolling watering and compacting the same so as to achieve 100% density as per modified AASHO specifications Rate i/cs providing and using templates, camber, plates screens farm and directed, rate i/cs all cost of materials t&P carriage upto site of work. @ Rs. 3393.58 % Cft 36709 Cft BRICK ON EDGING Laying of including supplying of 9" x4 1/2" x 3" 1st class burnt bricks 3excavation for laying edging with small side parallel to the road. Rate including all cost of material T&P and carriage upto 3 chains. 98254.00 @ Rs. 827.05% Rft Re 11880 Rft BASE COURSE Preparing by supplying and spreading stone metal approved quality form 4. approved quarry properly graded to maximum size 1 1/2" required thickness of proper camber and spreading 15 cft screening and non plastic quarry fines filling depression with stone metal after initial rolling watering and compacting the same so as to achieve 100% density as per modified AASHO specifications Rate i/cs providing and using templates, camber, plates screens farm and directed, rate i/cs all cost of materials t&P carriage upto site of work. @ Rs. 3566.12% Cft Rs. 1309087.00 36709 Cft THREE COAT Providing Three Coat of surface dressing on new or existing surface with 40 + 5-25 +14 = 79 lbs of bitumen 80/100 penetration and 5.50 + 2.75 + 1.5 = 9.75 cft bajri of 3/4" x 1/2" gauge for first coat, 1/2" - 3/8" gauge for 2nd Coat, 3/8" - 1/4" for 3rd Coat i/c cleaning the road surface before lying each coat and rolling with power roller laying each coat separately. Rate includes all cost of materials T&P and carriage up to site of work. @ Rs. 993.63 Stt 729503.00 36709 Sft EARTH WORK for embankment form B.Pits i/c laying in 6" layer clod breaking dressing 6etc. complete load upt 100cft and lift up to 5.0 ft. (in ordinary soil). @ Rs. 3854.80 % Rft 328300.00 91581 Cft Rs. 7001699.00 TOTAL

 I/We undertake to accept any change in quantities rates and amount as per Technically, Sanctioned Estimates.

I/We shall not claim any change in the quoted premium.

NTRACTOR

Add: Diff: Cost Bitumen 25.89Tons @ Rs. 50035.07 =

G. TOTAL

DISTRICT OFFICER (ROADS)

Rs. 1295424.00

Rs. 8297123.00

NAME OF WORK:- CONSTRUCTION ROAD FROM MIRPURKHAS ROAD @ PIR KATHI DHINGANO BOZDAR ROAD DEH REECHAL VIA DEHS, GUJJO DARRO, KUBBI, DHANDH SHAH MILE 1/0-2/1 = (1.80 KM) 3' SPAN RCC SLAP CULVERT (PART-B) RATE S.NO ITEM OF WORK UNIT AMOUNT QTY 1. Excavation in foundation of building bridges and other structure i/c dag belling dressing refilling around structure with excavated stuff watering ramming lead upto 100" and lift upto 5 feet (in ordinary soil). 1190 Cft @ Rs. 1306/80 per %0 cft. Rs. 1555.00 2. Cement concrete brick on stone metal ballast Ratio 1:4:8 245 Cft @ Rs. 3584/10 per %0 Cft. Rs. 8781.00 B. Pucca brick work ratio 1:4 work in foundation and plinth in cement sand mortar. Ratio 1:4. 597 Cft @ Rs. 4150.30 per %0 Cft. Rs. 24777.00 4. Cement concrete plain i/c compacting finishing & curing etc complete (i/c screening of aggregate w/o shuttering) ratio 1:2:4 84 Cft @ Rs. 5941/10 per % cft. Rs. 4991.00 5. Fabrication of mild steel reinforcement for cement concrete i/c cutting bending binding laying in position making joints & festering i/c cost of binding wire also i/c removal of rust form bars. 5.67 Cwt. @ Rs. 2651/55 per Cwt Rs. 15034.00 6. R.C.C work i/c all labour & material except the cost of steel reinf: and its labor for binding and remning which will be paid separately rate including all kinds of forms moulds lighting shuttering curing rendering and finishing surface i/c screaming and finishing pre-cast laid in position complete in all respect ration 1:2:4. @ Rs. 114/00 per % cft. 7. Brick on edge flooring laid in 1:6 cement Mortar over a bed of 3/4" thick cement mortar 1:7 Bed flooring. @ Rs. 1736/13 per % Sft. Rs. 1372.00 79 Rft 8. Cement Plaster 1:3 upto 20.0' height 1/2 " thick. @ Rs. 604/18 per % Sft. Rs. 2181.00 9. Erection and removal of cetentering for cement concrete (Plan). 107 Sft @ Rs. 1405/75 per % Sft. Rs. 1504.00 **Grand Total** Rs. 69429.00

 I/We undertake to accept any change in quantities rates and amount as per Technically, Sanctioned Estimates.

I/We shall not claim any change in the quoted premium

DISTRICT OFFICER (ROADS)
TANDO ALLAHYAR

WORKS & SERVICES DEPARTMENT E.D.O. Issued to Mr./Messrs. Ms Grulan Must WORKS & SERVICES TANDO ALLAHYAR D.O. ROADS & TRANSPORT TANDO ALLAHYAR

And charged Rs: 3000 1
D.R. No. [0] 41 01 | dt. 04 | 1 | 00 |

TOFFICER ROADS TANDO ALLAHYAR

N.I.T. No. TC/G-55/DOR/230

Dated: 03-12-2010

B-1 TENDER FOR WORKS

I/ We hereby tender for the execution, for the Governor of Sindh, (hereinbefore) and hereinafter referred to as "Government"), of the work specified in the under written memorandum within the time specified in such memorandum at Part "A"12-10 % Above/Below Part "B"37.7% Above/Below, Part "C" ____ % Above/Below & Part "D" ____ % Above/Below the estimated rates entered in Schedule 'B' (memorandum showing items of work to be carried out and in accordance in all respects with the specifications of the annexed conditions instructions in writing referred to in Rule-I here of and in Clause-Wolfenberg conditions of contract and agree that when materials for the work are provided by the Government such materials and the rates to be paid for them shall be as provided in Schedule 'A' hereto.

MEMORANDUM

General Description

Construction of road from Hyderabad Mirpurkhas road @ Pir Kathi Dhingano Bozdar road Deh Recent via Dehs, Gujjo Darro, Kubbi. Dhandh Shah mele 140-7.1

Rs. 10000000 /= Estimated Cost (a)

Rs. 200000 /= Earnest Money 2% (b)

Security Deposit (i/c E/Money) 5% Rs. 500000 /= (c)

Rs. 300000 /= Percentage, if any, to be deducted from bills 3%

(06) Months Time allowed for the work from date of written order to commence

Should this tender be accepted. I/We hereby agree to abide by any fulfill all the terms and provisions of the conditions of contract annexed here to so far as applicable, and in default there of to forfeit and ay to Government the sum of money mentioned in the said conditions

Receipt / Call Deposit No. 0000 487- dated 21-12-2010 from learn Box & linusedat lutifabal Hyd in respect of the sum of 20000/2 is herewith forwarded representing the eathest manage (a) the time

value of which is to be absolutely forfeited to government should I / We not deposit the full amount of security deposit specified in the above memorandum, in accordance with Claured I (A) of the said conditions, otherwise the said sum of Rs. 20000072 shall be retained by Government on account of such security deposit as aforesaid or (b) the full value of where shall be retained by the Government on account of the security deposit specified in Charge 1. (B) of the conditions.

CONTRACTOR

OFFICERAROADS: TANDO ALLAGYAR

NAME OF WORK:- CONSTRUCTION

OF ROAD FROM HYDERABAD MIRPURKHAS ROAD @ PIR KATHI DHINGANO BOZDAR ROAD DEH REECHAL VIA DEHS, GUJJO DARRO, KUBBI, DHANDH SHAH MILE 1/0-2/1 = 1.80 KM (PART-A)

| QTY | S.NO | ITEM OF WORK | RATE | UNIT | AMOUNT |
|-----|------|--------------|------|------|--------|

1-**EARTH WORK**

Earth work for road embankment by bulldozers including ploughing, mixing, clod breaking dressing with optimum moisture content, lead up to 100 ft and lift up to 5 ft in all types of soil except rock. (If earthwork is done by other than departmental agency).

85 % Density

490000 Cft W/O Lead

@ Rs. 2515.39 %0 Cft

Rs. 1232541.00

362400 Cft With Lead @ Rs. 4408.53 %0 Cft

Rs. 1597651.00

95%to 100% Density

85655 Cft

@ Rs. 5377.55 %0 Cft

Rs. 460614.00

Preparing SUB-BASE COURSE by supplying and spreading stone metal approved quality form approved quarry properly graded to maximum size 1 1/2" required thickness of proper camber and spreading 15 cft screening and non plastic quarry fines filling depression with stone metal after initial rolling watering and compacting the same so as to achieve 100% density as per modified AASHO specifications Rate i/cs providing and using templates, camber, plates screens farm and directed, rate i/cs all cost of materials t&P carriage upto site of work.

36709 Cft

@ Rs. 3393.58 % Cft

BRICK ON EDGING Laying of including supplying of 9" x4 1/2" x 3" 1st class burnt bricks 3excavation for laying edging with small side parallel to the road. Rate including all cost of material T&P and carriage upto 3 chains.

11880 Rft

@ Rs. 827.05% Rft

Rs. 98254.00

4-BASE COURSE Preparing by supplying and spreading stone metal approved quality form approved quarry properly graded to maximum size 1 1/2" required thickness of proper camber and spreading 15 cft screening and non plastic quarry fines filling depression with stone metal after initial rolling watering and compacting the same so as to achieve 100% density as per modified AASHO specifications Rate i/cs providing and using templates, camber, plates screens farm and directed, rate i/cs all cost of materials t&P carriage upto site of work.

36709 Cft

@ Rs. 3566.12% Cft

Rs. 1309087.00

5-THREE COAT Providing Three Coat of surface dressing on new or existing surface with 40 + 25 +14 = 79 lbs of bitumen 80/100 penetration and 5.50 + 2.75 + 1.5 = 9.75 cft bajri of $\frac{3}{4}$ " x $\frac{1}{2}$ " gauge for first coat, $\frac{1}{2}$ " – $\frac{3}{8}$ " gauge for $\frac{2}{9}$ " Coat, $\frac{3}{8}$ " – $\frac{1}{4}$ " for $\frac{3}{9}$ " Coat i/c cleaning the road surface before lying each coat and rolling with power roller laying each coat separately. Rate includes all cost of materials T&P and carriage up to site of work.

36709 Sft

@ Rs. 993.63 Sft

729503.00

EARTH WORK for embankment form B.Pits i/c laying in 6" layer clod breaking dressing 6etc. complete load upt 100cft and lift up to 5.0 ft. (in ordinary soil).

91581 Cft

@ Rs. 3854.80 % Rft

328300.00

TOTAL

Rs. 7001699.00

Add: Diff: Cost Bitumen 25.89Tons @ Rs. 50035.07 =

Rs. 1295424.00

G. TOTAL

Rs. 8297123.00

I/We undertake to accept any change in quantities rates and amount as per Technically, Sanctioned Estimates.

I/We shall not claim any change in the quoted premium.

DISTRICT OFFICER (ROADS) TANDÓ ALLAHYAR

NAME OF WORK:- CONSTRUCTION OF ROAD FROM HYDERABAD MIRPURKHAS ROAD @ PIR KATHI DHINGANO BOZDAR ROAD DEH REECHAL VIA DEHS, GUJJO DARRO, KUBBI, DHANDH SHAH MILE 1/13/2/1 = (1.80 KM) 3' SPAN RCC SLAP CULVERT (PART-B)


| | CULV | ERT (PART-B) | | | |
|-----|--|------------------|-------------------|------------------------|--------|
| QT | Y S.NO ITEM OF W | ORK | RATE | UNIT AMOUNT | |
| 1. | Excavation in foundation of building bridges and other structure i/c dag belling dressing refilling around structure with excavated stuff watering ramming lead upto 100" and lift upto 5 feet (in ordinary soil). | | | | |
| | 1190 Cft | @ Rs. 1306/80 | per %0 cft. | Rs. 1555.00 | |
| 2. | Cement concrete brick on stone metal ballast Ratio 1:4:8 | | | | |
| | 245 Cft | @ Rs. 3584/10 | per %0 Cft. | Rs. 8781.00 | |
| 3. | Pucca brick work ratio Ratio 1:4. | 1:4 work in fo | undation and p | linth in cement sand m | nortar |
| | 597 Cft | @ Rs. 4150.30 | per %0 Cft. | Rs. 24777.00 | |
| 4. | . Cement concrete plain i/c compacting finishing & curing etc complete (i/c screening of aggregate w/o shuttering) ratio 1:2:4 | | | | |
| | 84 Cft | @ Rs. 5941/10 | per % cft. | Rs. 4991.00 | |
| 5. | Fabrication of mild steel reinforcement for cement concrete i/c cutting bending binding laying in position making joints & festering i/c cost of binding wire also i/c removal of rust form bars. | | | | |
| | 5.67 Cwt. | @ Rs. 2651/5 | 5 per Cwt | Rs. 15034.00 | |
| 6. | R.C.C work i/c all labour & material except the cost of steel reinf: and its labor for binding and remning which will be paid separately rate including all kinds of forms moulds lighting shuttering curing rendering and finishing surface i/c screaming and finishing pre-cast laid in position complete in all respect ration 1:2:4. | | | | |
| _ 4 | 81 Cft | @ Rs. 114/00 | | Rs. 9234.00 | |
| 7. | Brick on edge flooring laid in 1:6 cement Mortar over a bed of ¾" thick cement mortar 1:7 Bed flooring. | | | | |
| | 79 Rft | @ Rs. 1736/1 | 3 per % Sft. | Rs. 1372.00 | |
| 8. | 8. Cement Plaster 1:3 upto 20.0' height 1/2 " thick. | | | | |
| | 361 Sft | @ Rs. 604/18 | per % Sft. | Rs. 2181.00 | |
| 9. | 9. Erection and removal of cetentering for cement concrete (Plan). | | | | |
| | 107 Sft | @ Rs. 1405/7 | 5 per % Sft. | Rs. 1504.00 | |
| | | Gra | nd Total | Rs. 69429.00 | |
| | | washing a second | | | |
| м | IAMe undertake to ac | cent any chan | ide in duantities | s rates and amount as | s ner |

 I/We undertake to accept any change in quantities rates and amount as per Technically, Sanctioned Estimates.

I/We shall not claim any change in the quoted premium.

CONTRACTOR

DISTRICT OFFICER (ROADS)
TANDO ALLAHYAR



to tar as applicable, and in default thereof to forfeit and pay to Government the sums of money mentioned in the said conditions.

dated 21-12-10 from Government Treasury or Receipt No. 280129 sub-Treasury at Mational bank of Characters of the sum of Rs. 900000 is herewith forwarded representing the earnest money [(a) the full value of

which is to be absolutely, forfeited to Covernment should not deposit

the full amount of security deposit specified in the above memorandum, in accordance with Clause (1,1A) of the said conditions, otherwise the said sum of Rs......shall be retained by Goevenment on account of such security deposite as aforesaid J. or . (b) the full value of which shall be retained by the Govennment on account of the security deposit specified in clause I (B) of the conditions]. **

(Witnesses) BS: MIMAY FIVE ACC BATA British And,

(Address) BS: MIMAY FIVE ACC BATA British And,

(Occupation Form Invited Fou Accompany Note

(Occupation Form Invited Fou Accompany Note

(Occupation Form Invited Fou Accompany Note

(Sind. Dated the

of Sind.

DISTRICT OFFICER PROADS) Division (or his suly authorized Assistant)

Dated the

day of

100

"Amount to be specified in words and figures

Strike out (a) it no ca h aroudty deposit is to be taken.

**Strike out (b)
if any cash society
ty denograph to be taken.

CONT: ntractor below anossignature of witness to comin elemeturo,

Bignature of the officers by actu pred.

Condition of Costract

Clause 1.—The Persons whose tender may be accepted (hereinafter called

the contractor) shall (A) [(within one day for a contract of Rs. 1,000 or. oss, or two days for a contract of more than Rs. 1,000 upto Rs. 2,000 and o on, upto a limit of ten days, for a contract of Rs. 10,000 or more of the receipt by him of the notification of the acceptance of his tender.) deposit will the Executive Engineer in cash or Govt: Securities endorsed to Executive Engineer (if donosited for more then ty, elve months) a sum sufficient with the amount of the carnest money deposited by him with his tender to make up the full security deposit specified in the tender), or (B) (perhit Government at the time of making any payment to him for work done under the contracts to deduct such sum as well (With the earnest money deposited by him.) amount more percent of all moneys so payable: such deduction to be held by Government by way of security deposit): Provided always that in the event up the full amount of.......percent by deducting a sufficient sum from every such payment as last aforesaid. All compensation other sums of money payble by the contractor to Government under the terms of his contract may be deducted from, or paid by the sale of a sufficient part of his security deposit, or from the interest arising therefrom, or from any to the contractor under is due or may be ome due and in the event of his security deposit being uced by reason of any such deduction or sale as aforesaid the contractor shall within ten days thereafter, make good in cash or with Government securities endorsed as aforesaid any sum or sums which may have been deducted from, or raised by sale of his security deposit or any part thereof. The security, deposit referred to, when paid in cash, may, at the cost of the depositor, be converted into interest-bearing securities provided that it a depositor has expressly desired his in writing.

TANDO ALKANYAN,

activity deposits.

- (a) To rescind the contract (of which rescision notice in writen to the contractor under the band of the Executive Engideer shall be conclusive evidonce) and in that case the security deposit of the contra7tor shall stand forfeated and be absolutely at the disposal of the Government.
- (b) To employ iabour paid by the Public Work Department and to the supply materials to carry out the work, or any part of the work, debiting the contractor with the cost of the lahour and the price of the materials (as to the correctness of which cost and, price the certificate of the Executive Engineer shall be final and conclusive against the contractor) and crediting him with the value of the work done, in all respects in the same manner and at the same rates as if it had been carried out by the contractor under the terms of his contract; and in that case the certificate of the Executive Engineer, as to the value of the work done shall be final and conclusive against the contractor.
- (c) . To measure up the work of the contractor and to take such part thereof as shall be unexecuted out of the hands, and to give it to another, contractor to complete in which case any expenses which may be incurred in excess of the sum which would have been paid to the original contractor if the whole work had been executed by him (as to the amount of which excess expenses the certificates in writing of the Executive Engineer shall be final and conclusive) shall be borne and paid by the original contractor and shall be deducted from any money due to him by the Government under the contract or otherwise or from him security deposit or the proceeds of sale thereof, or a sufficient part thereof.

In the event of any of the above courses being adopted by the Executive. Engineer, the contractor shall have no clsim to compensation for any loss sustained by him by teason of his having purchased or procured any materials, or entered into any engagements, or made any advances on account of, or with a view to the execution or the work of the performance of the contract. And in case the contract shall be rescinded under the provision faforcsaid, the contractor shall not be entitled to recover or to be paid any sum or any work therefore actually performed by him under this contract unless and until the Executive Engineer shall have certified in writing the performance of such work and the amount payable in respect thereof, and he shall only be entitled to be paid the amount to certified.

Clause 4.- If the progress of any particular portion of the work is unsatisfactory Executive Engineer shall, notwithstanding that all the general proviess of the work is in accordance with the conditions mentioned in clause 2; be entitled to take action under clause 3 (b) after giving the configure 10 day's notice in writing. The contractor will have no claim for compensation, for any loss sustained by him owing to such action.

Action when the propress of any particular position of the work is unsatisfactory.

Clause 5.—In any case in which any of the powers conferred upon the Executive Engineer by the clause 3 and 4 thereof shall have become exercise Contractor remsins liable to compensation able and the same shall not have been exercised, the non-exercise thereof shall action not taken ander Clauseo 3 not constitute a waiver of any of the conditions hereof and such powers shall notwithstanding be exerciseable in the event of any luture case of default by the contractor for which under any clause or clauses hereof he is declared liable to pay compensation amounting to the whole of his security deposit

and the liability of the contractor for past and future compensation shall remain unaffected. In the event of the Executive Engineer taking action under sub-clause (a) or (c) of clause 3, he may, if he so desires take possession of all or any tools, plant, materials and stores in or upon the works, or the contractor, or procured by him and intended to be used for the execution of the work or any part thereof, paying or allowing for the same in account at the contract rates, or in the case of contract not being applicable, at current market rates, to be certified by the Executive Engineer whose certificate thereof shall be final. In the after-

native the Executive Engineer may, after giving notice in writing to the contractor or his clerk of the works, foreman or other authorized agent require him to remove such tools, plant, materials, or stores from the premises villa n time to be specified in such notice, and in the event of the contractor fairing to comply with any such requisition, the Executive Engineer may remove them at the contractor's expense or sale than by auction or principles on

recount of the contractor and at his risk in all respects, and the

of the Executive Engineer as to the expense of any such removed (1) (2) amuont of the proceeds any expense of and such sale shaper of contractors clusive again.

Power to take possession of er ractor's plant,

against the final payment only and not as payments for work ctually done and completed, and shall not preclude the Engineer-in-charge from requiring any had, unsound, imperfect or unskilful work to be removed or taken away and re-constructed, or re-crected not shall any such payment be considered as an admission of the due performance of the contract or any part thereof in any respect or the accruning of any claim; nor shall it conclude, determine; or effect in any other way the papers of the Engineer-in-charge as to the final settlement and adjustment of the accounts or otherwise, or in any way vary or effect the contract. The final Bill shall be submitted by the contractor within one month of the date tixed for the completion of the fork otherwise Engineer-in-charge's certificate of the measurements and of the total amount payable for the works shall be final and binding on all parties.

Clause 9.—The rates for several items of works estimated to cost more than Rs. 1.000 agreed to within, shall be valid only when the item concerned is accepted as having been completed full in accordance with the sanctioned specifications. In cases where the items of work are not accepted as so completed the Engineer-in-charge may make payment on account of such items at such reduced rates as he may consider reasonable in the preparation of final or on account bills.

used rates on account of item of work not accopied as completed to be at the direction of the Engineo-inches at

Chase 10.—A bill shall be submitted by the contractor as frequently as the progress of the work may justify for all work executed and not included in any previous bill and the Engineer-in-charge shall take or cause to be taken the requisite measurements for the purpose of having the same verified and the claim, as for as admisisble, adjusted, if possible before the expiry of ten days from the presentation of the bill, at any time depute a subordinate to measure up the said work in the presence of the contractor or his authorised agent, whose countersignature to the measurement list will be sufficient warrant and the Engineer-in-charge may prepare a bill from such list which shall be binding on the contractor in all respects.

Bill to be submitted monthly.

Clause 11.—The contractor shall submit all bills on the printed forms to be had on application at the office of the Engineer-in charge. The charges to be made in the bills shall always be entered at the rates specified in the tender or in the case of any extra work ordered in pursuance of these conditions, and not mentioned or provided for in the tender at the rates become feel provided for such work.

Bills to be on printed forms.

Clause 12,-If the specification or estimate of the work provides for the use of any special description of materials to be supplied from the store of the P.W.D or il it is required that the contractor, shall use certain stores to be provided by the Engineer-in-charge (such material and stores, and the prices to be charged therefore as heremafter mentioned being so far as practicable for the convenience of the contractor but not so as in any way to control the meaning or effect of this contract specified in the schedule or. memorandum hereto annexed) the contractor shall be supplied with such materials and stores as may be required from time to time to be used by bim for the purposes of the contract only and the value of the full quantity of the materials and stores so supplied shall be set off or deducted contract, or otherwise, or from the security deposits, or the preceeds of sale thereof, if the security deposits is held in Government securities, the same or a sufficient portion thereof stall in that case be sold for the purpose. All materials supplied to the contractor shall remain the absolute property of Government and shall on no account be removed from the sire of the work, and shall at all times be open to inspection by the Engineer-in-charge, Any such materials unused and in perfectly good condition at the time of completion or determination of the contract shall be refunded to the P.W.D. store, if the Engineer-in-charge so requires by a notice in writing under his band, but the contractor shall not be entitled to return any such materials except with the consent of the Engineer-in charge and he shall have no claim for compensation on account of any such material supplied to him as aforesaid but remaining unused by him or for, any wastage in or damage to any such materials.

Store supplied by Gov. regent

Clause 13.—The contractor shall execute the whole and every part of the work in the most substantial and work-mani-like manner and both as regards material; and all other matters in strict accordance with the special tions lodged in the office of the Executive Engineer and initialled by the part of the contract. The contract Regions (ROADS)

Works to be exbuted in Accordaace with accordaaces, desvings anders, etc.

CONTRACTOR

that any materials or articles provided by him for the execution of the work are unsound, or of a quality inferior to that contracted for, or are otherwise not in accordance with the contract, it shall be lawful for the Engineer-incharge to intimate this fact in writing to the contractor and then not with standing the fact that the work, materials or articles complained of may have been inadvertently passed, certified and paid for, the contractor shall be bound forthwith to rectify or remove and reconstruct the work so specified in whole or in part, as the case may require, or it so required, shall remove the materials or articles so charge and cost; and in the event of his failing to do so within a period to be specified and provide other proper & suitable materials or articles at his own proper by the Engineer-in-charge in the writing intimation aforesaid, the contractor shall be liable to pay compensation at the rate of one percent. On the amount of the estimate for every day not exceeding ten days, during which the failur eso continues, and in the case of any such failure the Engineer-in-charge may rectify or remove, and reexecute the work or remove and replace the materials or articles complained of as the case may be at the risk and expense in all respects of the contractor. Should the Engineer-in-charge consider that any such inferior work or materials as described above may be accepted or made use of; it shall be his discretion to accept the same at such reduced rates as he may fix therefore.

Clause 18.—All works under or in course of execution executed in Works be oppursuance of the contract shall at all times be open to the inspection and supervision of the Engineer-in-charge and his subordinates, and the contractor shall at all times during the usual working hours, and at all other times at which reasonable notice of the intention of the Engineer-in-charge of Contractor or his subordinate to visit the work shall have been given to the contractor, responsible agent either himself be present to receive orders and instructions, or have a responsible agent duly accredited in writing present for that purpose, Orders given to the contractor's duly authorised agent shall be considered to have the same force an effect as if they had been given to the contractor himself.

responsible agent

Clause 19.—The contractor shall give not less than five days notice in writing to the Engineer-in-charge or his subordinate-in-charge of the work before covering up or otherwise placing beyond the reach of measurement any work in order that the same may be measured, and correct dimensions thereof taken before the same is so covered up or placed beyond the reach of measurement, and shall not cover up or place beyond the reach of measurement any work without the consent in writing of the Engineer- in -charge or his subordinate-in-charge of the work; and if any work shall be covered up or placed beyond the reach of measurement without such notice having been given to consent obtained, the same shall be uncovered at the contractor expense, and in default thereof no payment or allowance shall be made for such work, or for the materials with which the same was

Notice to be given before work is covered up.

Clause 20.-If the contractor or his workmen, or servents shall break, Clause 20.—If the contractor or his workmen, or servants shall break, Contractor his deface, injure, or destroy any part of a building in which they may be work to for desired, and for his land, or any building, road, fence, enclosure of grass land of cultivated ground perfections for continuous to the premises on which the work or any part thereof is being executed, or if any damage shall be done to the work, while it is in progress from any cause whatever or if any imperfections become apparent in it within three months of the grant of a certificate of completion, final or otherwise, by the Engineer-in-charge, the contractor snall make good the same at his own expense, or in default the Engineer-in-charge may cause the same to be made good by other workmen, and deduct the expenses of (which the certificate of the Engineer-in-charge shall be final) from any sums that may then be due or may thereafter become due to the contractor. or from his security deposits or the proceeds of sale thereof, or of a sufficient portion thereof.

three months siter

Clause 21.-The contractor shall supply at his own cost all material texcept such special material, if any, as may, in accordance with the contract, be supplied from the P.W.D. Stores), plant, tools, appliances, imrlements, laddets, cordage, tackle, scaffolding and temporary work requisite or proper for the execution of the work, whether in the original, altered or substituted form, and whether included in the specifications, or other documents, forming part of the contract of referred to in these conditions or not, and which may be necessary for the purpose of satisfying or complying with the requirement of the Engineer-in-charge as to any matters as to which

CONTRACTOR

Contractor to supply plant, ladders scaffoldings, etc.

DISTRICT OFFICER (ROADS TANDO ALLABYAN,

:ted 302-

i to 10 ed.

ire oes

cre

lon ed bal

Or. OB r

10 Or

10

Clause 45 .- If any materials, such as stones metal, bajri, sand etc. are required to be conveyed by rail, the contractors will be granted certificates by the Engineer-in-charge of the work to the effect that the materials are required for Government or semi Government works thereby enabling them to have the benefit of concessionary freight charges from the rankay. In case, however, such a concession is withdrawn by the railway at any time during the currency of the contract, no claim shall be preferable against Government on this account.

Certificata concessionary fre the Rallway.

Clause 46.—When tendered rates are the same preference will be given at the discretion of the accepting authority to those who tender for the carting of materials by vehicles having penumatic tyres.

acceptance of ten ders when tendered rates sto samo,

Procedure

Clause 47.—Any sum due to the Government by the contractor shall be liable for recovery as arrears of Laud Revenue.

Recovery of duct from contractor as-errears of Land Revenue.

Clause 48 - Certified that no member of Legislative Assembly is in partnership with me and that Government will have the right to terminate the contract at any stage if it is discovered that a member of Legislative Assertive is a partner in the contract.

Partnership M L.A'S bidden.

Clause 49-1/We hold myself/ourselves responsible to pay the Sales Tax as livied in accordance with Pakistan General Sales Tax Act. 1943, or any other law for "te time being in force.

Payment of Sale

CONT

Clause 50.—Certified that no Government servant has directly or indirectly a share or interest in the work.

Interest or share Government ervant in the Work

Clause - 51. The contractor will not be allowed to withdraw his and ask for the return of ernest money before expiry of the period shown as under, commencing from the date of opening of the tender and that if it is withdrawn in violation of this condition earnest money shall be forfleted.

When the sanctioning authority for the tender is:-

Executive Engineer

One month.

Superintending Engineer

Two months.

Chief Engineer

Three months.

Government .

Six months.

Clause 52."If any question, difference or objection whatsoever shall arise in any way contracted with or arising out of this instrument or the meaning or objection of any part thereof, the rights, duties or liabilities of either party, then save in so far as the decision of any such matter is here in before provided for as has been so decided, every such matter including whether its decision has been otherwise provided for any or regards the right of and obligations of the parties as the result of such termination shall all by Chief Engineer, (Irrigation), Department and his decision shall be final and binding and where the matter involves a claim for or the payment recovery or deduction of money, only the amount, if any awarded in such

be referred for arbitration to such person as may be appointed in this beh-CONT arbitration shall be recoverable in respect of the matters so referred;

Certified that the Tender has been executed under my personal supervision and I am satisfied that it has been correctly prepared in accordance with the orders issued vide Government P. W.D. circular Memo No. 1015 W. Divisional Accounts Officer. dated 14th September, 1937, and subsequent orders is hed in this

DISTRIBATE AREA AREA AREA AREA. Tando Allabyat.

Cartified that I have noted the content of Government P. W. D. Circular Memorandum No. 1006-1 dated 21st February, 1950, wherein the responsibility of getting the tender checked efficiently is placed on

Contractor

Eugineer.

DISTRICT OFFICER (ROADS) TANDO ALLANYAR.

SCHEDULE, B.

Memorandum Showing Items of Work To be Carried out

| | Overtition | Item of w | Tenders rates | | | Total | |
|--------|---|-----------|---------------|------|----------|--|--|
| Item (| Quantities estimated but may be more or less | | In figu | ires | In words | Unit | amount according to estimated quantities |
| | | | Rs. | Ps. | | | |
| 44. | | | | | | 1 | |
| | | | - 14 | | | e de la companya de l | |
| | | | | | / / | 1 16 | |
| | | | | | / . | UC | |
| 2007 | | | | 1/ | 4 | | |
| | | | | X | | | |
| | | | | | χ | | / |
| | De Paris | | 1/4 | | 6 | | |
| | | | | 1 | 2 | | |
| | | | | 100 | ? | 1/ | |
| | | 1-/- | | | | | |
| | | | 150 | | / | | |
| | | l de co | W. | la i | / / | | |
| + 1 | | 1 0 | | 1 | / | + | |
| | | 100 | | | | | |
| 1 | | | | / | | | |
| | | | / | 1 | | 1 | |
| | | | / | - | | | |
| | | | | | | | |
| | | | | | | 12.6 | |
| | 1 | -/ | | | | + | |
| | | | | | | | |
| | | 4 | | | | | |
| | | | | | | 7- 18 | |
| | | | | 1 1 | | | |
| • | | | | | | | |
| 1. 1. | | | 1000 | | | | |
| . E.V | | | COMMEN | | | | |
| | 220 | 1 | | | | | |
| A. | | | | | | | |

Note 1-All work shall be carried out as per Public works Departments Head-book and other specifications of the Division or as directed.

Note 2—All the columns in the Schedule should be filled in in ink and the total of the entries in the last column should be struck by the contracter under his signature.

Note 3—Rates quoted include clearance of site (prior to commencement of Work and at its close) in all respects and hold good work under all conditions. Site moisture.

Weather, etc. Weather, etc.

Signature of

Executive Engineer (Signature of---Assistant Engines:

SINDH PUBLIC PROCUREMENT REGULATORY AUTHORITY

CONTRACT EVALUATION FORM

TO BE FILLED IN BY ALL PROCURING AGENCIES FOR PUBLIC CONTRACTS OF WORKS, SERVICES & GOODS

| 1) | NAME OF THE ORGANIZATION / DEPTT. Warks & Services Department | |
|-----|--|-----|
| | PROVINCIAL/LOCAL GOVT/OTHER District Gout | |
| 35 | Calabian and Rand | |
| 3) | ALT 11 220 do ted 3-12-2-10 | |
| 4) | C 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 | 0:1 |
| 5) | 1 1-0 / 1 / 1 / 1 / 1 | 5/ |
| 6) | 3 | 1 |
| 7) | TENDER ESTIMATED VALUE 7.5. 10.000 (m) | |
| 8) | ENGINEER'S ESTIMATE (For civil works only) A 424 (m) | |
| 9) | ESTIMATED COMPLETION PERIOD (AS PER CONTRACT) Six Months | |
| 10) | TENDER OPENED ON (DATE & TIME) 04-01-2011 at 2:00 Pm | |
| 11) | NUMBER OF TENDER BOCUMENTS SOLD 03 NOS (Attach list of buyers) | |
| 12) | NUMBER OF BIDS RECEIVED 03 NOS | |
| 13) | NUMBER OF BIDDERS PRESENT AT THE TIME OF OPENING OF BIDS 03 NOS | |
| 14) | BID EVALUATION REPORT (Enclose a copy) Attached | |
| 15) | (Enclose a copy) NAME AND ADDRESS OF THE SUCCESSFUL BIDDER M/s Jaffar Luni Court 1:0 | 9 |
| 16) | CONTRACT AWARD PRICE Re 2 9252660/2 | |
| 17) | RANKING OF SUCCESSFUL BIDDER IN EVALUATION REPORT 1st Nevambes. | |
| | | |
| | | |
| 18) | METHOD OF PROCUREMENT USED : - (Tick one) | |
| | [STATE OF THE STATE OF THE STAT | |
| | a) SINGLE STAGE - ONE ENVELOPE PROCEDURE Domestic/Local | |
| | b) SINGLE STAGE – TWO ENVELOPE PROCEDURE | |
| | | |

| AWARD OF CONTRACT E.D.O (WAS) |
|--|
| |
| T WAS INCLUDED IN ANNUAL PROCUREMENT PLAN? |
| Yes No |
| |
| Yes 3-12 2010 |
| PRA Identification No.) |
| No |
| Yes National News 11-12-2010 |
| (wspapers and dates) Abrat dated H-12-2010 |
| No |
| |
| Dempter 11 fnt. |
| |
| RETERIA / TENDER DOCUMENTS? |
| Yes No No |
| |
| CRITERIA |
| TENDER DOCUMENTS? |
| |
| MPETENT AUTHORITY WAS OBTAINED FOR USING A |
| COMPETITIVE BIDDING? Yes No |
| ED FROM ALL THE BIDDERS? |
| ED FROM ALL THE BIDDERS: Yes V No |
| DID WAS LOWEST FULL HAVE A TO THE TOTAL OF THE PARTY OF T |
| , BID WAS LOWEST EVALUATED Yes No |
| |
| BIDDER WAS TECHNICALLY Yes No |
| |
| |
| |

| 32) ANY DEVIATION FROM SPECIFICATIONS GIVEN IN (If yes, give details) 33) WAS THE EXTENSION MADE IN RESPONSE TIME? (If yes, give reasons) | No THE TEN | DER NOTICE / DOCUMENTS |
|--|--------------|--|
| 33) WAS THE EXTENSION MADE IN RESPONSE TIME? | Yes | DER NOTICE / DOCUMENTS |
| 33) WAS THE EXTENSION MADE IN RESPONSE TIME? (If yes, give reasons) | | |
| 33) WAS THE EXTENSION MADE IN RESPONSE TIME? (If yes, give reasons) | No | |
| 33) WAS THE EXTENSION MADE IN RESPONSE TIME? (If yes, give reasons) | 1 | - |
| ¥ | Yes | |
| | No. | — |
| 34) DEVIATION FROM QUALIFICATION CRITERIA (If yes, give detailed reasons.) | Yes | |
| | No | V |
| 36) WAS A VISIT MADE BY ANY OFFICER/OFFICIAL OF SUPPLIER'S PREMISES IN CONNECTION WITH THE PER ASCERTAINED REGARDING ENLANGING OF THE PER ASCERTAINED REGARDING PER ASCERTAINED REGARD PER ASCERTAINED R | THE PROPERTY | Yes No OCURING AGENCY TO THE |
| BE ASCERTAINED REGARDING FINANCING OF VISIT. (If yes, enclose a copy) | , IF ABRO | DAD: |
| 37) WERE PROPER SAFEGUARDS PROVIDED ON MOBIL THE CONTRACT (BANK GUARANTEE ETC.)? | LIZATIO | The second secon |
| 38) SPECIAL CONDITIONS, IF ANY (If yes, give Brief Description) | Yes 4 | |
| 39) Date of Award of Contract: 08-01-2010 | No | 10 |
| Signature & Official Stamp of Authorized Officer | 1/4 | TRICT OFFICER (ROADS) |
| | | |
| | | |

To,

M/S Jaffar Sani Constt: Co. Government Contractor, Karachi.

SUBJECT:

100

CONSTRUCTION OF ROAD FROM HYDERABAD MIRPURKHAS ROAD @ PIR KATHI DHINGANO BOZDAR ROAD DEH REECHAL VIA DEHS, GUJJO DARRO, KUBBI, DHANDH SHAH MILE 0/0-1/0.

REFERENCE: Your B-I tender dated 04-01-2011,

Your quoted rate premium i.e. Part "A" @ 10.50% Above (Ten Point Five Zero% Above) for Road work, Part "B" @ 34.95% Above (Thirty Four Point Nine Five % Above) for culverts & Part "C" @ 33.00% Above (Thirty Three Point Zero % Above) for 10° span Bridge the tender being the lowest is hereby approved.

You are accordingly informed to please start the aforesaid work within 7 (Seven) days from the date of issue of this work order under the supervision of the Deputy District Officer (Roads) Tando Allahyar and note that the work is to be completed with in a period of (06) Months.

You are also requested to please execute the whole and every parc of the work exactly full in accordance with the specification, design, drawings and instructions in writing relating to the work duly singed by the undersigned and lodged in my office. You are entitled to have access to the same for the purpose of inspection during office tours. If required to make or cause to be made copies of the same specifications and all such Design, Drawings and instruction as aforesaid. The extra conditions as per-fixecutive District Officer (W&S) Department Tando Allahyar letter No. quoted above, is also given below for your information and strict compliance.

- No premiums shall be allowed on non schedule items.
- No separate payment for carriage of materials shall be made. Premium quoted by the contractor covers the cost of carriage of materials involved.
- All materials required for construction shall be procured and brought at site by contractor at his own cost from approved sources/quarries.
- iv) No payment of extra item shall be made unless written order is given to contractor by the District Officer for execution of such extra items and approved by the competent authority.
- Income Tax shall be deducted from the bill on the value of work done and paid for as per latest orders of competent authority in this regard.

185 D

- vi) Contractor shall arrange bitumen from the National Refinery only and payment on account of bitumens item / work done shall be made on production of such certificate by the contractor from the National Refinery.
- vii) Work will be carried out strictly as per PWD specification.
- viii) All requisite codal formalities will be observed before start of work.
- ix) Water charges and all leads and lifts of material are included in the item of work.
- x) If any omission and error found in schedule "B" which will be jointly initialed by the Contractor and District Officer before issuance of work order.
- xi) Item of earth work 95% compaction shall not be executed without use of vibratory road roller.
- No escalation whatever will be allowed the work is continued is next year for want of requisite funds.

The photo-state copies of Schedule-B, (Part A & B) duly attested by the undersigned also enclosed herewith for your information & guidance.

You should give in writing the name of your authorized agent who would receive instructions at the site of work during the course of its execution and also attend whis office for signing the agreement.

DISTRICT OFFICER (ROADS)
TANDO ALLAHOAR

Copy forwarded to the Deputy District Officer (Roads) Tando Allahyar for information and necessary action. The copies of Schedule-B (Part A & B) are enclosed herewith for his record and carrying out the work accordingly. The work should strongly be carried out as per P.W.D. specifications. The date of start of work should also be reported to this office for record.

huna

SECTION OF THE STATE OF

DISTRICT OFFICER (ROADS)

Department of the second

OFFICE OF THE DISTRICT OFFICER (ROADS) TANDO ALLAHYAR

COMPARATIVE STATEMENT

B.I

Date of issue

04-01-2011

Date of opening

04-01-2011

NAME OF WORK:

Construction of road from Hyderabad Mirpurkhas road @ Pir

Kathi Dhingano Bozdar road Deh Reechal via Dehs, Gujjo Darro,

Kubbi, Dhandh Shah mile 0/0-1/0

| S.No | Name of Contractor Whom Tender issued | Road Work Part (A) Construction | Road Work Part (B) Culverts | M. Structure (1) (2) (3) |
|------|--|---------------------------------------|-----------------------------------|-----------------------------|
| 01 | 02 | 03 | 04 | 05 |
| | | | | |
| 0 | Taffar Sari Const! Company | 10.50% | 34.95% | 33.00% |
| | Company | Above | Above | Alove |
| | | | 1 | |
| 2 | Rufi & Co. | 11.80% | 37.00% | 36.10% |
| | | Abou | Above | Above |
| | | | 1 | 1 |
| (3) | Kamsan Hyder | 12.10% Alcore | 37.70% | 36.50% |
| | | AJeoro | Alove | Above |
| | | | | |
| | | | | 20018 |

Certified that the tenders have been opened before us.

DIVISIONAL ACCOUNTS OFFICER

DISTRICT OFFICER (ROADS)

TANDO ALLAHYAR

Opened in my Persence

DISTRICT OFFICER (ROADS)

TANDO ALLAHYAR

EXECUTIVE DISTRICT OFFICER
WORKS & SERVICES DEPARTMENT
MANDO ALLAHYAR

| | 1 | (4) | |
|--------|---|-----|-----------------------------|
| NAME O | 4 | | EPARTM NDO AL)RT TAN |
| 7 | | | |
| | | 1 | - 1 |

NDO

IENT E.D.O. Issued to Mr./Messrs. Joffan Comi Coni

D.R. No. 10/36

dt. 04/1/2011

-55/DOR/230

B-1 TENDER FOR WORKS

DISTRICT OFFICER ROADS TANDO ALLAHYAR

I/ We hereby tender for the execution, for the Governor of Sindh, (hereinbefore) and hereinafter referred to as "Government"), of the work specified in the under written memorandum within the time specified in such memorandum at Part "A" 10. So % Above/Below Part "B" 34.95% Above/Below (Part "C" 32.0% Above/Below & Part "D" — % Above/Below the estimated rates entered in Schedule 'B' (memorandum showing items of work to be carried out and in accordance in all respects with the specifications, designs, drawings and instructions in writing referred to in Rule-I here of and in Clause-12 of the annexed conditions of contract and agree that when materials for the work are provided by the Government such materials and the rates to be paid for them shall be as provided in Schedule 'A' hereto.

MEMORANDUM\

General Description

Construction of road from Hyderabad Mirpurkhas road @ Pir Kathi Dhingano Bozdar road Deh Reechal vis Dehs, Gujjo Darro, Kubbi, Dhandh Shah mile 0/0-1/0

(a) Estimated Cost

10000000 /= Rs.

Earnest Money 2% (b)

200000 /=

Security Deposit (i/c E/Money) 5% (c)

500000 /=

Percentage, if any, to be deducted from bills 3%

300000 /=

Time allowed for the work from (e) date of written order to commence.

Should this tender be accepted. I/We hereby agree to abide by any fulfill all the terms and provisions of the conditions of contract annexed here to so far as applicable, and in default there of to forfeit and ay to Government the sum of money mentioned in the said conditions

Receipt / Call Deposit No. 00/8989 dated 22-12-2010 ' from upt good led: Airpost - lournagen in respect of the sum of

in respect of the sum of

Rs. 20000/3 is herewith forwarded representing the earnest money (a) the full

value of which is to be absolutely forfeited to government should 1 / We not deposit the full amount of security deposit specified in the above memorandum, in accordance with Clausent (A) of the said conditions, otherwise the said sum of Rs. shall be retained by Government on account of such security deposit as aforesaid, or (b) the full value of which shall be retained by the Government on account of the security deposit specified in Clause-1

B) of the conditions.

CONTRACTOR

NAME OF WORK:- CONSTRUCTION

OF ROAD FROM HYDERABAD MIRPURKHAS ROAD @ PIR KATHI DHINGANO BOZDAR ROAD DEH REECHAL VIA DEIIS, GUJJO DARRO, KUBBI, DHANDH SHAH MILE 0/0-1/0 = 1.61 KM (PART-A)

| QTY | S.NO | ITEM OF WORK | RATE | UNIT | AMOUNT |
|-----|------|--------------|------|------|--------|
|-----|------|--------------|------|------|--------|

1-EARTH WORK

Earth work for road embankment by bulldozers including ploughing, mixing, clod breaking, dressing with optimum moisture content, lead up to 100 ft and lift up to 5 ft in all types of soil except rock. (If earthwork is done by other than departmental agency).

85 % Density

498590 Cft W/O Lead

@ Rs. 2515.39 %0 Cft

Rs. 1254148.00

346930 Cft With Lead @ Rs. 4408.53 %0 Cft

Rs. 1529451.00

76138 Cft

95%to 100% Density @ Rs. 5377.55 %0 Cft

Rs. 40936.00

Preparing SUB-BASE COURSE by supplying and spreading stone metal approved quality form 2approved quarry properly graded to maximum size 1 1/2" required thickness of proper camber and spreading 15 cft screening and non plastic quarry fines filling depression with stone metal after initial rolling watering and compacting the same so as to achieve 100% density as per modified AASHO specifications Rate i/cs providing and using templates, camber, plates screens farm and directed, rate i/cs all cost of materials t&P carriage upto site of work.

32630 Cft

@ Rs. 3364.27 % Cft

Rs. 1097761.00

3-BRICK ON EDGING Laying of including supplying of 9" x4 1/2" x 3" 1st class burnt bricks excavation for laying edging with small side parallel to the road. Rate including all cost of material T&P and carriage upto 3 chains.

10560 Rft

@ Rs. 827.05% Rft

87336.00

BASE COURSE Preparing by supplying and spreading stone metal approved quality form 4approved quarry properly graded to maximum size 1 1/2" required thickness of proper camber and spreading 15 cft screening and non plastic quarry fines filling depression with stone metal after initial rolling watering and compacting the same so as to achieve 100% density as per modified AASHO specifications Rate i/cs providing and using templates, camber, plates screens farm and directed, rate i/cs all cost of materials t&P carriage upto site of work.

32630 Cft

@ Rs. 3535.78% Cft

Rs. 1153725.00

THREE COAT Providing Three Coat of surface dressing on new or existing surface with 40 + 5-25 +14 = 79 lbs of bitumen 80/100 penetration and 5.50 + 2.75 + 1.5 = 9.75 cft bajri of 3/4" x 1/2" gauge for first coat, 1/2" - 3/8" gauge for 2nd Coat, 3/8" - 1/4" for 3rd Coat i/c cleaning the road surface before lying each coat and rolling with power roller laying each coat separately. Rate includes all cost of materials T&P and carriage up to site of work.

65261 Sft

@ Rs. 991.37 Sft

Rs. 646978.00

EARTH WORK for embankment form B.Pits i/c laying in 6" layer clod breaking dressing 6etc. complete load upt 100cft and lift up to 5.0 ft. (in ordinary soil).

81404 Cft

@ Rs. 3854.80 % Rft

Rs. 313796.00

TOTAL

Rs. 6492631.00

Add: Diff: Cost Bitumen 23.01Tons @ Rs. 50035.07 =

Rs. 1151321.00

G. TOTAL

Rs. 7643952.00

I/We undertake to accept any change in quantities rates and amount as per Technically, Sanctioned Estimates.

I/We shall not claim any change in the quoted premium.

CONTRACTOR

DISTRICT OFFICER (ROADS) TANDO ALLAHYAR

FROM NAME OF WORK:- CONSTRUCTION OF ROAD HYDERABAD MIRPURKHAS ROAD @ PIR KATHI DHINGANO BOZDAR ROAD DEH REECHAL VIA DEHS, GUJJO DARRO, KUBBI, DHANDH SHAH MILE 0/0-1/0 = (1.61 KM) 3' SPAN RCC SLAP CULVERT (PART-E)

RATE AMOUNT UNIT S.NO ITEM OF WORK QTY

1. Excavation in foundation of building bridges and other structure i/c dag belling dressing refilling around structure with excavated stuff watering ramming lead upto 100" and lift upto 5 feet (in ordinary soil).

1190 Cft

@ Rs. 1306/80

per %0 cft.

Rs. 1555.00

Cement concrete brick on stone metal ballast Ratio 1:4:8

245 Cft

@ Rs. 3584/10

per %0 Cft.

Rs. 8781.00

3. Pucca brick work ratio 1:4 work in foundation and plinth in cement sand mortar Ratio 1:4.

597 Cft

@ Rs. 4150.30

per %0 Cft.

Rs. 24777.00

4. Cement concrete plain i/c compacting finishing & curing etc complete (i/c screening of aggregate w/o shuttering) ratio 1:2:4

84 Cft

@ Rs. 5941/10

per % cft.

Rs. 4991.00

5. Fabrication of mild steel reinforcement for cement concrete i/c cutting bending binding laying in position making joints & festering i/c cost of binding wire also i/c removal of rust form bars.

5.67 Cwt.

@ Rs. 2651/55

per Cwt

Rs. 15034.00

6. R.C.C work i/c all labour & material except the cost of steel reinf: and its labor for binding and remning which will be paid separately rate including all kinds of forms moulds lighting shuttering curing rendering and finishing surface i/c screaming and finishing pre-cast laid in position complete in all respect ration 1:2:4.

@ Rs. 114/00

per % cft.

7. Brick on edge flooring laid in 1:6 cement Mortar over a bed of 3/4" thick cement mortar 1:7 Bed flooring.

79 Rft

@ Rs. 1736/13

per % Sft.

Rs. 1372.00

8. Cement Plaster 1:3 upto 20.0' height 1/2 " thick.

361 Sft

@ Rs. 604/18

per % Sft.

Rs. 2181.00

Erection and removal of cetentering for cement concrete (Plan).

107 Sft

@ Rs. 1405/75 per % Sft.

Rs. 1504.00

Grand Total

Rs. 69429.00

I/We undertake to accept any change in quantities rates and amount as per Technically, Sanctioned Estimates.

I/We shall not claim any change in the quoted premium 2.

CONTRACTOR

DISTRICT OFFICER (ROADS) TANDO ALLAHYAR

ALLAHYAR

WORKS & SERVICES DEPARTMENT E.D.O. Issued to Mr./Messrs. Roof & Co.
WORKS & SERVICES TANDO ALLAHYAR
D.O. ROADS & TRANSPORT TANDO

Sourcement Contt And charged Rs: 3000 | = D.R. No. (0/34 dt. 04/1/2011

N.I.T. No. TC/G-55/DOR/230 Dated: 03-12-2010

DISTRICT OFFICER ROADS TANDO ALLAHYAR

B-1 TENDER FOR WORKS

I/ We hereby tender for the execution, for the Governor of Sindh, (hereinbefore) and hereinafter referred to as "Government"), of the work specified in the under written memorandum within the time specified in such memorandum at Part "A" //-80 % Above Below Part "B" 37.0% Above Below (Part "C" 36.10% Above Below & Part "D" — % Above Below the estimated rates entered in Schedule 'B' (memorandum showing items of work to be carried out and in accordance in all respects with the specifications, designs, drawings and in structions in writing referred to in Rule-I here of and in Clause-12 of the annexed conditions of contract and agree that when materials for the work are provided by the Government such materials and the rates to be paid for them shall be as provided in Schedule A hereto.

MEMORANDUM

General Description 1.

: Construction of road from Hyderabad Mirpurkhas road @ Pir Kathi Dhingano Bozdar road Deh Reechal via Dehs, Gujjo Darro, Kubbi, Dhandh Shah mile 0/0-1/0

Estimated Cost (a)

Rs. 10000000 /=

Earnest Money 2% (b)

Rs. 200000 /=

Security Deposit (i/c E/Money) 5% (c)

Rs. 500000 /=

Percentage, if any, to be deducted

Rs. 300000 /=

from bills 3%

(06) Months

Time allowed for the work from (e) date of written order to commence.

Should this tender be accepted. I/We hereby agree to abide by any fulfill all the terms and provisions of the conditions of contract annexed here to so far as applicable, and in default there of to forfeit and ay to Government the sum of money mentioned in the said conditions.

Receipt / Call Deposit No. 00000 10 481 dated 21-12-2070 from The bouls of punjal Saddat Cant Hyderalous in respect of the sum of 2000057-____ is herewith forwarded representing the earnest money (a) the full value of which is to be absolutely forfeited to government should I / We not deposit the full amount of security deposit specified in the above memorandum, in accordance with Clause01 (A) of the said conditions, otherwise the said sum of Rs. 2000007z shall be retained by Government on account of such security deposit as aforesaid, or (b) the full value of which shall be retained by the Government on account of the security deposit specified in Clause-1 (B) of the conditions.

ICT OFFICER (ROADS) ANDO ALLAHYAR

NAME OF WORK:- CONSTRUCTION OF ROAD FROM HYDERABAD MIRPURKHAS ROAD @ PIR KATHI DHINGANO BOZDAR ROAD DEH REECHAL VIA DEHS, GUJJO DARRO, KUBBI,

| | DHA | NDH SHAH MILE 0/0-1/0 = 1.61 | KM (PART-A) |
|-----|--|--|---|
| QTY | S.NO ITEM | OF WORK RATE | UNIT AMOUNT |
| 1- | dressing with optimum m | pankment by bulldozers including ploisture content, lead up to 100 ft an is done by other than departmental 85 % Density | d lift up to 5 ft in all types of soil |
| | 498590 Cft W/O Lead 346930 Cft With Lead | @ Rs. 2515.39 %0 Cft | Rs. 1254148.00 Rs. 1529451.00 |
| | 76138 Cft | 95%to 100% Density @ Rs. 5377.55 %0 Cft | Rs. 40936.00 |
| 2- | approved quarry properly g and spreading 15 cft scree after initial rolling watering modified AASHO specificat | JRSE by supplying and spreading st graded to maximum size 1 ½" requi ning and non plastic quarry fines fill and compacting the same so as to ions Rate i/cs providing and using te all cost of materials t&P carriage up @ Rs. 3364.27 % Cft | ired thickness of proper camber ling depression with stone metal achieve 100% density as per mplates, camber, plates screens |
| 3- | BRICK ON EDGING Laying excavation for laying edginaterial T&P and carriage 10560 Rft | ng of including supplying of 9" x4 ½ ng with small side parallel to the roa e upto 3 chains. @ Rs. 827.05% Rft | " x 3" 1 st class burnt bricks d. Rate including all cost of Rs. 87336.00 |
| 4- | approved quarry properly of and spreading 15 cft screen after initial rolling watering modified AASHO specificate | g by supplying and spreading stor graded to maximum size 1 ½" requining and non plastic quarry fines fill and compacting the same so as to ions Rate i/cs providing and using te all cost of materials t&P carriage up | ired thickness of proper camber ling depression with stone metal achieve 100% density as per implates, camber, plates screens |
| | 32630 Cft | @ Rs. 3535.78% Cft | Rs. 1153725.00 |
| 5- | 25 +14 = 79 lbs of bitumen gauge for first coat, 1/2" – surface before lying each | hree Coat of surface dressing on n 80/100 penetration and 5.50 + 2.75 3/8" gauge for 2 nd Coat, 3/8" – 1/4" coat and rolling with power roller la ials T&P and carriage up to site o @ Rs. 991.37 Sft | $5 + 1.5 = 9.75$ cft bajri of $\frac{3}{4}$ " x $\frac{1}{2}$ " for 3^{rd} Coat i/c cleaning the road ying each coat separately. Rate |
| 6- | EARTH WORK for emba | unkment form B.Pits i/c laying in 6 00cft and lift up to 5.0 ft. (in ordina @ Rs. 3854.80 % Rft | " layer clod breaking dressing |

TOTAL

Rs. 6492631.00

Rs. 1151321.00

Add: Diff: Cost Bitumen 23.01Tons @ Rs. 50035.07 =

Rs. 7643952.00

G. TOTAL

I/We undertake to accept any change in quantities rates and amount as per Technically, Sanctioned Estimates.

I/We shall pot claim any change in the quoted premium. 2.

DISTRICT OFFICER (ROADS) CONTRACTOR

TANDO ALLAHYAR

ROAD NAME OF WORK:- CONSTRUCTION OF FROM MIRPURKHAS ROAD @ PIR KATHI DHINGANO BOZDAR ROAD DEH REECHAL VIA DEHS, GUJJO DARRO, KUBBI, DHANDH SHAH MILE 0/0-1/0 = (1.61 KM) 10' SPAN BRIDGE (PART-B) RATE UNIT **AMOUNT** ITEM OF WORK S.NO QTY 1. Excavation in foundation of building bridges and other structure i/c dag belling dressing refilling around structure with excavated stuff watering ramming lead upto 100" and lift upto 5 feet (in ordinary soil). Rs. 6073.00 @ Rs. 1306/80 per %0 cft. 4647 Cft Cement concrete brick on stone metal ballast Ratio 1:4:8 Rs. 48063.00 @ Rs. 3584/10 per %0 Cft. 1341 Cft 3. Pucca brick work ratio 1:4 work in foundation and plinth in cement sand mortar Ratio 1:4. per %0 Cft. Rs. 119197.00 @ Rs. 4150.30 2872 Cft 4. Cement concrete plain i/c compacting finishing & curing etc complete (i/c screening of aggregate w/o shuttering) ratio 1:2:4 Rs. 9743.00 @ Rs. 5941/10 per % cft. 164 Cft 5. Fabrication of mild steel reinforcement for cement concrete i/c cutting bending binding laying in position making joints & festering i/c cost of binding wire also i/c removal of rust form bars. Rs. 130403.00 @ Rs. 2651/55 per Cwt 49.18 Cwt. 6. R.C.C work i/c all labour & material except the cost of steel reinf: and its labor for binding and remning which will be paid separately rate including all kinds of forms moulds lighting shuttering curing rendering and finishing surface i/c screaming and finishing pre-cast laid in position complete in all respect ration 1:2:4. Rs. 77634.00 per % cft. @ Rs. 114/00 681 Cft Cement Plaster 1:3 upto 20.0' height 1/2 " thick. Rs. 3281.00 @ Rs. 604/18 per % Sft. 543 Sft Erection and removal of cetentering for cement concrete (Plan). per % Sft. 675.00 @ Rs. 1405/75 Rs.

 I/We undertake to accept any change in quantities rates and amount as per Technically, Sanctioned Estimates.

Grand Total

I/We shall not claim any change in the quoted premium.

CONTRACTOR

DISTRICT OFFICER (ROADS)
TANDO ALLAHYAR

Rs.395069.00

| | | | SCHEDU | LE "B" | | 14 |
|-------------------|-----|---|---|--------------------------------------|----------------------|---|
| | IAI | ME OF WORK | | | | |
| *** | WA. | ME OF WORK:- | MIRPURKHAS ROA ROAD DEH REECH | AL VIA DEH | THI S, GU | DHINGANO BOZDAR JJO DARRO, KUBBI, 1) 3' SPAN RCC SLAP |
| | Q1 | TY S.NO ITEM | OF WORK | RATE | UN | IT AMOUNT |
| | 1. | Excavation in found refilling around stru upto 5 feet (in ordin | cture with excavated st | es and other str tuff watering ra | ucture mming | i/c dag belling dressing lead upto 100" and lift |
| | | 1190 Cft | @ Rs. 1306/80 | per %0 cft. | Rs. | 1555.00 |
| | 2. | Cement concrete br | ick on stone metal balla | ast Ratio 1:4:8 | | |
| | | 245 Cft | @ Rs. 3584/10 | per %0 Cft. | Rs. | 8781.00 |
| The second second | 3. | Pucca brick work Ratio 1:4. | ratio 1:4 work in four | ndation and p | linth ir | n cement sand mortar |
| | | 597 Cft | @ Rs. 4150.30 | per %0 Cft. | Rs. | 24777.00 |
| | 4. | Cement concrete pl aggregate w/o shutt | ain i/c compacting finis ering) ratio 1:2:4 | hing & curing e | etc cor | mplete (i/c screening of |
| | | 84 Cft | @ Rs. 5941/10 | per % cft. | Rs. | 4991.00 |
| | 5. | Fabrication of mild slaying in position material form bars. | steel reinforcement for aking joints & festering in | cement concre /c cost of bindir | ete i/c o ng wire | cutting bending binding also i/c removal of rust |
| | | 5.67 Cwt. | @ Rs. 2651/55 | per Cwt | Rs. | 15034.00 |
| | 6. | binding and remnin moulds lighting shu | g which will be paid s | separately rate g and finishing | includ | reinf: and its labor for ling all kinds of forms ce i/c screaming and 2:4. |
| | 12 | 81 Cft | @ Rs. 114/00 | per % cft. | Rs. | 9234.00 |
| | 7. | Brick on edge flooring. | ng laid in 1:6 cement N | Nortar over a be | ed of 3 | 4" thick cement mortar |
| | | 79 Rft | @ Rs. 1736/13 | per % Sft. | Rs. | 1372.00 |
| | 8. | Cement Plaster 1:3 (| upto 20.0' height 1/2 " th | nick. | | |
| | | 361 Sft | @ Rs. 604/18 | per % Sft. | Rs. | 2181.00 |
| | 9. | | I of cetentering for cem | ent concrete (F | Plan). | |
| | | 107 Sft | @ Rs. 1405/75 | per % Sft. | Rs. | 1504.00 |
| | | | Grand | Total | Rs. | 69429.00 |

I/We undertake to accept any change in quantities rates and amount as per 1. Technically, Sanctioned Estimates.

2. I/We shall not claim/any change in the quoted premium

CONTRACTOR

DISTRICT OFFICER (ROADS) TANDO ALLAHYAR

WORKS & SERVICES DEPARTMENT E.D.O. WORKS & SERVICES TANDO ALLAHYAR D.O. ROADS & TRANSPORT TANDO ALLAHYAR

Issued to Mr./Messrs. Kamram Hydra(0:

work: Cometars

And charged Rs: 3001=

D.R. No. 10137

dt. 4111 2011

DISTRICT OFFICER ROADS TANDO ALLAHYAR

N.I.T. No. TC/G-55/DOR/230 Dated: 03-12-2010

B-1 TENDER FOR WORKS

I/ We hereby tender for the execution, for the Governor of Sindh, (hereinbefore) and hereinafter referred to as "Government"), of the work specified in the under written memorandum within the time specified in such memorandum a Part "A" /2-10% Above/Below Part "B" 37.7% Above/Below Part "C" 36.5% Above/Below & Part "B" - % Above/Below the estimated rates entered in Schedule (memorandum showing items of work to be carried out and in accordance all respects with the specifications designs and appropriate the specifications of the specification of the spec was uctions in writing referred to in Rule-I here of and in Clause-12 of the amexed conditions of contract and agree that when materials for the work are provided by the Government such materials and the rates to be paid for them shall be as provident in Schedule 'A' hereto.

DED MEMORANDUM "INOPOLI"

General Description 1

: Construction of road from Hyderabad Mirpurkhas mad @ Pir Kathi Dhingano Bozdar road Den Reechal via Debs, Gujjo Darro, Kubbi, Dhandh Shab mile 0/0-1/0

Estimated Cost (a)

100000000 /= Rs.

Earnest Money 2% (b)

200000 /= Rs.

Security Deposit (i/c E/Money) 5% (C)

500000 /= Rs.

Percentage, if any, to be deducted

300000 /= Rs.

from bills 3%

(06) Months

Time allowed for the work from (e) date of written order to commence.

Should this tender be accepted. I/We hereby agree to abide by any fulfill all the terms and provisions of the conditions of contract annexed here to so far as applicable, and in default there of to forfeit and ay to Government the sum of money mentioned in the said conditions

Receipt / Call Deposit No. 4967001 dated 31/12/3010 from this Dance Class at Gum MRA HID: in respect of the sum of Rs. 200,000 = is herewith forwarded representing the earnest money (a) the full value of which is to be absolutely forfeited to government should I / We not deposit the full amount of security deposit specified in the above memorandum in accordance with Clause01

(A) of the said conditions, otherwise the said sum of Rs. 2000 - shall be retained by Government on account of such security deposit as aforesaid, or (b) the full value of which shall be retained by the Government on account of the security deposit specified in Clause-1

(B) of the conditions.

ICER (ROADS)

NAME OF WORK:- CONSTRUCTION ROAD FROM MIRPURKHAS ROAD @ PIR KATHI DHINGANO BOZDAR ROAD DEH REECHAL VIA DEHS, GUJJO DARRO, KUBBI, DHANDH SHAH MILE 0/0-1/0 = 1.61 KM (PART-A)

| provide an artist of the history | | | | | |
|----------------------------------|------|--------------|------|------|--------|
| QTY | S.NO | ITEM OF WORK | RATE | UNIT | AMOUNT |

1-EARTH WORK

Earth work for road embankment by bulldozers including ploughing, mixing, clod breaking, dressing with optimum moisture content, lead up to 100 ft and lift up to 5 ft in all types of soil except rock. (If earthwork is done by other than departmental agency).

85 % Density

498590 Cft W/O Lead

@ Rs. 2515.39 %0 Cft

Rs. 1254148.00

346930 Cft With Lead @ Rs. 4408.53 %0 Cft

Rs. 1529451.00

95%to 100% Density

76138 Cft

@ Rs. 5377.55 %0 Cft

Rs. 40936.00

Preparing SUB-BASE COURSE by supplying and spreading stone metal approved quality form 2approved quarry properly graded to maximum size 1 1/2" required thickness of proper camber STATE OF THE PARTY and spreading 15 cft screening and non plastic quarry fines filling depression with stone metal after initial rolling watering and compacting the same so as to achieve 100% density as per modified AASHO specifications Rate i/cs providing and using templates, camber, plates screens farm and directed, rate i/cs all cost of materials t&P carriage upto site of work.

32630 Cff

@ Rs. 3364.27 % Cft

Rs. 1097761.00

BRICK ON EDGING Laying of including supplying of 9" x4 1/2" x 3" 1st class burnt bricks 3excavation for laying edging with small side parallel to the road. Rate including all cost of material T&P and carriage upto 3 chains.

10560 Rft

@ Rs. 827.05% Rft

Rs. 87336.00

BASE COURSE Preparing by supplying and spreading stone metal approved quality form 4approved quarry properly graded to maximum size 1 1/2" required thickness of proper camber and spreading 15 cft screening and non plastic quarry fines filling depression with stone metal after initial rolling watering and compacting the same so as to achieve 100% density as per modified AASHO specifications Rate i/cs providing and using templates, camber, plates screens farm and directed, rate i/cs all cost of materials t&P carriage upto site of work.

32630 Cft

@ Rs. 3535.78% Cft

Rs. 1153725.00

5-THREE COAT Providing Three Coat of surface dressing on new or existing surface with 40 + 25 +14 = 79 lbs of bitumen 80/100 penetration and 5.50 + 2.75 + 1.5 = 9.75 cft bajri of 3/4" x 1/2" gauge for first coat, 1/2" - 3/8" gauge for 2nd Coat, 3/8" - 1/4" for 3rd Coat i/c cleaning the road surface before lying each coat and rolling with power roller laying each coat separately. Rate includes all cost of materials T&P and carriage up to site of work.

65261 Sft

@ Rs. 991.37 Sft

Rs. 646978.00

6-EARTH WORK for embankment form B.Pits i/c laying in 6" layer clod breaking dressing etc. complete load upt 100cft and lift up to 5.0 ft. (in ordinary soil).

81404 Cft

@ Rs. 3854.80 % Rft

Rs. 313796.00

TOTAL

Rs. 6492631.00

Add: Diff: Cost Bitumen 23.01Tons @ Rs. 50035.07 =

Rs. 1151321.00

G. TOTAL

Rs. 7643952.00

I/We undertake to accept any change in quantities rates and amount as per Technically, Sanctioned Estimates.

I/We shall not claim any change in the quoted premium. 2.

> DISTRICT OFFICER (ROADS) TANDO ALLAHYAR

NAME OF WORK:- CONSTRUCTION OF ROAD FROM HYDERABAD MIRPURKHAS ROAD @ PIR KATHI DHINGANO BOZDAR ROAD DEH REECHAL VIA DEHS, GUJJO DARRO, KUBBI, DHANDH SHAH MILE 0/0-1/0 = (1.61 KM) 10' SPAN BRIDGE (PART-B)

QTY S.NO ITEM OF WORK RATE UNIT AMOUNT

 Excavation in foundation of building bridges and other structure i/c dag belling dressing refilling around structure with excavated stuff watering ramming lead upto 100" and lift upto 5 feet (in ordinary soil).

4647 Cft

@ Rs. 1306/80

per %0 cft.

Rs. 6073.00

Cement concrete brick on stone metal ballast Ratio 1:4:8

1341 Cft

@ Rs. 3584/10

per %0 Cft.

Rs. 48063.00

3. Pucca brick work ratio 1:4 work in foundation and plinth in cement sand mortar Ratio 1:4.

2872 Cft

@ Rs. 4150.30

per %0 Cft.

Rs. 119197.00

 Cement concrete plain i/c compacting finishing & curing etc complete (i/c screening of aggregate w/o shuttering) ratio 1:2:4

164 Cft

@ Rs. 5941/10

per % cft.

Rs. 9743.00

 Fabrication of mild steel reinforcement for cement concrete i/c cutting bending binding laying in position making joints & festering i/c cost of binding wire also i/c removal of rust form bars.

49.18 Cwt.

@ Rs. 2651/55

per Cwt

Rs. 130403.00

6. R.C.C work i/c all labour & material except the cost of steel reinf: and its labor for binding and remning which will be paid separately rate including all kinds of forms moulds lighting shuttering curing rendering and finishing surface i/c screaming and finishing pre-cast laid in position complete in all respect ration 1:2:4.

681 Cft

@ Rs. 114/00

per % cft.

Rs. 77634.00

7. Cement Plaster 1:3 upto 20.0' height 1/2 " thick.

543 Sft

@ Rs. 604/18

per % Sft.

Rs. 3281.00

8. Erection and removal of cetentering for cement concrete (Plan).

48 Sft

@ Rs. 1405/75

per % Sft.

Rs. 675.00

Grand Total

Rs.395069.00

 I/We undertake to accept any change in quantities rates and amount as per Technically, Sanctioned Estimates.

2. I/We shall not claim any change in the quoted premium.

NTRACTOR

DISTRICT OFFICER (ROADS)

TANDO ALLAHYAR

NAME OF WORK:- CONSTRUCTION ROAD FROM HYDERABAD MIRPURKHAS ROAD @ PIR KATIH DHINGANO BOZDAR ROAD DEH REECHAL VIA DEHS, GUJJO DARRO, KUBBI, SLAP


| | <u>D</u> | <u>HANDH SHAH MI</u> ULVERT (PART-C | $\frac{\text{ILE } 0/0-1/0}{1} = (1)$ | .61 KM) 3' SPAN | RCC SLAP |
|----|---|--|---------------------------------------|---|--------------------------------|
| QT | Y S.NO ITEM O | F WORK | RATE | UNIT AMO | DUNT |
| 1. | Excavation in foundati refilling around structuupto 5 feet (in ordinary | re with excavated | es and other str stuff watering ra | ucture i/c dag bel mming lead upto | ling dressing 100" and lift |
| | 1190 Cft | @ Rs. 1306/80 | per %0 cft. | Rs. 1555.00 | |
| 2. | Cement concrete brick | on stone metal bal | last Ratio 1:4:8 | | |
| | 245 Cft | @ Rs. 3584/10 | per %0 Cft. | Rs. 8781.00 | |
| 3. | Pucca brick work rat Ratio 1:4. | tio 1:4 work in fo | undation and p | linth in cement | sand mortar |
| | 597 Cft | @ Rs. 4150.30 | per %0 Cft. | Rs. 24777.00 | |
| 4. | Cement concrete plair aggregate w/o shutteri | n i/c compacting fin ng) ratio 1:2:4 | ishing & curing | etc complete (i/c | screening of |
| | 84 Cft | @ Rs. 5941/10 | per % cft. | Rs. 4991.00 | 20 |
| 5. | Fabrication of mild ste laying in position making form bars. | el reinforcement fo ng joints & festering | r cement concre i/c cost of bindi | ete i/c cutting ben ng wire also i/c rer | ding binding moval of rust |
| | 5.67 Cwt. | @ Rs. 2651/55 | per Cwt | Rs. 15034.00 | |
| 6. | R.C.C work i/c all lab binding and remning moulds lighting shutte finishing pre-cast laid in | which will be paid ring curing renderi | separately rate ng and finishing | including all kin surface i/c scr | ds of forms |
| | 81 Cft | @ Rs. 114/00 | per % cft. | Rs. 9234.00 | |
| 7. | Brick on edge flooring 1:7 Bed flooring. | laid in 1:6 cement | Mortar over a b | ed of 34" thick cer | ment mortar |
| | 79 Rft | @ Rs. 1736/13 | per % Sft. | Rs. 1372.00 | |
| 8. | Cement Plaster 1:3 upt | to 20.0' height 1/2 " | thick. | | |
| | 361 Sft | @ Rs. 604/18 | per % Sft. | Rs. 2181.00 | |
| 9. | Erection and removal o | f cetentering for cer | ment concrete (F | Plan). | |
| | 107 Sft | @ Rs. 1405/75 | per % Sft. | Rs. 1504.00 | |
| | | Grand | d Total | Rs.69429.00 | 99 |

I/We undertake to accept any change in quantities rates and amount as per Technically, Sanctioned Estimates.

I/We shall not claim any change in the quoted premium. 2.

CONTRACTOR

DISTRICT OFFICER (ROADS) TANDO ALLAHYAR



mont the sums of money mentioned in the said conditions.

Receipt No. 00/8918 dated 22-12-10 from Government Treasury or sub-Treasury at 1-1-1 book Airporties fresher of the suin of Res. 20000872 is herewith forwarded representing the earnest money (10) the full value of

which is to be absolutely, forfeited to Government should we - not deposit

the full amount of security deposit specified in the above memorandum in accordance with Clause 1 (A) of the said conditions, otherwise the said sum of Rs. shall be retained by Goevenment on account of such security deposite as aforesaid J. or (b) the latt value of which shall be retained by the Govennment on account of the security deposit specified in clause I (B) of the conditions]. "

Amount to be epscified in words and figures

Strike out (a) if

deposit is to be

**Strike out (b) if any cash security denosit is to be

isken.

taken-

(Witnesses TRAMITY SETT ALL OF WORLD FOR THE CONTROL OF SIGNATURE OF STREET OF SIGNATURE OF SIGN Dated the

Tis above tender is hereby accepted by me on behalf of the covernor DETRICTOR FEER (ROADS) of Sind. TANDO ALLASYA

Division (or he duly authorized Assistant)

Deren the

day of

Condition of Contract

(60)

appriv deposits,

Clause 1.-The Persons whose tender may be accepted (herrinafter called

the contractor) shall (A) [(within one day for a contract of Rs. 1,000 or. oss, or two days for a contract of more than Rs. 1,000 upto Rs. 2,000 and o on, upto a limit of ten days, for a contract of Rs. 10,000 or more of the acceptance of his tender) deposit with the Executive Ingineer in cash or Govi; Securities endorsed to Executive Engineer (if denosited for more then twelve months) a sum sufficient with the amount of the carnest money deposited by him with his tender to make up the full security deposit specified in the tender), or (B) (posmit Government at the time of making any payment to him for work done under the contracts to deduct such sum as well (With the earnest money deposited by him.) amount more percent of all moneys so payable: such deduction to be hold by Government by way of security deposit): Provided always that in the event any payment to the contractor for work done under the contract to make up the full amount of percent by deducting a sufficient sum from every such payment as last aforesaid. All compensation other sums of money payble by the contractor to Government under the terms of his contract may be deducted from, or paid by the side of a sufficient part of his security deposit, or from the interest arising therefrom, or from any is due or may become due to the contractor under sums which and in the event of his security deposit being reduced by reason of any such deduction or sale as aforesaid the contractor , shall within ten days thereafter, make good in cash or with Government securities endorsed as aforesaid any sum or sums which may have been deducted from, or raised by sale of his security deposit or any part thereof. The security deposit referred to, when said in cash, may, at the cost of the depositor be converted into interest-bearing securities provided that the depositor has pressly desired this in writing.

BISTRICT OFFICER (ROADS YANDO ALLAHYAR

(a) To rescind the contract (of which rescisiou notice in writen to the contractor under the band of the Executive Engideer shall be conclusive evidonce) and in that case the security deposit of the contra7tor shall stand forfeated and be absolutely at the disposal of the Government.

(b) To employ iabour paid by the Public Work Department and to the supply materials to carry out the work, or any part of the work, debiting the contractor with the cost of the lahour and the price of the materials (as to the correctness of which cost and, price the certificate of the Executive Engineer shall be final and conclusive against the contractor) and crediting him with the value of the work done, in all respects in the same manner and at the same rates as if it had been carried out by the contractor under the terms of his centract; and in that case the certificate of the Executive on Engineer, as to the value of the work done shall be final and conclusive against the contractor.

11

(c) To measure up the work of the contractor and to take such part thereof as shall be unexecuted out of the hands, and to give it to another contractor to complete in which case any expenses which may be incurred. in excess of the sum which would have been paid to the original contractor if the whole work had been executed by him (as to the amount of which excess expenses the certificates in writing of the Executive Engineer shall be final and conclusive) shall be borne and paid by the original contractor and shall be deducted from any money due to him by the Government under the contret or otherwise or from him security deposit or the proceeds of sale thereof, or a sufficient part thereof.

In the event of any of the above courses being adopted by the Executive Engineer, the contractor shall have no claim to compensation for any loss sustained by him by reason of his buying purchased or procured any materials, or entered into any engagements, or made any advances on account of, or with a view to the execution of the work or the performance of the contract. And in case the contract shall be rescinded under the provision laforesaid, the contractor shall hot be entitled to recover or to be paid any sum or any work therefore actually performed by him under this contract unless and until the Executive Engineer shall have certified in writing the perform-unce of such work and the amount payable in respect thereof, and he shall only be entirted to be paid the amount to certified

Clause 4, -11 the progress of any particular portion of the work is unsatisfactory Executive Engineer shall, notwithstanding that all the general property of the work is in accordance with the conditions mentioned in clause), be entitled to take action under clause 3 (b) after giving the continual 10 day's notice in writing. The contractor will have no claim for compensation, for any loss sustained by him owing to such action.

Clause 5 .- In any case in which any of the powers conferred upon the Executive Engineer by the clause 3 and 4 thereof shall have become exerciseable and the same shall not have been exercised, the non-exercise thereof shall put constitute a waiver of any of the conditions hereof and such powers shall notwithstanding be exerciseable in the event of any future case of default by the contractor for which under any clause or clauses bereof he is declared liable to pay compensation amounting to the whole of his security deposit and the liability of the contractor for past and future compensation shall remain unaffected. In the event of the Executive Engineer taking action under sub-clause (a) or (c) of clause 3, he may, if he so destres, take possession of all or any tools, plant, materials and stores in or upon the works, or the site thereof or belonging to the contractor, or procured by him and intended to be used for the execution of the work or any part thereof, paying or allowing for the same in account at the contract rates, or in the case of contract not being applicable, at current market rates, to be certified by possession of the Executive Engineer whose certificate thereof shall be final. In the afternative the Executive Engineer may, after giving notice in writing to the contractor or his clerk of the works, foreman or other authorized agent require him to remove such tools, plant, materials, or stores from the presuites villia a time to be specified in such notice, and in the event of the contractor failing to comply with any such requisition, the Executive Engineer may rector them at the contractor's expense or sale them by auction or private self of necount of the contractor and at his risk is all respects, and the contractor of the Executive Engineer as to the expense of any such removal and the annual and the annual of the projects any expense of and such sale shall be fivel stated to the contractor clusive and use the contractor.

Action when the progress of any particular position of the work le unratisfactor

CONT:

Contractor femsine linble compensation action not taken under clauses 3

Power to take require removal of or sell. oc.

against the final payment only and not as payments for work clume done and completed, and shall not preclude the Engineer-in-charge from requiring any had, unsound, imperfect or unskilful work to be removed or taken away and re-constructed, or re-crected nor shall any such payment be considered as an admission of the due performance of the contract or any part thereof in any respect of the accruning of any claim; nor shall it coinclude, determine; or effect in any other way for sowers of the Engineer-in-charge as to the final settlement and adjustment of the accounts of otherwise, or in any way vary or effect the contract. The final Bill shall be submitted by the contractor within one month of the date taxed for the completion of the fork otherwise Engineer-in-charge's certificate of the measurements and of the total amount payable for the works shall be final and binding on all parties.

14

10

773

10

10

C

33

S

Clause 9.—The rates for several items of works estimated to cost more than Rs. 1.000 agreed to within, shall be valid only when the item concerned is accepted as having been completed full in accordance with the sanctioned specifications. In cases where the items of work are not accepted as so completed the Engineer-in-charge may make payment on account of such items at such reduced rates as he may consider reasonable in the preparation of final or on account bills.

Bill to be submitted meethly.

Payment at red-

uced rates on account of item of work not accopied as completed to be at the direction of the Enginee-in-

Chase 10.—A bill shall be submitted by the contractor as frequently as the progress of the work may justify for all work executed and not included in any previous bill and the Engineer-in-charge shall take or cause to be ten the requisite measurements for the purpose of having the same verified and the claim, as for as admisisble, adjusted, if possible before the expiry of ten days from the presentation of the bill, at any time depute a subordinate to measure up the said work in the presence of the contractor or his authorised agent, whose countersignature to the measurement list will be sufficient warrant and the Engineer-in-charge may prepare a bill from such list which shall be binding on the contractor in all respects

Clause 11.—The contractor shall subnut all bills on the printed forms to be had on application at the other of the Engineer- in charge. The charges to be made in the bills shall always be entered at the rates specified in the tender or in the ease of any extra work ordered in pursuance of these conditions, and not mentioned or provided for in the tender at the rates becomister provided for such work.

Bills to be on salrated forms.



Store supplied by Government

Clause 12.—If the specification of estimate of the work provides for the use of any special description of materials to be supplied from the store of the B.W.D or if it is required that the contractor, shall use certain stores to be provided by the Engineer-in-charge (such material and stores, and the prices to be charged therefore as heremafter mentioned being to far as practicable for the convenience of the contractor but not so as in any way to control the meaning or effect of this contract specified in the schedule or, memorandum hereto annexed) the contractor shall be supplied with such materials and stores as may be required from time to time to be used by bim for the purposes of the contract only and the value of the full quantity of the materials and stores so supplied shall be set off or deducted contract, or otherwise, or from the security deposits, or the preceeds of sale thereof, if the security deposits is held in Government securities, the same or a sufficient portion thereof shall in that case be sold for the purpose. All uniterials supplied to the contractor shall remain the absolute property of Government and shall on no account be removed from the site of the work. and shall at all times be open to inspection by the Engineer-in-charge. Any such materials unused and in perfectly good condition at the time of completion or determination of the contract shall be refunded to the P.W.D. store, if the Engineer-in-charge so requires by a motice in writing under his hand, but the commeter shall not be entitled to return any such materials except with the consent of the Engineer-in-charge and he shall have no claim for compensation on account of any such material supplied to him as aforesaid but remaining unused by him or for, any wastage in or damage to any such materials.

Clause 13.—The contractor shall execute the whole and every part of the work in the most substantial and work-man-like manner and both as regards material and all other matters in strict accordance with the specificition lodged in the office of the Executive Engineer and initialled by the parties the said specification being a part of the contract. The contractor shall also the

MAGISSI

Whicks to be cresound in accordance who accordations, comings prices, sice

TANDO ALLANYA

that any materials or articles provided by him for the execution of the work are unsound, or of a quality inferior to that contracted for, or are otherwise not in accordance with the contract, it shall be lawful for the Engineer-incharge to intimate this fact in writing to the contractor and then not with standing the fact that the work, materials or articles complained of may have been inadvertently passed, certified and paid for, the contractor shall be bound forlliwith to rectify or remove and reconstruct the work so specified in whole or in part, as the case may require, or it so required, shall remove the materials or articles so charge and cost; and in the event of his failing to do so within a period to be specified and provide other proper & suitable materials or articles at his own proper by the Engineer-in-charge in the writing intimation aforesaid, the contractor shall be liable to pay compensation at the rate of one percent. On the amount of the estimate for every day not exceeding ten days, during which the failur eso continues, and in the case of any such failure the Engineer-in-charge may rectify or remove, and reexecute the work or remove and replace the materials or articles complained of as the case may be at the risk and expense in all respects of the contractor. Should the Engineer-in-charge consider that any such inferior work or materials as described above may be accepted or made use of; it shall be within his discretion to accept the same at such reduced rates as he may fla therefore.

Clause 18 .- All works under or in course of execution executed in pursuance of the contract shall at all times be open to the inspection and surrivision of the Engineer-in-charge and his subordinates, and the contractor shall at all times during the usual working hours, and at all other times at which reasonable notice of the intention of the Engineer-in-charge or his subordinate to visit the work shall have been given to the contractor, either himself be present to receive orders and instructions, or have a respensible agent duly accredited in writing present for that purpose, Orders given to the contractor's duly authorised agent shall be considered to have the same force an effect as if they had been given to the contractor himself.

on to inspecting

Contractor or responsible agent to be present.

Clause 19.—The contractor shall give not less than five days notice in writing to the Engineer-in-charge or his subordinate-in-charge of the work before covering up or otherwise placing beyond the mash of measurement any work in order that the same may be measured, and correct dimensions thereof taken before the same is so covered up or placed beyond the reach of measurement, and shall not cover up or place beyond the reach of measurement any work without the consent in writing of the Engineer- in -charge or his subordinate-in-charge of the work; and if any work shall be covered up or placed beyond the reach of measurement without such notice having been given to consent obtained, the same shall be uncovered at the contractor's expense, and in default thereof no payment or allowance shall be made for such work, or for the materials with which the same was executed CONT.

Notice to nives before work is covered up.

Clause 20.-If the contractor or his workmen, or servants shall break, deface, injure, or destroy any part of a building in which they may be working, or any building, road, fence, enclosure of grass land of cultivated ground continuous to the premises on which the work or any part thereof is being executed, or if any damage shall be done to the work, while it is in progress from any cause whetever or if any imperfections become apparent in it within three months of the great of a certificate of completion, final or otherwise, by the Engineer-in-charge, the contractor snall make good the same at his own expense, or in default the Engineer-in-charge may cause the same to be made good by other workmen, and deduct the expenses of (which the certificate of the Engineer-in-charge shall be final) from any sums tha contractor. that may then be due or may thereafter become due to or from his security deposits or the proceeds of sale thereof, or of a suffi

Contractor Highto for demage done, and for his demaga perfections for three months after certificate.

Clause 21.—The contractor shall supply at his own cost all material texcept such special material, if any, as may, in accordance with the contract, be supplied from the P.W.D. Stores), plant, tools, appliances, implements, ladders, cordage, tackle, scaffolding and temporary work requisite or proper for the execution of the work, whether in the original, altered or substituted form, and whether included in the specifications, or other docume ents, forming part of the contract of referred to in these conditions or not, and which may be necessary for the purpose of satisfying or complying with the requirements of thy Engineer-in-charge as to any matters as to which

cient portion thereof.

Coultestor to vipply plant, laiders scaffoldings, ctc.

OISTRICT OFF (ROADS) VANDO ALLANYAN,

thereupon stand forfeited and be absolutery at the disposal of Government and the same consequences shall ensure as if the contract had been rescinded under clause 3 thereof and in addition the contractor shall not be entitled to recover or be paid for any work therefore actually performed under the contract.

uitled

utrac.

countime

same

actor actor

cof,

icce-

and

OT OF

ista-

ages

s to paid

ccs.

(35

ary

ing

Cor

20-

111

ed

er

ha

10

)13

28

11:

94

the

Clause 27.-All sums payable by a contractor by way of compensation under any of these conditions shall be considered as a reasonable compensation to be applied to the use of Government without reference to the actual loss or damage sustained, and whether any damage has or has not been sustained.

Sum payable by way of compensa-tion to be consi-dered as reasonable compensation with sctust loss.

in

Clause 28,—In the case of a tender by partners any change in the constitution of a firm shall be forthwith notified by the contractor to 100 NT to be notified Engineer-in-charge for his information.

Works to be under direction Superintending

Changes in

Engineer

Clause 29.—All works to be executed under the contract shall be executed under the direction and subject to the approval in all respects of the Superintending Engineer of the circle for the time being, who shall be entitled to direct at what point or points and in what manner they are to be commenced and from time to time carried on.

> Decision of Supdig: Engince to be final,

Clause 30.—Except where otherwise specified in the contract and subject to the powers delegated to him by Government under the Code rules then in serce, the decision of the Superintending Engineer of the circle for the time being shall be final, conclusive and binding on all parties to the contract upon all questions relating to the meaning of the specifications, designs drawings, and instructions hereinbefore mentioned and as to the quality of workmanship, or materials used on the work or as to any other question, claim, right, matter, or thing whatsoever in any way arising out of, or relating to the contract design, drawings, specifications, estimates, instructions, orders or these conditions or otherwise concerning the works, or the execution, or CONT. failure to execute the same, whether arising, during the progress of the work. or after the completion or abandonment thereof.

Clause 31,-The contractor shall obtain from the P.W.D. stores all stores and articles of European or American manufacture which may be required for the work, or any part thereof or in making up any articles required therefor or in connection therewith, unless he has obtained permission in writing from the Engineer-in-charge to obtain such stores and articles elsewhere. The value of such stores and articles as may be supplied to the contractor by the Engineer-in-charge will be debited the contractor in his account at the rates shown in the schedule in form "A" attached to the contract, and if they are not entered in the said schedule, they shall be debited to him at cost price which for the purpose of the contract shall include the cost of carriage and all other expenses whatsoever, which shall have been incurred in obtaining delivery of the same at the stores aforesaid.

Stores of Europ-can by American manufecture to be obtained from Government.

Clause 32.—When the estimate on which a tender is made includes lump none in respect of part of the work, the contractor shall be entitled to payment in respect of the items of work involved or the part or the work in question at the same rates as are payable under this contract for such items. or if the part of the work in question is not in the opinion of the Engineerin-charge capable of measurement, the Engineer-in-charge may at his discretion pay the lump sum amount entered in the estimate, and the certificate in writing of the Engineer-in-charge shall be final and conclusive against the contractor with regard to any sum payable to him under the provisions of this clause.

Lomp same h loy cuestantita ryrient keys or enimals.

Clause 33.—In the case of any class of work for which there is no such speci-Action where no fication as is mentioned in Rule I such work shall be carried out in accordance with the Divisional specification, and in the event of there being no Divisional specification, then in such case the work shall be carried out in all respects in accordance with the instructions and requirements of the Engineer-in-charge,

OISTRICT OFFICER (ROADS TANDO ALLABYAR.

CUNTRACTOR

Clause 45.— If any materials, such as stones metal, bajti, sand etc. are required to be conveyed by and, the contractors will be granted certificates by the Engineer-in-charge of the work to the effect that the materials are required for Government or semi Government works thereby enabling them to have the benefit of concessionary freight charges from the ratiway. In case, however, such a concession is withdrawn by the railway at any time during the currency of the contract, no claim shall be preferable against Government on this account.

clause 46.—When tendered rates are the same preference will be given at the discretion of the accepting authority to those who tender for the carting of materials by vehicles having penumatic tyres.

Clause 47.—Any sum due to the Government by the contractor shall be liable for recovery as arrears of Laud Revenue.

Clause 48—Certified that no member of Legislative Assembly is in partnership with me and that Government will have the right to terminate the contract at any stage if it is discovered that a member of Legislative Assembly is a pattner to the contract

Clause 49—1/We hold myself/ourselves responsible to pay the Sales Tax as livied in accordance with Pakistan General Sales Tax Act, 1948, or any other law for the time being in force.

Cic. 50.—Certified that no Government servant has directly or indirectly a share or interest in the work.

Clause -51.—The contractor will not be allowed to withdraw his and ask for the return of ernest money before expiry of the period shown as under, commencing from the date of opening of the tender and that if it is withdrawn in violation of this condition earnest money shall be forfieted.

When the sanctioning authority for the tender is:-

Executive Engineer One month.

Superintending Engineer Two months.

Chief Engineer Three months.

Government Six months.

- Clause 52."If any question, difference or objection whatsoever shall arise in any way contracted with or arising out of this instrument or the meaning or objection of any part thereof, the rights, duties or liabilities of either party, Len save in so far as the decision of any such matter is here in before provided for as has been so decided, every such matter including whether its decision has been otherwise provided for any or regards the right of and obligations of the parties as the result of such termination shall be referred for arbitration to such person as may be appointed in this behalf by Chief Engineer, (Irrigation), Department and his decision shall be final and binding and where the matter involves a claim for or the payment recovery or deduction of money, only the amount, if any awarded in such arbitration shall be recoverable in respect of the matters so referred;"

Certified that the Tender has been executed under my personal supervision and I am satisfied that it has been correctly prepared in accordance with the orders issued vide Government P. W. D. circular Memo No. 1015 W with the orders issued vide Government P. W. D. circular Memo No. 1015 W with the orders issued vide Government P. W. D. circular Memo No. 1015 W with the orders issued in this connection. dated 14th September, 1937, and subsequent orders pissued in Accounts Office.

Divisional free Gibrass Proposed all the orders of the order of the

Certified that I have noted the content of Government P. W. D. Circular Memorandum No. 1006-1 dated 21st February, 1950, wherein the responsibility of getting the tender checked efficiently is placed on me.

Controller

Clod

per-

d to

acd.

Lice

foes

tion

ised

ipal

MOI.

ion

no

01

her

110

11

63

ites

20

t-

d.

of

10

de

m

10

d

S

n ic iy

0.0

OF.

CUNTRACTOR

Executive Engineer,

PRINCI OF SE ROADS

Certificate for concessionary from the Railway.

O.A.

Procedure of acceptance of tenders when tendered rates are same.

Recovery of dust from contractor as errease of Land Revenue,

Partnership of M L A'S for bidden.

Payment of Sale

Interest or share. Government terrant in the work

SCHEDULE .B.

Memorandum Showing Items of Work To be Carried out

| | Ouantities - | | Tenders | Tenders rates | | · Total |
|--|--|--|------------|--|--|--|
| Hein No. | Quantities estimated but may be more or less | Item of week | In figures | In words | Unit | amount according to estimated quantities |
| | more or less | | Rs. Ps. | Shoot of the state | | quantities |
| NAS-10-YANG TERMINANG | | | Short Land | | | |
| Section of the sectio | | And the second of the second o | | | Ave de La Company de la Company de la Company de Compan | |
| | | The state of the s | | | And desired and de | |

Note 1-All work shall be carried out as per Public works Departments Head-book can other specifications of the Division or as directed.

Note 2—All the columns in the Schedule should be filled in, in ink and the total of the entries in the last column should be struck by the contracter under his signature. Note 3—Rates quoted include clearance of site (prior to commencement of Work and at its close) in all respects and hold good work under all conditions. Site moisture. Weather, etc.

Contractor).

ICT OFFICER (ROADS Signature of-Assistant Engineer