

NIT Sr. No. SPPRA Serial No.35557

Method and procedure of procurement: Open Competitive Bidding (National/ International Competitive Bidding) (Single Stage-One Envelope)


Description of work: REPLACEMENT OF 15" DIA SUNK DOWN SEWER PIPE LINE AT FRONT OF BIRYANI SHOP TO SHAHI MASJID FOR IMPROVEMENT OF SEWERAGE SYSTEM AT METROVILLE UC-04 SITE TOWN

Date of Opening: 08-01-2018


BIDDERS' ELIGIBILITY/ QUALIFICATION REPORT

Eligibility/ Qualification Criteria:


S. No.	Eligibility / Qualification Criteria	Bidders' Name	
		M/s.Barang Construction Co.	M/s.Gul Sawab & Co.
1.	Registration with PEC (if applicable)	N/A	N/A
2.	NTN	Yes ✓	Yes ✓
3.	Sales Tax Registration (FBR)	N/A	N/A
4.	Registration with Sindh Revenue Board (SRB)	✓ Yes	✓ Yes
Qualification Criteria:			
5.	Minimum three years' experience of relevant field.	Yes	Yes ✓
6.	Turnover of at least last three years	Yes ✓	Yes
7.	Required Bid Security is attached.	Yes ✓	Yes ✓
8.	Bid is signed, named and stamped by the authorized person of the firm along with Authorization letter.	Yes	Yes
9.	Any other factor deemed to be relevant by the procuring agency subject to provision of Rule-44	N/A	N/A
10.	Qualified/ disqualified	Qualified ✓	✓ Qualified


(Arshad Ali)
D.A.O (District West)
Member / Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit - KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Owais Malik)
S.E (District West-A)
Member


(Saifuddin)
Director (Design & Estimate)
Convener

NIT Sr. No. SPPRA Serial No.35557

Method of Procurement: Single Stage Single Envelope.

Name of Work: REPLACEMENT OF 15" DIA SUNK DOWN SEWER PIPE LINE AT FRONT OF BIRYANI SHOP TO SHAHI MASJID FOR IMPROVEMENT OF SEWERAGE SYSTEM AT METROVILLE UC-04 SITE TOWN

MINUTES OF BID OPENING MEETING.

A meeting of the procurement committee of this department was held on 08-01-2018 for opening the bids received in respect of subject NIT till deadlines of submission. The meeting was attended by all / following members of the procurement committee and the representative of bidders.


(Attendance sheet is enclosed).

2. Two bidders submitted their bids till the deadline of submission.
 - i. M/s. Barang Construction Co.
 - ii. M/s. Gul Sawab & Co.
3. The bids were opened at 2:30 P.M in the presence of the above mentioned participants and the rates quoted by bidders were read aloud and encircled by Chairman of the Procurement Committee.


S. No	Name of Firm	Quoted Price	Amount of Bid Security	Pay Order No. / Date
01	M/s.Barang Construction Co.	Rs.4,65,580/-	Rs.10,000/-	P.O# 19636506 dt:05-01-2018 Rs.9,000/- & P.O # 19636512 dt:08-01-2018 Rs.1,000/- from HBL Metroville I Site Branch Karachi
02	M/s.Gul Sawab & Co.	Rs.6,54,320/-	Rs.10,000/-	Less amount P.O Attached. P.O # 19636505 dt:05-01-2018 Rs.9,000/- & P.O # 19636513 dt:08-01-2018 Rs.1,000/- from HBL Metroville I Site Branch Karachi

4. The bids do not contain any cutting or over-writing.
5. The committee shall examine all the bids as per the qualification / eligibility criteria provided in the bidding document and verify the documents and bid security submitted by the bidders (if required).


The meeting ended with the vote of thanks to and from the chair.


(Arshad Ali)
D.A.O (District West)
Member Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit – KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Owais Malik)
S.E (District West-A)
Member


(Saifuddin) 8.1.18
Director (Design & Estimate)
Convener



KARACHI WATER & SEWERAGE BOARD

OFFICE OF THE DIRECTOR (DESIGN & ESTIMATE)

BID EVALUATION REPORT

1	Name of Procuring Agency:	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No:	SPPRA Serial No.35557 I.D No.
3	Tender Description/Name of Work/Item:	REPLACEMENT OF 15" DIA SUNK DOWN SEWER PIPE LINE AT FRONT OF BIRYANI SHOP TO SHAHI MASJID FOR IMPROVEMENT OF SEWERAGE SYSTEM AT METROVILLE UC-04 SITE TOWN
4	Method of Procurement:	Single Stage (One Envelop)
5	Tender Published:	Through SPPRA Web Site
6	Total Bid Documents Sold:	2 Nos
7	Total Bid Received:	2 Nos
8	Technical Bid Opening Date (if applicable):	N/A
9	No. of Bid Technically Qualified (if applicable)	N/A
10	Bid (s) Rejected:	NIL
11	Financial Bid Opening Date:	08-01-2018

12 BID EVALUATION REPORT


S#	Name of Firm / Bidder	COST OFFERED BY THE BIDDER	RANKING IN TERMS OF COST	COMPARISON WITH ESTIMATED COST	REASON FOR ACCEPTANCE / REJECTION	REMARKS
1	M/s.Barang Construction Co.	Rs.4,65,544/-	1 st Lowest	@0.175% Below	Pay Order and required documents are attached. P.O# 19636506 dt:05-01-2018 Rs.9,000/- & P.O # 19636512 dt:08-01-2018 Rs.1,000/- from HBL Metroville 1 Site Branch Karachi Total Rs.10,000/-	Substantially Responsive
2	M/s.Gul Sawab & Co.	Rs.4,67,868/-	2 nd Lowest	@0.324% Above	Pay Order and required documents are attached. P.O # 19636505 dt:05-01-2018 Rs.9,000/- & P.O # 19636513 dt:08-01-2018 Rs.1,000/- from HBL Metroville 1 Site Branch Karachi Total Rs.10,000/-	Substantially Responsive

The all concerned bidders are being informed accordingly.


The E.E Concerned for compliance of Rule-45 of SPPRA 2010 **M/s.Barang Construction Co.** declared as the lowest responsive bidder by the Committee and recommended for sanction from Competent Authority.


Arshad Ali
D.A.O (District West)
Member / Secretary


(Saif-ul-Maque)
Additional Director Internal
Audit – KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Owais Maq)
S.E (District West-A)
Member


(Saifuddin) 9.1.18
Director (Design & Estimate)
Convener

COMPARATIVE STATEMENT

Name of Work: REPLACEMENT OF 15" DIA SUNK DOWN SEWER PIPE LINE AT FRONT OF BIRYANI SHOP TO SHAHI MASJID FOR IMPROVEMENT OF SEWERAGE SYSTEM AT METROVILLE UC-04 SITE TOWN

Item No	Description of Work	Estimated Cost				M/s.Barang Construction Co.		M/s.Gul Sawab & Co.		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
1	Dismantling and removal of road metalling	1710.00	Cft	605.00	%Cft	10,345.50	605.00	10,345.50	605.00	10,345.50
2	Excavation for pipe line in trenches and pits in all kind of soil of murum i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by Engineer Incharge providing fence guards, lights, flags sand temporary crossing for non-vehicular traffic wherever required lift upto 5 ft (1.52 m) and lead upto one chain (30.5m). 0' - 5' Depth	8550.00	Cft	4650.00	%0Cft	39,757.50	4650.00	39,757.50	4650.00	39,757.50
	5' - 8' Depth	3990.00	Cft	5200.00	%0Cft	20,748.00	5200.00	20,748.00	5200.00	20,748.00
3	Providing, & Laying of RCC Pipes with Rubber Ring Joint and fitting in trench including cutting, fitting, jointing with rubber ring i/c testing with water to specified pressure. 15" Dia	380.00	Rft	436.00	P/Rft	165,680.00	434.00	164,920.00	440.00	167,200.00
4	Providing manhole 4' feet inside with C.I Frame 15 Kg and 5 feet clear depth cast in situ with 1:2:4 CC in 9" thick wall, 1:4:8: C.C in 6ft dia and 6" inch thick in foundation 1:2:4 C.C in benching 12" thick cement plastering with 1:3 C.M on all inside wall surfaces, channel and benching i/c making required nos of main and branch channels, 3/4" dia m.s foot rest @12" c/c i/c cost of excavation in all kinds of soil, backfilling and disposal of excavated stuff etc complete as per design and instruction of Engineer Incharge.	8.00	Nos	14529.29	Each	116,234.32	14528.00	116,224.00	14530.00	116,240.00
5	Add/Deduct per ft depth	24.00	(+)Ft	2538.62	P/ft	60,926.88	2537.00	60,888.00	2537.00	60,888.00

Amir
09/01/18

T


hb-

CP


Amir


**Name of Work: REPLACEMENT OF 15" DIA SUNK DOWN SEWER PIPE LINE AT FRONT OF BIRYANI SHOP
TO SHAHI MASJID FOR IMPROVEMENT OF SEWERAGE SYSTEM AT METROVILLE UC-04 SITE TOWN**


Item No	Description of Work	Estimated Cost				M/s.Barang Construction Co.		M/s.Gul Sawab & Co.		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
6	Making connection with the existing manhole including the cost of cutting hole in wall, making them good in C.C 1:2:4 and making the required channel etc. complete	20.00	Nos	180.00	Each	3,600.00	180.00	3,600.00	181.00	3,620.00
7	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete.	11868.40	Cft	2760.00	%0Cft	32,756.78	2760.00	32,756.78	2760.00	32,756.78
8	Full hire charges of pumping set per day i/c of wages of driver and assistant fuel or electric energy platform for placing the pump etc at lower depth with suction and delivery pipes for pumping out water found at various depth from trenches including the cost of erection and dismantling after completion of the job. Hire charges of pumping set upto 10 HP pumping out water from 10 ft deep trench	6.00	Days	1500.00	P/Day	9,000.00	1500.00	9,000.00	1500.00	9,000.00
9	Manufacturing and supplying of 21" dia RCC Manhole covers cast in situ 1:2:4 concrete ratio 3" deep at centre, reinforced with 1/2" dia tor steel bars at 4" C/C welded to a 3/16" thick 2" wide M.S plate two hook of 3/8" dia tor bar including compacting i/c cutting and transportation with in 10 miles. 21" dia cover.	8.00	Nos	913.63	Each	7,309.04	913.00	7,304.00	914.00	7,312.00
TOTAL QUOTED / CORRECTED COST						466,358		465,544		467,868


Arshad Ali
D.A.O (District West)
Member / Secretary


(Saif-ul-Haque)
Addl. Director Internal
Audit KMC - Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (K.M.C)
Member


(Owais Malik)
S.E (District West-A)
Member


SAIFUDDIN
(Saifuddin)
Director (Design & Estimate)
Convener

ATTENDANCE OF PARTICIPATE CONTRACTOR

Name of Work: - REPLACEMENT OF 15" DIA SUNK DOWN SEWER PIPE LINE AT FRONT OF BIRYANI SHOP TO SHAHI MASJID FOR IMPROVEMENT OF SEWERAGE SYSTEM AT METROVILLE UC-04 SITE TOWN

Date of Opening & Time : 08/01/2018 2:00 P.M

Estimated Cost : 466,358/-

S.NO	NAME OF FIRM	NAME OF PERSON & DESIGNATION	SIGNATURE
1	M/s. Barang Construction Co	محمد اسحاق خان	محمد اسحاق خان
2	M/s. C/o Sawab & Co	محمد اسحاق خان	محمد اسحاق خان
3	M/s.		
4			
5			
6			
7			
8			
9			
10			