



KARACHI WATER & SEWERAGE BOARD

OFFICE OF THE DIRECTOR (DESIGN & ESTIMATE)

BID EVALUATION REPORT

1	Name of Procuring Agency:	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No:	SPPRA Serial No.35702 I.D No. _____
3	Tender Description/Name of Work/Item:	REPLACEMENT OF 12" DIA, 10" DIA, 8" DIA, 6" DIA AND 4" DIA A.C PIPE LINE BY 315 MM, 250 MM, 200 MM, 160 MM AND 110 MM P.E PIPE LINE INCLUDING REPAIR OF 18" DIA, 15" DIA AND 12" DIA HEAVY WATER LEAKAGES IN UC NO.02, 06 AND UC NO.05, MANZOOR COLONY, REHMAN COLONY AND MEHMOODABAD NO.06, FOR IMPROVEMENT OF WATER SUPPLY IN JAMSHED TOWN
4	Method of Procurement:	Single Stage (One Envelop)
5	Tender Published:	Through SPPRA Web Site
6	Total Bid Documents Sold:	3 Nos
7	Total Bid Received:	3 Nos
8	Technical Bid Opening Date (if applicable):	N/A
9	No. of Bid Technically Qualified (if applicable)	N/A
10	Bid (s) Rejected:	01 No
11	Financial Bid Opening Date:	03-01-2018

12 BID EVALUATION REPORT

S#	Name of Firm / Bidder	COST OFFERED BY THE BIDDER	RANKING IN TERMS OF COST	COMPARISON WITH ESTIMATED COST	REASON FOR ACCEPTANCE / REJECTION	REMARKS
1	M/s.Nawab & Co.	Rs.9,83,843/-	1 st Lowest	@0.017% Below	Pay Order and required documents are attached. P.O # AAA 13294606 dt:26-12-2017 Rs.20,000/-from ABL Paposh Nagar Branch Karachi	Substantially Responsive
2	M/s.A.Dawood Shah & Co.	Rs.9,84,429/-	2 nd Lowest	@0.043% Above	Pay Order and required documents are attached. P.O # AAA 13294605 dt:26-12-2017 Rs.20,000/-from ABL Paposh Nagar Branch Karachi	Substantially Responsive
3	M/s. Ali Mohammad & Sons	Rs.9,87,164/-	-	@0.321% Above	Pay Order not attached, required documents are attached.	Un Responsive

The all concerned bidders are being informed accordingly.

The E.E Concerned for compliance of Rule-45 of SPPRA 2010 M/s.Nawab & Co. declared as the lowest responsive bidder by the Committee and recommended for sanction from Competent Authority.

(Muhammad Nawaz Khan)
D.A.O (District East)
Member / Secretary

(Saif-ul-Haque)
Additional Director Internal
Audit – KMC Member

(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member

(Roshin Din Memon)
S.E (District East-A)
Member

(Saifuddin)
Director (Design & Estimate)
Convener

4.1.18

Method of Procurement: Single Stage Single Envelope.

Name of Work: REPLACEMENT OF 12" DIA, 10" DIA, 8" DIA, 6" DIA AND 4" DIA A.C PIPE LINE BY 315 MM, 250 MM, 200 MM, 160 MM AND 110 MM P.E PIPE LINE INCLUDING REPAIR OF 18" DIA, 15" DIA AND 12" DIA HEAVY WATER LEAKAGES IN UC NO.02, 06 AND UC NO.05, MANZOOR COLONY, REHMAN COLONY AND MEHMOODABAD NO.06, FOR IMPROVEMENT OF WATER SUPPLY IN JAMSHED TOWN

MINUTES OF BID OPENING MEETING.

A meeting of the procurement committee of this department was held on 03-01-2018 for opening the bids received in respect of subject NIT till deadlines of submission. The meeting was attended by all / following members of the procurement committee and the representative of bidders. (Attendance sheet is enclosed).

2. Three bidders submitted their bids till the deadline of submission.

- i. M/s. Ali Mohammad & Sons
- ii. M/s. A. Dawood Shah & Co.
- iii. M/s. Nawab & Co.


3. The bids were opened at 2:30 P.M in the presence of the above mentioned participants and the rates quoted by bidders were read aloud and encircled by Chairman of the Procurement Committee.

S. No	Name of Firm	Quoted Price	Amount of Bid Security	Pay Order No. / Date
01	M/s.Nawab & Co.	Rs.9,83,843/-	Rs.20,000/-	P.O # AAA 13294606 dt:26-12-2017 from ABL Paposh Nagar Branch Karachi
02	M/s.A.Dawood Shah & Co.	Rs.9,84,429/-	Rs.20,000/-	P.O # AAA 13294605 dt:26-12-2017 from ABL Paposh Nagar Branch Karachi
03	M/s. Ali Mohammad & Sons	Rs.9,87,164/-	-	Pay order not attached


4. The bids do not contain any cutting or over-writing.


5. The committee shall examine all the bids as per the qualification / eligibility criteria provided in the bidding document and verify the documents and bid security submitted by the bidders (if required).


The meeting ended with the vote of thanks to and from the chair.


(Muhammad Nawaz Khan)
D.A.O (District East)
Member / Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit – KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Roshin Din Memon)
S.E (District East-A)
Member


(Saifuddin)
Director (Design & Estimate)
Convener

Method and procedure of procurement: Open Competitive Bidding (National/ International Competitive Bidding) (Single Stage–One Envelope)


Description of work: **REPLACEMENT OF 12" DIA, 10" DIA, 8" DIA, 6" DIA AND 4" DIA A.C PIPE LINE BY 315 MM, 250 MM, 200 MM, 160 MM AND 110 MM P.E PIPE LINE INCLUDING REPAIR OF 18" DIA, 15" DIA AND 12" DIA HEAVY WATER LEAKAGES IN UC NO.02, 06 AND UC NO.05, MANZOOR COLONY, REHMAN COLONY AND MEHMOODABAD NO.06, FOR IMPROVEMENT OF WATER SUPPLY IN JAMSHED TOWN**


Date of Opening: 03-01-2018


BIDDERS' ELIGIBILITY/ QUALIFICATION REPORT


Eligibility/ Qualification Criteria:

S. No.	Eligibility / Qualification Criteria	Bidders' Name		
		M/s.Nawab & Co.	M/s.A. Dawood Shah & Co.	M/s.Ali Mohammad & Sons
1.	Registration with PEC (if applicable)	N/A	N/A	N/A
2.	NTN	Yes	Yes	Yes
3.	Sales Tax Registration (FBR)	N/A	N/A	N/A
4.	Registration with Sindh Revenue Board (SRB)	Yes	Yes	Yes
	Qualification Criteria:			
5.	Minimum three years' experience of relevant field.	Yes	Yes	Yes
6.	Turnover of at least last three years	Yes	Yes	Yes
7.	Required Bid Security is attached.	Yes	Yes	No
8.	Bid is signed, named and stamped by the authorized person of the firm along with Authorization letter.	Yes	Yes	Yes
9.	Any other factor deemed to be relevant by the procuring agency subject to provision of Rule-44	N/A	N/A	N/A
10.	Qualified/ disqualified	Qualified	Qualified	Disqualified


(Muhammad Nawaz Khan)
D.A.O (District East)
Member / Secretary


(Saif-ul-Haqq)
Additional Director Internal
Audit – KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Roshin Din Memon)
S.E (District East-A)
Member


(Saifuddin)
Director (Design & Estimate)
Convener

COMPARATIVE STATEMENT

Name of Work: REPLACEMENT OF 12" DIA, 10" DIA, 8" DIA, 6" DIA AND 4" DIA A.C PIPE LINE BY 315 MM, 250 MM, 200 MM, 160 MM AND 110 MM P.E PIPE LINE INCLUDING REPAIR OF 18" DIA, 15" DIA AND 12" DIA HEAVY WATER LEAKAGES IN UC NO.02, 06 AND UC NO.05, MANZOOR COLONY, REHMAN COLONY AND MEHMOODABAD NO.06, FOR IMPROVEMENT OF WATER SUPPLY IN JAMSHED TOWN

Item No	Description of Work	Estimated Cost				M/s.Nawab & Co.		M/s.A.Dawood Shah & Co.		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
1	Dismantling and removal road metalling	2190.00	Cft	605.00	%Cft	13,249.50	590.00	12,921.00	600.00	13,140.00
2	Excavation for pipe line in trenches and pits in all kind of soil of murum i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by Engineer Incharge. Providing fence, lights, flags and temporary crossing for non-vehicular traffic wherever required lift upto 5'-0' ft (1.52m) and lead upto one chain (30.5m).	3285.00	Cft	4650.00	%0Cft	15,275.25	5000.00	16,425.00	4000.00	13,140.00
3	Excavation for pipe line in trenches and pits in Wet Soils clay or mud i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by Engineer Incharge. Providing fence, lights, flags and temporary crossing for non-vehicular traffic wherever required lift upto 5'-0' ft (1.52m) and lead upto one chain (30.5m).	3231.56	Cft	5400.00	%0Cft	17,450.42	5000.00	16,157.80	6000.00	19,389.36
4	Providing Laying & Fixing of Polyethylene pipe in trench i/c fitting jointing and testing etc. complete in all respect the high density Polyethylene P.E pipes (HDPE-100) for W/S conforming ISO 4427/DIN-8074/8075 B.S 3580 & PSI 3051 (PN-10). 315 MM	40.00	Rft	1998.00	P/Rft	79,920.00	2000.00	80,000.00	3000.00	120,000.00
	250 MM	80.00	Rft	1267.00	P/Rft	101,360.00	1200.00	96,000.00	1000.00	80,000.00
	200 MM	80.00	Rft	833.00	P/Rft	66,640.00	840.00	67,200.00	800.00	64,000.00
	160 MM	100.00	Rft	530.00	P/Rft	53,000.00	500.00	50,000.00	600.00	60,000.00
	110 MM	80.00	Rft	268.00	P/Rft	21,440.00	300.00	24,000.00	400.00	32,000.00


m/w

Wb


Key


Name of Work: REPLACEMENT OF 12" DIA, 10" DIA, 8" DIA, 6" DIA AND 4" DIA A.C PIPE LINE BY 315 MM, 250 MM, 200 MM, 160 MM AND 110 MM P.E PIPE LINE INCLUDING REPAIR OF 18" DIA, 15" DIA AND 12" DIA HEAVY WATER LEAKAGES IN UC NO.02, 06 AND UC NO.05, MANZOOR COLONY, REHMAN COLONY AND MEHMOODABAD NO.06, FOR IMPROVEMENT OF WATER SUPPLY IN JAMSHED TOWN


Item No	Description of Work	Estimated Cost				M/s.Nawab & Co.		M/s.A.Dawood Shah & Co.		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
5	Full hire charges of pumping set p/day inclusive wages of driver & assistant fuel or electric energy plate forms required for placing pumps etc at lower depth with suction and delivery pipes for pumping out water found at various depth from trenches i/c cost of erection and dismantling after completion of the job. i) Hire charges of pumping set of upto 10 H.P pumping out water from 10ft deep trench).	48.00	Days	1500.00	P/Day	72,000.00	1500.00	72,000.00	2000.00	96,000.00
6	P/F Split Collar 9" wide on A.C Pipe fabricated with 1/4" thick M.S plate weighting as metioned against each item it included the cost of 4 Nos 1/4" thick flanged nut & bolt rubber packing labur and sealing material etc complete. Net Weight = 12.31 Kg 8" dia	10.00	Nos	2510.00	Each	25,100.00	2000.00	20,000.00	3000.00	30,000.00
	Net Weight = 10.49 Kg 6" dia	10.00	Nos	2129.00	Each	21,290.00	2000.00	20,000.00	1300.00	13,000.00
	Net Weight = 8.68 Kg 4" dia	16.00	Nos	1835.00	Each	29,360.00	2000.00	32,000.00	3000.00	48,000.00
7	High Density Polyethylene fitting (P.E-100) per each equivalent make. 160 MM X 110 MM	6.00	Nos	3754.00	Each	22,524.00	4000.00	24,000.00	3000.00	18,000.00
	250 MM X 110 MM	6.00	Nos	9297.00	Each	55,782.00	9000.00	54,000.00	8000.00	48,000.00
8	Refilling the excavated stuff in trench 6" thick layer i/c watering ramming to full compaction etc.	6379.77	Cft	2760.00	%Cft	17,608.17	3000.00	19,139.31	2000.00	12,759.54
9	Repair of leaking joints (External vatta) on PRCC pipe i/c excavation, labour, sealing material, gunny bags, de-watering andrefillingthe excavated stuff etc complete. 18" dia	10.00	No	13841.00	Each	138,410.00	14000.00	140,000.00	10000.00	100,000.00
	15" Dia	10.00	No	10729.00	Each	107,290.00	11000.00	110,000.00	10000.00	100,000.00
	12" Dia	13.00	No	9716.00	Each	126,308.00	10000.00	130,000.00	9000.00	117,000.00
TOTAL QUOTED / CORRECTED COST						984,007		983,843		984,429


(Muhammad Nawaz Khan)
D.A.O (Distt. East)
Member / Secretary


(Saif-ul-Haque)
Addl. Director Internal
Audit KMC - Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (K.M.C)
Member


(Roshin Din Memon)
S.E (Dist. East-A)
Member


(Saifuddin)
Director (Design & Estimate)
Convener

