



KARACHI WATER & SEWERAGE BOARD

OFFICE OF THE CHIEF ENGINEER (IP&D)

BID EVALUATION REPORT

1	Name of Procuring Agency :	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No:	KWSB/DPR/2013/73 published in daily "The News" daily "Kawish" Hyderabad dated: 08-06-2013 daily Nawa-e-Waqt" dt:09-06-2013. SPPRA Serial No.16661 I.D No. /2013
3	Tender Description/Name of Work/Item:	REPLACEMENT OF DAMAGED PUMPING MAIN 15" DIA M.S PRCC PIPE WITH M.S 15" DIA LINE AND STRENGTHENING OF 8" DIA CONNECTION FROM 48" DIA W/LINE AT COAST GUARD P/S STATION KORANGI TOWN.
4	Method of Procurement:	Single Stage (One Envelop)
5	Tender Published:	Through Press / Web Site
6	Total Bid Documents Sold:	3 Nos ✓
7	Total Bid Received:	3 Nos ✓
8	Technical Bid Opening Date (if applicable):	N/A
9	No. of Bid Technically Qualified (if applicable)	N/A
10	Bid (s) Rejected:	NIL
11	Financial Bid Opening Date:	25-06-2013

12 BID EVALUATION REPORT

S #	Name of Firm / Bidder	COST OFFERED BY THE BIDDER	RANKING IN TERMS OF COST	COMPARISON WITH ESTIMATED COST	REASON FOR ACCEPTANCE/ REJECTION	REMARKS
1	M/s.Zahir Enterprises ✓	Rs.14,62,568/-	1 st Lowest	@0.010%Below	Substantially Responsive	P.O # 8955800 HBL Hassan Square, Gulshan-e-Iqbal Branch Karachi Rs.29,320/- Recommended for Sanction
2	M/s.Kashif Engg. Works ✓	Rs.14,73,043/-	2 nd Lowest	@0.706%Above	Substantially Responsive	P.O # POGIK 0041496 Bank Alfalah Ltd Block-13, Gulshan-e-Iqbal Branch Karachi Rs.30,000/-
3	M/s.Saqib Moin Enterprises ✓	Rs.14,97,686	3 rd Lowest	@2.391%Above	Substantially Responsive	P.O # POGIK 0041499 Bank Alfalah Ltd Block-13, Gulshan-e-Iqbal Branch Karachi Rs.30,000/-

The all concerned bidders are being informed accordingly.


M/s. Zahir Enterprises declared as the lowest responsive bidder by the Committee and recommended for sanction from Competent Authority.



(Nadeem Ahmed Khan)
Accounts Officer (Landhi / Korangi)
Member / Secretary



(Saif-ul-Haque)
Additional Director Internal
Audit – KMC Member



(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member



(Jamil Akhtar)
Chief Engineer (Landhi / Korangi)
Member



(Abdul Rahim Khattai)
Chief Engineer (IPD)
Convener

10/2/13

COMPARATIVE STATEMENT

Name of Work: **REPLACEMENT OF DAMAGED PUMPING MAIN 15" DIA M.S PRC PIPE WITH M.S 15" DIA LINE AND STRENGTHENING OF 8" DIA CONNECTION FROM 48" DIA W/LINE AT COAST GUARD P/S STATION KORANGI TOWN**

Item No	Description of Work	Estimated Cost				M/s.Zahir Enterprises		M/s.Kashif Engg. Works		M/s.Saqib Moin Enterprises		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	Rate	Amount	
1	Excavation for pipe line in trenches and pits in wet silt clay or mud i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by Engineer Incharge providing fence guards, lights, flags sand temporary crossing for non-vehicular traffic wher ever required lift upto 5 ft (1.52 m) and lead upto one chain (30.5m) 0'-5"											
		5' to 8'										
2	Providing Laying & Fixing in trench i/c fitting, jointing and testing etc complete in all respect the high density Polyethylene P.E pipes (HDPE-100) for W/S Conforming ISO 4427 Din 8074 / 8075 BS-3580 & PSI 3051 (PN-10) 225 mm	9,726.41 4,711.69	Ch Ch	%0Ch %0Ch	5400.00 5950.00	52,522.61 28,034.56	5400.00 5950.00	52,522.61 28,034.56	5500 6000	53,495.26 28,270.14	5600 6100	54,467.90 28,741.31
3	Manufacturing supplying & fixing black steel M.S pipe made out of M.S sheet conforming API 51 grade X-42 ERW & externally asphalt coated with fiber glass 5 mm thick & internally c/c lining 8 mm thick (AWWA Specification) i/c laying jointing with helical welding in trenches i/c cost of bends of any degree & testing with water specified pressure for different dia of pipes as below (straight) 16" dia (6.4 mm thick).	200	Rft	P/Rft	1044.00	208,800.00	1044.00	208,800.00	1050	210,000.00	1100	220,000.00
4	Providing and Fixing M.S Split Collar tee on PRC pipe of different sizes having width as mentioned against each item with 3/8" thick M.S plate excluding the cost of the neck, it includes the cost of 3/4" thick M.S square bars on both ends 4 Nos 3/4" thick M.S flange with a total weight as mentioned. Net Weight 48" x 48" width 2'-6" (328.14 Kg.) Net Weight 12" x 12" width 2'-6" (128.17 Kg.)	60	Rft	P/Rft	3742.24	224,534.40	3742.00	224,520.00	3800	228,000.00	3900	234,000.00
		1.00 1.00	No No	Each Each	57716.00 22622.00	57,716.00 22,622.00	57716.00 22622.00	57,716.00 22,622.00	57800 22700	57,800.00 22,700.00	57900 22850	57,900.00 22,850.00

Name of Work: **REPLACEMENT OF DAMAGED PUMPING MAIN 15" DIA M.S PRCC PIPE WITH M.S 15" DIA LINE AND STRENGTHENING OF 8" DIA CONNECTION FROM 48" DIA W/LINE AT COAST GUARD P/S STATION KORANGI TOWN**

Item No	Description of Work	Estimated Cost			M/s.Zahir Enterprises			M/s.Kashif Engg. Works			M/s.Sagib Moin Enterprises		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	Rate	Amount		
10	Construction of C.C. Block masonry chamber size as required dimension with 24" x 24" C.I cover & frame Weight 65 KG fix in RCC 1:2:4 slab with steel 1/2" Dia for main bars @ 6" C/C with bent up both way both side bent up C.C 1:3:6 block masonry wall set in 1.6" C/M 8" thick c/c 1:4:8 in foundation 2" thick C.C 1:2:4 flooring 1/2" thick Cement Plaster 1:3 inside wall surface 1'-0" deep upto roof slab i/c M.S footrest 5/8" dia bars at every 2'-0" deep i/c curing, dewatering excavation refilling etc Complete. (6' x 6' x 6')	4.00	Nos	55923.00	Each	223,692.00	55923.00	223,692.00	55950	223,800.00	56000	224,000.00	
11	Refilling the executed stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete.	14438.10	CR	2760.00	%0CH	39,849.16	2760.00	39,849.16	2770	39,993.54	2800	40,426.68	
	TOTAL QUOTED / CORRECTED COST					1,462,710.73		1,462,568.33		1,473,042.93		1,497,685.89	
	SAY					1,462,711		1,462,568	1st	2nd		3rd	


 (Nadeem Ahmed Khan)
 Accounts Officer (L.K)
 Member / Secretary


 (Saif-ul-Haque)
 Addl. Director Internal
 Audit KMC - Member


 (Magsood Ahmed Shaikh)
 Superintending Engineer (K.M.C)
 Member


 (Jamil Akhtar)
 Chief Engineer (L.K)
 Member


 (Abdul Rahim Khatri)
 Chief Engineer (IPD)
 Convener