



OFFICE OF THE EXECUTIVE ENGINEER (Sew) LIAQUATABAD ZONE
ST-7 KDA BUILDING LIAQUATABAD ZONE

No: KWSB/EE (Sew) /Sppra/2014/ 783

Dated: 20/6/ 2014

The Enforcement-II)
Sindh Public Procurement Regulatory Authority
Government of Sindh
KARAICH

Subject: Replacement of 8", 12" dia old defective sewer at Haji Mureed Goth of Gulbehar Area in Liaquatabad Zone (Sewerage)

Reference: Serial No.19660 / 2014 OF SPPRA WEB SITE.

With reference of above subjected work, enclosed please find herewith following documents for uploading on SPPRA web site as required by SPPRA.

6. Contract evaluation Form (Prescribed Performa duly signed).
7. Letter of Commencement / Work Order.
8. Bill of Quantities.
9. Copy of agreement.
10. Bid Evaluation Report.

Submitted for necessary action please.

Executive Engineer (Sew)
Liaquatabad Zone, KW&SB

Copy to:

Chief Engineer (Central) KW&SB
S.E (Liaquatabad Zone) KW&SB

9-02
17416

C
20/6

M/Ch

SINDH PUBLIC PROCUREMENT REGULATORY AUTHORITY

CONTRACT EVALUATION FORM

TO BE FILLED IN BY ALL PROCURING AGENCIES FOR PUBLIC CONTRACTS OF WORKS, SERVICES & GOODS

- 1) NAME OF THE ORGANIZATION / DEPTT. Karachi Water & Sewerage Board
- 2) PROVINCIAL / LOCAL GOVT./ OTHER Local Govt
- 3) TITLE OF CONTRACT Repl. of 8", 12" dia old/defective sewer at Haji Mureed Goth
- 4) TENDER NUMBER _____
- 5) BRIEF DESCRIPTION OF CONTRACT Improvement of sewerage system
- 6) FORUM THAT APPROVED THE SCHEME M.D KW&SB
- 7) TENDER ESTIMATED VALUE Rs.9,61,650/-
- 8) ENGINEER'S ESTIMATE Rs.9,63,673/-
(For civil works only)
- 9) ESTIMATED COMPLETION PERIOD (AS PER CONTRACT) 15 days
- 10) TENDER OPENED ON (DATE & TIME) 21/04/2014 at 2.30 p.m
- 11) NUMBER OF TENDER DOCUMENTS SOLD 03 Nos
(Attach list of buyers)
- 12) NUMBER OF BIDS RECEIVED 03 Nos
- 13) NUMBER OF BIDDERS PRESENT AT THE TIME OF OPENING OF BIDS 03 Nos
- 14) BID EVALUATION REPORT attached
(Enclose a copy)
- 15) NAME AND ADDRESS OF THE SUCCESSFUL BIDDER M/s Zafar Construction C/O Town committee Hub
- 16) CONTRACT AWARD PRICE Rs.9,61,650
- 17) RANKING OF SUCCESSFUL BIDDER IN EVALUATION REPORT
(i.e. 1st, 2nd, 3rd EVALUATION BID).
M/s Zafar Construction
M/s Safeer Enterprises
M/s Unity Associates

18) METHOD OF PROCUREMENT USED : - (Tick one)

- a) SINGLE STAGE – ONE ENVELOPE PROCEDURE Domestic/ Local
- b) SINGLE STAGE – TWO ENVELOPE PROCEDURE _____
- c) TWO STAGE BIDDING PROCEDURE _____
- d) TWO STAGE – TWO ENVELOPE BIDDING PROCEDURE _____

PLEASE SPECIFY IF ANY OTHER METHOD OF PROCUREMENT WAS ADOPTED i.e. EMERGENCY, DIRECT CONTRACTING ETC. WITH BRIEF REASONS:

19) APPROVING AUTHORITY FOR AWARD OF CONTRACT _____

20) WHETHER THE PROCUREMENT WAS INCLUDED IN ANNUAL PROCUREMENT PLAN?

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

21) ADVERTISEMENT :

i) SPPRA Website
(If yes, give date and SPPRA Identification No.)

Yes	Sr. No 19660 of SPPRA web site
No	

ii) News Papers
(If yes, give names of newspapers and dates)

Yes	
No	

22) NATURE OF CONTRACT

Domestic/ Local	<input checked="" type="checkbox"/>	Int.	<input type="checkbox"/>
--------------------	-------------------------------------	------	--------------------------

23) WHETHER QUALIFICATION CRITERIA WAS INCLUDED IN BIDDING / TENDER DOCUMENTS?
(If yes, enclose a copy)

Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
-----	--------------------------	----	-------------------------------------

24) WHETHER BID EVALUATION CRITERIA WAS INCLUDED IN BIDDING / TENDER DOCUMENTS?
(If yes, enclose a copy)

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

25) WHETHER APPROVAL OF COMPETENT AUTHORITY WAS OBTAINED FOR USING A METHOD OTHER THAN OPEN COMPETITIVE BIDDING?

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

26) WAS BID SECURITY OBTAINED FROM ALL THE BIDDERS?

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

27) WHETHER THE SUCCESSFUL BID WAS LOWEST EVALUATED BID / BEST EVALUATED BID (in case of Consultancies)

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

28) WHETHER THE SUCCESSFUL BIDDER WAS TECHNICALLY COMPLIANT?

Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
-----	--------------------------	----	-------------------------------------

29) WHETHER NAMES OF THE BIDDERS AND THEIR QUOTED PRICES WERE READ OUT AT THE TIME OF OPENING OF BIDS?

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

30) WHETHER EVALUATION REPORT GIVEN TO BIDDERS BEFORE THE AWARD OF CONTRACT?
(Attach copy of the bid evaluation report)

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

31) ANY COMPLAINTS RECEIVED
(If yes, result thereof)

Yes	
No	<input checked="" type="checkbox"/>

32) ANY DEVIATION FROM SPECIFICATIONS GIVEN IN THE TENDER NOTICE / DOCUMENTS
(If yes, give details)

Yes	
No	<input checked="" type="checkbox"/>

33) WAS THE EXTENSION MADE IN RESPONSE TIME?
(If yes, give reasons)

Yes	
No	<input checked="" type="checkbox"/>

34) DEVIATION FROM QUALIFICATION CRITERIA
(If yes, give detailed reasons.)

Yes	
No	<input checked="" type="checkbox"/>

35) WAS IT ASSURED BY THE PROCURING AGENCY THAT THE SELECTED FIRM IS NOT BLACK LISTED?

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

36) WAS A VISIT MADE BY ANY OFFICER/OFFICIAL OF THE PROCURING AGENCY TO THE SUPPLIER'S PREMISES IN CONNECTION WITH THE PROCUREMENT? IF SO, DETAILS TO BE ASCERTAINED REGARDING FINANCING OF VISIT, IF ABROAD:
(If yes, enclose a copy)

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------


37) WERE PROPER SAFEGUARDS PROVIDED ON MOBILIZATION ADVANCE PAYMENT IN THE CONTRACT (BANK GUARANTEE ETC.)?

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

38) SPECIAL CONDITIONS, IF ANY
(If yes, give Brief Description)

Yes	
No	<input checked="" type="checkbox"/>

Signature & Official Stamp of
Authorized Officer


MUHAMMAD ASIF
Executive Engineer
Liaquatbad Town (SEW)
Karachi Water & Sewerage Board

FOR OFFICE USE ONLY

SPPRA, Block. No.8, Sindh Secretariat No.4-A, Court Road, Karachi
Tele: 021-9205356; 021-9205369 & Fax: 021-9206291

Print

Save

Reset

OFFICE OF THE EXECUTIVE ENGINEER (Sew)
LIAQUATABAD TOWN, K.W.&.S.B

No: KW&SB/EE /LQT/Sew/2014/W-38

Dated: 19/6/2014

M/s Zafar Construction,
Govt. Contractor
C/O Town Committee Hub Distt.
Karachi

LETTER OF COMMENCEMENT

SUBJECT:- Replacement of 8", 12" dia old / defective sewer at Haji Mureed Goth of Gulbehar Area in Liaquatabad Zone (Sewerage)


Consequent upon the condition of Contract and letter of acceptance vide no. KW&SB/CE/Central/2014/89 Dated 18-06-2014 and subsequent you are hereby directed to commence the work in strict accordance with the contract, expedition and diligence, the date of commencement of work shall be reckoned from the 14 day of the received of the letter.

Please be noted that M/s Zafar Construction shall act as the engineer on this project through their authorized representative, the names and designation of the personnel's deputed will be communicated to you accordingly.

Therefore, you are advised to attend the office of the undersigned to obtain necessary instruction to carry out the work assigned to your firm and get it complete the same within (15) Twenty five days positively, failing which penalty of Rs.500 per days will be charged.

The expenditure will be charge under BG No.O-023-18 for year Current Financial year 2013-14

Please acknowledge the receipt of this letter by signing in the space provided below


EXECUTIVE ENGINEER
LIAQUATABAD TOWN (W/D)


MUHAMMAD ASIF
Executive Engineer
Liaquatabad Town(SEW)
Karachi Water & Sewerage Board

1. The C.E, (Central), KWSB
2. S.E. Liaquatabad Town.
3. A.E.E. Liaquatabad Town Sew.
4. Office Copy.

Received the latter.

With directive to communicate the names along-with the Designation of the personnel's engaged for the works.

Signature _____
Address _____
Date _____



27

KARACHI WATER & SEWREAGE BOARD
OFFICE OF THE EXECUTIVE ENGINEER (SEW)
ST-7 KDA BUILDING LIAQUATABAD ZONE

Estimate on item rate basis

Time Limit 15 Days

Penalty Rs.500/ Per Day

Tender Cost Rs.1000/-

Earnest Money 2% of Total Bid

Date of Receiving 21-4-2014 at 2.00 P.M

Date of opening 21-4-2014 at 3.00 P.m.

M/s Zaffar Construction Co.
Pay order No. 22 Dt DT: 16-4-2014 Bank/Br

Amount _____ B/No _____ Dt _____
[Signature]
TENDER CLERK
Finance Department


Name of Work: - **REPLACEMENT OF 8", 12" DIA OLD / DEFECTIVE SEWER AT HAJI MUREED GOTH OF GULBEHAR AREA IN LIAQUATABAD ZONE.**

SR No	DESCRIPTION	QUANTITY	RATE in Rupees / in Figer	PER	AMOUNT
1	Dismantling & removing road mantling.	495 Cft	(605) six hundred & five	%Cft.	2994.75/2
2	Dismantling cement concrete plain 1:2:4	625 Cft	(3327.50) Three thousand three hundred twenty seven & fifty paises.	%Cft	20796.87/2
3	Excavation for pipe line in trenches, and pits in all kind of soils of murum i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade, cutting joint holes and disposal of surplus earth within a one chain as directed by engineer In charge, Providing fence guards, lights, flags and temporary crossing for non vehicular traffic where ever required lift up to 5 ft. (1.52m) and lead up to one chain (30.5m).0 to 5	9550 cft	(4650) four thousand six hundred fifty.	%0cft	44407.50/2
	Add for additional lift of every three ft or part there of in item No.1 to 15 (A&B) excavation for pipe lines and storage tanks trenches and pits.	1980 cft	(5200) five thousand two hundred	%0Cft	10296/2
4	Full hire charges of the pumping per day inclusive of wage of driver & Assistant, fuel or Electric. Energy plate from required for placing pumps etc. at lower depth with suction and delivery pipes for pumping out water found at various depths from trenches i/c the cost of erection and dismantling after completion of the job. Hire charges pumping set of up to 10 HP pumping out water from 10 ft deep trench.	10 days	(1500) One thousand five hundred	Each	15000/2
5	Providing, Laying RCC pipes with Rubber Ring Joint and fitting in trench i/c cutting rubber ring i/c testing with water to specified pressure. 8" dia	500Rft	(206) Two hundred & six.	P/Rft	103000/2

[Signatures]

	12" dia	220 Rft	367/3 Three hundred sixty six P/Rft	80740/2
6	Providing Manhole 4 feet internal diameter without RCC manhole cover with C.I frame (15 kg) and 5 feet clear depth cast in situ 1:2:4, 9" thick wall 1:4:8 cement concrete in 6ft dia and 6 inch thick in foundation. 1;2;4, 1;2;4 CC in benching 1/2" cement plaster 1:3 cement mortar on inside wall and surface of channel and benching to top Including making required number of main and branches channels 3/4" dia abrs M.S rest at 12" C/C kind of soil back filling and disposal of excavated stuff etc complete, as per design and instruction of the engineer in charge	20 Nos	14529.29/2 Twelve thousand five hundred twenty nine and twenty nine hundredths Each	290585.8
7	Extra for depth beyond 5' depth, if less then 5, deduction will be made at the same rate.	+10 Rft	2538.62/2 Two thousand five hundred thirty eight and sixty two hundredths P/Rft	25386.20
8	Making connections with the existing manholes I/c cost of cutting holes in walls, making them good in cement concrete 1;2;4 and making the required channel etc complete.	10 Nos	1800/2 One hundred eighty Each	18000/2
9	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc. complete.	10990.5 Cft	2760/2 Two thousand & sixty %0 Cft	30333.78
10	Manufacturing and supplying of 21" dia RCC manhole covers cast in 1:2:4 concrete raion 3 inch deep at centre, reinforced with 1/2" inch dia to steel bars at 4" c/c welded to 3/16" thick 2" wide M.S.W plate two hook of 3/8" dia tor bar including compacting i/c curing, and transportation with in 10 miles	100 Nos	900/2 Nine hundred Each	90000/2
11	Manufacturing and supplying of RCC ring slabs of 21" inside 36" dia outside 7.5" width and 6" thick i/c 3/8" dia tor steel bars two hook concentric rings with 3/8" dia 8 Nos cross linked bars welded and two sunk type hooks casted in 1:1:-1/2:3 concrete with embedded 15 kg C.I frame			

	in perfect position i/c transportation charges for an average lead of 20 km per trip from casting yard to Town office (A minimum of 25 slabs per trip will be transported.	100 Nos	1900/- One thousand Nine hundred	Each	190000/- 25
12.	Shifting to the site and fixing of 36" dia ring slab in perfect position on damaged manholes i/c cutting of damaged portion of manholes in proper shape and laying of cement mortar of 2" thickness and disposal of debris.	100 Nos	563.09/- five hundred & Sixty three & Nine Paisa	Each	56309/-


 Executive Engineer
 Liaquatabad Zone (Sew)

Note: Participant /Contractor shall be bound to compliance all instruction / rule of SPPRA, 2010

I/we hereby quoted Rs 9,61,650/-
 Rupees Nine Lacs Sixty One thousand six hundred & fifty only

Contractor Signature Zafar.com

Wahid

Tender Received in Sealed Cover & Opened By Procurement Committee

P.O of the Bid Security Amount Rs. 29000/- P.O No. 99901361 Date 16-6-14

Rs. 1 P.O No. 1 Date 1


Rs. 1 P.O No. 1 Date 1


Bank Name, Southern Bank Gwlbahar Rd Karachi

Bin Quoted Rs. 961650/- (Rupees) Nine Lacs Sixty One thousand Six Hundred


No Cutting or Overwriting (Rise only)

Above/Below the S.P.O.R. (Limit)


 A.O to C.E. (Central)
 KW&SB
 Secretary / Member


 S.E (T/S) KMC
 Member


 Additional Director (I&A) KMC
 Member


 Chief Engineer
 (Central), KW&SB
 Member


 Chief Engineer
 (P&D), KW&SB



**OFFICE OF THE EXECUTIVE ENGINEER (SEW) LIAQUATABAD TOWN
KARACHI WATER & SEWERAGE BOARD**

ABSTRACT OF COST

Name of Work: *Replacement of 8" & 12" DIA old/defective sewers at Hojo Muneed Goth of Gulbahar Area in Wagwat Zone.*

S.No	Ref No	DESCRIPTION	QUANTITY	RATE	PER	AMOUNT
1.	pub-52 P-13 ITM-51	Dismantling & removing road metalling.	495 cft	605.00	%Cft.	RS 2994.75/2
2.	pub-52 P-10 ITM-19/c	Dismantling Cement concrete plane 1:2:4	625 cft	3327.50	% cft	RS 20796.87/2
3	pub-53 P-62 ITM-5	Excavation for pipe line in trenches, and pits in all kind of soils of murum i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade, cutting joint holes and disposal of surplus earth within a one chain as directed by engineer In charge, Providing fence guards, lights, flags and temporary crossing for non vehicular traffic where ever required lift up to 5 ft. (1.52m) and lead up to one chain (30.5m). Add for additional lift of every three ft or part there of in item No.1 to 15 (A&B) excavation for pipe lines and storage tanks trenches and pits. 5 to 8 ft 8 to 11 ft	9550 cft	4650.00	%0Cft	RS 44407.50/2
			1980 cft	5200.00	%0Cft	RS 10296/2
4	pub-53 P-76 ITM-23	Full hire charges of the pumping per day inclusive of wage of driver & Assistant, fuel or Electric. Energy plate from required for placing pumps etc. at lower depth with suction and delivery pipes for pumping out water found at various depths from trenches i/c the cost of erection and dismantling after completion of the job.	10 days	1500	P/Day	RS 15000/2
5	pub-53 P-18 ITM-B 2	Providing, Laying RCC pipes with (Rubber Ring Joint and fitting in trench i/c cutting rubber ring i/c testing with water to specified pressure. 8" dia 12" dia	500 Rft	206.00	P/Rft	RS 103000/2
			220 Rft	367.00	P/Rft	RS 80740/2
6	Based on schd rate 2012	Providing Manhole 4 feet internal diameter without RCC manhole cover with C.I frame (15 kg) and 5 feet clear depth cast in situ 1:2:4 using 50% crush stone and 50% graded bajri 9" thick wall 1:4:8 cement concrete in 6ft dia and 6 inch thick in foundation. 1;2;4, 1;2;4 CC in benching 1/2" cement plaster 1:3 cement mortar on inside wall and surface of channel and benching to top Including making required nuber of main and branches channels 3/4" dia abrs M.S rest at 12" C/C kind of soil back filling and disposal of excavated stuff etc complete, as per design and instruction of the engineer in charge.	20 nos	14529.29	Each	RS 290585.80/2

17/20/22

10
7
9
6

7		Extra for depth beyond 5' depth, if less then 5, deduction will be made at the same rate.	+ 10 R/P	2538.62	P/Rft	Rs. 2538.62
8	pub-54 P-31 ITM-3	Making connections with the existing manholes I/c cost of cutting holes in walls, making them good in cement concrete 1;2;4 and making the required channel etc complete.	10 Nos	180.00	Each	Rs. 1800/-
9	pub-53 P-77 ITM-24	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc. complete.	10590.5	2760.00	%OCft	Rs. 30333.78
10	pub-54 P-31 ITM-1	Manufacturing and supplying of 21" R.C.C. manhole cover cast in 1:2:4 concrete ratio 3 inch deep at center, reinforced with 1/2 inch dia to steel bars at 4" c/c welded to 3/16" thick 2" wide M.S plate two hook of 3/8" dia tor bar including compacting I/c curing, and transportation with in 10 miles. 21 inch dia 24 inch dia	100 Nos	913.63 1057.25	Each Each	Rs. 91363/-
11	pub-54 P-31 ITM-2	Manufacturing and Supplying RCC ring slabs of 21" inside 36" dia outside 7.5" width and 6" thick i/c 3/8" dia tor steel bars two concentric rings with 3/8" dia 8 Nos cross linked bars welded and two sunk type hooks casted in a 1:1-1/2:3 concrete with embedded 15 kg C.I frame in perfect position I/C transportation charges for an average lead of 20 km. per trip from casting yard to town offices (A minimum of 25 slabs per trip will be transported).	100 Nos	1906.60	Each	Rs. 190660/-
12	pub-54 P-31 ITM-4	Shifting to the site and fixing of 36" dia ring slab in perfect position on damaged manholes including cutting of damaged portion of manhole in proper shape and laying of cement mortar of 2" thickness and disposal of debris	100 Nos	563.09	Each	Rs. 56309/-
			Total			Rs. 9,63,673.78

SAY 9,63,673.78

Sub-Engineer (Sew)
Liaquatabad Zone KW&SB

Assistant Ex-Engineer (Sew)
Liaquatabad Zone, KW&SB

Checked Technically
for amount
Rs 9,63,673.


Executive Engineer (Sew)
Liaquatabad Zone, KW&SB

Executive Engineer (Sew)
Liaquatabad Town (SEW)
Karachi Water & Sewerage Board

After Zaidi
Calculation checked automatically per Rs. 9,63,673.78
in the light of letter no. KW&SB/Dir/Design/2012/722 dt. 29/8/12

18/3/14
10/3/14
19/03/14

2585.8



AAMIR ALI STAMP VENDOR
Licence No. 48, Sect No. 1, City Court Karachi.

S. No. **137526** DATE **16 JUN 2014**

ISSUED TO WITH ACCESS

THROUGH WITH ADDRESS

PURPOSE

VALUE RS

STAMP VENDOR'S SIGNATURE

MALIK SHEER AF

CONTRACT AGREEMENT

Sanction Amount Rs.961,650/-

THIS CONTRACT AGREEMENT (hereinafter called the "Agreement") made on the 18th day of June 2014 between The Karachi Water & Sewerage Board represented by it's The Chief Engineer (Central), KW&SB (hereinafter called the "Employer") of the one part and M/s. Zafar Construction. (hereinafter called the "Contractor") of the other part.


WHEREAS the Employer is desirous that certain Works, viz REPLACEMENT OF 8", 12" DIA OLD / DEFECTIVE SEWER AT HAJI MUREED GOTH OF GULBEHAR AREA IN LIAQUATABAD ZONE (SEWERAGE). Should be executed by the Contractor and has accepted a Bid by the Contractor for the execution and completion of such Works and the remedying of any defects therein.

NOW This Agreement witness as follows:-

1. In this Agreement words and expressions shall have the same meanings as are respectively assigned to them in the Conditions of Contract hereinafter referred to.
2. The following documents after incorporating addenda, if any except those parts relating to Instructions to Bidders, shall be deemed to form and be read and construed as part of this Agreement, viz:
 - a. The Letter of Sanction;
 - b. The completed Form of Bid along with Schedules to Bid;
 - c. Conditions of Contract & Contract Data;
 - d. The priced Schedule of Prices;
 - e. The Specifications; and
 - f. The Drawings.

M. Ali
E.E.

M. Asif
MUHAMMAD ASIF
Executive Engineer
Liaquatabad Town(SEW)
Karachi Water & Sewerage Board



YAMIR ALI STAMP VENDOR

Case No. 48, Seat No. ... City Court Karachi

No. 139337 DATE

18 JUN 2014

SUED TO WITH ADDRESS
PROSECUTED BY WITH ADDRESS

PURPOSE
VALUERS (ATTESTED)

STAMP VENDOR'S SIGNATURE

Page-2

- 3. In consideration of the payments to be made by the Employer to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the Employer to execute and complete the Works and remedy defects therein in conformity and in all respects within the provisions of the Contract.
- 4. The Employer hereby covenants to pay the Contractor, in consideration of the execution and completion of the Works as per provisions of the Contract, the Contract Price or such other sum as may become payable under the provisions of the Contract at the times and in the manner prescribed by the Contract.

IN WITNESS WHEREOF the parties hereto have caused this Contract Agreement to be executed on the day, month and year first before written in accordance with their respective laws.

Signature of the Contractor

M/s. Zafar Construction
Proprietor

Signature of the Employer

CHIEF ENGINEER, CENTRAL
KW&SB

Witness:

1. M/s Zafar Const
[Signature]

Witness:

[Signature]
SUPERINTENDING ENGINEER
LIAQUATABAD TOWN
KW&SB

2. M/s Unity Associates
[Signature]

[Signature]
EXECUTIVE ENGINEER SEW
LIAQUATABAD TOWN
KW&SB

081111



AAMIR ALI STAMP VENDOR
 Licence No. 48, Seat No. City Court Karachi.
 S. No. **138818** DATE **16 JUN 2014**
 ISSUED TO WITH ADDRESS
 THROUGH WITH ADDRESS
 FROM
 VERIFIED BY
 STAMP VENDOR'S SIGNATURE **SHAB ALAM**
ADVOCATE KBA-2399
 (ATTESTED)

[Handwritten Signature]
Karachi

17 JUN 2014

REPLACEMENT OF 8", 12" DIA OLD / DEFECTIVE
SEWER AT HAJI MUREED GOTH OF GULBEHAR AREA
IN LIAQUATABAD ZONE (SEWERAGE)

BY

M/s. Zafar Construction


Rs. 961,650/-

[Handwritten Signature]

[Handwritten Signature]
MUHAMMAD ASIF
 Executive Engineer
 Liaquatnabad Town(SEW)
 Karachi Water & Sewerage Board

[Handwritten Signature]
 E.E

B877853



STAMP VENDOR

Plot No 16, Block 14,
Marsheedah Karachi

110425

27 MAY 2014

Zaidi Mehmood
Advocate

(Handwritten signature)

Not For Used Freewill & Divorce

**REPLACEMENT OF 8", 12" DIA OLD / DEFECTIVE
SEWER AT HAJI MUREED GOTH OF GULBEHAR AREA
IN LIAQUATABAD ZONE (SEWERAGE)**

BY

M/s. Zafar Construction

Rs. 961,650/-

(Handwritten signature)

(Handwritten signature)
MUHSIN AD ASIF
Executive Engineer
Liaquatabad Town(SEW)
Karachi Water & Sewerage Board

(Handwritten signature)
E.E



KARACHI WATER & SEWERAGE BOARD

OFFICE OF THE CHIEF ENGINEER (IP&D)

BID EVALUATION REPORT

1	Name of Procuring Agency	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No	SPPRA Serial No.19660 I.D No. /2014
3	Tender Description/Name of Work/Item	REPLACEMENT OF 8", 12" DIA OLD / DEFECTIVE SEWER AT HAJI MUREED GOTH OF GULBEHAR AREA IN LIAQUATABAD ZONE (SEWERAGE).
4	Method of Procurement	Single Stage (One Envelop)
5	Tender Published	Through Web Site
6	Total Bid Documents Sold	03 Nos
7	Total Bid Received	03 Nos
8	Technical Bid Opening Date (if applicable)	N/A .
9	No. of Bid Technically Qualified (if applicable)	N/A .
10	Bid (s) rejected	Two
11	Financial Bid Opening Date	21/4/2014

12 Bid Evaluation Report

S #	NAME OF FIRM OR BIDDER	COST OFFERED BY THE BIDDERS	RANKING IN TERMS OF COST	COMPARISON WITH ESTIMATED COST	REASON FOR ACCEPTANCE/ REJECTION	REMARKS
1	M/s. Zaffar Construction Co	Rs. 961,650/-	1st Lowest	@ 0.2098% Below	Substantially Responsive	P.O # 00901361 Dt: 16-04-2014 Rs.20,000/- Soneri Bank Gulbahar Br Karachi
2	M/s. Safeer Enterprises	Rs. 964,328/-	2nd Lowest	@ 0.0680% Above	Un Responsive bid due to unqualified	P.O # 00901363 Dt: 16-04-2014 Rs.??,000/- Soneri Bank Gulbahar Br Karachi
3	M/s. Unity Associates	Rs. 966,869/-	3rd Lowest	@ 0.3317% Above	Un Responsive bid due to unqualified	P.O # 00901362 Dt: 16-04-2014 Rs.21,000/- Soneri Bank Gulbahar Br Karachi

The all concerned bidder are being informed accordingly.

The E.E Concerned for compliance of rule 45 of SPPRA 2010 M/s. Zaffar Construction Co. declared as the lowest responsive bidder by the Committee and recommended for Sanction from Competent Authority.

(Abdul Jabbar Shaikh)
Accounts Officer (Central)
Member/Secretary

(Saif-ul-Haque)
Additional Director Internal
Audit - KMC Member

(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member

(Syed Fahim Akhtar Zaidi)
Chief Engineer (Central)
Member

(Abdul Rahim Khattak)
Chief Engineer (IPD),
(Convener)

MUHAMMAD ASIF
Executive Engineer
Liaquatabad Town(SEW)
Karachi Water & Sewerage Board



KARACHI WATER & SEWERAGE BOARD

OFFICE OF THE CHIEF ENGINEER (IP&D)

BID EVALUATION REPORT


1	Name of Procuring Agency	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No	SPPRA Serial No.19660 I.D No. /2014
3	Tender Description/Name of Work/Item	REPLACEMENT OF 8", 12" DIA OLD / DEFECTIVE SEWER AT HAJI MUREED GOTH OF GULBEHAR AREA IN LIAQUATABAD ZONE (SEWERAGE).
4	Method of Procurement	Single Stage (One Envelop)
5	Tender Published	Through Web Site
6	Total Bid Documents Sold	03 Nos
7	Total Bid Received	03 Nos
8	Technical Bid Opening Date (if applicable)	N/A
9	No. of Bid Technically Qualified (if applicable)	N/A
10	Bid (s) rejected	Two
11	Financial Bid Opening Date	21/4/2014

12 Bid Evaluation Report

S #	NAME OF FIRM OR BIDDER	COST OFFERED BY THE BIDDERS	RANKING IN TERMS OF COST	COMPARISON WITH ESTIMATED COST	REASON FOR ACCEPTANCE/ REJECTION	REMARKS
1	M/s. Zaffar Construction Co	Rs. 961,650/-	1st Lowest	@ 0.2098% Below	Substantially Responsive	P.O # 00901361 Dt: 16-04-2014 Rs.20,000/- Soneri Bank Gulbahar Br Karachi
2	M/s. Safer Enterprises	Rs. 964,328/-	2nd Lowest	@ 0.0680% Above	Un Responsive bid due to unqualified	P.O # 00901363 Dt: 16-04-2014 Rs.22,000/- Soneri Bank Gulbahar Br Karachi
3	M/s. Unity Associates	Rs. 966,869/-	3rd Lowest	@ 0.3317% Above	Un Responsive bid due to unqualified	P.O # 00901362 Dt: 16-04-2014 Rs.21,000/- Soneri Bank Gulbahar Br Karachi

The all concerned bidder are being informed accordingly.

The E.E Concerned for compliance of rule 45 of SPPRA 2010 M/s. Zaffar Construction Co. declared as the lowest responsive bidder by the Committee and recommended for Sanction from Competent Authority.


(Abdul Jabbar Shaikh)
Accounts Officer (Central)
Member/Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit - KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Syed Fahim Akhtar Zaidi)
Chief Engineer (Central)
Member


(Abdul Rahim Khattak)
Chief Engineer (IPD),
(Convener)

BIDDERS QUALIFICATION REPORT

56

Rule-46(i) (a) Single Stage One Envelope Procedure

Opening Date: 21-04-2014

Name of Work: **REPLACEMENT OF 8", 12" DIA OLD / DEFECTIVE SEWER AT HAJI MUREED GOTH OF GULBEHAR AREA IN LIAQUATABAD ZONE (SEWERAGE).**

Name of Bidder M/s. Zaffar Construction Co.

S.No	Eligibility	Yes	No
1	Relevant experience	Yes	—
2	Turnover Statement	Yes	—
3	Registration with Income Tax	Yes	—
4	Registration with Sales Tax where applicable.	—	—
Qualified			

Name of Bidder M/s. Safer Enterprises.

S.No	Eligibility	Yes	No
1	Relevant experience	—	—
2	Turnover Statement	—	—
3	Registration with Income Tax	—	—
4	Registration with Sales Tax where applicable.	—	—
Disqualified			

Name of Bidder M/s. Unity Associates

S.No	Eligibility	Yes	No
1	Relevant experience	—	—
2	Turnover Statement	—	—
3	Registration with Income Tax	—	—
4	Registration with Sales Tax where applicable.	—	—
Disqualified			

(Abdul Jabbar Shaikh)
Accounts Officer (Central)
Member / Secretary

(Syed Fahim Akhtar Zaidi)
Chief Engineer (Central)
Member

(Saif-ul-Haque)
Additional Director Internal
Audit – KMC Member

(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member

(Abdul Raheem Khattar)
Chief Engineer (IPD)
Convener

NIT Sr. No. 19660

Method of Procurement: Single Stage Single Envelope.

Name of Work: REPLACEMENT OF 8", 12" DIA OLD / DEFECTIVE SEWER AT HAJI MUREED GOTH OF GULBEHAR AREA IN LIAQUATABAD ZONE (SEWERAGE).

MINUTES OF BID OPENING MEETING.

A meeting of the procurement committee of this department was held on 21-04-2014 for opening the bids received in respect of subject NIT till deadlines of submission. The meeting was attended by all / following members of the procurement committee and the representative of bidders. (Attendance sheet is enclosed).

2. Three bidders submitted their bids till the deadline of submission.

- i. M/s. Zaffar Construction Co.
- ii. M/s. Safer Enterprises.
- iii. M/s. Unity Associates


3. The bids were opened at 02:30 P.M in the presence of the above mentioned participants and the rates quoted by bidders were read aloud and encircled by Chairman of the Procurement Committee.

S. No	Name of Firm	Quoted Price	Amount of Bid Security	Pay Order No. / Date
01	M/s. Zaffar Construction Co	Rs. 961,650/-	Rs.20,000/-	P.O # 00901361 Dt: 16-04-2014 Soneri Bank Gulbahar Br Karachi
02	M/s. Safer Enterprises	Rs. 964,328/48	Rs.22,000/-	P.O # 00901363 Dt: 16-04-2014 Soneri Bank Gulbahar Br Karachi
03	M/s. Unity Associates	Rs. 966,869/28	Rs.21,000/-	P.O # 00901362 Dt: 16-04-2014 Soneri Bank Gulbahar Br Karachi

4. The bids do not contain any over-writing or cutting.

5. The committee shall examine all the bids as per the qualification / eligibility criteria provided in the bidding document and verify the documents and bid security submitted by the bidders (if required).


The meeting ended with the note of thanks to and from the chair.



(Abdul Jabbar Shaikh)
Accounts Officer (Central)
Member / Secretary




(Saif-ul-Haque)
Additional Director Internal
Audit – KMC Member



(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member



(Syed Fahim Akhtar Zaidi)
Chief Engineer (Central)
Member



(Abdul Raheem Khattai)
Chief Engineer (IPD)
Convener

COMPARATIVE STATEMENT

NAME OF WORK: REPLACEMENT OF 8", 12" DIA OLD / DEFECTIVE SEWER AT HAJI MUREED GOTH OF GUI.BEHAR AREA IN LIAQUATABAD ZONE (SEWERAGE).

S.No	Description of Work	Engineer's Estimate			M/s. Zaffar Construction Co		M/s. Safeer Enterprises		M/s. Unity Associates	
		Quantity	Rate	Unit	Rate	Amount	Rate	Amount	Rate	Amount
1	Dismantling & removing road mantling	495	Cft	605.00	2,994.75	605.00	2,994.75	610.00	3,019.50	
2	Dismantling Cement concrete plane 1:2:4	625	Cft	3,327.50	20,796.57	3,327.50	20,796.88	3,330.00	20,812.50	
3	Excavation for pipe line in trenches, and pits in all kind of soils of murum i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade, cutting joint holes and disposal of surplus earth within a one chain as directed by engineer in charge, Providing fence guards, lights, flags and temporary crossing for non vehicular traffic where ever required lift up to 5 ft. (1.52m) and lead up to one chain (30.5m)									
	Add for additional lift of every three ft or part there of in item No.1 to 15 (A&B) excavation for pipe lines and storage tanks trenches and pits. 5 to 8 ft	9550	Cft	4,650.00	44,407.50	4,650.00	44,407.50	4,650.00	44,407.50	44,407.50
	Full hire charges of the pumping per day inclusive of wage of driver & Assistant, fuel or Electric. Energy plate from required for placing pumps etc. at lower depth with suction and delivery pipes for pumping out water found at various depths from trenches i/c the cost of erection and dismantling after completion of the job. Hire charges pumping set of up to 10 HP pumping out water from 10 ft deep trench	1980	Cft	5,200.00	10,296.00	5,200.00	10,296.00	5,200.00	10,296.00	10,296.00
4		10	Day	1,500.00	15,000.00	1,500.00	15,000.00	1,500.00	15,000.00	15,000.00

[Handwritten signature]

[Handwritten mark]

[Handwritten mark]

[Handwritten signature]

[Handwritten mark]

NAME OF WORK: REPLACEMENT OF 8", 12" DIA OLD / DEFECTIVE SEWER AT HAJI MUREED GOTH OF GUI.BEHAR AREA IN LIAQUATABAD ZONE (SEWERAGE).

S.No	Description of Work	Engineer's Estimate			M/s. Zaffar Construction Co		M/s. Safeer Enterprises		M/s. Unity Associates			
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount	Rate	Amount	
5	Providing, Laying RCC pipes with Rubber Ring Joint and fitting in trench i/c cutting rubber ring i/c testing with water to specified pressure. 8" dia	500	Rft	206.00	P/Rft	103,000.00	206.00	103,000.00	210.00	105,000.00	215.00	107,500.00
	12" dia	220	Rft	367.00	P/Rft	80,740.00	367.00	81,400.00	370.00	81,400.00	370.00	81,400.00
6	Providing Manhole 4 feet internal diameter without RCC manhole cover with C.I frame (15 kg) and 5 feet clear depth cast in situ 1:2:4 9" thick wall 1:4:8 cement concrete in 6ft dia and 6 inch thick in foundation. 1:2:4, 1:2:4 CC in benching Vz" cement plaster 1:3 cement mortar on inside wall and surface of channel and benching to top Including making required number of main and branches channels%" dia abrs M/S rest at 12" C/C kind of soil back filling and disposal of excavated stuff etc complete, as per design and instruction of the engineer in charge	20	Nos	14,529.29	Each	290,585.80	14,529.29	290,585.80	14,530.00	290,600.00	14,530.00	290,600.00
7	Extra for depth beyond 5' depth, if less then 5, deduction will be made at the same rate	10	Rft	2,538.62	P/Rft	25,386.20	2,538.62	25,386.20	2,540.00	25,400.00	2,540.00	25,400.00
8	Making connections with the existing manholes i/c cost of cutting holes in walls, making them good in cement concrete 1:2:4 and making the required channel etc cofr lete	10	Nos	180.00	Each	1,800.00	180.00	1,800.00	180.00	1,800.00	180.00	1,800.00

[Handwritten signatures and initials]

NAME OF WORK: REPLACEMENT OF 8", 12" DIA OLD / DEFECTIVE SEWER AT HAJI MUREED GOTH OF GULBEHAR AREA IN LIAQUATABAD ZONE (SEWERAGE).

S.No	Description of Work	Engineer's Estimate			M/s. Zaffar Construction Co		M/s. Safer Enterprises		M/s. Unity Associates		
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount	Rate	Amount
9	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc. complete	10990.5	2,760.00	% 0 Cft	30,333.78	2,760.00	30,333.78	2,760.00	30,333.78	2,760.00	30,333.78
10	Manufacturing and supplying of 21" dia RCC Manhole cover in cast 1:2.4 concrete ratio 3" deep at centre reinforced with 1/2" dia to steel bars 4" c/c welded to 3/16" thick 2" wide M.S plat and two hook of 3/8" dia for bars i/c compacting, curing & transportation within 10 miles. 21" Dia	100	913.63	Each	91,363.00	900	90,000	900	90,000	900	90,000
11	Manufacturing and supplying RCC ring slabs of 21" inside diameter 36" outside diameter 7.5" width and 6" thick i/c 3/8" dia for steel bars two concentric rings with 3/8" dia 8 Nos. cross linked bars welded and two sunk type hooks casted in 1:1-1/2:3 concrete with embedded 15 Kg C.I frame in perfect position i/c transportation charges for an average lead of 20 Km per trip from casting yard to town office (A minimum of 25 slabs per trip will be transported)	100	1,906.60	Each	190,660.00	1900	190,000	1900	190,000	1900	190,000
12	Shifting to the site and fixing of 36" dia Ring slab in perfect position on damaged Manhole i/c cutting of damaged portion in proper shape and laying of cement mortar of 2" thickness and disposal of debris.	100	563.09	Each	56,309.00	563.09	56,309	563	56,300	563	56,300
	Total Quoted / Corrected Cost				963,672.60		961,649.91		964,328.41		966,869.28
	Say				963,673		961,650		964,328		966,869

(Abdul Jabbar Shaikh)
Accounts Officer (Central)
Member/Secretary

(Saif-ul-Haque)
Additional Director Internal
Audit - KMC Member

(Abdul Rahim Khattak)
Chief Engineer (IPD) (Convener)

(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member