



KARACHI WATER & SEWERAGE BOARD

OFFICE OF THE CHIEF ENGINEER (IP&D)

BID EVALUATION REPORT


1	Name of Procuring Agency:	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No:	SPPRA Serial No.26921 I.D # _____
3	Tender Description/Name of Work/Item:	REPLACEMENT OF 8" DIA, 12" DIA & 15" DIA RCC SEWERS AT KECHS, GREEN BELT MEHMOODABAD & 116-N, BLOCK-2, UC NO.7, JAMSHED TOWN (SEWERAGE)-I
4	Method of Procurement:	<u>Single Stage (One Envelop)</u>
5	Tender Published:	<u>SPPRA Web Site</u>
6	Total Bid Documents Sold:	<u>3 Nos</u>
7	Total Bid Received:	<u>3 Nos</u>
8	Technical Bid Opening Date (if applicable):	<u>N/A</u>
9	No. of Bid Technically Qualified (if applicable)	<u>N/A</u>
10	Bid (s) Rejected:	<u>02 Nos</u>
11	Financial Bid Opening Date:	<u>31-03-2016</u>

12 BID EVALUATION REPORT

S#	Name of Firm / Bidder	COST OFFERED BY THE BIDDER	RANKING IN TERMS OF COST	COMPARISON WITH ESTIMATED COST	REASON FOR ACCEPTANCE / REJECTION	REMARKS
1	M/s.A. Dawood Shah & Co.	Rs.4,65,886/-	1 st Lowest	@0.139% Below	Pay Order and required documents are available. P.O # 13660307 dt: 31-03-2016 Rs.9,400/- from HBL Gujjar Chowk Manzoor Colony Branch Karachi	Substantially Responsive
2	M/s.Murad & Co.	Rs.4,67,558/-	-	@0.219% Above	Pay Order attached but required documents are available. P.O # 13660306 dt: 31-03-2016 Rs.9,500/-from HBL Gujjar Chowk Manzoor Colony Branch Karachi	Un Responsive
3	M/s.Ali Muhamma d & Sons	Rs.4,69,166/-	-	-	Pay order and required documents are not available.	Un Responsive


The all concerned bidders are being informed accordingly.

The E.E Concerned for compliance of Rule-45 of SPPRA 2010 **M/s.A. Dawood Shah & Co.** declared as the lowest responsive bidder by the Committee and recommended for sanction from Competent Authority.

(Amir Haq) 
D.A.O (District East)
Member / Secretary

(Saif-ul-Haque) 
Additional Director Internal
Audit – KMC Member





(Maqsood Ahmed Shaikh) 
Superintending Engineer (KMC)
Member

(Syed Muhammad Jamil Akhter) 
Chief Engineer (W&S)
Member

(Syed Mashkoor ul-Hasnain) 
Chief Engineer (IPD)
Convener

COMPARATIVE STATEMENT
Name of Work: REPLACEMENT OF 8" DIA, 12" DIA & 15" DIA RCC SEWERS AT KECHS, GREEN BELT MEHMOODABAD & 116-N, BLOCK-2, UC NO.7, JAMSHED TOWN (SEWERAGE)-I

Sl. No	Description of Work	Estimated Cost				M/s.A. Dawood Shah & Co.		M/s.Murad & Co.		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
1	Dismantling and removal road maling	1905.00	Cft	605.00	%Cft	11,525.25	600	11,430.00	610	11,620.50
2	Excavation for pipe line in trenches and pits in all kind of soils of murum i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by Engineer Incharge providing fence guards, lights, flags sand temporary crossing for non-vehicular traffic wherever required lift upto 5 ft (1.52 m) and lead upto i. Lift 00' - 05ft									
	ii. Lift 05' - 08'	6932.50	Cft	4650.00	%0Cft	32,236.13	4,645	32,201.46	4,655	32,270.79
3	Providing M/H 4' feet inside with C.I Frame (15 Kg) and 5 feet clear depth 1:2:4 cast in situ with in 9" thick wall, 1:4:8: C.C in 6ft dia and 6" inch thick in foundation 1:2:4 C.C in benching 12" thick cement plastering with 1:3 C.M on all inside wall surfaces, channel and benching i/c making required nos of main and branch channels, 3/4" dia m.s foot rest @12" C/C i/c cost of excavation in all kinds of soil, backfilling and disposal of excavated stuff etc complete as per design and instruction of Engineer Incharge.	2752.50	Cft	5200.00	%0Cft	14,313.00	5,150	14,175.38	5,300	14,588.25
3(i)	Add or deduct for extra / less depth then 5ft to 4ft dia manhole i/c footrest.	8.00	Nos	14529.29	Each	116,234.32	14,525	116,200.00	14,530	116,240.00
		3.00	(+)Ft	2538.62	P/ft	7,615.86	2,535	7,605.00	2,540	7,620.00

Name of Work: REPLACEMENT OF 8" DIA, 12" DIA & 15" DIA RCC SEWERS AT KECHS, GREEN BELT MEHMOODABAD & 116-N, BLOCK-2, UC NO.7, JAMSHED TOWN (SEWERAGE)-I

Item No	Description of Work	Estimated Cost				M/s.A. Dawood Shah & Co.		M/s. Murad & Co.		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
	Full hire charges of pumping set per day i/c of wages of driver and assistant fuel or electric energy platform for placing the pump etc at lower depth with suction and delivery pipes for pumping out water found at various depth from trenches including the cost of erection and dismantling after completion of the job. Hire charges of pumping set upto 10 HP pumping out water from 10 ft deep trench	10.00	Days	1500.00	P/Day	15,000.00	1,500	15,000.00	1,500	15,000.00
5	Providing, & Laying of RCC Pipes with Rubber Ring Joint and fitting in trench including cutting, fitting, jointing with rubber ring i/c testing with water to specified pressure. 08" Dia Pipe	275.00	Rft	206.00	P/Rft	56,650.00	206	56,650.00	207	56,925.00
	12" dia	295.00	Rft	367.00	P/Rft	108,265.00	367	108,265.00	366	107,970.00
	15" dia	95.00	Rft	436.00	P/Rft	41,420.00	436	41,420.00	440	41,800.00
6	Manufacturing and supplying of 21 inch diameter RCC Manhole Covers cast in 1:2:4 cement concrete ratio 3" inch deep at centre rein-forced with 1/2" dia M.S tor bars with 4" c/c welded to a 3/16" thick 2" wide M.S Flat and tow hook of 3/8" dia tor bars including compacting, curing and transportation within 10 miles etc. 21" dia	8.00	Nos	913.63	Each	7,309.04	910	7,280.00	915	7,320.00
7	Making connection with the existing manhole including the cost of cutting hole in wall, making them good in C.C 1:2:4 and making the required channel etc. complete	4.00	Nos	180.00	Each	720.00	180	720.00	185	740.00

Name of Work: REPLACEMENT OF 8" DIA, 12" DIA & 15" DIA RCC SEWERS AT KECHS, GREEN BELT MEHMOODABAD & 116-N, BLOCK-2, UC NO.7, JAMSHED TOWN (SEWERAGE)-I

Item No	Description of Work	Estimated Cost				M/s. A. Dawood Shah & Co.		M/s. Murad & Co.		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
9	Sand Haro or any other source sand of same modules of the fineness (Hill Sand)	1568.50	Cft	714.29	%Cft	11,203.64	714	11,199.09	720	11,293.20
10	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete.	892.50	Cft	2425.00	%Cft	21,643.13	2,400	21,420.00	2,430	21,687.75
	TOTAL QUOTED / CORRECTED COST	8116.50	Cft	2760.00	%0Cft	22,401.54	466,537	465,886	467,558	467,558

(Amir Haidar)
D.A.O (Distt. East)
Member / Secretary

(Saif-ul-Haque)
Addl. Director Internal Audi
KMC - Member

(Magsood Ahmed Shaikh)
Superintending Engineer (K.M.C)
Member

(Syed Muhammad Jamil Akhter)
Chief Engineer (W&S)
Member

(Syed Masud-ur-Rashtain)
Chief Engineer (IPD)
Member

NIT No. SPPRA Serial No.26921

Method and procedure of procurement: Open Competitive Bidding (National/ International Competitive Bidding) (Single Stage-One Envelope)


Description of work: **REPLACEMENT OF 8" DIA, 12" DIA & 15" DIA RCC SEWERS AT KECHS, GREEN BELT MEHMOODABAD & 116-N, BLOCK-2, UC NO.7, JAMSHED TOWN (SEWERAGE)-I**


Date of Opening: 31-03-2016


BIDDERS' ELIGIBILITY/ QUALIFICATION REPORT


Eligibility/ Qualification Criteria:


S. No.	Eligibility / Qualification Criteria	Bidders' Name		
		M/s.A. Dawood Shah & Co.	M/s.Murad & Co.	M/s.Ali Muhammad & Sons
1.	Registration with PEC (if applicable)	N/A	N/A	N/A
2.	NTN	Yes	No	No
3.	Sales Tax Registration (FBR)	N/A	N/A	N/A
4.	Registration with Sindh Revenue Board (SRB)	Yes	No	No
	Qualification Criteria:			
5.	Minimum three years' experience of relevant field.	Yes	No	No
6.	Turnover of at least last three years	Yes	No	No
7.	Required Bid Security is attached.	Yes	Yes	No
8.	Bid is signed, named and stamped by the authorized person of the firm along with Authorization letter.	Yes	Yes	Yes
9.	Any other factor deemed to be relevant by the procuring agency subject to provision of Rule-44	N/A	N/A	N/A
10.	Qualified/ disqualified	Qualified	Disqualified	Disqualified


(Amir Hamid)
D.A.O (District East)
Member / Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit – KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Syed Muhammad Jamil Akhter)
Chief Engineer (W&S)
Member


(Syed Mashkoor-ul-Hasnain)
Chief Engineer (IPD)
Convener

NIT No. SPPRA Serial No.26921

Method of Procurement: Single Stage Single Envelope.

Name of Work: REPLACEMENT OF 8" DIA, 12" DIA & 15" DIA RCC SEWERS AT KECHS, GREEN BELT MEHMOODABAD & 116-N, BLOCK-2, UC NO.7, JAMSHED TOWN (SEWERAGE)-I

MINUTES OF BID OPENING MEETING.

A meeting of the procurement committee of this department was held on 31-03-2016 for opening the bids received in respect of subject NIT till deadlines of submission. The meeting was attended by all / following members of the procurement committee and the representative of bidders. **(Attendance sheet is enclosed).**

2. Three bidders submitted their bids till the deadline of submission.
- M/s. A. Dawood Shah & Co.
 - M/s. Murad & Co.
 - M/s. Ali Muhammad & Sons


3. The bids were opened at 2:30 P.M in the presence of the above mentioned participants and the rates quoted by bidders were read aloud and encircled by Chairman of the Procurement Committee.


S. No	Name of Firm	Quoted Price	Amount of Bid Security	Pay Order No. / Date
01	M/s.A. Dawood Shah & Co.	Rs.4,65,885/-	Rs.9,400/-	P.O # 13660307 dt: 31-03-2016 from HBL Gujjar Chowk Manzoor Colony Branch Karachi
02	M/s.Murad & Co.	Rs.4,67,558/-	Rs.9,500/-	P.O # 13660306 dt: 31-03-2016 from HBL Gujjar Chowk Manzoor Colony Branch Karachi
03	M/s.Ali Muhammad & Sons	Rs.4,69,166/-	-	Pay order not attached.


4. The bids do not contain any over-writing or cutting.


5. The committee shall examine all the bids as per the qualification / eligibility criteria provided in the bidding document and verify the documents and bid security submitted by the bidders (if required).


The meeting ended with the vote of thanks to and from the chair.


(Amir Halmi)
D.A.O (District East)
Member / Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit – KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Syed Muhammad Jamil Akhter)
Chief Engineer (W&S)
Member


(Syed Mashkoor-ul-Hasnain)
Chief Engineer (IPD)
Convener

