



NAME OF WORK:

WORK OF RECTIFIED OF CHOCKED / RUSTED A.C & C.I PIPE AT SHARIFABAD BLOCK NO.01 AND COMMERCIAL AREA BLOCK-5 FOR RE-LAYING FOR IMPROVEMENT OF WATER SUPPLY SYSTEM AND REPLACEMENT OF DAMAGED PORTION IN LIAQUATABAD TOWN.

Date of Opening: 28-12-2017

Time of Opening: 2:30 PM

Sr, No. _____

S. NO.	NAME OF CONTRACTOR	NAME OF FIRMS	SIGNATURE
1,	Aleem Ahmed	Treat cont Co	
2,	Nadeem Ahmed	SOH Enterprises	

Method and procedure of procurement: Open Competitive Bidding (National/ International Competitive Bidding) (Single Stage–One Envelope)

Description of work: WORK OF RECTIFIED OF CHOCKED / RUSTED A.C & C.I PIPE AT SHARIFABAD BLOCK NO-1 AND COMMERCIAL AREA BLOCK-5 FOR RE-LAYING FOR IMPROVEMENT OF WATER SUPPLY SYSTEM AND REPLACEMENT OF DAMAGED PORTION IN LIAQUATABAD TOWN

Date of Opening: 28-12-2017


BIDDERS' ELIGIBILITY/ QUALIFICATION REPORT


Eligibility/ Qualification Criteria:


S. No.	Eligibility / Qualification Criteria	Bidders' Name	
		M/s. Trust Construction Co.	M/s.S.O.H Construction Co.
1.	Registration with PEC (if applicable)	N/A	N/A
2.	NTN	Yes	Yes
3.	Sales Tax Registration (FBR)	N/A	N/A
4.	Registration with Sindh Revenue Board (SRB)	Yes	Yes
	Qualification Criteria:		
5.	Minimum three years' experience of relevant field.	Yes	Yes
6.	Turnover of at least last three years	Yes	Yes
7.	Required Bid Security is attached.	Yes	Yes
8.	Bid is signed, named and stamped by the authorized person of the firm along with Authorization letter.	Yes	Yes
9.	Any other factor deemed to be relevant by the procuring agency subject to provision of Rule-44	N/A	N/A
10.	Qualified/ disqualified	Qualified	Qualified


(A. Shahid Ali)
D.A.O (District Central)
Member / Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit – KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Ghulam Muhammad Hub)
S.E (District Central-B)
Member


(Saifuddin)
Director (Design & Estimate)
Convener

NIT No. SPPRA Serial No.35571

Method of Procurement: Single Stage Single Envelope.

Name of Work: WORK OF RECTIFIED OF CHOCKED / RUSTED A.C & C.I PIPE AT SHARIFABAD BLOCK NO-1 AND COMMERCIAL AREA BLOCK-5 FOR RE-LAYING FOR IMPROVEMENT OF WATER SUPPLY SYSTEM AND REPLACEMENT OF DAMAGED PORTION IN LIAQUATABAD TOWN ✓

MINUTES OF BID OPENING MEETING.


A meeting of the procurement committee of this department was held on 28-12-2017 for opening the bids received in respect of subject NIT till deadlines of submission. The meeting was attended by all / following members of the procurement committee and the representative of bidders. **(Attendance sheet is enclosed).**


2. Two bidders submitted their bids till the deadline of submission.
 - i. M/s. Trust Construction Co.
 - ii. M/s. S.O.H Construction Co.
3. The bids were opened at 3:00 p.m in the presence of the above mentioned participants and the rates quoted by bidders were read aloud and encircled by Chairman of the Procurement Committee.


S. No	Name of Firm	Quoted Price	Amount of Bid Security	Pay Order No. / Date
01	M/s.Trust Construction Co.	Rs.9,94,823/-	Rs.20,100/-	P.O # 18281513 dt:19-09-2017 from HBL Nazimabad Branch Karachi
02	M/s.S.O.H Construction Co.	Rs.10,04,910/-	Rs.20,100/-	P.O # 18281889 dt:23-11-2017 from HBL Nazimabad Branch Karachi


4. The bids do not contain any cutting or over-writing.
5. The committee shall examine all the bids as per the qualification / eligibility criteria provided in the bidding document and verify the documents and bid security submitted by the bidders (if required).


The meeting ended with the vote of thanks to and from the chair.


(Arshad Ali)
D.A.O (District Central)
Member / Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit – KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Ghulam Muhammad Hub)
S.E (District Central-B)
Member


(Saifuddin)
Director (Design & Estimate)
Convener



KARACHI WATER & SEWERAGE BOARD

OFFICE OF THE DIRECTOR (DESIGN & ESTIMATE)

BID EVALUATION REPORT

1	Name of Procuring Agency:	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No:	SPPRA Serial No.35571 I.D No. _____
3	Tender Description/Name of Work/Item:	WORK OF RECTIFIED OF CHOKED / RUSTED A.C & C.I PIPE AT SHARIFABAD BLOCK NO-1 AND COMMERCIAL AREA BLOCK-5 FOR RE-LAYING FOR IMPROVEMENT OF WATER SUPPLY SYSTEM AND REPLACEMENT OF DAMAGED PORTION IN LIAQUATABAD TOWN
4	Method of Procurement:	Single Stage (One Envelop)
5	Tender Published:	Through SPPRA Web Site
6	Total Bid Documents Sold:	2 Nos
7	Total Bid Received:	2 Nos
8	Technical Bid Opening Date (if applicable):	N/A
9	No. of Bid Technically Qualified (if applicable)	N/A
10	Bid (s) Rejected:	NIL
11	Financial Bid Opening Date:	28-12-2017

12 BID EVALUATION REPORT

MR. Faisal R.D.
D. check

S#	Name of Firm / Bidder	COST OFFERED BY THE BIDDER	RANKING IN TERMS OF COST	COMPARISON WITH ESTIMATED COST	REASON FOR ACCEPTANCE / REJECTION	REMARKS
1	M/s.Trust Construction Co.	Rs.9,94,824/-	1 st Lowest	@0.045% Below	Pay Order and required documents are available. P.O # 18281513 dt:19-09-2017 Rs.20,100/- from HBL Nazimabad Branch Karachi	Substantially Responsive
2	M/s.S.O.H Construction Co.	Rs.10,04,911/-	2 nd Lowest	@0.969% Above	Pay Order and required documents are available. P.O # 18281889 dt:23-11-2017 Rs.20,100/- from HBL Nazimabad Branch Karachi	Substantially Responsive

The all concerned bidders are being informed accordingly.

The E.E Concerned for compliance of Rule-45 of SPPRA 2010 **M/s.Trust Construction Co.** declared as the lowest responsive bidder by the Committee and recommended for sanction from Competent Authority.

(Arshad Ali)
D.A.O (District Central)
Member / Secretary

(Ghulam Muhammad Hub)
S.E (District Central-B)
Member

(Saif-ul-Haque)
Additional Director Internal
Audit – KMC Member

(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member

(Saifuddin)
Director (Design & Estimate)
Convener

COMPARATIVE STATEMENT

Name of Work: WORK OF RECTIFIED OF CHOKED / RUSTED A.C & C.I PIPE AT SHARIFABAD BLOCK NO-1 AND COMMERCIAL AREA BLOCK-5 FOR RE-LAYING FOR IMPROVEMENT OF WATER SUPPLY SYSTEM AND REPLACEMENT OF DAMAGED PORTION IN LIAQUATABAD TOWN

Item No	Description of Work	Estimated Cost				M/s.Trust Construction Co.		M/s.S.O.H Construction Co.		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
1	Dismantling and removing road metalling	10000.00	Cft	605.00	%Cft	60,500.00	610.00	61,000.00	615.00	61,500.00
2	Excavation for pipe line in trenches and pits in all kind of soils of murum i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by Engineer Incharge providing fence guards, lights, flags sand temporary crossing for non-vehicular traffic wherever required lift upto 5 ft (1.52 m) and lead upto one chain (30.5m).	49471.23	Cft	4650.00	%0Cft	230,041.22	4700.00	232,514.78	4720.00	233,504.21
3	Labour taken for taking out existing pipe from trenches than cleaning of pies and re-laying of pipes after cleaning. (i) Labour for taking out	40.00	Nos	250.00	Each	10,000.00	260.00	10,400.00	265.00	10,600.00
	(ii) Labour for cleaning	40.00	Nos	250.00	Each	10,000.00	260.00	10,400.00	265.00	10,600.00
	(iii) Labour for re-laying	40.00	Nos	250.00	Each	10,000.00	260.00	10,400.00	265.00	10,600.00
	(iv) Fitter	20.00	Nos	400.00	Each	8,000.00	410.00	8,200.00	420.00	8,400.00
4	Providing Laying & Fixing in trenches i/c fitting jointing and testing etc. complete in all respect the high density Polyethylene P.E pipes (HDPE-100) for W/S conforming ISO 4427 DIN-8074-8075 B.S 3580 & PSI 3051. 90 mm	500.00	Rft	148.00	P/Rft	74,000.00	150.00	75,000.00	152.00	76,000.00
	160 mm	100.00	Rft	440.00	P/Rft	44,000.00	445.00	44,500.00	447.00	44,700.00
5	C.I Sluice Valve heavy pattern (Test Pressure 21.0 Kg/sq.com or 300 lb/sq.inch) (Imported) 6" Dia	2.00	Nos	9360.00	Each	18,720.00	9000.00	18,000.00	9150.00	18,300.00
6	Fixing of sluice valve with 2 cast iron tail pieces one end flanged & other with socket i/c the cost of nut, bolts & rubber packing, labour etc complete 6" dia	2.00	Nos	1886.00	Each	3,772.00	1800.00	3,600.00	1900.00	3,800.00

Qureshi
29/12/17

[Signature]

Us.

[Signature]

Name of Work: WORK OF RECTIFIED OF CHOKED / RUSTED A.C & C.I PIPE AT SHARIFABAD BLOCK NO-1 AND COMMERCIAL AREA BLOCK-5 FOR RE-LAYING FOR IMPROVEMENT OF WATER SUPPLY SYSTEM AND REPLACEMENT OF DAMAGED PORTION IN LIAQUATABAD TOWN

Item No	Description of Work	Estimated Cost				M/s.Trust Construction Co.		M/s.S.O.H Construction Co.		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
7	Construction of C.C. block masonry chamber of size 4'x4'x4' inside with 24" x 24" C.I cover & frame Weight 65 kg fixed in RCC Slab 1:2:4: 6" thick with steel 1/2" dia bars 6" C/C bend up both way, 12" inch thick C:C: 1:3:6 block masonry 6" inch C.C 1:4:8 in foundation, 2" thick C.C 1:2:4 flooring, 1/2" thick cement plaster i/c P/F M.S footrest 5/8" bars at every 2'.0" feet deep i/c curing watering excavation refilling and disposal of surplus earth complete. 4'x4'x4'	1.00	No	28357.00	Each	28,357.00	25000.00	25,000.00	26000.00	26,000.00
8	Full hire charges of pumping set per day i/c of wages of driver and assistant fuel or electric energy platform for placing the pump etc at lower depth with suction and delivery pipes for pumping out water found at various depth from trenches including the cost of erection and dismantling after completion of the job. Hire charges of pumping set upto 10 HP pumping out water from 10 ft deep trench	40.00	Days	1500.00	P/Day	60,000.00	1450.00	58,000.00	1470.00	58,800.00
9	Repair of leakages of joints (External Vatta) on PRCC Pipe line. It includes the cost of excavation, labour, sealing material, gunny bags, de-watering and refilling of the excavation stuff etc. complete. 12" Dia	10.00	Nos	9716.00	Each	97,160.00	9700.00	97,000.00	9800.00	98,000.00
	15" Dia	10.00	Nos	10729.00	Each	107,290.00	10800.00	108,000.00	11000.00	110,000.00
	18" Dia	7.00	Nos	13841.00	Each	96,887.00	14000.00	98,000.00	14150.00	99,050.00
10	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete.	49471.23	Cft	2760.00	%0Cft	136,540.59	2725.00	134,809.10	2730.00	135,056.46
TOTAL QUOTED / CORRECTED COST						995,268		994,824		1,004,911

(Ashad Ali)
D.A.O. (Distt. Central)
Member / Secretary

(Saif-ul-Haque)
Addl. Director Internal Audit
KMC - Member

(Maqsood Ahmed Shaikh)
Superintending Engineer (K.M.C)
Member

(Ghulam Muhammad Hub)
S.E (District Central-B)
Member

(Saifuddin)
Director (Design & Estimate)
Convener

29.12.17