



# KARACHI WATER & SEWERAGE BOARD

## OFFICE OF THE DIRECTOR (DESIGN & ESTIMATE)

### BID EVALUATION REPORT

|    |  |   |
|----|--|---|
| 1  | Name of Procuring Agency:                        | KARACHI WATER & SEWERAGE BOARD  |
| 2  | Tender Reference No:                             | KWSB/DPR/36/2018 published in daily "Ummat", "Jasarat".<br>"Business Recorder" & "Soabh" dt:08-02-2018.<br>SPPRA Serial No.36738 I.D No.  |
| 3  | Tender Description/Name of Work/Item:            | REPLACEMENT OF 8", 6" AND 4" DIA WATER LINE BY P/L 110 MM & 160 MM & 200 MM P.E WATER LINES IN NAWA LANE, REXER LANE, CHAKIWARA, SIDU LANE, OLD KALRI, NAWABAD AREA FOR THE IMPROVEMENT OF WATER SUPPLY IN ADJACENT AREA LYARI TOWN (WATER) KW&SB |
| 4  | Method of Procurement:                           | Single Stage (One Envelop)  |
| 5  | Tender Published:                                | Through Press / SPPRA Web Site  |
| 6  | Total Bid Documents Sold:                        | 4 Nos   |
| 7  | Total Bid Received:                              | 4 Nos   |
| 8  | Technical Bid Opening Date (if applicable):      | N/A   |
| 9  | No. of Bid Technically Qualified (if applicable) | N/A   |
| 10 | Bid (s) Rejected:                                | NIL   |
| 11 | Financial Bid Opening Date:                      | 05-03-2018  |

### 12 BID EVALUATION REPORT

| S # | Name of Firm / Bidder     | COST OFFERED BY THE BIDDER | RANKING IN TERMS OF COST | COMPARISON WITH ESTIMATED COST | REASON FOR ACCEPTANCE / REJECTION   | REMARKS                  |
|-----|---------------------------|----------------------------|--------------------------|--------------------------------|---|--------------------------|
| 1.  | M/s.Sanaullah Enterprises | Rs.14,89,043/-             | 1 <sup>st</sup> Lowest   | @13.823% Below                 | Pay order and required documents are attached. P.O # 19525122 dated:18-12-2017 Rs.34,500/-from HBL Taimuria Market Branch Karachi   | Substantially Responsive |
| 2.  | M/s.Sadrudin Mandokhail.  | Rs.15,70,500/-             | 2 <sup>nd</sup> Lowest   | @9.109% Below                  | Pay order and required documents are attached. P.O#14330119 dated:26-02-2018 Rs.26,500/- & P.O#14330167 dated:05-02-2018 Rs.5,000/- from UBL Gulshan-e-Zubaida Branch Karachi Total Rs.31,500/- | Substantially Responsive |
| 3.  | M/s.Koh-e-Moor & Co.      | Rs.17,27,185/-             | 3 <sup>rd</sup> Lowest   | @0.014% Below                  | Pay order and required documents are attached. P.O # 19526210 dated:12-02-2018 Rs.35,000/-from HBL Taimuria Market Branch Karachi   | Substantially Responsive |
| 4.  | M/s.Noor Rehman & Bros    | Rs.17,58,035/-             | 4 <sup>th</sup> Lowest   | @1.744% Above                  | Pay order and required documents are attached. P.O # 12054874 dated:27-12-2017 Rs.36,000/-from UBL Manghopir Branch Karachi   | Substantially Responsive |

The all concerned bidders are being informed accordingly.

The E.E Concerned for compliance of Rule-45 of SPPRA 2010 **M/s.Sanaullah Enterprises** declared as the lowest responsive bidder by the Committee and recommended for sanction from Competent Authority.

(Nadeem Ahmed Khan)  
D.A.O (Dist. South-A)  
Member / Secretary

(Saif-ul-Haque)  
Additional Director Internal  
Audit – KMC Member

(Maqsood Ahmed Shaikh)  
Superintending Engineer (KMC)  
Member

(Muhammad Aslam Awan)  
S.E (District South-A)  
Member

(Munir Ahmed Bhatti)  
Director (Design & Estimate)  
Convener

## COMPARATIVE STATEMENT

**Name of Work: REPLACEMENT OF 8", 6" AND 4" DIA WATER LINE BY P/L 110 MM & 160 MM & 200 MM P.E WATER LINES IN NAWA LANE, REXER LANE, CHAKIWARA, SIDU LANE, OLD KALRI, NAWABAD AREA FOR THE IMPROVEMENT OF WATER SUPPLY IN ADJACENT AREA LYARI TOWN (WATER) KW&SB**

| Item No | Description of Work  | Estimated Cost |      |         |        | M/s.Sanaullah Enterprises |         | M/s.Sadrudin Mandokhail |         | M/s.Koh-e-Moor & Co. |         | M/s.Noor Rehman & Brothers |         |            |
|---------|--|----------------|------|---------|--------|---------------------------|---------|-------------------------|---------|----------------------|---------|----------------------------|---------|------------|
|         |  | Quantity       | Rate | Per     | Amount | Rate                      | Amount  | Rate                    | Amount  | Rate                 | Amount  | Rate                       | Amount  |            |
| 1       | Dismantling and removing road metalling etc.   | 3250.00        | Cft  | 605.00  | %Cft   | 19,662.50                 | 605.00  | 19,662.50               | 200.00  | 6,500.00             | 605.00  | 19,662.50                  | 620.00  | 20,150.00  |
| 2       | Dismantling and removing cement concrete plain 1:4:8   | 2750.00        | Cft  | 1663.75 | %Cft   | 45,753.13                 | 1600.00 | 44,000.00               | 200.00  | 5,500.00             | 1663.00 | 45,732.50                  | 1710.00 | 47,025.00  |
| 3       | Excavation for pipe line in trenches and pits in all kind of soils of murum i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by Engineer Incharge providing fence guards, lights, flags sand temporary crossing for non-vehicular traffic wherever required lift upto 5 ft (1.52 m) and lead upto one chain (30.5m). upto 0' to 5' Ft | 27000.00       | Cft  | 4650.00 | %0Cft  | 125,550.00                | 4600.00 | 124,200.00              | 4000.00 | 108,000.00           | 4650.00 | 125,550.00                 | 4780.00 | 129,060.00 |
|         | upto 5' to 8' ft   | 6000.00        | Cft  | 5200.00 | %0Cft  | 31,200.00                 | 5000.00 | 30,000.00               | 2000.00 | 12,000.00            | 5200.00 | 31,200.00                  | 5350.00 | 32,100.00  |
| 4       | Full hire charges of pumping set per day i/c of wages of driver and assistant fuel or electric energy platform for placing the pump etc at lower depth with suction and delivery pipes for pumping out water found at various depth from trenches including the cost of erection and dismantling after completion of the job. Hire charges of pumping set upto 10 HP pumping out water from 10 ft deep trench.   | 28.00          | Days | 1500.00 | P/Day  | 42,000.00                 | 1500.00 | 42,000.00               | 500.00  | 14,000.00            | 1500.00 | 42,000.00                  | 1550.00 | 43,400.00  |

**Name of Work: REPLACEMENT OF 8", 6" AND 4" DIA WATER LINE BY P/L 110 MM & 160 MM & 200 MM P.E WATER LINES IN NAWA LANE, REXER LANE, CHAKIWARA, SIDU LANE, OLD KALRI, NAWABAD AREA FOR THE IMPROVEMENT OF WATER SUPPLY IN ADJACENT AREA LYARI TOWN (WATER) KW&SB**

| Item No | Description of Work  | Estimated Cost |      |          |        | M/s.Sanaullah Enterprises |          | M/s.Sadrudin Mandokhail |          | M/s.Koh-e-Moor & Co. |          | M/s.Noor Rehman & Brothers |          |            |
|---------|--|----------------|------|----------|--------|---------------------------|----------|-------------------------|----------|----------------------|----------|----------------------------|----------|------------|
|         |  | Quantity       | Rate | Per      | Amount | Rate                      | Amount   | Rate                    | Amount   | Rate                 | Amount   | Rate                       | Amount   |            |
| 5       | Construction of Block Masonry chamber size 6'x6'x6' inside dimation with 24"x24" C.I Cover and frame weight 65 Kg fix in RCC 1:2:4 slab 6" thick with steel 1/2" dia tor main bars @6" C/C bentup 1/4" dia 8" C.C distribution bars B/M wall set 1:6 cm 6" thick C.C 1:4:8 in foundation 2" thick CC 1:2;4 flooring 1/2" thick 1-0 to al in side wall surfaced top & bottom slab outer side wall surface 1-0 deep upto roof slab i/c M.S footrest 5/8" dia bars at every 2-0 deep i/c curing de-watering excavation refilling & disposal of surplus earth etc. | 1.00           | No   | 55923.00 | Each   | 55,923.00                 | 50000.00 | 50,000.00               | 10000.00 | 10,000.00            | 55900.00 | 55,900.00                  | 57500.00 | 57,500.00  |
| 6       | P/F G.I Pipe and Specials i/c fixing, cutting, & fitting complete with i/c the cost of cutting trench upto 2 1/2' deep re fillig watering ramming and disposal of surpluses earth within one chain and paiintign 2 coats of bitumen paint to pieps & special after cleaning & lasso in lath soaked and mix phalt composition wapped tightly round pipe and testing to a presshre head of 200'ft and handling 3/4" dia.   | 200.00         | Rft  | 86.36    | P/Rft  | 17,272.00                 | 70.00    | 14,000.00               | 50.00    | 10,000.00            | 86.00    | 17,200.00                  | 90.00    | 18,000.00  |
| 7       | Providing & Laying and Jointing of Polyethylene pipe in trench i/c fitting jointing and testing etc. complete in all respect the high density Polyethylene P.E pipes (HDPE-100) for W/S conforming ISO 4427/DIN-8074/8075 B.S 3580 & PSI 3051 (PN-10). 110 MM  | 1100.00        | Rft  | 268.00   | P/Rft  | 294,800.00                | 200.00   | 220,000.00              | 380.00   | 418,000.00           | 268.00   | 294,800.00                 | 270.00   | 297,000.00 |
|         | 160 MM   | 800.00         | Rft  | 530.00   | P/Rft  | 424,000.00                | 405.00   | 324,000.00              | 500.00   | 400,000.00           | 530.00   | 424,000.00                 | 535.00   | 428,000.00 |
|         | 200 MM   | 500.00         | Rft  | 833.00   | P/Rft  | 416,500.00                | 800.00   | 400,000.00              | 800.00   | 400,000.00           | 833.00   | 416,500.00                 | 850.00   | 425,000.00 |

**Name of Work: REPLACEMENT OF 8", 6" AND 4" DIA WATER LINE BY P/L 110 MM & 160 MM & 200 MM P.E WATER LINES IN NAWA LANE, REXER LANE, CHAKIWARA, SIDU LANE, OLD KALRI, NAWABAD AREA FOR THE IMPROVEMENT OF WATER SUPPLY IN ADJACENT AREA LYARI TOWN (WATER) KW&SB**

| Item No | Description of Work   | Estimated Cost |      |          |        | M/s.Sanaullah Enterprises |          | M/s.Sadrudin Mandokhail |         | M/s.Koh-e-Moor & Co. |          | M/s.Noor Rehman & Brothers |          |           |
|---------|---|----------------|------|----------|--------|---------------------------|----------|-------------------------|---------|----------------------|----------|----------------------------|----------|-----------|
|         |   | Quantity       | Rate | Per      | Amount | Rate                      | Amount   | Rate                    | Amount  | Rate                 | Amount   | Rate                       | Amount   |           |
| 8       | Manufacturing, supplying & fixing black steel M.S pipe made out of M.S sheet conforming API 5L grade X-42 & externally asphalt coated with fiber galss 5mm thick & internally C.C lining 8mm thick (AWWA Specification) i/c laying jointing with helical welding in trenches i/c cost of bends of any degree & testing with water specified pressure for different dia of pipes 5.6 mm thick 8" dia   | 20.00          | Rft  | 1648.37  | P/Rft  | 32,967.40                 | 1600.00  | 32,000.00               | 2500.00 | 50,000.00            | 1648.00  | 32,960.00                  | 1690.00  | 33,800.00 |
| 9       | P/F M.S Split Collar tee on PRCC Pipe of different sizes having width as mentioned against each item to suit pipe the size of connection fabricated with 3/8" thick M.S plate excluding the cost of Neck its includes the cost of 3/4" thick M.S flanges with a total weight as mentioned against each item. It also includes the cost of Nuts & Bolts, rubber packing, labour and sealing material and all the tools and plants 12" x 12" (Weight 104.86 Kg) | 2.00           | Nos  | 19037.00 | Each   | 38,074.00                 | 15000.00 | 30,000.00               | 3000.00 | 6,000.00             | 19000.00 | 38,000.00                  | 19500.00 | 39,000.00 |
| 10      | P/F M.S Split Collar 9" wide on AC pipe fabricated with 1/4" thick M.S plate having dimension and weight as mentioned against each item i/c or cost of labour and sealing material cost of 4 Nos 1/4" thick flanges Nuts & bolts rubber packing and sealing etc. (Weight 08.68 Kg) 04"dia   | 2.00           | Nos  | 1835.00  | Each   | 3,670.00                  | 1500.00  | 3,000.00                | 2000.00 | 4,000.00             | 1800.00  | 3,600.00                   | 1900.00  | 3,800.00  |
|         | (Weight 10.48 Kg) 06"dia  | 2.00           | Nos  | 2129.00  | Each   | 4,258.00                  | 1800.00  | 3,600.00                | 2000.00 | 4,000.00             | 2100.00  | 4,200.00                   | 2200.00  | 4,400.00  |
|         | (Weight 12.31 Kg) 08"dia  | 1.00           | No   | 2510.00  | Each   | 2,510.00                  | 2000.00  | 2,000.00                | 1000.00 | 1,000.00             | 2500.00  | 2,500.00                   | 2600.00  | 2,600.00  |



**Name of Work: REPLACEMENT OF 8", 6" AND 4" DIA WATER LINE BY P/L 110 MM & 160 MM & 200 MM P.E WATER LINES IN NAWA LANE, REXER LANE, CHAKIWARA, SIDU LANE, OLD KALRI, NAWABAD AREA FOR THE IMPROVEMENT OF WATER SUPPLY IN ADJACENT AREA LYARI TOWN (WATER) KW&SB**

| Item No.                             | Description of Work   | Estimated Cost |      |          |        | M/s.Sanaullah Enterprises |                  | M/s.Sadrudin Mandokhail |                  | M/s.Koh-e-Moor & Co. |          | M/s.Noor Rehman & Brothers |          |           |
|--------------------------------------|---|----------------|------|----------|--------|---------------------------|------------------|-------------------------|------------------|----------------------|----------|----------------------------|----------|-----------|
|                                      |   | Quantity       | Rate | Per      | Amount | Rate                      | Amount           | Rate                    | Amount           | Rate                 | Amount   | Rate                       | Amount   |           |
| 11                                   | P/F M.S tail piece (DHOLKI) on A.C pipe fabricated with 1/2" thick M.S plate having dimension and weight as mentioned against each item it i/c the cost of sealing material (Wt. 6.290 Kg)                                    | 3.00           | Nos  | 1098.00  | Each   | 3,294.00                  | 1000.00          | 3,000.00                | 2000.00          | 6,000.00             | 1100.00  | 3,300.00                   | 1100.00  | 3,300.00  |
|                                      | (Wt. 8.410 Kg) 06" dia  | 3.00           | Nos  | 1422.00  | Each   | 4,266.00                  | 1000.00          | 3,000.00                | 2000.00          | 6,000.00             | 1400.00  | 4,200.00                   | 1450.00  | 4,350.00  |
|                                      | (Wt. 12.75 Kg) 08" dia  | 1.00           | No   | 2199.00  | Each   | 2,199.00                  | 1500.00          | 1,500.00                | 1500.00          | 1,500.00             | 2200.00  | 2,200.00                   | 2200.00  | 2,200.00  |
| 12                                   | P/F 0-9" long 1/4" thick M.S Neck to existing M.S Pipe to a split collar tee having a total weight as mentioned against each item. It includes the cost of fabrication and welding to the split collar tee. 04" dia (6.66 Kg) | 3.00           | Nos  | 1229.00  | Each   | 3,687.00                  | 1000.00          | 3,000.00                | 2000.00          | 6,000.00             | 1200.00  | 3,600.00                   | 1250.00  | 3,750.00  |
|                                      | 06" dia (10.90 Kg)  | 3.00           | Nos  | 1984.00  | Each   | 5,952.00                  | 1000.00          | 3,000.00                | 2000.00          | 6,000.00             | 2000.00  | 6,000.00                   | 2000.00  | 6,000.00  |
|                                      | 08" dia (15.75 Kg)  | 1.00           | No   | 2804.00  | Each   | 2,804.00                  | 1500.00          | 1,500.00                | 2000.00          | 2,000.00             | 2800.00  | 2,800.00                   | 3000.00  | 3,000.00  |
| 13                                   | High Density Polyethylene fitting (PE-100) (Per Each) (PN-10) 04" Dia (110 mm)  | 1.00           | No   | 2069.00  | Each   | 2,069.00                  | 1500.00          | 1,500.00                | 3000.00          | 3,000.00             | 2000.00  | 2,000.00                   | 2200.00  | 2,200.00  |
|                                      | 06" dia (160 mm)  | 2.00           | Nos  | 4349.00  | Each   | 8,698.00                  | 3000.00          | 6,000.00                | 3000.00          | 6,000.00             | 4300.00  | 8,600.00                   | 4500.00  | 9,000.00  |
|                                      | 08" dia (200 mm)  | 1.00           | No   | 6788.00  | Each   | 6,788.00                  | 5000.00          | 5,000.00                | 3000.00          | 3,000.00             | 6800.00  | 6,800.00                   | 7000.00  | 7,000.00  |
| 14                                   | Repair of leaking, joints (External vatta) on PRCC pipe of various diameter. It includes the cost of excavation, labour, sealing material gunny bags dewatering & refilling the excaged stuff etc complete. 15" Dia           | 4.00           | Nos  | 10729.00 | Each   | 42,916.00                 | 8000.00          | 32,000.00               | 4000.00          | 16,000.00            | 10700.00 | 42,800.00                  | 11000.00 | 44,000.00 |
| 15                                   | Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete.  | 33000.00       | Cft  | 2760.00  | %Cft   | 91,080.00                 | 2760.00          | 91,080.00               | 2000.00          | 66,000.00            | 2760.00  | 91,080.00                  | 2800.00  | 92,400.00 |
| <b>TOTAL QUOTED / CORRECTED COST</b> |   |                |      |          |        | <b>1,727,893</b>          | <b>1,489,043</b> | <b>1,570,500</b>        | <b>1,727,185</b> | <b>1,758,035</b>     |          |                            |          |           |

(Nadeem Ahmed Khan)  
D.A.O (Distt. South-A)  
Member / Secretary

(Saif-ullah Haque)  
Addl. Director Internal Audit  
KMC - Member

(Maqsood Ahmed Shaikh)  
Superintending Engineer (K.M.C)  
Member

(Muhammad Aslam Awan)  
S.E (District South)-A  
Member

(Munir Ahmed Bhatti)  
Director (Design & Estimate)  
Convener



NIT-Sr. No. **SPPRA Serial No.36738**

Method of Procurement: **Single Stage Single Envelope.**

Name of Work: **REPLACEMENT OF 8", 6" AND 4" DIA WATER LINE BY P/L 110 MM & 160 MM & 200 MM P.E WATER LINES IN NAWA LANE, REXER LANE, CHAKIWARA, SIDU LANE, OLD KALRI, NAWABAD AREA FOR THE IMPROVEMENT OF WATER SUPPLY IN ADJACENT AREA LYARI TOWN (WATER) KW&SB**

**MINUTES OF BID OPENING MEETING.**


A meeting of the procurement committee of this department was held on 05-03-2018 for opening the bids received in respect of subject NIT till deadlines of submission. The meeting was attended by all / following members of the procurement committee and the representative of bidders. (Attendance sheet is enclosed).

2. Four bidders submitted their bids till the deadline of submission.
  - i. M/s. Sanaullah Enterprises
  - ii. M/s.Sadrudin Mandokhail
  - iii. M/s.Koh-e-Moor & Co.
  - iv. M/s.Noor Rehman & Brothers
3. The bids were opened at 2:30 P.M in the presence of the above mentioned participants and the rates quoted by bidders were read aloud and encircled by Chairman of the Procurement Committee.


| S. No | Name of Firm               | Quoted Price   | Amount of Bid Security | Pay Order No. / Date   |
|-------|----------------------------|----------------|------------------------|--|
| 1.    | M/s.Sanaullah Enterprises  | Rs.14,89,042/- | Rs.34,500/-            | P.O # 19525122 dated:18-12-2017 from HBL Taimuria Market Branch Karachi  |
| 2.    | M/s.Sadrudin Mandokhail.   | Rs.15,70,500/- | Rs.31,500/-            | P.O#14330119 dated:26-02-2018 Rs.26,500/- & P.O#14330167 dated:05-02-2018 Rs.5,000/- from UBL Gulshan-e-Zubaida Branch Karachi |
| 3.    | M/s.Koh-e-Moor & Co.       | Rs.17,27,184/- | Rs.35,000/-            | P.O # 19526210 dated:12-02-2018 from HBL Taimuria Market Branch Karachi  |
| 4.    | M/s.Noor Rehman & Brothers | Rs.17,58,035/- | Rs.36,000/-            | P.O # 12054874 dated:27-12-2017 from UBL Manghopir Branch Karachi  |


4. The bids do not contain any cutting or over-writing.
5. The committee shall examine all the bids as per the qualification / eligibility criteria provided in the bidding document and verify the documents and bid security submitted by the bidders (if required).


The meeting ended with the vote of thanks to and from the chair.

  
(Nadeem Ahmed Khan)  
D.A.O (Dist. South-A)  
Member / Secretary

  
(Saif-ul-Haque)  
Additional Director Internal  
Audit – KMC Member

  
(Maqsood Ahmed Shaikh)  
Superintending Engineer (KMC)  
Member

  
(Muhammad Aslam Awan)  
S.E (District South-A)  
Member

  
(Munir Ahmed Bhatti)  
Director (Design & Estimate)  
Convener

**Method and procedure of procurement: Open Competitive Bidding (National/ International Competitive Bidding) (Single Stage–One Envelope)**


Description of work: **REPLACEMENT OF 8", 6" AND 4" DIA WATER LINE BY P/L 110 MM & 160 MM & 200 MM P.E WATER LINES IN NAWA LANE, REXER LANE, CHAKIWARA, SIDU LANE, OLD KALRI, NAWABAD AREA FOR THE IMPROVEMENT OF WATER SUPPLY IN ADJACENT AREA LYARI TOWN (WATER) KW&SB**

Date of Opening: 05-03-2018


**BIDDERS' ELIGIBILITY/ QUALIFICATION REPORT**


Eligibility/ Qualification Criteria:


| S. No. | Eligibility / Qualification Criteria   | Bidders' Name             |                          |                      |                         |
|--------|--|---------------------------|--------------------------|----------------------|-------------------------|
|        |  | M/s.Sanaullah Enterprises | M/s.Sadruddin Mandokhail | M/s.Koh-e-Moor & Co. | M/s.Noor Rehman & Bros. |
| 1.     | Registration with PEC (if applicable)  | N/A                       | N/A                      | N/A                  | N/A                     |
| 2.     | NTN  | Yes                       | Yes                      | Yes                  | Yes                     |
| 3.     | Sales Tax Registration   | N/A                       | N/A                      | N/A                  | N/A                     |
| 4.     | Registration with Sindh Revenue Board (SRB)  | Yes                       | Yes                      | Yes                  | Yes                     |
|        | <b>Qualification Criteria:</b>   |                           |                          |                      |                         |
| 5.     | Minimum three years' experience of relevant field.   | Yes                       | Yes                      | Yes                  | Yes                     |
| 6.     | Turnover of at least last three years  | Yes                       | Yes                      | Yes                  | Yes                     |
| 7.     | Required Bid Security is attached.   | Yes                       | Yes                      | Yes                  | Yes                     |
| 8.     | Bid is signed, named and stamped by the authorized person of the firm along with Authorization letter. | Yes                       | Yes                      | Yes                  | Yes                     |
| 9.     | Any other factor deemed to be relevant by the procuring agency subject to provision of Rule-44         | N/A                       | N/A                      | N/A                  | N/A                     |
| 10.    | Qualified/ disqualified  | Qualified                 | Qualified                | Qualified            | Qualified               |

  
(Nadeem Ahmed Khan)  
D.A.O (Dist. South-A)  
Member / Secretary

  
(Saif-ul-Haque)  
Additional Director Internal  
Audit – KMC Member

  
(Maqsood Ahmed Shaikh)  
Superintending Engineer (KMC)  
Member

  
(Muhammad Aslam Awan)  
S.E (District South-A)  
Member

  
(Munir Ahmed Bhatti)  
Director (Design & Estimate)  
Convener

