

KARACHI WATER & SEWERAGE BOARD

OFFICE OF THE DIRECTOR (DESIGN & ESTIMATE)

BID EVALUATION REPORT


1	Name of Procuring Agency:	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No:	SPPRA Serial No.36291 I.D No.
3	Tender Description/Name of Work/Item:	REPLACEMENT OF 12" DIA & 8" DIA SUNK DOWN SEWERS AT 15-A AND E-MARKET RESIDENTIAL, 80-E, 60-O AND 75-O NEAR CURCH, BLOCK-06, PECHS, UC-07 JAMSHED TOWN (SEWERAGE)-I.
4	Method of Procurement:	Single Stage (One Envelop)
5	Tender Published:	Through SPPRA Web Site
6	Total Bid Documents Sold:	2 Nos
7	Total Bid Received:	2 Nos
8	Technical Bid Opening Date (if applicable):	N/A
9	No. of Bid Technically Qualified (if applicable)	N/A
10	Bid (s) Rejected:	NIL
11	Financial Bid Opening Date:	07-02-2018

17 BID EVALUATION REPORT

S#	Name of Firm / Bidder	COST OFFERED BY THE BIDDER	RANKING IN TERMS OF COST	COMPARISON WITH ESTIMATED COST	REASON FOR ACCEPTANCE / REJECTION	REMARKS
1	M/s.Yasin Enterprises	Rs.9,80,492/-	1 st Lowest	@0.083% Below	Pay Order and required documents are attached. P.O # 50617208 dt:09-01-2018 Rs.20,000/-from Summit Bank, Gulshan-e-Iqbal (2) Branch Karachi	Substantially Responsive
2	M/s. Serena Enterprises	Rs.9,92,262/-	2 nd Lowest	@1.116% Above	Pay Order and required documents are attached. P.O # 04120657 dt:13-11-2017 Rs 20,500/-from Bank Al Habib Ltd Gulshan Block 2 Branch Karachi	Substantially Responsive

The all concerned bidders are being informed accordingly.

The E.E Concerned for compliance of Rule-15 of SPPRA 2010 M/s.Yasin Enterprises declared as the lowest responsive bidder by the Committee and recommended for sanction from Competent Authority.


(S.M. Rizwan Rizvi)
D.A.O (District East)
Member / Secretary


(Saif-ul-Ilaque)
Additional Director Internal
Audit – KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Roshin Din Memon)
S.E (District East-A)
Member


(Munir Ahmed Bhatti)
Director (Design & Estimate)
Convener

NIT No. SPPRA Serial No.36291

Method and procedure of procurement: Open Competitive Bidding (National/ International Competitive Bidding) (Single Stage-One Envelope)


Description of work: REPLACEMENT OF 12" DIA & 8" DIA SUNK DOWN SEWERS AT 15-A AND E-MARKET RESIDENTIAL, 80-E, 60-O AND 75-O NEAR CURCH, BLOCK-06, PECHS, UC-07 JAMSHED TOWN (SEWERAGE)-I.

Date of Opening: 07-02-2018

BIDDERS' ELIGIBILITY/ QUALIFICATION REPORT

Eligibility/ Qualification Criteria:

S. No.	Eligibility / Qualification Criteria	Bidders' Name	
		M/s. Yasin Enterprises	M/s. Serena Enterprises
1.	Registration with PEC (if applicable)	N/A	N/A
2.	NTN	Yes	Yes
3.	Sales Tax Registration (FBR)	N/A	N/A
4.	Registration with Sindh Revenue Board (SRB)	Yes	Yes
Qualification Criteria:			
5.	Minimum three years' experience of relevant field.	Yes	Yes
6.	Turnover of at least last three years	Yes	Yes
7.	Required Bid Security is attached.	Yes	Yes
8.	Bid is signed, named and stamped by the authorized person of the firm along with Authorization letter.	Yes	Yes
9.	Any other factor deemed to be relevant by the procuring agency subject to provision of Rule-44	N/A	N/A
10.	Qualified/ disqualified	Qualified	Qualified


(S.M. Rizwan Rizvi)
D.A.O (District East)
Member / Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit - KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Roshin Din Memon)
S.E (District East-A)
Member


(Munir Ahmed Bhatti)
Director (Design & Estimate)
Convener

NIT No. SPPRA Serial No. 36291

Method of Procurement: Single Stage Single Envelope.

Name of Work: REPLACEMENT OF 12" DIA & 8" DIA SUNK DOWN SEWERS AT 15-A AND E-MARKET RESIDENTIAL, 80-E, 60-O AND 75-O NEAR CURCH, BLOCK-06, PECHS, UC-07 JAMSHED TOWN (SEWERAGE)-I.

MINUTES OF BID OPENING MEETING.


A meeting of the procurement committee of this department was held on 07-02-2018 for opening the bids received in respect of subject NIT till deadlines of submission. The meeting was attended by all / following members of the procurement committee and the representative of bidders. (Attendance sheet is enclosed).

2. Two bidders submitted their bids till the deadline of submission.
 - i. M/s. Yasin Enterprises
 - ii. M/s. Safer Enterprises
3. The bids were opened at 2:30 P.M in the presence of the above mentioned participants and the rates quoted by bidders were read aloud and encircled by Chairman of the Procurement Committee.


S. No	Name of Firm	Quoted Price	Amount of Bid Security	Pay Order No. / Date
01	M/s. Yasin Enterprises	Rs.9,80,491/-	Rs.20,000/-	P.O # 50617208 dt:09-01-2018 from Summit Bank, Gulshan-e-Iqbal (2) Branch Karachi
02	M/s. Serena Enterprises	Rs.9,92,261/-	Rs.20,500/-	P.O # 04120657 dt:13-11-2017 from Bank Al Habib Ltd Gulshan Block 2 Branch Karachi

4. The bids do not contain any cutting or over-writing.
5. The committee shall examine all the bids as per the qualification / eligibility criteria provided in the bidding document and verify the documents and bid security submitted by the bidders (if required).

The meeting ended with the vote of thanks to and from the chair.


(S.M. Rizwan)
D.A.O (District East)
Member / Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit - KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member



(Roshin Din Memon)
S.E. (District East-A)
Member


(Munir Ahmed Bhatti)
Director (Design & Estimate)
Convener

COMPARATIVE STATEMENT

**Name of Work: REPLACEMENT OF 12" DIA & 8" DIA SUNK DOWN SEWERS AT 15-A AND E-MARKET
RESIDENTIAL, 80-E, 60-O AND 75-O NEAR CURCH, BLOCK-06, PECHS, UC-07 JAMSHED TOWN (SEWERAGE)-I.**

Item No	Description of Work	Estimated Cost				M/s.Yasin Enterprises		M/s.Serena Enterprises		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
1	Dismantling and removing road metalling	3727.50	Cft	605.00	%Cft	22,551.38	604.50	22,532.74	607.00	22,625.93
2	Excavation for pipe line in trenches and pits in all kind of soi of murum i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by Engineer Incharge providing fence guards, lights, flags sand temporary crossing for non-vehicular traffic wherever required lift upto 5 ft (1.52 m) and lead upto one chain (30.5m). i) Lift 00' - 05'ft	14910.00	Cft	4650.00	%0Cft	69,331.50	4649.00	69,316.59	4655.00	69,406.05
	ii) Lift 05' - 08'	5220.00	Cft	5200.00	%0Cft	27,144.00	5199.00	27,138.78	6205.00	32,390.10
3	Providing Manhole 4' feet inside without manhole cover with C.I Frame 15 Kg 5 feet clear depth 1:2:4 cast in situ with in 9" thick wall, 1:4:8: C.C in 6ft dia and 6" inch thick in foundation 1:2:4 C.C in benching 1/2" thick cement plaster with 1:3 cement mortar on all inside wall surfaces of channel and benching i/c making required nos of main and branch channels, 3/4" dia M.S Foot rest @12" c/c i/c cost of excavation in all kinds of soil, backfilling and disposal of excavated stuff etc complete as per design and instruction of Engineer Incharge.	13.00	Nos	14529.29	Each	188,880.77	14529.00	188,877.00	14600.00	189,800.00
3(i)	Add / deduct per ft depth	28.75	(+)Ft	2538.62	P/ft	72,985.33	2538.00	72,967.50	2545.00	73,168.75
4	Full hire charges of pumping set per day i/c of wages of driver and assistant fuel or electric energy platform for placing the pump etc at lower depth with suction and delivery pipes for pumping out water found at various depth from trenches including the cost of erection and dismantling after completion of the job. Hire charges of pumping set upto 10 HP pumping out water from 10 ft deep trench	18.00	Days	1500.00	P/Day	27,000.00	1490.00	26,820.00	1510.00	27,180.00






**Name of Work: REPLACEMENT OF 12" DIA & 8" DIA SUNK DOWN SEWERS AT 15-A AND E-MARKET
RESIDENTIAL, 80-E, 60-O AND 75-O NEAR CURCH, BLOCK-06, PECHS, UC-07 JAMSHED TOWN (SEWERAGE)-I.**


Item No	Description of Work	Estimated Cost				M/s.Yasin Enterprises		M/s.Serena Enterprises		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
5	Providing & Laying of RCC Pipes with Rubber Ring Joint and fitting in trench including cutting, fitting, jointing with rubber ring i/c testing with water to specified pressure.i. 12" Dia	580.00	Rft	367.00	P/Rft	212,860.00	366.50	212,570.00	370.00	214,600.00
	ii. 08" Dia	795.00	Rft	206.00	P/Rft	163,770.00	205.75	163,571.25	208.00	165,360.00
6	Manufacturing and supplying of RCC Manhole covers cast in situ 1:2:4 concrete ratio 3" deep at centre, reinforced with 1/2" dia tor steel bars @ 4" C/C welded to a 3/16" thick 2" wide M.S plate two hook of 3/8" dia tor bar including compacting i/c cutting and transportation with in 10 miles. 21" dia.	25.00	Nos	913.63	Each	22,840.75	913.00	22,825.00	920.00	23,000.00
7	Making connection with the existing manhole including the cost of cutting hole in wall, making them good in C.C 1:2:4 and making the required channel etc. complete	10.00	Nos	180.00	Each	1,800.00	179.00	1,790.00	182.00	1,820.00
8	Manufacturing and supplying of RCC Ring Slab of 21" dia (inside) and 36" dia outside 7 1/2" width and 6" thick i/c 3/8" dia tor steel bars two concentric rings with 3/8" dia 8 Nos cross linked bars welded and two sunk type hooks, casted in 1:1 1/2:3 concrete with embedded 15 Kg C.I Frame in perfect position i/c transportation charges for an average lead of 20 Km per trip from casting yard to town office. (A minimum of 25 slabs per trip will be transported.	25.00	Nos	1906.60	Each	47,665.00	1906.00	47,650.00	1910.00	47,750.00
9	Shifting to the site and fixing 36" dia ring slab in perfect position on damaged manhole i/c cutting of the position of damaged manhole in proper shape laying in layer of C.M in 2" thickness and disposal of the debris.	25.00	Nos	563.09	Each	14,077.25	563.00	14,075.00	570.00	14,250.00
10	Sand Haro or any other source sand of same modules of the fineness (Hill Sand)	1740.00	Cft	2425.00	%Cft	42,195.00	2424.00	42,177.60	2430.00	42,282.00


**Name of Work: REPLACEMENT OF 12" DIA & 8" DIA SUNK DOWN SEWERS AT 15-A AND E-MARKET
RESIDENTIAL, 80-E, 60-O AND 75-O NEAR CURCH, BLOCK-06, PECHS, UC-07 JAMSHED TOWN (SEWERAGE)-I.**


Item No	Description of Work	Estimated Cost				M/s.Yasin Enterprises		M/s.Serena Enterprises		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
11	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete.	17244.48	Cft	2760.00	%Cft	47,594.76	2759.00	47,577.52	2775.00	47,853.43
12	Carriage of 100 Cft / 5 Tons of all materials like stonne aggregate, spawl, coal, lime, surkhi etc B.G Rail fastening points and crossing bridges, Girders, pipes sheet Rail, M.S Bars etc. or 1000 Nos bricks, 10"x 5"x3" or 1000 Nos: tiles, 12" x6"x2" or 150 Cft of timber or 100 Maunds of fuel wood by trucks or any other means owned by the Contractors. <u>Carriage for 05 Miles</u>	2885.52	Cft	714.29	%Cft	20,610.98	714.00	20,602.61	720.00	20,775.74
TOTAL QUOTED / CORRECTED COST						981,307		980,492		992,262


(S.M.Rizwan Rizvi)
D.A.O (Distt. East)
Member / Secretary


(Saif-ul-Haque)
Addl. Director Internal Audit
KMC - Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (K.M.C)
Member


(Roshin Din Memon)
S.E (District East-A)
Member


(Munir Ahmed Bhatti)
Director (Design & Estimate)
Convener

