

NIT Sr. No. SPPRA Serial No.36236

Method and procedure of procurement: Open Competitive Bidding (National/ International Competitive Bidding) (Single Stage–One Envelope)

Description of work: REPLACEMENT OF 24", 18" 12" & 8" DIA SEWERAGE LINE IN TAISER TOWN & DIFFERENT PLACES OF UC-38 DUE TO HEAVY RAIN IN SURJANI GADAP TOWN

Date of Opening: 02-02-2018

**BIDDERS' ELIGIBILITY/ QUALIFICATION REPORT**

Eligibility/ Qualification Criteria:


S. No.	Eligibility / Qualification Criteria	Bidders' Name	
		M/s.Khan Zaman & Brothers	M/s.Usmania Construction Co.
1.	Registration with PEC (if applicable)	N/A	N/A
2.	NTN	Yes	Yes
3.	Sales Tax Registration (FBR)	N/A	N/A
4.	Registration with Sindh Revenue Board (SRB)	Yes	Yes
	<b>Qualification Criteria:</b>		
5.	Minimum three years' experience of relevant field.	Yes	Yes
6.	Turnover of at least last three years	Yes	Yes
7.	Required Bid Security is attached.	Yes	Yes
8.	Bid is signed, named and stamped by the authorized person of the firm along with Authorization letter.	Yes	Yes
9.	Any other factor deemed to be relevant by the procuring agency subject to provision of Rule-44	N/A	N/A
10.	Qualified/ disqualified	Qualified	Qualified



(Muhammad Khalid Khan)  
Accounts Officer (Dist. West)  
Member / Secretary




(Saif-ul-Maque)  
Additional Director Internal  
Audit – KMC Member



(Maqsood Ahmed Shaikh)  
Superintending Engineer (KMC)  
Member



(Owais Malik)  
S.E (District West-A)  
Member



(Munir Ahmed Bhatti)  
Director (Design & Estimate)  
Convener

**Method of Procurement: Single Stage Single Envelope.**

Name of Work: **REPLACEMENT OF 24", 18" 12" & 8" DIA SEWERAGE LINE IN TAISER TOWN & DIFFERENT PLACES OF UC-38 DUE TO HEAVY RAIN IN SURJANI GADAP TOWN**

**MINUTES OF BID OPENING MEETING.**

A meeting of the procurement committee of this department was held on 02-02-2018 for opening the bids received in respect of subject NIT till deadlines of submission. The meeting was attended by all / following members of the procurement committee and the representative of bidders.

**(Attendance sheet is enclosed).**

2. Two bidders submitted their bids till the deadline of submission.
  - i. M/s. Khan Zaman & Brothers
  - ii. M/s. Usmania Construction Co.
3. The bids were opened at 2:30 P.M in the presence of the above mentioned participants and the rates quoted by bidders were read aloud and encircled by Chairman of the Procurement Committee.


S. No	Name of Firm	Quoted Price	Amount of Bid Security	Pay Order No. / Date
01	M/s.Khan Zaman & Brothers	Rs.9,29,266/-	Rs.20,000/-	P.O # AAA 14622380 dt:01-02-2018 from ABL PIB Colony Branch Karachi
02	M/s.Usmania Construction Co.	Rs.9,30,538/-	Rs.20,000/-	P.O # 14347223 dt:01-02-2018 from UBL Civic Centre Branch Karachi

4. The bids do not contain any cutting or over-writing.
5. The committee shall examine all the bids as per the qualification / eligibility criteria provided in the bidding document and verify the documents and bid security submitted by the bidders (if required).


The meeting ended with the vote of thanks to and from the chair.

  
(Muhammad Khalid Khan)  
Accounts Officer (Dist. West)  
Member / Secretary

  
(Saif-ul-Haque)  
Additional Director Internal  
Audit – KMC Member

  
(Maqsood Ahmed Shaikh)  
Superintending Engineer (KMC)  
Member

  
(Owais Malik)  
S.E (District West-A)  
Member

  
(Munir Ahmed Bhati)  
Director (Design & Estimate)  
Convener



# KARACHI WATER & SEWERAGE BOARD

## OFFICE OF THE DIRECTOR (DESIGN & ESTIMATE)

### BID EVALUATION REPORT

1	Name of Procuring Agency:	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No:	SPPRA Serial No.36236 I.D No._____
3	Tender Description/Name of Work/Item:	<b>REPLACEMENT OF 24", 18" 12" &amp; 8" DIA SEWERAGE LINE IN TAISER TOWN &amp; DIFFERENT PLACES OF UC-38 DUE TO HEAVY RAIN IN SURJANI GADAP TOWN</b>
4	Method of Procurement:	Single Stage (One Envelop)
5	Tender Published:	Through SPPRA Web Site
6	Total Bid Documents Sold:	2 Nos
7	Total Bid Received:	2 Nos
8	Technical Bid Opening Date (if applicable):	N/A
9	No. of Bid Technically Qualified (if applicable)	N/A
10	Bid (s) Rejected:	NIL
11	Financial Bid Opening Date:	02-02-2018

### 12 BID EVALUATION REPORT

S#	Name of Firm / Bidder	COST OFFERED BY THE BIDDER	RANKING IN TERMS OF COST	COMPARISON WITH ESTIMATED COST	REASON FOR ACCEPTANCE / REJECTION	REMARKS
1	M/s.Khan Zaman & Brothers	Rs.9,29,268/-	1 <sup>st</sup> Lowest	@0.007% Below	Pay Order and required documents are attached. P.O # AAA 14622380 dt:01-02-2018 Rs.20,000/- from ABL PIB Colony Branch Karachi	Substantially Responsive
2	M/s.Usmania Construction Co.	Rs.9,30,540/-	2 <sup>nd</sup> Lowest	@0.130% Above	Pay Order and required documents are attached. P.O # 14347223 dt:01-02-2018 Rs.20,000/- from UBL Civic Centre Branch Karachi	Substantially Responsive

The all concerned bidders are being informed accordingly.

The E.E Concerned for compliance of Rule-45 of SPPRA 2010 **M/s.Khan Zaman & Brothers** declared as the lowest responsive bidder by the Committee and recommended for sanction from Competent Authority.

(Muhammad Khalid Khan)  
Accounts Officer (Dist. West)  
Member / Secretary

(Saif-ul-Haque)  
Additional Director Internal  
Audit – KMC Member

(Maqsood Ahmed Shaikh)  
Superintending Engineer (KMC)  
Member

(Owais Malik)  
S.E (District West-A)  
Member

(Munir Ahmed Bhatti)  
Director (Design & Estimate)  
Convener

## COMPARATIVE STATEMENT

**Name of Work: REPLACEMENT OF 24", 18" 12" & 8" DIA SEWERAGE LINE IN TAISER TOWN  
& DIFFERENT PLACES OF UC-38 DUE TO HEAVY RAIN IN SURJANI GADAP TOWN**

Item No	Description of Work	Estimated Cost				M/s.Khan Zaman & Brothers		M/s.Usmania Construction Co.		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
1	Excavation for pipe line in trenches and pits in all kind of soil of murum i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by Engineer Incharge providing fence guards, lights, flags sand temporary crossing for non-vehicular traffic wherever required lift upto 5 ft (1.52 m) and lead upto one chain (30.5m). 0' - 5' Depth	12142.50	Cft	4650.00	%0Cft	56,462.63	4650.00	56,462.63	4650.00	56,462.63
2	Add for additional lift upto 5' - 8' Depth	5544.00	Cft	5200.00	%0Cft	28,828.80	5200.00	28,828.80	5200.00	28,828.80
	Add for additional lift upto 8' - 11' Depth	2808.00	Cft	5750.00	%0Cft	16,146.00	5750.00	16,146.00	5750.00	16,146.00
3	Providing, & Laying of RCC Pipes with Rubber Ring Joint and fitting in trench including cutting, fitting, jointing with rubber ring i/c testing with water to specified pressure.24" Dia	48.00	Rft	790.00	P/Rft	37,920.00	790.00	37,920.00	790.00	37,920.00
	18" Dia	240.00	Rft	539.00	P/Rft	129,360.00	539.00	129,360.00	540.00	129,600.00
	12" Dia	288.00	Rft	367.00	P/Rft	105,696.00	367.00	105,696.00	367.00	105,696.00
	8" Dia	213.00	Rft	206.00	P/Rft	43,878.00	206.00	43,878.00	210.00	44,730.00
4	Providing manhole 4' feet inside without C.I Frame 15 Kg and 5 feet clear depth cast in situ with 1:2:4 CC in 9" thick wall, 1:4:8: C.C in 6ft dia and 6" inch thick in foundation 1:2:4 C.C in benching 12" thick cement plastering with 1:3 C.M on all inside wall surfaces, channel and benching i/c making required nos of main and branch channels, 3/4" dia m.s foot rest @12" c/c i/c cost of excavation in all kinds of soil, backfilling and disposal of excavated stuff etc complete as per design and instruction of Engineer Incharge.	15.00	Nos	13479.29	Each	202,189.35	13479.00	202,185.00	13479.00	202,185.00
5	Add/Deduct per ft depth	60.00	(+)Rft	2538.62	P/Rft	152,317.20	2538.00	152,280.00	2538.00	152,280.00





**Name of Work: REPLACEMENT OF 24", 18" 12" & 8" DIA SEWERAGE LINE IN TAISER TOWN  
& DIFFERENT PLACES OF UC-38 DUE TO HEAVY RAIN IN SURJANI GADAP TOWN**


Item No	Description of Work	Estimated Cost				M/s.Khan Zaman & Brothers		M/s.Usmania Construction Co.		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
6	Full hire charges of pumping set per day i/c of wages of driver and assistant fuel or electric energy platform for placing the pump etc at lower depth with suction and delivery pipes for pumping out water found at various depth from trenches including the cost of erection and dismantling after completion of the job. Hire charges of pumping set upto 10 HP pumping out water from 10 ft deep trench	24.00	Days	1500.00	P/Day	36,000.00	1500.00	36,000.00	1500.00	36,000.00
7	Manufacturing and supplying of 21" dia RCC Manhole covers cast in situ 1:2:4 concrete ratio 3" deep at centre, reinforced with 1/2" dia tor steel bars at 4" C/C welded to a 3/16" thick 2" wide M.S plate two hook of 3/8" dia tor bar including compacting i/c cutting and transportation with in 10 miles. 21" dia cover.	20.00	Nos	913.63	Each	18,272.60	913.00	18,260.00	920.00	18,400.00
8	Manufacturing and supplying of RCC Ring Slab of 21" dia (inside) and 36" dia outside 7 1/2" width and 6" thick i/c 3/8" dia tor steel bars two concentric rings with 3/8" dia 8 Nos cross linked bars welded and two sunk type hooks, casted in 1:1 1/2:3 concrete with embedded 15 Kg C.I Frame in perfect position i/c transportation charges for an average lead of 20 Km per trip from casting yard to town office. (A minimum of 25 slabs per trip will be transported).	20.00	Nos	1906.60	Each	38,132.00	1906.00	38,120.00	1906.00	38,120.00
9	Shifting to the site and Fixing of 36" dia (outer) Ring Slab in perfect position on damaged manholes i/c cutting of the damaged manhole i/c cutting of damaged portion of manhole in proper shape and laying of cement mortar of 2" thickness and disposal of the debris.	20.00	Nos	563.09	Each	11,261.80	563.00	11,260.00	565.00	11,300.00
10	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete.	19156.39	Cft	2760.00	%0Cft	52,871.64	2760.00	52,871.64	2760.00	52,871.64
<b>TOTAL QUOTED / CORRECTED COST</b>						<b>929,336</b>		<b>929,268</b>		<b>930,540</b>




(Muhammad Khalid Khan)  
Accounts Officer (Dist. West)  
Member / Secretary



(Saif-ul-Haque)  
Addl. Director Internal  
Audit KMC - Member



(Maqsood Ahmed Shaikh)  
Superintending Engineer (K.M.C)  
Member



(Owais Malik)  
S.E (District West-A)  
Member



(Munir Ahmed Bhatti)  
Director (Design & Estimate)  
Convener

## ATTENDANCE OF PARTICIPATE CONTRACTOR

Name of Work: - REPLACEMENT OF 24", 18", 12" & 8" DIA SEWERAGE LINE IN TAISER TOWN & DIFFERENT PLACES OF UC-38 DUE TO HEAVY RAIN IN SURJANI GADAP TOWN

Date of Opening & Time : 02-02-18 2:30 P.M.

Estimated Cost :

S.NO	NAME OF FIRM	NAME OF PERSON & DESIGNATION	SIGNATURE
1	M/s. <i>مہینو خان ٹرانس اینڈ پرائز</i>	<i>خان زمان</i>	<i>خان زمان</i>
2	M/s. <i>مہینو خان ٹرانس اینڈ پرائز</i>	<i>خان زمان</i>	<i>خان زمان</i>
3	M/s.		
4			
5			
6			
7			
8			
9			
10			

NIT Sr. No. SPPRA Serial No.36236

Method and procedure of procurement: Open Competitive Bidding (National/ International Competitive Bidding) (Single Stage–One Envelope)

Description of work: REPLACEMENT OF SUNK DOWN PORTION OF SEWERAGE LINE 18", 12" & 8" DIA IN DIFFERENT PLACES OF SURJANI TOWN DUE TO HEAVY RAIN IN UC-39 & 38 GADAP TOWN

Date of Opening: 02-02-2018

**BIDDERS' ELIGIBILITY/ QUALIFICATION REPORT**

Eligibility/ Qualification Criteria:


S. No.	Eligibility / Qualification Criteria	Bidders' Name	
		M/s.Khan Zaman & Brothers	M/s.Usmania Construction Co.
1.	Registration with PEC (if applicable)	N/A	N/A
2.	NTN	Yes	Yes
3.	Sales Tax Registration (FBR)	N/A	N/A
4.	Registration with Sindh Revenue Board (SRB)	Yes	Yes
	<b>Qualification Criteria:</b>		
5.	Minimum three years' experience of relevant field.	Yes	Yes
6.	Turnover of at least last three years	Yes	Yes
7.	Required Bid Security is attached.	Yes	Yes
8.	Bid is signed, named and stamped by the authorized person of the firm along with Authorization letter.	Yes	Yes
9.	Any other factor deemed to be relevant by the procuring agency subject to provision of Rule-44	N/A	N/A
10.	Qualified/ disqualified	Qualified	Qualified



(Muhammad Khalid Khan)  
Accounts Officer (Dist. West)  
Member / Secretary



(Saif-ul-Haque)  
Additional Director Internal  
Audit – KMC Member



(Maqsood Ahmed Shaikh)  
Superintending Engineer (KMC)  
Member



(Owais Malik)  
S.E (District West-A)  
Member



(Munir Ahmed Bhatti)  
Director (Design & Estimate)  
Convener

NIT Sr. No. SPPRA Serial No.36236

**Method of Procurement: Single Stage Single Envelope.**

Name of Work: REPLACEMENT OF SUNK DOWN PORTION OF SEWERAGE LINE 18", 12" & 8" DIA IN DIFFERENT PLACES OF SURJANI TOWN DUE TO HEAVY RAIN IN UC-39 & 38 GADAP TOWN

**MINUTES OF BID OPENING MEETING.**

A meeting of the procurement committee of this department was held on 02-02-2018 for opening the bids received in respect of subject NIT till deadlines of submission. The meeting was attended by all / following members of the procurement committee and the representative of bidders.

**(Attendance sheet is enclosed).**

2. Two bidders submitted their bids till the deadline of submission.
  - i. M/s. Khan Zaman & Brothers
  - ii. M/s. Usmania Construction Co.
3. The bids were opened at 2:30 P.M in the presence of the above mentioned participants and the rates quoted by bidders were read aloud and encircled by Chairman of the Procurement Committee.

S. No	Name of Firm	Quoted Price	Amount of Bid Security	Pay Order No. / Date
01	M/s.Khan Zaman & Brothers	Rs.9,24,890/-	Rs.20,000/-	P.O # AAA 14622381 dt:01-02-2018 from ABL PIB Colony Branch Karachi
02	M/s.Usmania Construction Co.	Rs.9,25,886/-	Rs.20,000/-	P.O # 14347221 dt:01-02-2018 from UBL Civic Centre Branch Karachi

4. The bids do not contain any cutting or over-writing.
5. The committee shall examine all the bids as per the qualification / eligibility criteria provided in the bidding document and verify the documents and bid security submitted by the bidders (if required).


The meeting ended with the vote of thanks to and from the chair.

  
(Muhammad Khalid Khan)  
Accounts Officer (Dist. West)  
Member / Secretary

  
(Saif-ul-Haque)  
Additional Director Internal  
Audit – KMC Member

  
(Maqsood Ahmed Shaikh)  
Superintending Engineer (KMC)  
Member

  
(Owais Malik)  
S.E (District West-A)  
Member

  
(Munir Ahmed Bhati)  
Director (Design & Estimate)  
Convener



# KARACHI WATER & SEWERAGE BOARD

## OFFICE OF THE DIRECTOR (DESIGN & ESTIMATE)

### BID EVALUATION REPORT

1	Name of Procuring Agency:	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No:	SPPRA Serial No.36236 I.D No._____
3	Tender Description/Name of Work/Item:	<b>REPLACEMENT OF SUNK DOWN PORTION OF SEWERAGE LINE 18", 12" &amp; 8" DIA IN DIFFERENT PLACES OF SURJANI TOWN DUE TO HEAVY RAIN IN UC-39 &amp; 38 GADAP TOWN</b>
4	Method of Procurement:	<u>Single Stage (One Envelop)</u>
5	Tender Published:	<u>Through SPPRA Web Site</u>
6	Total Bid Documents Sold:	<u>2 Nos</u>
7	Total Bid Received:	<u>2 Nos</u>
8	Technical Bid Opening Date (if applicable):	<u>N/A</u>
9	No. of Bid Technically Qualified (if applicable)	<u>N/A</u>
10	Bid (s) Rejected:	<u>NIL</u>
11	Financial Bid Opening Date:	02-02-2018

### 12 BID EVALUATION REPORT


S#	Name of Firm / Bidder	COST OFFERED BY THE BIDDER	RANKING IN TERMS OF COST	COMPARISON WITH ESTIMATED COST	REASON FOR ACCEPTANCE / REJECTION	REMARKS
1	M/s.Khan Zaman & Brothers	Rs.9,24,893/-	1 <sup>st</sup> Lowest	@0.007% Below	Pay Order and required documents are attached. P.O # AAA 14622381 dt:01-02-2018 Rs.20,000/- from ABL PIB Colony Branch Karachi	Substantially Responsive
2	M/s.Usmania Construction Co.	Rs.9,25,889/-	2 <sup>nd</sup> Lowest	@0.100% Above	Pay Order and required documents are attached. P.O # 14347221 dt:01-02-2018 Rs.20,000/- from UBL Civic Centre Branch Karachi	Substantially Responsive

The all concerned bidders are being informed accordingly.

The E.E Concerned for compliance of Rule-45 of SPPRA 2010 **M/s.Khan Zaman & Brothers** declared as the lowest responsive bidder by the Committee and recommended for sanction from Competent Authority.

  
(Muhammad Khalid Khan)  
Accounts Officer (Dist. West)  
Member / Secretary

  
(Saif-ul-Haque)  
Additional Director Internal  
Audit – KMC Member

  
(Maqsood Ahmed Shaikh)  
Superintending Engineer (KMC)  
Member

  
(Owais Malik)  
S.E (District West-A)  
Member

  
(Munir Ahmed Bhatti)  
Director (Design & Estimate)  
Convener

## COMPARATIVE STATEMENT

**Name of Work: REPLACEMENT OF SUNK DOWN PORTION OF SEWERAGE LINE 18", 12" & 8" DIA  
IN DIFFERENT PLACES OF SURJANI TOWN DUE TO HEAVY RAIN IN UC-39 & 38 GADAP TOWN**

Item No	Description of Work	Estimated Cost				M/s.Khan Zaman & Brothers		M/s.Usmania Construction Co.		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
1	Excavation for pipe line in trenches and pits in all kind of soil of murum i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by Engineer Incharge providing fence guards, lights, flags sand temporary crossing for non-vehicular traffic wherever required lift upto 5 ft (1.52 m) and lead upto one chain (30.5m). 0' - 5' Depth	10965.00	Cft	4650.00	%0Cft	50,987.25	4650.00	50,987.25	4650.00	50,987.25
2	Add for additional lift upto 5' - 8' Depth	5274.00	Cft	5200.00	%0Cft	27,424.80	5200.00	27,424.80	5200.00	27,424.80
	Add for additional lift upto 8' - 11' Depth	4140.00	Cft	5750.00	%0Cft	23,805.00	5750.00	23,805.00	5750.00	23,805.00
3	Providing, & Laying of RCC Pipes with Rubber Ring Joint and fitting in trench including cutting, fitting, jointing with rubber ring i/c testing with water to specified pressure. 18" Dia	160.00	Rft	539.00	P/Rft	86,240.00	539.00	86,240.00	540.00	86,400.00
	12" Dia	426.00	Rft	367.00	P/Rft	156,342.00	367.00	156,342.00	367.00	156,342.00
	8" Dia	174.00	Rft	206.00	P/Rft	35,844.00	206.00	35,844.00	210.00	36,540.00
4	Providing manhole 4' feet inside without C.I Frame 15 Kg and 5 feet clear depth cast in situ with 1:2:4 CC in 9" thick wall, 1:4:8: C.C in 6ft dia and 6" inch thick in foundation 1:2:4 C.C in benching 12" thick cement plastering with 1:3 C.M on all inside wall surfaces, channel and benching i/c making required nos of main and branch channels, 3/4" dia m.s foot rest @12" c/c i/c cost of excavation in all kinds of soil, backfilling and disposal of excavated stuff etc complete as per design and instruction of Engineer Incharge.	18.00	Nos	13479.29	Each	242,627.22	13479.00	242,622.00	13479.00	242,622.00
5	Add/Deduct per ft depth	57.00	(+)Rft	2538.62	P/Rft	144,701.34	2538.00	144,666.00	2538.00	144,666.00






**Name of Work: REPLACEMENT OF SUNK DOWN PORTION OF SEWERAGE LINE 18", 12" & 8" DIA  
IN DIFFERENT PLACES OF SURJANI TOWN DUE TO HEAVY RAIN IN UC-39 & 38 GADAP TOWN**

Item No	Description of Work	Estimated Cost				M/s.Khan Zaman & Brothers		M/s.Usmania Construction Co.		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
6	Full hire charges of pumping set per day i/c of wages of driver and assistant fuel or electric energy platform for placing the pump etc at lower depth with suction and delivery pipes for pumping out water found at various depth from trenches including the cost of erection and dismantling after completion of the job. Hire charges of pumping set upto 10 HP pumping out water from 10 ft deep trench	24.00	Days	1500.00	P/Day	36,000.00	1500.00	36,000.00	1500.00	36,000.00
7	Manufacturing and supplying of 21" dia RCC Manhole covers cast in situ 1:2:4 concrete ratio 3" deep at centre, reinforced with 1/2" dia tor steel bars at 4" C/C welded to a 3/16" thick 2" wide M.S plate two hook of 3/8" dia tor bar including compacting i/c cutting and transportation with in 10 miles. 21" dia cover.	20.00	Nos	913.63	Each	18,272.60	913.00	18,260.00	920.00	18,400.00
8	Manufacturing and supplying of RCC Ring Slab of 21" dia (inside) and 36" dia outside 7 1/2" width and 6" thick i/c 3/8" dia tor steel bars two concentric rings with 3/8" dia 8 Nos cross linked bars welded and two sunk type hooks, casted in 1:1 1/2:3 concrete with embedded 15 Kg C.I Frame in perfect position i/c transportation charges for an average lead of 20 Km per trip from casting yard to town office. (A minimum of 25 slabs per trip will be transported).	20.00	Nos	1906.60	Each	38,132.00	1906.00	38,120.00	1906.00	38,120.00
9	Shifting to the site and Fixing of 36" dia (outer) Ring Slab in perfect position on damaged manholes i/c cutting of the damaged manhole i/c cutting of damaged portion of manhole in proper shape and laying of cement mortar of 2" thickness and disposal of the debris.	20.00	Nos	563.09	Each	11,261.80	563.00	11,260.00	563.00	11,260.00
10	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete.	19319.45	Cft	2760.00	%0Cft	53,321.68	2760.00	53,321.68	2760.00	53,321.68
<b>TOTAL QUOTED / CORRECTED COST</b>						<b>924,960</b>		<b>924,893</b>		<b>925,889</b>




(Muhammad Khalid Khan)  
Accounts Officer (Dist. West)  
Member / Secretary




(Saif-ul-Haque)  
Addl. Director Internal  
Audit KMC - Member



(Maqsood Ahmed Shaikh)  
Superintending Engineer (K.M.C)  
Member



(Owais Malik)  
S.E (District West-A)  
Member



(Munir Ahmed Bhatti)  
Director (Design & Estimate)  
Convener

## ATTENDANCE OF PARTICIPATE CONTRACTOR

Name of Work: - REPLACEMENT OF SUNKDOWN PORTION OF SEWERAGE LINE 18", 12" & 8" DIA IN DIFFERENT PLACES OF SURJANI TOWN DUE TO HEAVY RAIN IN UC-39 & 38 GADAP TOWN

Date of Opening & Time : 02-02-18 at 2.28.11

Estimated Cost :

S.NO	NAME OF FIRM	NAME OF PERSON & DESIGNATION	SIGNATURE
1	M/s. <i>سید محمد زبیر</i>	<i>کان زبیر</i>	<i>کان زبیر</i>
2	M/s. <i>سید محمد زبیر</i>	<i>کان زبیر</i>	<i>کان زبیر</i>
3	M/s.		
4			
5			
6			
7			
8			
9			
10			