

Name of Work:-

REPAIR / RENOVATION OF FLAT NO. A-1 POLICE  
OFFICE FLAT KHEKHSAN CLIFTON HATIM ALVI  
ROAD KARACHI.

ANNUAL PROCUREMENT PLAN

S. #	Description	QTY	RATE	UNIT	AMOUNT
1.	Dismantling of Glazed Tile Bath Room	600Rft.		P.Rft.	
2.	Providing & Fixing of flooring & tile glazed tiles on wall and floor facing in required color and pattern specification jointed in white cement and pigment over a base of 1:2 grey cement 3/4" thick including washing and filling of joints with slurry of white cement and pigment in desired shape with finishing cleaning and cost of wax polish etc. complete including cutting tiles to proper profile.	600		P.Sft.	
3	Preparing Surface Matt Finish Color 3 Coat	6315		P.Sft.	
4	Providing & fixing Bath Room Accessories Commed Wash Basin Sanitary fitting include pipe P-trape floor trape etc in all respect as per instruction Engineer Incharge	1		Each	
5	Repairing of Electric point wire Holder & Energy Saver	40		Each	
Total					

  
Sub Engineer