

### KARACHI WATER & SEWERAGE BOARD

## NOTICE INVITING TENDER

(Under SPPR-2010)

Executive Engineer Civil E&M Sew KW&SB invites sealed Tenders on Item Rate Basis through website under rule 17 (4) in terms of SPPR Rule-2010, single-stage single envelop for the work mentioned below, from the intending participants, reputed / experienced contracting firms.

Estimated cost of tender below 1.00 Million

1.	Name of Work	
1004		Emergent Desalting and cleaning of sump /well/channel and leaking joints of 18" dia PRCC Rising main at Ejector £ 12 sewage pumping station, Ranchore line.
2.	Eligibility of Contractor	Contractor should be national tax payer, should have work experience in relevant filed Such firms / contractors may form a joint venture clearly indicating leader partner and responsibility of each partner. Tender documents shall be issued to leader of the J.V
3.	Earnest Money	2% of quoted amount in shape of pay order / Bank Draft, in favor of Karachi Water & Sewerage Board.
4.	Note	<ul> <li>i) No Tender will be issued on the date of opening of tender,</li> <li>ii) Earnest Money in shape of Pay Order / Bank Drafts from any scheduled Bank of Pakistan in the favor of KW&amp;SB must be accompanied with the tender otherwise the tenders shall be treated as invalid and rejected.</li> <li>iii). Current registration of PEC be submitted at the time of submission of Tender documents.</li> </ul>
5.	Tenders can be Purchased from .	(i) Office of the Account Officer (Revenue), KW&SB at Head Office, 1st Floor Old KBCA — Annexe Building, — Behind Civic Centre, — Gulshan-e-Iqbal, Block-'4, Karachi.
6.	Tender Fee	Rs. 500/= Non-Refundable in shape of pay order in favour of KW&SB.
7.	Time limit for Completion of work.	15 days
8.	Last date of Issuing tender document	18.02.2012
9.	Date & Time receiving / Opening of Tenders.	20.02.2012 at 2:00 pm and to be opened at 2:30 pm
10.	Place of opening.	Tender will be opened by the Tender Opening Committee in the office of Chief Engineer (IP&D) Block 'B' 9th mile Karsaz.
11.	Funding Position	KW&SB own fund year 2011-12
12.	Scope of Work	For improvement of Sewerage System

- Note:- i) The procuring agency reserves the right to accept or reject any or all bids as per relevant provision of SPPR-2010.
  - ii). Tender can be seen on SPPRA Website No. www.pprasindh.gov.pk.
  - If any undesirable circumstances arise on the opening day or Government declare the Holiday the tender shall be opened on next working day at same time and venue.

KARACHI WATER & SEWERAGE BOARD

#### KARACHI WATER AN/D SWERAGE BOARD OFFICE OF THE EXECUTIVE ENGINEER CIVIL E&M SEW

#### BILL OF QUANTITY

Estimated Amount:	Item Rate Basis	Issued to M/s	
Time Limit	15 Days	Cost of Quotation	Rs.500 /-
Penalty Per Day	Rs: 100/-	Date of Opening	20.02.2012
Earnest money	@ 02 of quoted Amount		
		Receipt No:	Date:
		A.O Revenue Financ	e Department

# NAME OF WORK: EMERGENT DESILTING AND CLEANING OF SUMP WELL/CHANNEL AND LEAKING JOINTS OF 18"DIA PRCC RISING MAIN AT EJECTOR 12 SEWAGE PUMPING STATION, RANCHORE LANE.

S. #	Description of Work	Qty.	Rate (Rs.)	Per	Total (Rs.)
1-	De-silting and cleaning of sump/well/channel up to 40'-0 deep by manual and mechanical means i/c. disposal of sludge and garbage etc.	20700 sft		Per/ sft	
2	Full hire charges of submersible dewatering pumping set per day with delivery pipes, pumps operator, assistant, placing of pump at lower depths with delivery pipe i/c. cost of hire of hire electric generator for electric energy with fuel, generator operator, assistant and all related accessories i.e wire, holders, switches, sockets, cartage of pumping and electric generating sets for pumping out of water and various depth from trenches and dismantling after complete job	45 days		Per/ day	
3	Repairing of leaking joints on PRCC pipe (external vatta) i/c. the cost of labor and excavation, sealing materials de-watering, back filling etc.	17 Nos		each	

- Cont on Page 2

4	Supplying earth filling from approved out side sources within a radius 5 mile i/c. doffing, loading and unloading and filling in foundation, trenches, plinth or under floor in foundation, trenches plinth i/c. breaking clods, dressing, watering, and consolidation by ramming in layers not exceeding 9" in depth to full compaction of one chain and lift up to 5" ft.	17160 cft	% cft	
---	---	--------------	-------	--

Executive Engineer Civil E&M Sew KW&SB

I / we hereby quoted Rs:	for execution of
above mentioned work and bind to	comply the rules of KW&SB

Signature of Contractor With name of the firm