

KARACHI WATER AND SEWERAGE BOARD
OFFICE OF THE EXECUTIVE ENGINEER (SEW) MALIR TOWN DISTRICT MALIR
Malir Kala Board near T.M.A Malir Town Office, Karachi
 Cell # 03212223609

Notice Inviting Tenders through websites (Under 01 Million)

1	Name of Work.	CLEANING OF SEWERAGE PIPE OF 18" DIA BY WINCHING FROM NADE ALI MARKAZI IMAM BARGAH, KHOMEINI HOSPITAL JAFFER TAYYAR AND SURROUNDING SOCIETIES UC-07 MALIR TOWN, KW&SB.
2	Eligibility of Contractor.	All eligible Contractors Bidder should have NTN Certificate.
3	Tender can be purchased.	Tender documents can be purchased From office of the AO (Revenue), KW&SB at Head Office 1 st floor old KBCA Building behind Civic Centre Gulshan-e-Iqbal, Karachi from 9.00AM to 1.00PM in any working day except the date of opening of the Tenders.
4	Budget Position.	KW&SB own funds under B.G No. 82I4-16 (2013-2014).
5	Bid Security.	2% bid security of the quoted bid cost in shape of Pay order/Bank Draft, in Favour of K&SB.
6	Note.	III. No tender will be issued on the date of opening of tender. IV. Bid Security in shape of Pay Order/Bank Draft from any Schedule Bank of Pakistan in favour of KW&SB must be accompanied with the tender other wise the tenders shall be treated as invalid & rejected.
7	Tender Fee.	Rs.1,000/-, (non refundable) in shape of Pay order, in Favour of K&SB.
8	Start date / last date of issuing.	W.E.F, 1 st Hosting upto 19-09-2013.
9	Date of Receiving/ Opening of Tenders.	20-09-2013 at 2.00 PM and will be opened at 2.30 PM on same day.
10	Place of Opening.	Tenders will be opened by the Convener Procurement Committee-I in the office of the CE (IPD), KW&SB situated at Block-"B" 9 th Mile Karsaz Shakra-e-Faisal, Karachi.
11	Scope of work.	Improvement of Sewerage System in Malir.

Note: - The Procuring Agency may reject all or any bids subject to the relevant provisions of SPPRA-2010. Rules.

Tender can be downloaded from SPPRA website as well as KW&SB website.
www.pprasindh.gov.pk www.kw&sb.gov.pk

"In case of undesirable circumstances on submission/opening date & time or if Government declares Holiday the tender shall be submitted/opened on the next working day at the same time & venue".

KARACHI WATER AND SEWERAGE BOARD

KARACHI WATER & SEWERAGE BOARD
OFFICE OF THE EXECUTIVE ENGINEER (SEW)
MALIR TOWN, DISTRICT MALIR


Estimated Cost. **On Item Rate Basis** Issue to M/S _____
Tender Cost. **Rs. 900/=**
Time Limit. **(25) Days.** Pay Order No:- _____ Dated. _____
Penalty. **1000/=**

ISSUING AUTHORITY

NAME OF WORK:- **CLEANING OF SEWERAGE PIPE OF 18" DIA BY WINCHING FROM NADE ALI, MARKAZI IMAM BARGAH, KHOMEINI HOSPITAL JAFFER TAYYAR AND SURROUNDING SOCIETIES UC-07 MALIR TOWN, KW&SB.**

S.No	DESCRIPTION OF WORK	QTY.	RATE		PER UNIT / ITEM	AMOUNT IN RUPEES
			Rupees in Figures	Rupees in Words		
1-	Cleaning inside sewerage lines completely restoring original silt free space / diameter of pipe line by labour and equipment (Machincaly / Electrically driven). Including accessories like pulley's steel rope buckets and draggers sizing from 6" to 18"φ. Their "to and fro" pulling action (No of passes shall be as many as required) would be taken in tow phases (First phase entire length from down stream to up stream) bringing down peak hours sewerage to flow inside pipe line (as free flow) and in second phase from up stream to down stream of entire length ensuring no silt is observed in buckets (6"φ to 18"φ) except only sewage water and finally passing a steel ball of φ 12" lesser that the diameter of pipe but not exceeding 48" φ ball even for larger dia pipe to ensure perfect cleaning. The job includes all the hire/ cost of equipment and accessories of above winching machine/ devices along with / engines with winching drum set having steel rope pulley mounted over it, steel bucket fro 6"φ to 18" φ hooks and other protections likes safety barriers, traffic signs, traffic cones ensuring no damage to pipe along with ensuring safety to labor and other public property lives and removal silts/solid during desalting and clearance of site etc complete as per full satisfaction of site engineer.	6500 Rft			P/Rft	

S.No	DESCRIPTION OF WORK	QTY.	RATE		PER UNIT / ITEM	AMOUNT IN RUPEES
			Rupees in Figures	Rupees in Words		
2-	Manufacturing and supplying of R.C.C Ring Slab of 21"dia inside 36"dia outside 7.5 width and 6" thick i/c 3/8"dia tor steel bars two concentric ring with 3/8"dia 8 nos, cross linked bars welded and two sunk type hooks casted in 1:1 - 1/2: 3 concrete with embedded 15 Kg C.I. frame in perfect position i/c transportation charges for an average lead of 20 km per trip from casting yard to Town Offices (A minimum of 25 slabs per trip will be transported).	50 Nos.			Each	
3-	Manufacturing and supplying of 21 inch diameter RCC manhole covers cast in 1:2:4 concrete ratio 3"deep at the center, reinforced with 1/2" dia tor steel bars at 4" c/c welded to 3/16" thick 2" wide MS plate two hook of 3/8" dia tor bar including compacting i/c cutting, and transportation with in 10 miles. 21"φ manhole cover.	70 Nos.			Each	
TOTAL						


 EXECUTIVE ENGINEER (SEW)
 MALIR TOWN, DISTRICT MALIR
 K.W. & S.B

I hereby Amounting to Rs. _____ (In words) _____

Note:- All existing SPPRA Rule will be abide,
 Rate Analysis of each item have been filed by me.

Signature & Stamp of the Contractor

Address: _____