

KARACHI WATER & SEWERAGE BOARD

OFFICE OF THE EXECUTIVE ENGINEER (SEW)

SHAH FAISAL TOWN, DISTRICT EAST

Town Office, Shah Faisal Town, Behind Shama Shopping Centre, Karachi

Cell # 0300-8224464

NOTICE FOR INVITING TENDER THROUGH AUTHORITY'S WEBSITE (UNDER 1.00 MILLION).

1.	Name of work :-	REPAIR / RECONSTRUCTION OF INTERMEDIATE MANHOLES RCC COVERS AND PRE-CAST RING SLABS FOR (UC-01 TO 07) IN THE AREAS OF SHAH FAISAL TOWN.
2.	Eligibility of Contactor:	All eligible Contactor Bidder should having N.T.N Certificate.
3.	Tender can be purchased.	Tenders documents can be purchased from the Office of the Accounts Officer (Revenue), KW&SB at KW&SB Head Office, at 1 st Floor Old KBCA Annex Building, Behind Civic Centre, Gulshan-e-Iqbal Karachi, between 9.00 am to 1.00 pm in any working day except the date of opening of the tenders.
4.	Source of Funding.	KW&SB's own funds under B.G.No. I-023-32 (2013-2014).
5.	Bid Security.	2% of bid security of the quoted cost / price in shape of pay order / Bank Draft for any schedule bank of Pakistan in favour of KW&SB.
6.	Note.	i) No tender will be issued on the date of opening of tender. ii) Bid Security in Shape of Pay Order / Bank Draft from any Schedule Bank of Pakistan in favour of KW&SB must be accompanied with the Tender otherwise the tenders shall be treated as invalid & rejected.
7.	Tender Fee.	Rs.1000/= Non-Refundable in shape of Pay Order in favour of KW&SB.
8.	Start date / Last date of issuing of tender documents.	w.e.f. 1 st Hoisting upto <u>23-10-2013</u> , during working hours from 9.00 am to 1.00 pm.
9.	Date of submission / Opening of Tenders.	<u>24-10-2013</u> , at 2.00 PM and will be opened at 2.30 PM.
10.	Place of opening.	Tenders will be opened by the Procurement Committee-I , at the office of the Chief Engineer (IP&D), KW&SB at 9 th Mile Karsaz, Shahr-e-Faisal, Karachi.
11.	Scope of work	Improvement of Sewerage System.

Note :-

- The Procuring Agency may reject all or any bids subject to the relevant provision of SPP Rules-2010.
- Tender can be seen on SPPRA's Website.
- In case of undesirable Circumstances arise on submission / opened date and Time or if Government Declares Holiday the tender shall be submitted / opened on the next working day at the same time & venue.

KARACHI WATER & SEWERAGE BOARD

KARACHI WATER & SEWERAGE BOARD

OFFICE OF THE EXECUTIVE ENGINEER (SEW)
SHAH FIASAL TOWN, DISTRICT EAST

SUBJECT:- REPAIR / RECONSTRUCTION OF INTERMEDIATE MANHOLES
RCC COVERS AND PRE-CAST RING SLABS FOR (UC-01 TO 07) IN
THE AREAS OF SHAH FAISAL TOWN.

Estimated Cost _____
Tender Cost. _____
Time Limit. _____
Penalty _____

On Item Rate Basis.
Rs.1000/= _____
Rs.500/= Per Day _____

Issued to M/s. _____
Pay Order No. _____ Dated: _____

ISSUING AUTHORITY

S.NO.	DESCRIPTION	QTY.	RATE		PER UNIT / ITEM	AMOUNT IN RUPEES
			Rupees in Figures.	Rupees in Words.		
1.	Cement concrete plain including placing compacting, finishing and curing complete including screening and washing at stone aggregate with out shuttering 1:2:4	657.58 Cft			% Cft	
2.	Hire Charges of steel shuttering both side for the construction of the manhole (Circular) at side i/c its erection in proper position and removal after concrete etc complete.	77 Ft			P/Ft	
3.	Providing manholes 4' inside with C.I frame 15 Kg 5 ft clear depth 1:2;4 cast in situ in 9" thick wall 1:4:8 C.C in 6' dia and 6" thick in foundation 1:2;4 C.C in benching 1/2" thick C.P 1:3 mortar on inside wall surface of channel / benching i/c making required Nos of main and branches channel 3/4" dia bars M.S foot rest at 12" c/c including cost of excavation of all kinds of soil backfilling and disposal of excavated stuff etc complete and as per design and instruction of Engineer Incharge.	09 Nos.			Each	
4.	Add or deduct per ft depth	(+) 4 ft			P/Ft	

SUBJECT:- REPAIR / RECONSTRUCTION OF INTERMEDIATE MANHOLES
RCC COVERS AND PRE-CAST RING SLABS FOR (UC-01 TO 07) IN
THE AREAS OF SHAH FAISAL TOWN.

S.NO.	DESCRIPTION	QTY.	RATE		PER UNIT / ITEM	AMOUNT IN RUPEES
			Rupees in Figures.	Rupees in Words.		
5.	Manufacturing and supplying of RCC Ring Slab of 21" dia inside 36" dia out side 7.5 width and 6" thick i/c 3/8" tor steel bars to concentric ring with 3/8" dia 8 Nos cross linked bars welded and two sunk type hooks cast in a 1: 1 1/2 : 3 concrete embedded 15 Kg C.I frame in perfect position i/c transportation charges for an average lead of 20 KM per trip from casting yard to town office.	155 Nos.			Each	
6.	Shifting to the site and fixing of 36" Ring Slab in perfect position on damaged manholes including cutting of damage portion of manhole in proper shape and laying of cement mortar of 2" thickness and disposal of debris.	155 Nos.			Each	
7.	Manufacturing and supplying of 21" dia RCC Manhole cover cast in situ 1:2:4 concrete ratio 3" deep at centre reinforced with 1/2" dia tor bar steel at 4" c/c welded to 3/16" thick 2" wide M.S Plate two hook of 3/8" dia tor bar including compacting, curing and transportation within 10 Miles.	180 Nos.			Each	
	TOTAL					

Aria
EXECUTIVE ENGINEER (SEW)
SHAH FAISAL TOWN, DISTRICT EAST
K.W.&S.B.

I hereby quoted Amounting to Rs. _____ (In words) _____

Note :- All existing SPPRA Rule will be abide.

Signature & Stamp of the Contractor

Address _____