



**KARACHI METROPOLITAN CORPORATION**  
**OFFICE OF THE SUPERINTENDING ENGINEER (CM)**  
**ENGINEERING DEPARTMENT**

169/13-14

No. S.E/(CM)/ED/KMC/ 407 /13

Dated: - 10/10/2013

**NOTICE INVITING TENDERS**

**Through Website of SPPRA & KMC**

Tenders in sealed covers are invited on Schedule Plus offer rate basis for the following works from the reputable and experienced firm / contractor having valid NTN and paid up original challan of Professional Tax prescribed fee.

S. No.	Tender Reference No.	Name of Scheme	Estimated Cost	Bid Security	Tender Cost
1.	KMC/CM/ED/48/2013-14	Cleaning of Catch Pits / Chambers Providing of Manholes Covers / RCC Slabs, Supply of Materials and Repair of Trenches in Mauripur Road District (West) KMC (Rain Emergency 2013).	Rs.9,78,976/=	Rs.20,000/=	Rs.2,500/=
2.	KMC/CM/ED/49/2013-14	Cleaning of Catch Pits / Chambers Providing of Manholes Covers / RCC Slabs, Supply of Materials and Repair of Trenches in Metroville Road District (West) KMC (Rain Emergency 2013).	Rs.9,78,450/=	Rs.20,000/=	Rs.2,500/=
3.	KMC/CM/ED/50/2013-14	Repair of Trenches Underpass to Traffic Police Chowki at Shahra-e-Iqbal, Scheme-5, Clifton District South, KMC.	Rs.9,69,781/=	Rs.20,000/=	Rs.2,500/=
4.	KMC/CM/ED/51/2013-14	Restoration of Trenches / Patches in-front of Habib Metropolitan Bank Mohammad Masjid & Block-4 at University Road Gulistan-e-Johar.	Rs.9,65,616/=	Rs.20,000/=	Rs.2,500/=
5.	KMC/CM/ED/52/2013-14	Repair of Trench Plot No. 31 to International School, Scheme-05 Clifton District South, KMC.	Rs.9,59,756/=	Rs.20,000/=	Rs.2,500/=
6.	KMC/CM/ED/53/2013-14	Providing and Laying RCC Pipe SWD in different area of University Road & Sir Shah Suleman Road at Gulshan-e-Iqbal Karachi.	Rs.9,59,000/=	Rs.20,000/=	Rs.2,500/=
7.	KMC/CM/ED/54/2013-14	Repair of Trench near Mohatta Palace to Plot No. 52, Scheme-5 Clifton District South KMC.	Rs.9,57,580/=	Rs.20,000/=	Rs.2,500/=
8.	KMC/CM/ED/55/2013-14	Repair of Trench from 2 Talwar Petrol Pump to near Licence Office, Scheme-5 Clifton District South, KMC.	Rs.9,48,000/=	Rs.19,000/=	Rs.2,500/=
9.	KMC/CM/ED/56/2013-14	Repair/Maintenance of Flat No.B/6, Gulistan-e-Mustafa Fire Station, Fire Brigade KMC.	Rs.3,14,140/=	Rs.6,500/=	Rs.1,000/=
10.	KMC/CM/ED/57/2013-14	Repair/Maintenance work in Flat No.4 Officers Flats Karsaz Karachi.	Rs.4,97,930/=	Rs.10,000/=	Rs.1,000/=

Tender schedule shall be as follows:

SCHEDULE	DATE & TIME	VENUE
1. Receiving of Application & Issuance of Tender	From <b>21-10-2013</b> to <b>05-11-2013</b> During Office Hours	Office of Director Accounts, Engineering Department of 4 <sup>th</sup> Floor Civic Centre Gulshan-e-Iqbal.

SPPRA INWARD DIARY

NO: 5009

DATED: 11/10/13

*Handwritten signature*

DD

2. Dropping of Tender	<b>06-11-2013</b> 2:00 pm.	Committee Room of D.G. (TS) 4 <sup>th</sup> Floor, Civic Centre, Gulshan-e-Iqbal.
3. Opening of Tender	<b>06-11-2013</b> At 2:30 pm	Committee Room of D.G. (TS) 4 <sup>th</sup> Floor, Civic Centre, Gulshan-e-Iqbal.

**TERMS & CONDITIONS.**

1. In case due to any reason, if the tenders are not responded on the above date, the next date of submission and opening will be **22-11-2013** and the tender documents will be available for sale up to **21-11-2013**.
2. The tender documents will be issued to the contractor on submission of written request on letter head and on payment of non-refundable cost of tender price through pay order from any schedule Bank in favor of KMC. Bid Security in shape of pay order / bank guarantee from any schedule Bank in favor of KMC as mentioned above should be enclosed with the bid otherwise the tender will be rejected. No tender will be sold on the tender opening date.
3. In Case the date of opening or last date of sale is declared as public holiday by the Government or non working day due to any reason, the next official working day shall be deemed to be the date of sale and submission and opening of tenders accordingly. The time and venue shall remain the same.
4. The total bid amount as well as the rates of items must be filled both in figures and words and in case any correction made by the contractor himself then each correction must be initialed by the Contractor, otherwise the tenders are liable to be summarily rejected.
5. **Substantial Responsive Bid:**  
Only those bids, which comply with each eligibility criteria as well as minimum qualification criteria attached with the tender documents shall be declared substantially responsive bids at the time of tender opening and will be eligible for further evolution, otherwise the same will be declared as non-responsive / rejected.
6. The bidder is required to submit the above information, the signed evidence against evaluation criteria along with their bids. However Joint venture between two or more firms is allowed subject to compliance of conditions of stipulated rules of PEC.
7. If any fake documents are found then the tender is liable to be rejected/cancelled with out any compensation and with penalty as per rules.
8. Canvassing in connection with tenders is strictly prohibited and tenders submitted by the contractors who report canvassing will liable for rejection.
9. If a bidder submits a seriously unbalanced bid then he may be required to deposit extra performance security to a level sufficient to protect the procuring agency against financial losses, failing which the submitted bid security will be forfeited by the procuring agency.
10. Bid Security of the unsuccessful bidder shall be released once the contract has been finalized with the successful bidder or the validity period has expired.
11. The procuring agency may reject all or any bid subject to the relevant provisions of SPPRA Rules 2010.
12. The conditions of contract are available on KMC website ([www.karachicity.gov.pk](http://www.karachicity.gov.pk)).

  
Superintending Engineer (CM)  
Engineering Department, KMC.

**Not to be Published**

**Director (CB)SPPRA, GOS.**

With the request to upload on the SPPRA's website (with 10 sets of tender documents).

**Add: Director (I.T)Computer Section,**

**Administrator Secretariat, KMC.**

With the request to upload on the KMC's website.

1. D.G(TS), KMC.
2. Chief Engineer,(CM)E.D, KMC.
3. Chief Engineer(Concerned).
4. PS to Administrator, KMC.
5. Director (Accounts)E.D, KMC.
6. Office file.

Sr. # 1.

**KARACHI METROPOLITAN CORPORATION**

**ENGINEERING DEPARTMENT**



**Tender Reference No.KMC/CM/ED/ 48 /13-14**

**BILL OF QUANTITIES**

**CLEANING OF CATCH PITS / CHAMBERS PROVIDING OF MANHOLES  
COVERS / RCC SLABS, SUPPLY OF MATERIALS AND REPAIR OF  
TRENCHES IN MAURIPUR ROAD DISTRICT (WEST) KMC  
(RAIN EMERGENCY 2013).**

**NOTE:**

The Condition of contract will be available on KMC website ([www.karachicity.gov.pk](http://www.karachicity.gov.pk)).

Estimate Cost: - Rs.9,78,976/=

Bid Security: - Rs.20,000/=

Tender Cost: - Rs.2,500/=

# **MINIMUM QUALIFICATION / ELIGIBILITY CRITERIA**

The evidence / documents of the following minimum qualification / eligibility criteria will be checked during opening process of tender & if anyone is missing then the tender will be summarily rejected at the moment by the tender opening committee.

## **Eligibility:**

- i). NTN Certificate
- ii). Valid Professional TAX.

## **Minimum Qualification Criteria:**

- iii). Bid Security, as mentioned in the NIT & Bidding Documents, is furnished.
- iv). All rates quoted including the total amount of the bid shall be in figures & words (both).
- v). All corrections / overwriting shall be clearly re-written with initials & duly stamped by the bidder.
- vi). The bid shall be properly signed, named & stamped by the authorized person of the firm and authorization letter for signatory shall be enclosed with the tender by the authorized Person, if other than the signatory of the firm.
- vii). The minimum turn over / work experience with satisfactory completion report in last 2 years or at least two or more works in hand and their aggregate cost should be equal to the work cost in which bidder interested to participate.

**Signature of the Bidder with Stamp**

**KARACHI METROPOLITAN CORPORATIN**  
**ENGINEERING DEPARTMENT**

**Subject:-** CLEANING OF CATCH PITS / CHAMBERS PROVIDING OF MANHOLES COVERS / RCC SLABS, SUPPLY OF MATERIALS AND REPAIR OF TRENCHES IN MAURIPUR ROAD DISTRICT (WEST) KMC (RAIN EMERGENCY 2013).

Estimated Cost: **Rs.9,78,976/=**

Earnest Money: **Rs.20,000/=**

Tender Cost: **Rs.2,500/=**

S.No.	DESCRIPTION	QTY	UNIT	Rate (in figure)	Rate (in figure)	AMOUNT
1.	Excavation in shingle of gravel formation and rock not requiring blasting undressed, lead up to 100 ft (wet).	6922	% 0 Cft	6655.00	Sixty Six Hundred & Fifty Five Only.	46,066
2.	Providing and laying stone soling up to 9" thick i/c preparation of sub base etc complete.	5450	P/Cft	O/R		
3.	Cartage of 100 Cft / 5 Tones of all materials like stone aggregate, spawl, coal, lime, surkhi etc. B.G Rail fastenings points and crossing bridge girders pipes, 10"x5" or 1000 Maunds of fuel wood by trucks or any other means owned by the contractors (lead up to 15 miles etc).	6922	% Cft	1065.04	One Thousand Fifty Six & Four Paise Only.	73,722
4.	Manufacturing and supplying of RCC manhole cover cast in 1:2:4 concrete ratio 3 inch deep at centre, reinforced with ½" dia tor steel bars at 4" C/C welded to 3/16 thick 2" wide MS plate two hook of 3/8" dia tor bar including compacting i/c curing, and transportation with in 10 miles.					
	<b>21" Dia</b>	80	P/Cft	913.63	Nine Thousand Thirteen & Sixty Three Paise Only.	73,090
	<b>24" Dia</b>	35	P/Cft	1051.25	One Thousand Fifty One & Twenty Five Paise Only.	36,794
5.	Providing and fixing RCC precast slab / grating 4" to 6" thick i/c cost of transportation etc complete.	480	P/Sft	O/R		
6.	Manufacturing and supplying of RCC ring slab of 21" dia inside 36" dia outside 7.5 width and 6" thick i/c 3/8" dia tor steel bars two concentric rings with 3/8" dia 8 Nos. cross linked bars welded and two sunk type hooks,	50	P/Cft	1906.60	Nineteen Hundred Six & Sixty Paise Only.	95,330

	casted in a 1:1-1/2:3 concrete with embedded 15 Kg C.I frame in perfect position i/c transportation charges for an average lead of 20 KM per trip from casting yard to town offices (A minimum of 25 slabs per trip will be transported).					
7.	Cleaning inside sewerage lines completely restoring original silt free space/diameter of pipe lines by labor and equipment (Mechanically / Electrically driver) including accessories like pulley's steel rope, bucket and draggers sizing from 6" to 18" dia. Their "to and fro" pulling action (No. of passes shall be as many as required) would be taken in two phases (first phase entire length from down stream to up stream) bringing down peak hours sewerage to flow inside pipe line (as free flow) and in second phase from up stream to down stream of entire length ensuring no silt is observed in buckets (6" dia to 18" dia) except only sewage water and finally passing a steel ball of dia 12" lesser than the diameter of pipe but not exceeding 48" dia ball even for larger dia pipe to ensure perfect cleaning. The job includes all the hire/cost of equipment and accessories of above winching machine / devices along with / engines with winching drum set having steel rope pulley mounted over it, steel buckets from 6" to 18" dia hooks and other protection likes safety barriers, traffic signs, traffic cones ensuring no damage to pipe along with ensuring safety to labor and other public property / lives and removal of silts / solid during desalting and clearance of site etc complete as per full satisfaction of site Engineer.	2000	P/Ft	104.65	One Hundred Four & Sixty Five Paisa Only.	2,09,300
8.	Full hire Charges of the pumping set per day inclusive of wage of driver and Assistant fuel or electric energy plate forms required for placing pumps etc at lower depth with suction and delivery pipes for pumping out water found at various depths from trenches i/c the cost of erection and dismantling after completion of the job. Hire charges of pumping set of up to 10 HP pumping out water from 10 ft water from 10 ft deep trench.	55	P/Day	1500.00	Fifteen Hundred Only.	82,500

9.	P/L aggregate base course in proper grade and camber having CBR 80% as per AASHTO standard specification i/c spreading and compacting i/c spreading and compacting by approved mechanical means (motor grader, vibratory roller and smooth wheel roller etc) watering to maintain the moisture content the compaction of each layer shall 100 percent to the max dry density (Rate i/c all cost of materials T&P and carriage up to 3 chains).	3634	% Cft	5542.24	Fifty Four Hundred Forty Two & Twenty Four Paise Only.	2,01,405
----	--	------	-------	---------	---	----------

**KARACHI METROPOLITAN CORPORATION**  
**ENGINEERING DEPARTMENT**

Subject: CLEANING OF CATCH PITS / CHAMBERS PROVIDING OF MANHOLES COVERS / RCC SLABS, SUPPLY OF MATERIALS AND REPAIR OF TRENCHES IN MAURIPUR ROAD DISTRICT (WEST) KMC (RAIN EMERGENCY 2013).

Estimated Cost:- Rs. 9,78,976/=

Bid Security:- Rs. 20,000/=

Tender Cost: - Rs.2,500/=

I / We hereby quoted as follows:

1.	<b>PART - A:</b> (Items Based on S/R) amounting to Rs.8,18,207/= % Below the S/R.	Rs. _____
2.	<b>PART - B:</b> (Items Based on O/R)	Rs. _____
<b>GRAND TOTAL (A+B)</b>		Rs. _____

The total amount is Rs. \_\_\_\_\_ (in Figure) (Rupees \_\_\_\_\_ (In Words) \_\_\_\_\_ for complete job.

I / We have attached a pay order bearing No. \_\_\_\_\_ dated \_\_\_\_\_ issued from \_\_\_\_\_ amounting to Rs. \_\_\_\_\_ as per NIT.  
(Name of Bank)

**Completion Time : 30 Days**

**Penalty per day: Rs. 2,500/=**

**Note:**

- Tender must be quoted in figure & in words both otherwise liable to be cancelled.
- All over writing & correction if any must be initialed & stamped by the bidder.
- All prevailing rules regarding condition of contract will be applicable.
- 15% below is the maximum ceiling on schedule items 2012 by the authority.

**Signature of the Contractor with Stamp**

**Address:** \_\_\_\_\_

Checked By:-



Sr. # 2016

**KARACHI METROPOLITAN CORPORATION**

**ENGINEERING DEPARTMENT**



**Tender Reference No.KMC/CM/ED/ 49 /13-14**

**BILL OF QUANTITIES**

**CLEANING OF CATCH PITS / CHAMBERS PROVIDING OF MANHOLES  
COVERS / RCC SLABS, SUPPLY OF MATERIALS AND REPAIR OF  
TRENCHES IN METROVILLE ROAD DISTRICT (WEST) KMC  
(RAIN EMERGENCY 2013).**

**NOTE:**

The Condition of contract will be available on KMC website ([www.karachicity.gov.pk](http://www.karachicity.gov.pk)).

Estimate Cost: - Rs.9,78,450/=

Bid Security: - Rs.20,000/=

Tender Cost: - Rs.2,500/=

## **MINIMUM QUALIFICATION / ELIGIBILITY CRITERIA**

The evidence / documents of the following minimum qualification / eligibility criteria will be checked during opening process of tender & if anyone is missing then the tender will be summarily rejected at the moment by the tender opening committee.

### **Eligibility:**

- i). NTN Certificate
- ii). Valid Professional TAX.

### **Minimum Qualification Criteria:**

- iii). Bid Security, as mentioned in the NIT & Bidding Documents, is furnished.
- iv). All rates quoted including the total amount of the bid shall be in figures & words (both).
- v). All corrections / overwriting shall be clearly re-written with initials & duly stamped by the bidder.
- vi). The bid shall be properly signed, named & stamped by the authorized person of the firm and authorization letter for signatory shall be enclosed with the tender by the authorized Person, if other than the signatory of the firm.
- vii). The minimum turn over / work experience with satisfactory completion report in last 2 years or at least two or more works in hand and their aggregate cost should be equal to the work cost in which bidder interested to participate.

**Signature of the Bidder with Stamp**

**KARACHI METROPOLITAN CORPORATIN**  
**ENGINEERING DEPARTMENT**

**Subject:-** **CLEANING OF CATCH PITS / CHAMBERS PROVIDING OF MANHOLES COVERS / RCC SLABS, SUPPLY OF MATERIALS AND REPAIR OF TRENCHES IN METROVILLE ROAD DISTRICT (WEST) KMC (RAIN EMERGENCY 2013).**

Estimated Cost: **Rs.9,78,450/=**

Earnest Money: **Rs.20,000/=**

Tender Cost: **Rs.2,500/=**

S.No.	DESCRIPTION	QTY	UNIT	Rate (in figure)	Rate (in figure)	AMOUNT
1.	Excavation in shingle of gravel formation and rock not requiring blasting undressed, lead up to 100 ft (wet).	9838	% 0 Cft	6655.00	Sixty Six Hundred & Fifty Five Only.	65,472
2.	Providing and laying stone soling up to 9" thick i/c preparation of sub base etc complete.	6159	P/Cft	O/R		
3.	Cartage of 100 Cft / 5 Tones of all materials like stone aggregate, spawl, coal, lime, surkhi etc. B.G Rail fastenings points and crossing bridge girders pipes, 10"x5" or 1000 Maunds of fuel wood by trucks or any other means owned by the contractors (lead up to 15 miles etc).	9838	% Cft	1065.04	One Thousand Fifty Six & Four Paise Only.	1,04,779
4.	Manufacturing and supplying of RCC manhole cover cast in 1:2:4 concrete ratio 3 inch deep at centre, reinforced with 1/2" dia tor steel bars at 4" C/C welded to 3/16 thick 2" wide MS plate two hook of 3/8" dia tor bar including compacting i/c curing, and transportation with in 10 miles.					
	<b>21" Dia</b>	78	P/Cft	913.63	Nine Thousand Thirteen & Sixty Three Paise Only.	71,263
	<b>24" Dia</b>	25	P/Cft	1051.25	One Thousand Fifty One & Twenty Five Paise Only.	26,281
5.	Providing and fixing RCC precast slab / grating 4" to 6" thick i/c cost of transportation etc complete.	480	P/Sft	O/R		
6.	Manufacturing and supplying of RCC ring slab of 21" dia inside 36" dia outside 7.5 width and 6" thick i/c 3/8" dia tor steel bars two concentric rings with 3/8" dia 8 Nos. cross linked bars welded and two sunk type hooks,	35	P/Cft	1906.60	Nineteen Hundred Six & Sixty Paise Only.	66,731

	casted in a 1:1-1/2:3 concrete with embedded 15 Kg C.I frame in perfect position i/c transportation charges for an average lead of 20 KM per trip from casting yard to town offices (A minimum of 25 slabs per trip will be transported).					
7.	Cleaning inside sewerage lines completely restoring original silt free space/diameter of pipe lines by labor and equipment (Mechanically / Electrically driver) including accessories like pulley's steel rope, bucket and draggers sizing from 6" to 18" dia. Their "to and fro" pulling action (No. of passes shall be as many as required) would be taken in two phases (first phase entire length from down stream to up stream) bringing down peak hours sewerage to flow inside pipe line (as free flow) and in second phase from up stream to down stream of entire length ensuring no silt is observed in buckets (6" dia to 18" dia) except only sewage water and finally passing a steel ball of dia 12" lesser than the diameter of pipe but not exceeding 48" dia ball even for larger dia pipe to ensure perfect cleaning. The job includes all the hire/cost of equipment and accessories of above winching machine / devices along with / engines with winching drum set having steel rope pulley mounted over it, steel buckets from 6" to 18" dia hooks and other protection likes safety barriers, traffic signs, traffic cones ensuring no damage to pipe along with ensuring safety to labor and other public property / lives and removal of silts / solid during desalting and clearance of site etc complete as per full satisfaction of site Engineer.	1500	P/Ft	104.65	One Hundred Four & Sixty Five Paise Only.	1,56,975
8.	Full hire Charges of the pumping set per day inclusive of wage of driver and Assistant fuel or electric energy plate forms required for placing pumps etc at lower depth with suction and delivery pipes for pumping out water found at various depths from trenches i/c the cost of erection and dismantling after completion of the job. Hire charges of pumping set of up to 10 HP pumping out water from 10 ft water from 10 ft deep trench.	49	P/Day	1500.00	Fifteen Hundred Only.	73,500

9.	P/L aggregate base course in proper grade and camber having CBR 80% as per AASHTO standard specification i/c spreading and compacting i/c spreading and compacting by approved mechanical means (motor grader, vibratory roller and smooth wheel roller etc) watering to maintain the moisture content the compaction of each layer shall 100 percent to the max dry density (Rate i/c all cost of materials T&P and carriage up to 3 chains).	4,106	% Cft	5542.24	Fifty Four Hundred Forty Two & Twenty Four Paise Only.	2,27,564
----	--	-------	-------	---------	---	----------

**KARACHI METROPOLITAN CORPORATION**  
**ENGINEERING DEPARTMENT**

Subject: CLEANING OF CATCH PITS / CHAMBERS PROVIDING OF MANHOLES COVERS /  
RCC SLABS, SUPPLY OF MATERIALS AND REPAIR OF TRENCHES IN METROVILLE  
ROAD DISTRICT (WEST) KMC (RAIN EMERGENCY 2013).

Estimated Cost:- Rs. 9,78,450/=

Bid Security:- Rs. 20,000/=

Tender Cost: - Rs.2,500/=

I / We hereby quoted as follows:

1.	<b>PART – A:</b> (Items Based on S/R) amounting to Rs.7,92,565/= <b>% Below the S/R.</b>	Rs. _____
2.	<b>PART – B:</b> (Items Based on O/R)	Rs. _____
<b>GRAND TOTAL (A+B)</b>		Rs. _____

The total amount is Rs. \_\_\_\_\_ (Rupees \_\_\_\_\_  
(in Figure) (In Words) \_\_\_\_\_  
for complete job.

I / We have attached a pay order bearing No. \_\_\_\_\_ dated \_\_\_\_\_ issued from  
\_\_\_\_\_ amounting to Rs. \_\_\_\_\_ as per NIT.  
(Name of Bank)

**Completion Time : 30 Days**  
**Penalty per day: Rs. 2,500/=**

**Note:**

- Tender must be quoted in figure & in words both otherwise liable to be cancelled.
- All over writing & correction if any must be initialed & stamped by the bidder.
- All prevailing rules regarding condition of contract will be applicable.
- 15% below is the maximum ceiling on schedule items 2012 by the authority.

**Signature of the Contractor with Stamp**

**Address:** \_\_\_\_\_

Checked By:- \_\_\_\_\_

**KARACHI METROPOLITAN CORPORATION**

**ENGINEERING DEPARTMENT**



**Tender Reference No.KMC/CM/ED/ 50 /2013-14**

**BILL OF QUANTITIES**

**REPAIR OF TRENCHES UNDERPASS TO TRAFFIC POLICE CHOWKI AT  
SHAHRA-E-IQBAL, SCHEME-5, CLIFTON DISTRICT SOUTH, KMC.**

**NOTE:**

The Condition of contract will be available on KMC website ([www.karachicity.gov.pk](http://www.karachicity.gov.pk)).

Estimate Cost: - Rs.9,69,781/=

Bid Security: - Rs.20,000/=

Tender Cost: - Rs.2,500/=

## **MINIMUM QUALIFICATION / ELIGIBILITY CRITERIA**

The evidence / documents of the following minimum qualification / eligibility criteria will be checked during opening process of tender & if anyone is missing then the tender will be summarily rejected at the moment by the tender opening committee.

### **Eligibility:**

- i). NTN Certificate
- ii). Valid Professional TAX.

### **Minimum Qualification Criteria:**

- iii). Bid Security, as mentioned in the NIT & Bidding Documents, is furnished.
- iv). All rates quoted including the total amount of the bid shall be in figures & words (both).
- v). All corrections / overwriting shall be clearly re-written with initials & duly stamped by the bidder.
- vi). The bid shall be properly signed, named & stamped by the authorized person of the firm and authorization letter for signatory shall be enclosed with the tender by the authorized Person, if other than the signatory of the firm.
- vii). The minimum turn over / work experience with satisfactory completion report in last 2 years or at least two or more works in hand and their aggregate cost should be equal to the work cost in which bidder interested to participate.

**Signature of the Bidder with Stamp**



**KARACHI METROPOLITAN CORPORATIN**  
**ENGINEERING DEPARTMENT**

**Subject:-** **REPAIR OF TRENCHES UNDERPASS TO TRAFFIC POLICE CHOWKI AT SHAHRA-E-IQBAL, SCHEME-5, CLIFTON DISTRICT SOUTH, KMC.**

Estimated Cost: **Rs.9,69,781/=**

Earnest Money: **Rs.20,000/=**

Tender Cost: **Rs.2,500/=**

S.No.	DESCRIPTION	QTY	UNIT	Rate (in figure)	Rate (in figure)	AMOUNT
1.	Dismantling and removing of Road Metalling.	40	% Cft	605.00	Six Hundred & Five Only.	242
2.	Earth Work Excavation undressed lead up to a single throw of kassi phawrah or shovel.	440	% 0 Cft	1361.25	Thirteen Hundred Sixty One & Twenty Five Only	599
3.	Cartage of 100 Cft / 5 Tones of all materials like stone aggregate, spawl, coal, lime, surkhi etc. B.G Rail fastenings points and crossing bridge girders pipes sheets Rails M.S Bars etc or 1000 Nos. bricks 10'x5'x3' or 1000 Cft. Of timer or 100 Maunds of fuel wood by trucks or any other means owned by the contractors(lead up to 15 miles etc)	480	% Cft	1065.04	One Thousand Sixty Five & Four Paisa Only	5,112
4.	P/L Aggregate base course CBR 80% as per (AASHTO) standard specification i/c compacting to the required density by approved mechanical means (Vibratory roller road packer and smooth wheel roller etc) i/c watering with all lead and lift etc complete.	440	% Cft	5542.24	Fifty Four Hundred Forty Two & Twenty Four Paisa Only.	24,386
5.	Asphalt course laying to proper line & grade plant mixed asphalt concrete pavers finished (hydraulic / electronic) prepared to specified formula according to job mix formula approved by Engineer incharge i/c rolling & fixed using to proper line grade level and camber etc complete tack coat with bitumen 80/100 penetration all cost of material roller T&P and carriage of material from sand of supply to plant & plant to site of work 4 CM wearing course.	1888	% Sft	8274.73	Eighty Two Hundred Seventy Four & Seventy Three Paisa Only.	1,56,227

6.	Providing & Fixing pre-cast fair face RCC slab concrete 1:2:4 using screened graded bajri ¾" and down gauge having a minimum works cube crushing strength of 3000 lbs psi at 28 days of mix not leaner than 1:2:4 using sulphate resisting cement i/c the cost of mixing from approved benching plant transportation pouring with T-Mixture using fair face steel from work using the vibrator and complete including the cost of reinforcement as per shown in approved drawing including loading and unloading and fixing on drain with proper mean and jointing by 1:3 ratio on top as per direction of Engineer incharge.	1248	P/Sft	O.R		
----	---	------	-------	-----	--	--

**KARACHI METROPOLITAN CORPORATION**  
**ENGINEERING DEPARTMENT**

Subject: REPAIR OF TRENCHES UNDERPASS TO TRAFFIC POLICE CHOWKI AT SHAHRA-E-IQBAL, SCHEME-5, CLIFTON DISTRICT SOUTH, KMC.

Estimated Cost:- Rs. 9,69,781/=

Bid Security:- Rs. 20,000/=

Tender Cost: - Rs.2,500/=

I / We hereby quoted as follows:

1.	<b>PART - A:</b> (Items Based on S/R) amounting to Rs.1,86,566/=	Rs. _____
	<b>% Below the S/R.</b>	
<b>TOTAL</b>		Rs. _____

The total amount is Rs. \_\_\_\_\_ (Rupees \_\_\_\_\_  
(in Figure) (In Words) \_\_\_\_\_  
for complete job.

I / We have attached a pay order bearing No. \_\_\_\_\_ dated \_\_\_\_\_ issued from \_\_\_\_\_  
amounting to Rs. \_\_\_\_\_ as per NIT.  
(Name of Bank)

**Completion Time : 15 Days**

**Penalty per day: Rs. 2,500/=**

**Note:**

- Tender must be quoted in figure & in words both otherwise liable to be cancelled.
- All over writing & correction if any must be initialed & stamped by the bidder.
- All prevailing rules regarding condition of contract will be applicable.
- 15% below is the maximum ceiling on schedule items 2012 by the authority.

**Signature of the Contractor with Stamp**

**Address:** \_\_\_\_\_

Checked By:- \_\_\_\_\_

Sr. # 4.

**KARACHI METROPOLITAN CORPORATION**

**ENGINEERING DEPARTMENT**



**Tender Reference No.KMC/CM/ED/ 51 /2013-14**

**BILL OF QUANTITIES**

**RESTORATION OF TRENCHES / PATCHES IN-FRONT OF HABIB  
METROPOLITAN BANK MOHAMMAD/MASJID & BLOCK-4 AT  
UNIVERSITY ROAD GULISTAN-E-JOHAR.**

**NOTE:**

The Condition of contract will be available on KMC website ([www.karachicity.gov.pk](http://www.karachicity.gov.pk)).

Estimate Cost: - Rs.9,65,616/=  
Bid Security: - Rs.20,000/=  
Tender Cost: - Rs.2,500/=

## **MINIMUM QUALIFICATION / ELIGIBILITY CRITERIA**

The evidence / documents of the following minimum qualification / eligibility criteria will be checked during opening process of tender & if anyone is missing then the tender will be summarily rejected at the moment by the tender opening committee.

### **Eligibility:**

- i). NTN Certificate
- ii). Valid Professional TAX.

### **Minimum Qualification Criteria:**

- iii). Bid Security, as mentioned in the NIT & Bidding Documents, is furnished.
- iv). All rates quoted including the total amount of the bid shall be in figures & words (both).
- v). All corrections / overwriting shall be clearly re-written with initials & duly stamped by the bidder.
- vi). The bid shall be properly signed, named & stamped by the authorized person of the firm and authorization letter for signatory shall be enclosed with the tender by the authorized Person, if other than the signatory of the firm.
- vii). The minimum turn over / work experience with satisfactory completion report in last 2 years or at least two or more works in hand and their aggregate cost should be equal to the work cost in which bidder interested to participate.

**Signature of the Bidder with Stamp**

**KARACHI METROPOLITAN CORPORATIN**  
**ENGINEERING DEPARTMENT**

**Subject:-** **RESTORATION OF TRENCHES / PATCHES IN-FRONT OF HABIB METROPOLITAN BANK MOHAMMAD MASJID & BLOCK-4 AT UNIVERSITY ROAD GULISTAN-E-JOHAR.**

Estimated Cost: **Rs.9,65,616/=**

Earnest Money: **Rs.20,000/=**

Tender Cost: **Rs.2,500/=**

S.No.	DESCRIPTION	QTY	UNIT	Rate (in figure)	Rate (in figure)	AMOUNT
1.	Dismantling and removing of Road Metalling.	347	% Cft	605.00	Six Hundred & Five Only.	2,099
2.	Earth Work Excavation in ashes, sand soft soil or silt clearance undressed lead up to 50 ft ½ (excavation & embankment).	1065	% 0 Cft	1663.75	Sixteen Hundred Sixty Three & Paise Seventy Five Only.	1,772
3.	Cartage of excavated material earth work wet silt building material rubbish murrum earth including loading and unloading lead up to 15 miles.	1412	% Cft	1058.00	One Thousand Fifty Eight Only	14,938
4.	P/L aggregate base course over compacted granular sub base in confirm with lines, grades, thickness and typical cross section as shown in drawing for new pavement at grade / widening of existing pavement using well graded gravel or curve within a smooth gradation curve within the limits for grading "A" or "B" as per AASHTO-M-147 S-65 (1985) and compacting to 100% of the maximum dry density according to AASHTO T-180 method using approved mechanical means i/c watering with all lead and lift complete as per specification as directed by Engineer incharge.	3352	% Cft	5542.24	Fifty Four Hundred Forty Two & Twenty Four Paise Only.	1,85,775
5.	P/L 1 ½" thick Asphaltic concrete wearing course plant mix laying mechanically to proper line and grade plant mixed Asphalt concrete specified formula according to job mixed formula approved by the Engineer incharge rolling and finished to design proper grade line level and camber etc (machinery with POLs cost of material carriage).	12780.72	% Sft	6873.79	Sixty Eight Hundred Seventy Three & Seventy Nine Paise Only.	8,78,520
6.	Repair of RCC pipe leakage napco 18" dia pipe.	5	Each	O/R		

**KARACHI METROPOLITAN CORPORATION**  
**ENGINEERING DEPARTMENT**

Subject: RESTORATION OF TRENCHES / PATCHES IN-FRONT OF HABIB METROPOLITAN BANK MOHAMMAD/ MASJID & BLOCK-4 AT UNIVERSITY ROAD GULISTAN-E-JOHAR.

Estimated Cost:- Rs. 9,65,616/=

Bid Security:- Rs. 20,000/=

Tender Cost: - Rs.2,500/=

I / We hereby quoted as follows:

1.	<b>PART – A:</b> (Items Based on S/R) amounting to Rs.10,83,104/= % Below the S/R.	Rs. _____
2.	<b>PART – B:</b> (Items Based on O/R)	Rs. _____
<b>GRAND TOTAL (A+B)</b>		Rs. _____

The total amount is Rs. \_\_\_\_\_ (Rupees \_\_\_\_\_  
(in Figure) (In Words) \_\_\_\_\_  
\_\_\_\_\_ for complete job.

I / We have attached a pay order bearing No. \_\_\_\_\_ dated \_\_\_\_\_ issued from \_\_\_\_\_  
\_\_\_\_\_ amounting to Rs. \_\_\_\_\_ as per NIT.  
(Name of Bank)

**Completion Time : 15 Days**

**Penalty per day: Rs. 2,500/=**

**Note:**

- Tender must be quoted in figure & in words both otherwise liable to be cancelled.
- All over writing & correction if any must be initialed & stamped by the bidder.
- All prevailing rules regarding condition of contract will be applicable.
- 15% below is the maximum ceiling on schedule items 2012 by the authority.

**Signature of the Contractor with Stamp**

**Address:** \_\_\_\_\_

Checked By:- \_\_\_\_\_

St. # 5

**KARACHI METROPOLITAN CORPORATION**

**ENGINEERING DEPARTMENT**

*Correction in Part # 5  
only work to be done  
in the area of plot no. 31*



**Tender Reference No.KMC/CM/ED/ 52 /2013-14**

**BILL OF QUANTITIES**

**REPAIR OF TRENCH PLOT NO. 31 TO INTERNATIONAL SCHOOL,  
SCHEME-05 CLIFTON DISTRICT SOUTH, KMC.**

**NOTE:**

The Condition of contract will be available on KMC website ([www.karachicity.gov.pk](http://www.karachicity.gov.pk)).

Estimate Cost: - Rs.9,59,756/=

Bid Security: - Rs.20,000/=

Tender Cost: - Rs.2,500/=



## **MINIMUM QUALIFICATION / ELIGIBILITY CRITERIA**

The evidence / documents of the following minimum qualification / eligibility criteria will be checked during opening process of tender & if anyone is missing then the tender will be summarily rejected at the moment by the tender opening committee.

### **Eligibility:**

- i). NTN Certificate
- ii). Valid Professional TAX.

### **Minimum Qualification Criteria:**

- iii). Bid Security, as mentioned in the NIT & Bidding Documents, is furnished.
- iv). All rates quoted including the total amount of the bid shall be in figures & words (both).
- v). All corrections / overwriting shall be clearly re-written with initials & duly stamped by the bidder.
- vi). The bid shall be properly signed, named & stamped by the authorized person of the firm and authorization letter for signatory shall be enclosed with the tender by the authorized Person, if other than the signatory of the firm.
- vii). The minimum turn over / work experience with satisfactory completion report in last 2 years or at least two or more works in hand and their aggregate cost should be equal to the work cost in which bidder interested to participate.

**Signature of the Bidder with Stamp**

**KARACHI METROPOLITAN CORPORATIN**  
**ENGINEERING DEPARTMENT**

**Subject:-** **REPAIR OF TRENCH PLOT NO. 31 TO INTERNATIONAL SCHOOL,**  
**SCHEME-05 CLIFTON DISTRICT SOUTH, KMC.**

Estimated Cost: **Rs.9,59,756/=**

Earnest Money: **Rs.20,000/=**

Tender Cost: **Rs.2,500/=**

S.No.	DESCRIPTION	QTY	UNIT	Rate (in figure)	Rate (in figure)	AMOUNT
1.	Dismantling and removing of Road Metalling.	250	% Cft	605.00	Six Hundred & Five Only.	1,513
2.	Earth Work Excavation undressed lead up to a single throw of kassi phawrah or shovel.	2700	% 0 Cft	1361.25	Thirteen Hundred Sixty One & Twenty Five Only	3,675
3.	Cartage of 100 Cft / 5 Tones of all materials like stone aggregate, spawl, coal, lime, surkhi etc. B.G Rail fastenings points and crossing bridge girders pipes sheets Rails M.S Bars etc or 1000 Nos. bricks 10'x5'x3' or 1000 Cft. Of timer or 100 Maunds of fuel wood by trucks or any other means owned by the contractors(lead up to 15 miles etc)	2950	% Cft	1065.04	One Thousand Sixty Five & Four Paise Only	31,419
4.	P/L Granular Sub-Base Course as per (AASHTO) standard specifications i/c compacting to the required density by approved mechanical means (vibratory roller road packer and smooth wheel roller etc) i/c watering with all lead and lift etc complete.	792	% Cft	3341.71	Thirty Three Hundred Forty One & Seventy One Paise Only.	26,466
5.	P/L Aggregate base course CBR 80% as per (AASHTO) standard specification i/c compacting to the required density by approved mechanical means (Vibratory roller road packer and smooth wheel roller etc) i/c watering with all lead and lift etc complete.	1200	% Cft	5542.24	Fifty Four Hundred Forty Two & Twenty Four Paise Only.	66,507
6.	Asphalt course laying to proper line & grade plant mixed asphalt concrete pavers finished (hydraulic / electronic) prepared to specified formula according to job mix formula approved by Engineer incharge i/c rolling & fixed using to proper line grade level and	7200	% Sft	8274.73	Eighty Two Hundred Seventy Four & Seventy Three Paise Only.	5,95,780

	camber etc complete tack coat with bitumen 80/100 penetration all cost of material roller T&P and carriage of material from sand of supply to plant & plant to site of work 5 CM wearing course.					
7.	Providing & Fixing pre-cast fair face RCC slab concrete 1:2:4 using screened graded bajri ¾" and down gauge having a minimum works cube crushing strength of 3000 lbs psi at 28 days of mix not leaner than 1:2:4 using sulphate resisting cement i/c the cost of mixing from approved benching plant transportation pouring with T-Mixture using fair face steel from work using the vibrator and complete including the cost of reinforcement as per shown in approved drawing including loading and unloading and fixing on drain with proper mean and jointing by 1:3 ratio on top as per direction of Engineer incharge. <b>12" Thick</b>	528	P/Sft	O.R		

**KARACHI METROPOLITAN CORPORATION**  
**ENGINEERING DEPARTMENT**

Subject: REPAIR OF TRENCH PLOT NO. 31 TO INTERNATIONAL SCHOOL, SCHEME-05  
CLIFTON DISTRICT SOUTH, KMC.

Estimated Cost:- Rs. 9,59,756/=

Bid Security:- Rs. 20,000/=

Tender Cost: - Rs.2,500/=

I / We hereby quoted as follows:

1.	<b><u>PART - A:</u></b> (Items Based on S/R) amounting to Rs.7,25,360/=	Rs. _____
	<b>% Below the S/R.</b>	
2.	<b><u>PART - B:</u></b> (Items Based on O/R)	Rs. _____
<b>TOTAL</b>		Rs. _____

The total amount is Rs. \_\_\_\_\_ (Rupees \_\_\_\_\_ (In Words)  
(in Figure) \_\_\_\_\_ for complete job.

I / We have attached a pay order bearing No. \_\_\_\_\_ dated \_\_\_\_\_ issued from  
\_\_\_\_\_ amounting to Rs. \_\_\_\_\_ as per NIT.  
(Name of Bank)

**Completion Time : 15 Days**

**Penalty per day: Rs. 2,500/=**

**Note:**

- Tender must be quoted in figure & in words both otherwise liable to be cancelled.
- All over writing & correction if any must be initialed & stamped by the bidder.
- All prevailing rules regarding condition of contract will be applicable.
- 15% below is the maximum ceiling on schedule items 2012 by the authority.

**Signature of the Contractor with Stamp**

**Address:** \_\_\_\_\_

\_\_\_\_\_

Checked By:-

**KARACHI METROPOLITAN CORPORATION**

**ENGINEERING DEPARTMENT**



**Tender Reference No.KMC/CM/ED/ 53 /2013-14**

**BILL OF QUANTITIES**

**PROVIDING AND LAYING RCC PIPE SWD IN DIFFERENT AREA OF  
UNIVERSITY ROAD & SIR SHAH SULEMAN ROAD AT  
GULSHAN-E-IQBAL KARACHI.**

**NOTE:**

The Condition of contract will be available on KMC website ([www.karachicity.gov.pk](http://www.karachicity.gov.pk)).

Estimate Cost: - Rs.9,59,000/=

Bid Security: - Rs.20,000/=

Tender Cost: - Rs.2,500/=

## **MINIMUM QUALIFICATION / ELIGIBILITY CRITERIA**

The evidence / documents of the following minimum qualification / eligibility criteria will be checked during opening process of tender & if anyone is missing then the tender will be summarily rejected at the moment by the tender opening committee.

### **Eligibility:**

- i). NTN Certificate
- ii). Valid Professional TAX.

### **Minimum Qualification Criteria:**

- iii). Bid Security, as mentioned in the NIT & Bidding Documents, is furnished.
- iv). All rates quoted including the total amount of the bid shall be in figures & words (both).
- v). All corrections / overwriting shall be clearly re-written with initials & duly stamped by the bidder.
- vi). The bid shall be properly signed, named & stamped by the authorized person of the firm and authorization letter for signatory shall be enclosed with the tender by the authorized Person, if other than the signatory of the firm.
- vii). The minimum turn over / work experience with satisfactory completion report in last 2 years or at least two or more works in hand and their aggregate cost should be equal to the work cost in which bidder interested to participate.

**Signature of the Bidder with Stamp**

**KARACHI METROPOLITAN CORPORATIN**  
**ENGINEERING DEPARTMENT**

**Subject:-** **PROVIDING AND LAYING RCC PIPE SWD IN DIFFERENT AREA OF UNIVERSITY ROAD & SIR SHAH SULEMAN ROAD AT GULSHAN-E-IQBAL KARACHI.**

Estimated Cost: **Rs.9,59,000/=**

Earnest Money: **Rs.20,000/=**

Tender Cost: **Rs.2,500/=**

S.No.	DESCRIPTION	QTY	UNIT	Rate (in figure)	Rate (in figure)	AMOUNT
1.	Dismantling and removing of Road Metalling.	1125	% Cft	605.00	Six Hundred & Five Only.	6,806
2.	Dismantling of CC Plain & flooring situ in foundation and wall i/c disposal of surplus earth.	248	% Cft	3327.50	Thirty Three Hundred Twenty Seven & Fifty Paise Only.	8,252
3.	Earth Work Excavation in ashes, sand soft soil or silt clearance undressed lead up to 50 ft ½ (excavation & embankment).	9184	% 0 Cft	1663.75	Sixteen Hundred Sixty Three & Paise Seventy Five Only.	15,280
4.	Cartage of excavated material earth work wet silt building material rubbish murrum earth including loading and unloading lead up to 15 miles.	10557	% Cft	1058.00	One Thousand Fifty Eight Only	1,11,693
5.	Cement concrete plain including placing compacting finishing and curing complete i/c screening and washing at stone aggregate without shuttering. <b>Concrete 1:4:8</b>	12	% Cft	11288.75	Eleven Thousand Two Hundred Eighty Eight & Seventy Five Paise Only.	1,355
6.	<b>Concrete 1:2:4</b>	1148	% Cft	14429.25	Fourteen Thousand Four Hundred & Twenty Nine & Twenty Five Only.	1,65,648
7.	P/L 2" thick flooring cement concrete 1:2:4 i/c surfacing finishing and curing complete and dividing in to panels (2" thick).	744	% Sft	3275.50	Thirty Two Hundred Seventy Five & Fifty Paise Only.	24,370
8.	Providing and laying 4" thick dry stone metal etc complete.	744	% Sft	O/R.		
9.	R.C work in roof slab, beams, columns, raft, lintels and other structural members laid in situ or precast laid in position complete in all respect. i) Ratio (1:2:4) 90 Lbs cement 2 cft sand 4 cft shingle 1/8" to ¼ gauge.	96	P/Cft	258.61	Two Hundred Fifty Eight & Sixty One Paise Only.	24,827
10.	Fabrication of mild steel reinforcement for cement concrete i/c cutting, bending laying in position, making joints and fastening i/c cost of binding wires.	5.42	P/Cwt	4820.20	Forty Eighty Hundred Twenty & Twenty Paise Only.	26,125

11.	P/L 1 ½" thick Asphaltic concrete wearing course plant mix laying mechanically to proper line and grade plant mixed Asphalt concrete specified formula according to job mixed formula approved by the Engineer incharge rolling and finished to design proper grade line level and camber etc (machinery with POLs cost of material carriage).	459.66	% Sft	6873.79	Sixty Eight Hundred Seventy Three & Seventy Nine Paise Only.	31,596
12.	P/L Compacted granular Sub-Base in confirm with lines, grades, thickness and typical cross section as shown in drawing for new pavement at grade / widening of existing pavement using well graded gravel or curve within a smooth gradation curve within the limits for garding "A" or "B" as per AASHTO-M-147 S-65 (1985) and compacting to 100% of the maximum dry density according to AASHTO T-180 method using approved mechanical means i/c watering with all lead and lift complete as per specification as directed by Engineer incharge.	3288	% Cft	3341.71	Thirty Three Hundred Forty One & Seventy One Paise Only.	1,09,875
13.	P/L aggregate base course over compacted granular sub base in confirm with lines, grades, thickness and typical cross section as shown in drawing for new pavement at grade / widening of existing pavement using well graded gravel or curve within a smooth gradation curve within the limits for grading "A" or "B" as per AASHTO-M-147 S-65 (1985) and compacting to 100% of the maximum dry density according to AASHTO T-180 method using approved mechanical means i/c watering with all lead and lift complete as per specification as directed by Engineer incharge.	748	% Cft	5542.24	Fifty Four Hundred Forty Two & Twenty Four Paise Only.	41,456
14.	Providing & Laying RCC Pipes of ASTM C-76-62, T/C-76-70 of class II wall B and fixing and jointing with rubber ring i/c testing with water to a specified pressure.					



	a) 12" dia RCC pipe.	66	P/Rft	412.00	Four Hundred & Twelve Only.	27,192
	b) 18" dia RCC pipe.	424	P/Rft	618.00	Six Hundred & Eighteen Only.	2,62,032
15.	Providing chamber 3 x 1 ½" x ½" (1064 x 764 mm) inside dimension 7' (2.13 meter) deep as per approved design for 15" to 24" dia. Pipe with 24" inside dimension cast iron frame & RCC cover grating etc complete Add for extra depth beyond 4-1/2' i/c cost of CI foot rest for every 1 ft depth for depth less than 4-1/2' deduct at the same rates (3x12=36 inch)=36 x 4 = 144 inch.	1	Each	18820.00	Eighteen Thousand Eight Hundred & Twenty Only.	18,820
16.	Construction manhole for the required dia of circular sewer and 7'-9" with walls of B.B in cement mortar 1:3 cement plaster 1:3 1/2" thick inside of wall and 1" thick over benching and channel i/c fixing C.I manhole cover with frame of clear opening 2' x 2' of 4.5 cwt embedded in plain C.C 1:2:4 and two way reinforced 6" thick i/c fixing 1" dia M.S steps 6" wide projecting 4" from the face of wall at 12" C/C duly painted etc. complete as per standard specification and drawing. 49918-(3x2502)=42412	4	Each	42412.00	Forty Two Thousand Four Hundred & Twelve Only.	1,69,648
17.	Full hire charges of the pumping set per day inclusive of wages of driver and assistant fuel or electric energy plate forms required for placing pumps etc at lower depth with suction and delivery pipes for pumping out water found at various depths from trench i/c cost of erection and dismantling after completion of the job. Hire charges of pumping set of up to 10 Hp pumping out water from 10 ft deep trenches.	12	P/Day	1500	Fifteen Hundred Only.	18,000
18.	Assistant Machine Operator / Driver salary / wages	186.64	P/Day	250.00	Two Hundred & Fifty Only.	46,660

**KARACHI METROPOLITAN CORPORATION**  
**ENGINEERING DEPARTMENT**

Subject: PROVIDING AND LAYING RCC PIPE SWD IN DIFFERENT AREA OF UNIVERSITY ROAD & SIR SHAH SULEMAN ROAD AT GULSHAN-E-IQBAL KARACHI.

Estimated Cost:- Rs. 9,59,000/=  
Bid Security:- Rs. 20,000/=  
Tender Cost: - Rs.2,500/=

I / We hereby quoted as follows:

1.	<b>PART - A:</b> (Items Based on S/R) amounting to Rs.10,62,983/= % Below the S/R.	Rs. _____
2.	<b>PART - B:</b> (Items Based on O/R)	Rs. _____
<b>GRAND TOTAL (A+B)</b>		Rs. _____

The total amount is Rs. \_\_\_\_\_ (Rupees \_\_\_\_\_ (In Words)  
(in Figure) \_\_\_\_\_ for complete job.

I / We have attached a pay order bearing No. \_\_\_\_\_ dated \_\_\_\_\_ issued from  
\_\_\_\_\_ amounting to Rs. \_\_\_\_\_ as per NIT.  
(Name of Bank)

**Completion Time : 30 Days**  
**Penalty per day: Rs. 2,500/=**

**Note:**

- Tender must be quoted in figure & in words both otherwise liable to be cancelled.
- All over writing & correction if any must be initialed & stamped by the bidder.
- All prevailing rules regarding condition of contract will be applicable.
- 15% below is the maximum ceiling on schedule items 2012 by the authority.

**Signature of the Contractor with Stamp**

**Address:** \_\_\_\_\_

Checked By:-

Sr. #7

**KARACHI METROPOLITAN CORPORATION**  
**ENGINEERING DEPARTMENT**



**Tender Reference No.KMC/CM/ED/ 54 /2013-14**

**BILL OF QUANTITIES**

**REPAIR OF TRENCH NEAR MOHATTA PALACE TO PLOT NO. 52,**  
**SCHEME-5 CLIFTON DISTRICT SOUTH KMC.**

**NOTE:**

The Condition of contract will be available on KMC website ([www.karachicity.gov.pk](http://www.karachicity.gov.pk)).

Estimate Cost: - Rs.9,57,580/=

Bid Security: - Rs.20,000/=

Tender Cost: - Rs.2,500/=

## **MINIMUM QUALIFICATION / ELIGIBILITY CRITERIA**

The evidence / documents of the following minimum qualification / eligibility criteria will be checked during opening process of tender & if anyone is missing then the tender will be summarily rejected at the moment by the tender opening committee.

### **Eligibility:**

- i). NTN Certificate
- ii). Valid Professional TAX.

### **Minimum Qualification Criteria:**

- iii). Bid Security, as mentioned in the NIT & Bidding Documents, is furnished.
- iv). All rates quoted including the total amount of the bid shall be in figures & words (both).
- v). All corrections / overwriting shall be clearly re-written with initials & duly stamped by the bidder.
- vi). The bid shall be properly signed, named & stamped by the authorized person of the firm and authorization letter for signatory shall be enclosed with the tender by the authorized Person, if other than the signatory of the firm.
- vii). The minimum turn over / work experience with satisfactory completion report in last 2 years or at least two or more works in hand and their aggregate cost should be equal to the work cost in which bidder interested to participate.

**Signature of the Bidder with Stamp**

**KARACHI METROPOLITAN CORPORATIN**  
**ENGINEERING DEPARTMENT**

**Subject:-** **REPAIR OF TRENCH NEAR MOHATTA PALACE TO PLOT NO. 52,**  
**SCHEME-5 CLIFTON DISTRICT SOUTH KMC.**

Estimated Cost: **Rs.9,57,580/=**

Earnest Money: **Rs.20,000/=**

Tender Cost: **Rs.2,500/=**

S.No.	DESCRIPTION	QTY	UNIT	Rate (in figure)	Rate (in figure)	AMOUNT
1.	Dismantling and removing of Road Metalling.	595	% Cft	605.00	Six Hundred & Five Only.	3,600
2.	Earth Work Excavation undressed lead up to a single throw of kassi phawrah or shovel.	2400	% 0 Cft	1361.25	Thirteen Hundred Sixty One & Twenty Five Only	3,267
3.	Cartage of 100 Cft / 5 Tones of all materials like stone aggregate, spawl, coal, lime, surkhi etc. B.G Rail fastenings points and crossing bridge girders pipes sheets Rails M.S Bars etc or 1000 Nos. bricks 10'x5'x3' or 1000 Cft. Of timer or 100 Maunds of fuel wood by trucks or any other means owned by the contractors(lead up to 15 miles etc)	2995	% Cft	1065.04	One Thousand Sixty Five & Four Paisa Only	31,898
4.	P/L Granular Sub-Base Course as per (AASHTO) standard specifications i/c compacting to the required density by approved mechanical means (vibratory roller road packer and smooth wheel roller etc) i/c watering with all lead and lift etc complete.	1200	% Cft	3341.71	Thirty Three Hundred Forty One & Seventy One Paisa Only.	40,101
5.	P/L Aggregate base course CBR 80% as per (AASHTO) standard specification i/c compacting to the required density by approved mechanical means (Vibratory roller road packer and smooth wheel roller etc) i/c watering with all lead and lift etc complete.	1200	% Cft	5542.24	Fifty Four Hundred Forty Two & Twenty Four Paisa Only.	66,507
6.	Asphalt course laying to proper line & grade plant mixed asphalt concrete pavers finished (hydraulic / electronic) prepared to specified formula according to job mix formula approved by Engineer incharge i/c rolling & fixed using to proper line grade level and	7200	% Sft	8274.73	Eighty Two Hundred Seventy Four & Seventy Three Paisa Only.	5,95,780

	camber etc complete tack coat with bitumen 80/100 penetration all cost of material roller T&P and carriage of material from sand of supply to plant & plant to site of work 5 CM wearing course.				
6.	Providing & Fixing pre-cast fair face RCC slab concrete 1:2:4 using screened graded bajri ¾" and down gauge having a minimum works cube crushing strength of 3000 lbs psi at 28 days of mix not leaner than 1:2:4 using sulphate resisting cement i/c the cost of mixing from approved benching plant transportation pouring with T-Mixture using fair face steel from work using the vibrator and complete including the cost of reinforcement as per shown in approved drawing including loading and unloading and fixing on drain with proper mean and jointing by 1:3 ratio on top as per direction of Engineer incharge. <b>12" Thick</b>	504	P/Sft	O.R	

**KARACHI METROPOLITAN CORPORATION**  
**ENGINEERING DEPARTMENT**

Subject: REPAIR OF TRENCH NEAR MOHATTA PALACE TO PLOT NO. 52, SCHEME-5 CLIFTON DISTRICT SOUTH KMC.

Estimated Cost:- Rs. 9,57,580/=  
Bid Security:- Rs. 20,000/=  
Tender Cost: - Rs.2,500/=

I / We hereby quoted as follows:

1.	<b>PART - A:</b> (Items Based on S/R) amounting to Rs.7,41,153/= <b>% Below the S/R.</b>	Rs. _____
2.	<b>PART - B:</b> (Items Based on O/R)	Rs. _____
<b>TOTAL</b>		Rs. _____

The total amount is Rs. \_\_\_\_\_ (Rupees \_\_\_\_\_  
(in Figure) (In Words) \_\_\_\_\_  
\_\_\_\_\_ for complete job.

I / We have attached a pay order bearing No. \_\_\_\_\_ dated \_\_\_\_\_ issued from \_\_\_\_\_  
\_\_\_\_\_ amounting to Rs. \_\_\_\_\_ as per NIT.  
(Name of Bank)

**Completion Time : 15 Days**  
**Penalty per day: Rs. 2,500/=**

**Note:**

- Tender must be quoted in figure & in words both otherwise liable to be cancelled.
- All over writing & correction if any must be initialed & stamped by the bidder.
- All prevailing rules regarding condition of contract will be applicable.
- 15% below is the maximum ceiling on schedule items 2012 by the authority.

**Signature of the Contractor with Stamp**

**Address:** \_\_\_\_\_

Checked By:- \_\_\_\_\_

Sr. # 8

**KARACHI METROPOLITAN CORPORATION**  
**ENGINEERING DEPARTMENT**



**Tender Reference No.KMC/CM/ED/ 55 /2013-14**

**BILL OF QUANTITIES**

**REPAIR OF TRENCH FROM 2 TALWAR PETROL PUMP TO NEAR  
LICENCE OFFICE, SCHEME-5 CLIFTON DISTRICT SOUTH, KMC.**

**NOTE:**

The Condition of contract will be available on KMC website ([www.karachicity.gov.pk](http://www.karachicity.gov.pk)).

Estimate Cost: -	Rs.9,48,000/=
Bid Security: -	Rs.19,000/=
Tender Cost: -	Rs.2,500/=



## **MINIMUM QUALIFICATION / ELIGIBILITY CRITERIA**

The evidence / documents of the following minimum qualification / eligibility criteria will be checked during opening process of tender & if anyone is missing then the tender will be summarily rejected at the moment by the tender opening committee.

### **Eligibility:**

- i). NTN Certificate
- ii). Valid Professional TAX.

### **Minimum Qualification Criteria:**

- iii). Bid Security, as mentioned in the NIT & Bidding Documents, is furnished.
- iv). All rates quoted including the total amount of the bid shall be in figures & words (both).
- v). All corrections / overwriting shall be clearly re-written with initials & duly stamped by the bidder.
- vi). The bid shall be properly signed, named & stamped by the authorized person of the firm and authorization letter for signatory shall be enclosed with the tender by the authorized Person, if other than the signatory of the firm.
- vii). The minimum turn over / work experience with satisfactory completion report in last 2 years or at least two or more works in hand and their aggregate cost should be equal to the work cost in which bidder interested to participate.

**Signature of the Bidder with Stamp**

**KARACHI METROPOLITAN CORPORATIN**  
**ENGINEERING DEPARTMENT**

**Subject:-** **REPAIR OF TRENCH FROM 2 TALWAR PETROL PUMP TO NEAR LICENCE OFFICE, SCHEME-5 CLIFTON DISTRICT SOUTH, KMC.**

Estimated Cost: **Rs.9,48,000/=**

Earnest Money: **Rs.19,000/=**

Tender Cost: **Rs.2,500/=**

S.No.	DESCRIPTION	QTY	UNIT	Rate (in figure)	Rate (in figure)	AMOUNT
1.	Dismantling and removing of Road Metalling.	1110	% Cft	605.00	Six Hundred & Five Only.	6,716
2.	Earth Work Excavation undressed lead up to a single throw of kassi phawrah or shovel.	11760	% 0 Cft	1361.25	Thirteen Hundred Sixty One & Twenty Five Only	16,008
3.	Cartage of 100 Cft / 5 Tones of all materials like stone aggregate, spawl, coal, lime, surkhi etc. B.G Rail fastenings points and crossing bridge girders pipes sheets Rails M.S Bars etc or 1000 Nos. bricks 10'x5'x3' or 1000 Cft. Of timer or 100 Maunds of fuel wood by trucks or any other means owned by the contractors(lead up to 15 miles etc).	12870	% Cft	1065.04	One Thousand Sixty Five & Four Paisa Only	1,37,070
4.	P/L Granular Sub-Base Course as per (AASHTO) standard specifications i/c compacting to the required density by approved mechanical means (vibratory roller road packer and smooth wheel roller etc) i/c watering with all lead and lift etc complete.	1125	% Cft	3341.71	Thirty Three Hundred Forty One & Seventy One Paisa Only.	37,594
5.	P/L Aggregate base course CBR 80% as per (AASHTO) standard specification i/c compacting to the required density by approved mechanical means (Vibratory roller road packer and smooth wheel roller etc) i/c watering with all lead and lift etc complete.	2235	% Cft	5542.24	Fifty Four Hundred Forty Two & Twenty Four Paisa Only.	1,23,869
6.	Asphalt course laying to proper line & grade plant mixed asphalt concrete pavers finished (hydraulic / electronic) prepared to specified formula according to job mix formula approved by Engineer incharge i/c rolling & fixed using	9600	% Sft	8274.73	Eighty Two Hundred Seventy Four & Seventy Three Paisa Only.	7,94,374

to proper line grade level and camber etc complete tack coat with bitumen 80/100 penetration all cost of material roller T&P and carriage of material from sand of supply to plant & plant to site of work 5 CM wearing course.					
---	--	--	--	--	--

**KARACHI METROPOLITAN CORPORATION**  
**ENGINEERING DEPARTMENT**

Subject: REPAIR OF TRENCH FROM 2 TALWAR PETROL PUMP TO NEAR LICENCE OFFICE, SCHEME-5 CLIFTON DISTRICT SOUTH, KMC.

Estimated Cost:- Rs. 9,48,000/=

Bid Security:- Rs. 19,000/=

Tender Cost: - Rs.2,500/=

I / We hereby quoted as follows:

1.	<b>PART - A:</b> (Items Based on S/R) amounting to Rs.11,15,632/= % Below the S/R.	Rs. _____
2.	<b>PART - B:</b> (Items Based on O/R)	Rs. _____
<b>TOTAL</b>		Rs. _____

The total amount is Rs. \_\_\_\_\_ (Rupees \_\_\_\_\_ (In Words) \_\_\_\_\_ (in Figure) \_\_\_\_\_ for complete job.

I / We have attached a pay order bearing No. \_\_\_\_\_ dated \_\_\_\_\_ issued from \_\_\_\_\_ amounting to Rs. \_\_\_\_\_ as per NIT.  
(Name of Bank)

**Completion Time : 15 Days**

**Penalty per day: Rs. 2,500/=**

**Note:**

- Tender must be quoted in figure & in words both otherwise liable to be cancelled.
- All over writing & correction if any must be initialed & stamped by the bidder.
- All prevailing rules regarding condition of contract will be applicable.
- 15% below is the maximum ceiling on schedule items 2012 by the authority.

**Signature of the Contractor with Stamp**

**Address:** \_\_\_\_\_

Checked By:- \_\_\_\_\_

**KARACHI METROPOLITAN CORPORATION**

**ENGINEERING DEPARTMENT**



**Tender Reference No.KMC/CM/ED/ 56 /2013-14**

**BILL OF QUANTITIES**

**REPAIR/MAINTENANCE OF FLAT NO.B/6, GULISTAN-E-MUSTAFA FIRE STATION, FIRE BRIGADE KMC.**

**NOTE:**

The Condition of contract will be available on KMC website ([www.karachicity.gov.pk](http://www.karachicity.gov.pk)).

Estimate Cost: - Rs.3,14,140/=

Bid Security: - Rs.6,500/=

Tender Cost: - Rs.1,000/=

## **MINIMUM QUALIFICATION / ELIGIBILITY CRITERIA**

The evidence / documents of the following minimum qualification / eligibility criteria will be checked during opening process of tender & if anyone is missing then the tender will be summarily rejected at the moment by the tender opening committee.

### **Eligibility:**

- i). NTN Certificate
- ii). Valid Professional TAX.

### **Minimum Qualification Criteria:**

- iii). Bid Security, as mentioned in the NIT & Bidding Documents, is furnished.
- iv). All rates quoted including the total amount of the bid shall be in figures & words (both).
- v). All corrections / overwriting shall be clearly re-written with initials & duly stamped by the bidder.
- vi). The bid shall be properly signed, named & stamped by the authorized person of the firm and authorization letter for signatory shall be enclosed with the tender by the authorized Person, if other than the signatory of the firm.
- vii). The minimum turn over / work experience with satisfactory completion report in last 2 years or at least two or more works in hand and their aggregate cost should be equal to the work cost in which bidder interested to participate.

**Signature of the Bidder with Stamp**

**KARACHI METROPOLITAN CORPORATIN**  
**ENGINEERING DEPARTMENT**

**Subject:-** **REPAIR/MAINTENANCE OF FLAT NO.B/6, GULISTAN-E-MUSTAFA**  
**FIRE STATION, FIRE BRIGADE KMC.**

Estimated Cost: **Rs.3,14,140/=**

Bid Security: **Rs.6,500/=**

Tender Cost: **Rs.1,000/=**

S.No.	DESCRIPTION	QTY	UNIT	Rate (in figure)	Rate (in figure)	AMOUNT
1.	Removing door with chowkat.	9	Each	142.18	One Hundred Forty Two & Eighteen Paisa Only.	1,279
2	P/F of G.I Frames / Chowkats of size 7" x 2" or 4½" x 3" for window using 20 gauge G.I Sheet i/c welded hinges and fixing at site with necessary hold fasts.	144	P/Rft	228.90	Two Hundred Twenty Eight & Ninety Paisa Only.	32,961
3.	1" thick battened door and window fitted in position complete with iron without chowkat.	146	P/Sft	583.67	Five Hundred Eighty Three & Sixty Seven Paisa Only.	85,216
4.	P/L Granite full porcelain matt finish floor tiles grade at any size and shape i/c 1" thick C/C bed or pigmentation chemical liquid as per site requirement.	348	P/Sft	O/R		
5.	P/F iron grill steel door with angle iron frame of 1 ½" x 1 ½" x ¼" and flat iron of ¼" x ¼" with approved design and loading arrangement etc.	19	P/Sft	231.60	Two Hundred Thirty One & Sixty Paisa Only.	4,400
6.	P/F cabinet shutters made ¾" thick lasani sheet fixed Formica over sheet i/c deodar as wood frame i/c catcher etc complete as per direction of E/L.	34	P/Sft	O/R		
7.	Scraping ordinary distemper oil bond distemper or paint on walls.	1662	% Sft	226.88	Two Hundred Twenty Six & Eighty Eight Paisa Only	3,771
8.	Distemping three coats.	1982	% Sft	1079.65	One Thousand Seventy Nine & Sixty Five Paisa Only.	21,398
9.	S/F in position Aluminum channels framing for sliding window & ventilators of Alcop with 5 mm thick tinted glass & locking arrangement.	37	P/Sft	1647.69	Sixteen Hundred Forty Seven & Sixty Nine Paaisa Only	60,964

10.	Preparing surface and painting guard bars, gates iron bars, grating, railing i/c standard braces etc and similar open work <b>two coats.</b>	87	% Sft	371.80 <u>302.80</u> 674.60	Six Hundred Seventy Four & Sixty Paisa Only.	587
11	Painting door and window any type two coats.	292	% Sft	657.91 <u>502.15</u> 1160.06	Eleven Hundred Sixty & Six Paisa Only	3,387
12.	P/L tiles glazed 6"x6"x 1/4" on floor or wall facing in required color and pattern of STILE specification jointed with W/C and pigmentation etc.	115	% Sft	30,509.77	Thirty Thousand Five Hundred Nine & Seventy Seven Paisa Only.	35,086
13.	P/F approved quality Mortice lock.	9	Each	1786.13	Seventeen Hundred Eighty Six & Thirteen Paisa Only.	16,075
14.	Aluminum wire gauge 144 mesh P.S fixed to chowkats with 3/4" deodar strips and screw.	19	P/Sft	222.40	Two Hundred Twenty Two & Forty Paisa Only	4,225



**KARACHI METROPOLITAN CORPORATION**  
**ENGINEERING DEPARTMENT**

Subject: REPAIR/MAINTENANCE OF FLAT NO.B/6, GULISTAN-E-MUSTAFA FIRE STATION,  
FIRE BRIGADE KMC.

Estimated Cost:- Rs. 3,14,140/=

Bid Security:- Rs. 6,500/=

Tender Cost: - Rs.1,000/=

I / We hereby quoted as follows:

1.	<b>PART - A:</b> (Items Based on S/R) amounting to Rs.2,69,349/= % Below the S/R.	Rs. _____
2.	<b>PART - B:</b> (Items Based on O/R)	Rs. _____
<b>GRAND TOTAL (A+B)</b>		Rs. _____

The total amount is Rs. \_\_\_\_\_ (Rupees \_\_\_\_\_  
(in Figure) (In Words)

\_\_\_\_\_ for complete job.

I / We have attached a pay order bearing No. \_\_\_\_\_ dated \_\_\_\_\_ issued from \_\_\_\_\_  
(Name of Bank) amounting to Rs. \_\_\_\_\_ as per NIT.

**Completion Time : 60 Days**

**Penalty per day: Rs. 1,000/=**

**Note:**

- Tender must be quoted in figure & in words both otherwise liable to be cancelled.
- All over writing & correction if any must be initialed & stamped by the bidder.
- All prevailing rules regarding condition of contract will be applicable.
- 20% below is the maximum ceiling on schedule items 2012 by the authority.

**Signature of the Contractor with Stamp**

**Address:** \_\_\_\_\_

Checked By:- \_\_\_\_\_

**KARACHI METROPOLITAN CORPORATION**

**ENGINEERING DEPARTMENT**



**Tender Reference No.KMC/CM/ED/ 57 /2013-14**

**BILL OF QUANTITIES**

**REPAIR/MAINTENANCE WORK IN FLAT NO.4 OFFICERS FLATS**  
**KARSAZ KARACHI.**

**NOTE:**

The Condition of contract will be available on KMC website ([www.karachicity.gov.pk](http://www.karachicity.gov.pk)).

Estimate Cost: - Rs.4,97,930/=

Bid Security: - Rs.10,000/=

Tender Cost: - Rs.1,000/=

## **MINIMUM QUALIFICATION / ELIGIBILITY CRITERIA**

The evidence / documents of the following minimum qualification / eligibility criteria will be checked during opening process of tender & if anyone is missing then the tender will be summarily rejected at the moment by the tender opening committee.

### **Eligibility:**

- i). NTN Certificate
- ii). Valid Professional TAX.

### **Minimum Qualification Criteria:**

- iii). Bid Security, as mentioned in the NIT & Bidding Documents, is furnished.
- iv). All rates quoted including the total amount of the bid shall be in figures & words (both).
- v). All corrections / overwriting shall be clearly re-written with initials & duly stamped by the bidder.
- vi). The bid shall be properly signed, named & stamped by the authorized person of the firm and authorization letter for signatory shall be enclosed with the tender by the authorized Person, if other than the signatory of the firm.
- vii). The minimum turn over / work experience with satisfactory completion report in last 2 years or at least two or more works in hand and their aggregate cost should be equal to the work cost in which bidder interested to participate.

**Signature of the Bidder with Stamp**

**KARACHI METROPOLITAN CORPORATIN**  
**ENGINEERING DEPARTMENT**

**Subject:-** REPAIR/MAINTENANCE WORK IN FLAT NO.4 OFFICERS FLATS  
KARSAZ KARACHI.

Estimated Cost: **Rs.4,79,930/=**

Bid Security: **Rs.10,000/=**

Tender Cost: **Rs.1,000/=**

S.No.	DESCRIPTION	QTY	UNIT	Rate (in figure)	Rate (in figure)	AMOUNT
1.	Dismantling Cement Block Masonry.	138	% Cft	1134.38	Eleven Hundred Thirty Four & Thirty Eight Only.	1,565
2.	Dismantling of cement concrete plain 1:2:4.	67	% Cft	3327.50	Thirty Three Hundred Twenty Seven & Fifty Paisa Only.	2,229
3.	Dismantling slates or tiles including battens purling and planking.	152	% Sft	605	Six Hundred & Five Only.	920
4.	Scraping ordinary paint.	3514	% Sft	226.88	Two Hundred Twenty Six & Eighty Eight paisa Only.	7,973
5.	Fabrication of Tor Steel reinforcement for cement concrete including cutting bending laying in position making joints and fastenings including cost of binding wire (also includes removal of rust from bars) Tor Bars.	6.69	P.Cwt	5001.00	Five Thousand One Only.	33,457
6.	Providing and laying tiles glazed 6"x6"x ¼" on floor or wall facing n required color and pattern of STILE specification jointed in white cement and pigment over a base of 1:2 grey cement mortar ¼" thick including washing and filing of joints with slaury of white cement and pigment in desired shape with finishing cleaning and cost of wax polish etc complete including cutting tiles to proper profile.	152	% Sft	30,509.77	Thirty Thousand Five Hundred Nine & Seventy Seven Paisa Only.	46,375
7.	Removing cement or lime plaster.	450	% Sft	121.00	One Hundred Twenty One Only.	545
8.	P/L 1:3:6 of Cement Concrete solid block masonry wall 6" and below in thickness set in 1:6 cement mortars in ground floor super structure i/c raking out joints and curing etc complete.	175	% Cft	15771.01	Fifteen Thousand Seven Hundred Seventy One & One Paisa Only.	27,599

9.	Pre-Cast Reinforced Cement Concrete Ratio 1:2:4 Slab 2" thick.	240	P/Sft	O/R		
10.	RCC Beam 5" x 9" (I. Section).	108	P/Rft	O/R		
12.	Erection & Fixing in position Pre-Cast Cement concrete or stone slab in roofs or lintels, lift up to 20 feet including all charges.	240	P/Cft	41.77	Forty One Rupees & Seventy Seven Paise Only.	10,025
13.	P/L 2" thick topping cement concrete 1:2:4 i/c surface finishing and dividing in to panels.	300	% Sft	3275.50	Thirty Two Hundred Seventy Five & Fifty Paise Only.	9,827
14.	Cement plaster 1:4 up to 12' height ½" thick.	1150	% Sft	2283.93	Twenty Two Hundred Eighty Three & Ninety Three Paise Only.	26,265
15.	Providing & fixing iron steel grill using solid square bars of size ½" x ½" placed at 4" i/c and frame of flat iron patti of ¾" x ¾" i/c circle shape at 1-0 apart equivalent fitted with screws are pins i/c painting 3 coats with 1 <sup>st</sup> coat of red oxide paint etc.	64	P/Sft	194.16	One Hundred Ninety Four & Sixteen Paise Only.	12,426
16.	Providing & fixing deodar wooden wardrobe i/c boxing with back shelves shutters drawers and brass fittings such as handles locking arrangement hanger rod shoe rod and mirror measuring 2'x1' complete as per approved design.	16	P/Sft	2364.63	Twenty Three Hundred Sixty Four & Sixty Three paise Only.	37,834
17.	Providing & fixing in position doors windows and ventilators of 2"x2" ¼" angle iron frames and 1 ¼" thick commercial ply wood veneer shutters of deodar wood (3 ply) on both sides i/c hold fasts, cheats iron tower bolts handles hinges and one mortise lock.	21	P/Sft	1227.36	Twelve Hundred Twenty Seven & Thirty Six Paise Only.	25,775
18.	Distempering two coats.	1177	% Sft	1079.65	One Thousand Seventy Nine & Sixty Five Paise Only.	12,707
19.	Preparing the surface & painting with matt finish paint of approved make to old matt finish surface. Two coat. 2 <sup>nd</sup> & subsequent coat.	6450	% Sft	1772.38	Seventeen Hundred Seventy Two & Thirty Eight paise Only.	11,432
20.	Providing & laying HALA or gattewrn tiles glazed 8" x 8" x ¼" on floor or wall facing in required pattern of STILE specification jointed in white cement and pigment	505	% Sft	34520.31	Thirty Four Thousand Five Hundred Twenty & Thirty One Paise Only.	1,74,328


	over a base of 1:2 grey cement mortar ¼" thick including washing and filling of joints with slurry of white cement and pigment in desired shape with finishing cleaning and cost of wax polish etc. complete including cutting tiles to proper profile..					
21.	Dismantling cement concrete plain 1:3:6.	265	% Cft	1306.80	Thirteen Hundred Six & Eighty Paiza Only	3,463
22.	P/L 1 thick toping cement concrete 1:2:4 i/c surface finishing and dividing in to panels. 2" thick.	600	% Sft	3275.50	Thirty Two Hundred Seventy Five & Fifty Paiza Only.	19,653
23.	S/F in position Aluminum channels framing for sliding window & ventilators of Alcop made with 5 mm thick tinted glass glazing (Belgium) & Aluminum fly screen i/c handles stoppers & locking arrangement etc complete. Deluxe model white.	80	P/Sft	1592.69	Fifteen Hundred Ninety Two & Sixty Nine Paiza Only.	1,27,415

**KARACHI METROPOLITAN CORPORATION  
ENGINEERING DEPARTMENT**

Subject: REPAIR/MAINTENANCE WORK IN FLAT NO.4 OFFICERS FLATS KARSAZ  
KARACHI.

Estimated Cost:- Rs. 4,97,930/=  
Bid Security:- Rs. 10,000/=  
Tender Cost: - Rs.1,000/=

I / We hereby quoted as follows:

<b>PART - A:</b>	
1. (Items Based on S/R) amounting to Rs.5,91,813/= % Below the S/R.	Rs. _____
	Rs. _____
(Items Based on S/R)	Rs. _____
<b>GRAND TOTAL (A+B)</b>	Rs. _____

The total amount is Rs. \_\_\_\_\_ (in Figure) (Rupees) \_\_\_\_\_ (In Words) \_\_\_\_\_ for complete job.

I / We have attached a pay order bearing No. \_\_\_\_\_ dated \_\_\_\_\_ issued from \_\_\_\_\_ amounting to Rs. \_\_\_\_\_ as per NIT.  
(Name of Bank)

Completion Time : 60 Days  
Penalty per day: Rs. 1,000/=

- Note:**
- Tender must be quoted in figure & in words both otherwise liable to be cancelled.
  - All over writing & correction if any must be initialed & stamped by the bidder.
  - All prevailing rules regarding condition of contract will be applicable.
  - 20% below is the maximum ceiling on schedule items 2012 by the authority.

**Signature of the Contractor with Stamp**

**Address:** \_\_\_\_\_

Checked By:-