$\frac{1^{\text{ST}} \ \text{Floor Co-operative Market Saddar Karachi..}}{\text{Cell: } \underline{0333-2313530}}$

NOTICE INVITING TENDER (ON ITEM RATE BASIS) (Under 1.00 Million)

Sealed tenders are invited under SPPRA Rule-2010 for the work mentioned below:-

Sr.	Detail	Description	
01.	NAME OF WORK	REPLACEMENT OF OLD & UNSERVICEABLE 15" DIA & 12" DIA IN DIFFERENT STREETS UC-1, 2, 5 & 6 SADDAR TOWN. (SEW).	
02.	Tender can be purchased.	Office of the Accounts Officer (Revenue), KW&SB Head Office, at 1 st Floor Old KBCA Annexy Building, Behind Civic Centre, Gulshan-e-Iqbal Karachi, between 9:00 am to 01:00 Pm in any working day except the date of opening of the tenders.	
03.	Tender Fee:	Rs.1,000/= Non Refundable in shape of Pay Order in favour of KW&SB.	
04.	Bid Security	2% of Bid Security of the Quoted Cost / Price in shape of Pay Order / Bank Draft for any schedule Bank of Pakistan in favour of KW&SB. Bid Security must be accompanied with the Tender otherwise the tenders shall be treated as invalid & rejected.	
05.	Issuing date of Tenders & Last Date Purchasing of Tenders.	w.e.f 1 st day of Hoisting of SPPRA Website, to 22/11/2013. from 9:00 am to 1:00 Pm	
06.	Date & time of submission of tenders & opening of Tenders.	25/11/2013. up to 02:00 Pm and will be opened at 02:30 Pm.	
07.	Place of Opening:	Tender will be open by the Procurement Committee-I, at the office of the Chief Engineer (IP&D), KW&SB at 9 th Mile Karsaz, Shahrah-e-Faisal, Karachi.	
08.	Source of Funding	KW&SB's Own Fund.	
09.	Estimated Cost	Rs.4,43,830/=	
10.	Scope of work	For improvement of Sewerage System.	

Note:

- 1. The Procuring Agency may reject all or any bids subject to the relevant provision of SPP Rule-2010.
- 2. Tender / biding documents may be downloaded from SPPRA Website.
- 3. In case of undesirable circumstances on submission of opening date & time or if Government declares Holiday the tender shall be submitted / opened on the next working day at the same time & venue.
- 4. No Tender shall be issued on the date of Opening of Tender.

(KARACHI WATER & SEWERAGE BOARD)



KARACHI WATER & SEWERAGE BOARD

OFFICE OF THE EXECUTIVE ENGINEER (SEW) (SADDAR OLD CITY, DISTRICT SOUTH)

1ST Floor Co-operative Market Saddar Karachi.. Cell: <u>0333-2313530</u>

SUBJECT:- REPLACEMENT OF OLD & UNSERVICEABLE 15" DIA & 12" DIA IN DIFFERENT STREETS UC-1, 2, 5 & 6 SADDAR TOWN, (SEW).

Estimated Cost	On Item Rate Basis.	Issued to M/S	
Time Limit	30 Days		
Tender Cost	Rs.1000/=	Pay Order No	Dated:
Penalty	Rs.1000/=		

				ISSUING	AUTHORITY
Sr.	Description	Quantity	Rate	Per	Amount
01.	Scarifying the existing road surface.	4500.04		0/ Cft	
02.	Diamentling and removing read metalling	1500 Sft. 3000 Cft.		% Sft % Cft	
03.	Dismantling and removing road metalling. Excavation for Pipe line in trenches, and pits in all kinds of Soils or murum i/c. trimming and dressing sides to true alignment and shape leveling of bads of trenches to correct level and grade cutting joint holes and disposal of surplus earth within a one chain as directed by the Engineer Incharge. Providing fence guard's	3000 Cit.		% CIL	
	ligts, flags and temporary crossing for nonvehicular traffic where over required lifts upto 5 ft (1.52m) and lead upto one chain (30.5m). i. Lift 0' - 5'	4500 Cft. 2475 Cft.		% 0Cft	
04.	Full Hire Charges of Pumping set per day inclusive of the wages of driver and assistant, fuel and electric energy plate from required for placing the pump etc, at lower depth with suction and delivery pipe for pumping out water pound at various depth from trenches including the cost of erection and dismantling after completion	00 D		0.0	
05.	of job of 10HP form 10 Feet Depth. Providing laying RCC Pipes with (Rubber Ring Joint and fitting i/c. cutting, fitting and jointing with rubber ring i/c. testing with water to specified pressure. 12" dia	06 Days.		P/Day P/Rft	
06.	Providing M/H 4 feet internal diameter without RCC manhole cover with CI frame (15Kg) and feet clear depth cast in situ 1:2: 9" thick wall 1:4:8 cement concrete in 6ft dia and 6 inch thick in foundation, 1:2:4 CC in benching ½" thick cement plaster 1:3 cement mortar on inside wall and surface of channel and benching to top including making required numbers of main and branches channels ¾" dia bars M.S foot rest at 12" C/C including cost of excavation in all kinds of soil, back filling and disposal of excavated stuff etc complete, as per design and instruction of	150 Rft.		P/Rft	
	the Engineer Incharge.	06 Nos.		Each	

SUBJECT:- REPLACEMENT OF OLD & UNSERVICEABLE 15" DIA & 12" DIA IN DIFFERENT STREETS UC-1, 2, 5 & 6 SADDAR TOWN, (SEW).

Sr.	Description	Quantity	Rate	Per	Amount
07.	Add / deduct per ft depth.	+ 8.0		P/Ft	
08.	Making connection with existing Manholes i/c. her cost of cutting holes in walls making them goodd in cement concrete 1:2:4 and making the required channel etc complete.	08 Nos.		Each	
09.	Refilling the excavated stuff in trenches 6" thick layer i/c. watering ramming to full compaction etc complete.	6340.5 Cft.		% 0Cft	
10.	Sand Haro or any other source Sand of the same modules of the Finences (Hill Sand).	2512.5 Cft		% Cft	
11.	Carriage of 100 Cft./5 Tons of all materials like stone aggregate. Spawl, coal, lime, surkhi, etc. B.G Rail fastening points and crossing bridge, Girders, Pipes, Sheet Rail, M.S Bars etc. Nos: 1000 Nos: titles, 12"x16"x2" or 150 Cft of timber or 100 Maunds of fuel wood by trucks or any other means owned by the contractors. 2nd Mile 407.00	3147 Cft		• % Cft	
12.	Manufacturing and supplying of 21" dia RCC manhole cover cast in 1:2:4 concrete ration 3 inch deep at center, reinforced with ½" dia tor steel bars at 4" c/c welded to 3/6" thick 2" wide MS plate Two hook of 3/8" dia tor bar including compacting i/c. curing and transportation in 10 miles. 21" dia	06 Nos.		Each	
	· · · · · · · · · · · · · · · · · · ·		2	Total	,

EXECUTIVE ENGINEER (SEW)
SADDAR OLD CITY DISTRICT SOUTH
(KW&SB)

I hereby quoted bid amount of Rs.	(Rupees in words
	Signature of Contractor
	Address