

# 209/13-14

## KEAMARI ZONE, DISTRICT MUNICIPAL CORPORATION (WEST), KARACHI

Mauripur Grex, Main Hawksbay Road, Karachi  
 Phone: 021-99241320 Fax: 021-99241321 Email: Keamaritown@gmail.com

No: EE/KZ/DMC(W)/ 04 /2013-14

Dated: 04.11.2013

**SUBJECT: NOTICE FOR INVITING TENDER.**

Keamari Zone, DMC(West), Karachi invites sealed tenders on Schedule Rate / Offer Rate Basis for the works mentioned below from the interested Firms/Contractors, according to the SPPRA Rules-2010. Details given below:-

S.No:	NAME OF WORK	ESTIMATED COST	EARNEST MONEY	TENDER COST	TIME LIMIT
	CONSTRUCTION OF UNDERGROUND WATER TANK AT UMER HISHOO GOTH UC.No:08, GABOPAT KEAMARI ZONE, KARACHI.	15,00,000/-	75,000 /-	2,000/-	60 Days
	IMPROVEMENT/DESILTING OF NALLAH BADDA GALI BHIT ISLAND UC.No:04, KEAMARI ZONE.	5,79,856/-	28,993/-	1,000/-	45 Days
3.	DESILTING/IMPROVEMENT OF NALLAH AHMED DOLLAH GALI CHIBA MOHALLAH BHIT ISLAND UC.No:04, KEAMARI ZONE.	5,78,546/-	28,927/-	1,000/-	45 Days
4.	IMPROVEMENT/CONSTRUCTION OF NALLAH BABA ISLAND UC.No:04, KEAMARI ZONE.	5,81,167/-	29,058/-	1,000/-	45 Days
5.	IMPROVEMENT/DESILTING OF NALLAH BLOCK-A SHER SHAH UC.No:07, KEAMARI ZONE.	9,91,430/-	49,572/-	1,000/-	45 Days
6.	PROVIDING, FIXING & SUPPLYING STREET LIGHTS AT DIFFERENT AREA OF KEAMARI ZONE, DMC(WEST), KARACHI.	15,50,000 (+) OPEN RATE	77,500 (+) 5% of O/R	2,000/-	60 Days

**TERMS & CONDITIONS:**

1. Tenders schedule shall be as follows:

SCHEDULE	DATE & TIME	VENUE
Receiving of Applications and Issuance of Tenders	From First date of publication of N.I.T. in the Newspapers/ hoisting in the SPPRA Website ( <a href="http://www.pprasinidh.gov.pk">www.pprasinidh.gov.pk</a> ), during Office Hours, except, the opening date of the tenders, no tender document will be issued on opening day.	i). Office of the Executive Engineer, Keamari Zone, DMC(West), Karachi, at Main Hawksbay Road, Mauripur, Grex, Karachi. ii). Bidding document can be downloaded from the SPPRA Website ( <a href="http://www.pprasinidh.gov.pk">www.pprasinidh.gov.pk</a> ).
Dropping of Tenders	On <u>25.11.2013</u> at 2:00 pm	Office of the Executive Engineer, Keamari Zone, DMC(West), Karachi, at Main Hawksbay Road, Mauripur, Grex, Karachi
Opening of Tenders	On <u>25.11.2013</u> at 2:30 pm	Office of the Executive Engineer, Keamari Zone, DMC(West), Karachi, at Main Hawksbay Road, Mauripur, Grex, Karachi

- The bidding documents will be issued to the interested Firms/Contractors on submission of written request on letter head and on payment of non-refundable cost of tender price mentioned against each work, through pay order from any scheduled Bank in favor of **Keamari Zone, DMC(West), Karachi**, and bidding document can also be downloaded from the SPPRA Website ([www.pprasinidh.gov.pk](http://www.pprasinidh.gov.pk)) with tender fee mentioned as above by mail or by hand.
- The Earnest Money equal 5% of offered rates/amount of Open Rate items and Earnest Money of schedule items mentioned against each work in shape of pay order from any scheduled Bank in favour of **Keamari Zone, DMC(West), Karachi** must be enclosed with tender documents, otherwise the tender will be rejected.
- The Contractors must mention their complete and correct present/postal address in tender documents and quote the rates both in-words and in-figures. Incomplete / Conditional tenders will be not accepted. In addition, the bidders must furnish the documentary evidence against each eligibility as well as minimum qualification criteria. Otherwise their tenders will be summarily rejected.
- If any fake documents are found then the tender is liable to be rejected/cancelled without any compensation with penalty as per rules.
- Canvassing in connection of tenders is strictly prohibited and tenders submitted by the contractors who are reported to be involved in canvassing will be liable for rejection.
- All the tenders will be dropped on as per above Schedule upto 02:00 pm and will be opened by the Procurement Committee, Keamari Zone, DMC(West) in the Office of the Executive Engineer of Keamari Zone, DMC(West), Karachi at Main Hawksbay Road, Mauripur, Grex, Karachi at 02:30 pm in presence of the such Contractors/Parties/Firms/Bidders who wish to be present.
- In case, the date of opening declared as a Public Holiday by the Government, or non working day due to any reason, the next official working day shall be deemed to be the date for submission and opening of tenders at the same time.
- The Authority of DMC(West), Karachi may reject all or any bids/tenders at any time prior to the acceptance of a bid or proposal, subject to the relevant provision of SPPRA Rules-2010.
- Tenders will not be received after the schedule time.

**EXECUTIVE ENGINEER  
KEAMARI ZONE, DMC(WEST)**

THE DIRECTOR (ADVERTISING),  
Information Department, Government of Sindh, Karachi.

Copy to:-

- ✓ The Managing Director, SPPRA, Government of Sindh, with the request for hoisting above mentioned bidding schedule amended NIT on the SPPRA Website, hoisting with bidding documents (bidding documents enclosed herewith).
- The Administrator, DMC(West), Karachi.
- The Municipal Commissioner, DMC(West), Karachi.
- The Superintending Engineer, DMC(West), Karachi.
- The Accounts Officer, DMC(West), Karachi.
- All Members/Chairman Procurement Committee, Keamari Zone, DMC(West).
- Notice Board.

7/11  
DMC(E-1)

# BIDDING DATA

WORK NO: 01

- (a). Name of Procuring Agency KEAMARI ZONE, DMC(WEST), KARACHI
- (b). Brief Description of Works CONSTRUCTION OF UNDERGROUND WATER TANK AT UMER HISHOO GOTH UC.No:08, GABOPAT KEAMARI ZONE, KARACHI.
- (c). Procuring Agency's address: Mauri Pur Grex, Main Hawksbay Road Karachi
- (d). Estimated Cost: Rs: 15,00,000/-
- (e). Amount of Bid Security: Rs: 75,000/- (05.00% of Estimated/Offered Amount)
- (f). Period of Bid Validity (days): 90 Days
- (g). (i). Security Deposit:-(i/c bid security): 05.00% of Estimated/Offered amount  
(ii). 5% Retention Money of bill amount will be deducted from Running Bill.
- (h). Percentage, if any, to be deducted from bills : (i). 07% Income Tax  
(ii). 01% Water Charges
- (i). Deadline for Submission of Bids along with time : 25.11.2013 at 02:00pm
- (j). Venue, Time and Date of Bid Opening: Office of the Executive Engineer, Keamari Zone, DMC(West), Karachi, at Main Hawksbay Road, Mauripur, Grex, Karachi at 02:30pm on 25.11.2013
- (k). Time for Completion from written order of commence: 60 Days
- (l). Liquidity damages: Rs: 2,000/- Per Day  
(0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).
- (m). Tender Cost Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: Rs: 2,000/- (Rupees: Two Thousand Only).  
(in words and figures)
- (n). Bidding Document issued to: M/S: \_\_\_\_\_

CONTRACTOR

EXECUTIVE ENGINEER  
KEAMARI ZONE, DMC(WEST)

# **DISTRICT MUNICIPAL CORPORATION (WEST)**

## **KEAMARI ZONE, KARACHI**

Estimated Cost Rs: 15,00,000/-

Earnest Money Rs: 75,000/-

Time Limit: 60 Days

Penalty Per Day Rs: 2,000/-


**SUBJECT:** CONSTRUCTION OF UNDERGROUND WATER TANK AT UMER HISHOO GOTH UC No.08, GABOPAT KEAMARI ZONE, KARACHI.

(01)

S.No:	DESCRIPTION OF WORK	QUANTITY	RATE	PER
1.	Excavation for tanks and reservoirs in all kind of soil, murum, hard average of soil i/c trimming and dressing sides to true alignment/ design section profile and shape leveling of beds of trenches correct level and grade i/c laying of earth in 6" thick layer for construction of tanks and dressing and disposal of surplus earth, excavation earth within one chain as directed by Engineer Incharge i/c providing fence guards, light, flags and temporary crossings for non vehicular traffic wherever required left upto 5' and lead upto 1 chain.	<u>2,653 Cft</u>	<u>4050.00</u>	<u>1000 Cft</u>
2.	Excavation for tanks and reservoirs in soft rock by hammering and chiseling where blasting is not practicable or prohibited i/c trimming and dressing sides to true alignment/design section profile and shape leveling of beds of trenches correct level and grade i/c laying of earth in 6" thick layer for construction of tanks and dressing and disposal of surplus earth, excavation earth within one chain as directed by Engineer Incharge i/c providing fence guards, light, flags and temporary crossings for non vehicular traffic wherever required left upto 5' and lead upto 1 chain.	<u>1,592 Cft</u>	<u>10720/-</u>	<u>1000 Cft</u>
3.	Excavation for tanks and reservoirs in hard rock where blasting is not practicable or prohibited by hammering and chiseling disintegrated rock by blasting i/c trimming and dressing sides to true alignment/ design section profile and shape leveling of beds of trenches to correct level and grade i/c laying of earth in 6" thick layer for construction of tanks and dressing and disposal of surplus earth, excavation earth within one chain as directed by Engineer Incharge i/c providing fence guards, light, flags and temporary crossings for non vehicular traffic wherever required left upto 5' and lead upto 1 chain.	<u>1,592 Cft</u>	<u>24100</u>	<u>1000 Cft</u>
4.	Extra for every 50ft additional lead or part there of (A) for each work (soft, ordinary, hard and very hard).	<u>5,837 Cft</u>	<u>2015.70/-</u>	<u>1000 Cft</u>
5.	Cement Concrete brick or stone blast 1-1/2" to 2" gauge (ratio 1:4:8) in bad tank.	<u>491 Cft</u>	<u>9416.28/-</u>	<u>% Cft</u>
6.	Reinforced Cement Concrete work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kind of forms moulds lifting shuttering, quarring rendering and finishing the exposed surface (including screening and washing of shingle) (a) RC work in roof slab beam columns rafts lentels and other structure members lead in situ or precast lead in position complete in all respect i) Ratio (1:2:4) 90 pound LBS Cement 02 Cft send 04 Cft shingle 1/8" to 1/4" gauge.	<u>1719 Cft</u>	<u>337.00</u>	<u>P/Cft</u>
7.	Fabrication of mild steel reinforcement for cement concrete i/c cutting, bending, binding, laying in position joints and fastening i/c cost of binding wire (also includes removal of rust from bars).	<u>100 Cwt</u>	<u>4820.20</u>	<u>P/Cwt</u>
8.	Providing and Fixing C I manhole covers with frame in cost of material etc complete. Weight of each frame 2x35=70 Kgs.	<u>70 Kgs</u>	<u>140.00</u>	<u>Per Kg</u>
9.	Providing and fixing CC foundation (1:3:6) MS bar angle iron 2" x 2" x 1/4" apart MS bar 3/4" dia spaced i/c a part painting three coats will anticonosive steel paint etc complete.	<u>15 Rft</u>	<u>799.00</u>	<u>Per Rft</u>

10.	Providing and fixing ventilator (weight not less than 80 lbs each roof of a approved design with water light joint including painting etc complete .	02 Nos	4870.00	Each
11.	Providing expansion joint in concrete work 9" wide corrugated PVC with bulb i/c soldering and providing wooden key of partal wood i/c cutting of plerks to the exact shape of structure and cost of the material and labour etc complete.	201 Rft	86.00	Per Rft
12.	Cement plaster 1:4 upto 20' height 1/2" thick in side tank and outside of tank .	801 Rft	2283.93	% Sft
13.	Cement Concrete plain i/c placing, compacting, finishing and curing complete i/c screening and washing of stone aggregate without shuttering (ratio 1:2:4).	79 Cft	14,429.25	%Cft
14.	Supplying of Dampo/Pidlo fixed with cement plaster etc complete.	11 Kg	125.00	Per Kg
15.	Water proofing layer over the domical of slat slab of the HSR in two quote of bitumen lead using 31 lbs 100 Sft Per 100 Sft.	482 Sft	2208.00	% Sft
16.	Preparing sub-grade i/c earth exaction and filling to an average depth of 9" dressing to required cash and consolidation with power roll.	2400 Sft	526.28	%Sft
17.	Cement concrete including placing compacting finishing and curing complete including screening and washing of stone screening and stone aggregate without shedding (1:4:8).	1200 Cft	11288.75	%Cft
18.	Providing and laying 2" thick topping and concrete (1:2:4) including surface finishing and dividing into panels.	2400 Sft	3275.50	%Sft

**Nomenclature, Quantities and Rates etc checked and found correct.**



**ASSTT: EX-ENGINEER (B&R)  
KEAMARI ZONE**



**EXECUTIVE ENGINEER  
KEAMARI ZONE**

\*\*\*\*\*

I/We hereby quoted Rates @ \_\_\_\_\_ % above/below the S/R.

Contractor's Signature: \_\_\_\_\_

Address : \_\_\_\_\_

# BIDDING DATA

WORK No. 02

- (a). Name of Procuring Agency KEAMARI ZONE, DMC(WEST), KARACHI
- (b). Brief Description of Works IMPROVEMENT/DESILTING OF NALLAH BADDA GALI BHIT ISLAND UC.No:04, KEAMARI ZONE.
- (c). Procuring Agency's address: Mauri Pur Grex, Main Hawksbay Road Karachi
- (d). Estimated Cost: Rs: 5,79,856/-
- (e). Amount of Bid Security: Rs: 28,993/- (05.00% of Estimated/Offered Amount)
- (f). Period of Bid Validity (days): 90 Days
- (g). (i). Security Deposit:-(i/c bid security): 05.00% of Estimated/Offered amount  
(ii). 5% Retention Money of bill amount will be deducted from Running Bill.
- (h). Percentage, if any, to be deducted from bills : (i). 07% Income Tax  
(ii). 01% Water Charges
- (i). Deadline for Submission of Bids along with time : 25.11.2013 at 02:00pm
- (j). Venue, Time and Date of Bid Opening: Office of the Executive Engineer, Keamari Zone, DMC(West), Karachi, at Main Hawksbay Road, Mauripur, Grex, Karachi at 02:30pm on 25.11.2013
- (k). Time for Completion from written order of commence: 45 Days
- (l). Liquidity damages: Rs: 1,000/- Per Day  
(0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).
- (m). Tender Cost Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: Rs: 1,000/- (Rupees: One Thousand Only).  
(in words and figures)
- (n). Bidding Document issued to: M/S: \_\_\_\_\_

CONTRACTOR

EXECUTIVE ENGINEER  
KEAMARI ZONE, DMC(WEST)

**DISTRICT MUNICIPAL CORPORATION (WEST)**  
**KEAMARI ZONE, KARACHI**

Estimated Cost Rs: 5,79,856/-

Earnest Money Rs: 28,993/-

Time Limit: 45 Days


Penalty Per Day Rs: 1,000/-

SUBJECT: IMPROVEMENT/DESILTING OF NALLAH BADDA GALI  
BHIT ISLAND UC.No:04, KEAMARI ZONE.

(02)

S.No:	DESCRIPTION OF WORK	QUANTITY	RATE	PER
1.	Dismantling cement concrete R.C.C. (1:2:4) disposal lead upto 10 miles etc.	<u>863 Cft</u>	<u>5445.00</u>	<u>%Cft</u>
2.	Earth work excavation undressed in ashes sand soil or silt clearance slush daldal etc.	<u>4,425 Cft</u>	<u>5188.13</u>	<u>1000 Cft</u>
3.	R.C.C. working roof slab beams, column, rafts, lintels and other structural members laid in sit or per-cast laid in position complete in all respect 1:2:4.	<u>863 Cft</u>	<u>337.00</u>	<u>P/Cft</u>
4.	P/L fabrication of mild steel reinforcement bars using for bars i/c cutting, bending, binding, laying using binding wire etc.	<u>30.82 Cwt</u>	<u>5001.70</u>	<u>P/Cwt</u>
5.	Removal old debris and rubbish of all kinds and sizes within 03 miles.	<u>5,288 Cft</u>	<u>1227.80</u>	<u>%Cft</u>

Nomenclature, Quantities and Rates etc checked and found correct.



ASSTT: EX-ENGINEER (B&R)  
KEAMARI ZONE



EXECUTIVE ENGINEER  
KEAMARI ZONE

\*\*\*\*\*

I/We hereby quoted Rates @ \_\_\_\_\_ % above/below the S/R.

Contractor's Signature: \_\_\_\_\_


Address : \_\_\_\_\_

# BIDDING DATA

Work No. 3

- (a). Name of Procuring Agency KEAMARI ZONE, DMC(WEST), KARACHI
- (b). Brief Description of Works DESILTING/IMPROVEMENT OF NALLAH AHMED DOLLAH GALI CHIBA MOHALLAH BHIT ISLAND UC.No:04, KEAMARI ZONE.
- (c). Procuring Agency's address: Mauri Pur Grex, Main Hawksbay Road Karachi
- (d). Estimated Cost: Rs: 5,78,546/-
- (e). Amount of Bid Security: Rs: 28,927/- (05.00% of Estimated/Offered Amount)
- (f). Period of Bid Validity (days): 90 Days
- (g). (i). Security Deposit:-(i/c bid security): 05.00% of Estimated/Offered amount  
(ii). 5% Retention Money of bill amount will be deducted from Running Bill.
- (h). Percentage, if any, to be deducted from bills : (i). 07% Income Tax  
(ii). 01% Water Charges
- (i). Deadline for Submission of Bids along with time : 25.11.2013 at 02:00pm
- (j). Venue, Time and Date of Bid Opening: Office of the Executive Engineer, Keamari Zone, DMC(West), Karachi, at Main Hawksbay Road, Mauripur, Grex, Karachi at 02:30pm on 25.11.2013
- (k). Time for Completion from written order of commence: 45 Days
- (l). Liquidity damages: Rs: 1,000/- Per Day  
(0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).
- (m). Tender Cost Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: Rs: 1,000/- (Rupees: One Thousand Only).  
(in words and figures) /
- (n). Bidding Document issued to: M/S:

CONTRACTOR

  
EXECUTIVE ENGINEER  
KEAMARI ZONE, DMC(WEST)

# **DISTRICT MUNICIPAL CORPORATION (WEST)** **KEAMARI ZONE, KARACHI**

Estimated Cost Rs: 5,78,546/-

Earnest Money Rs: 28,927/-

Time Limit: 45 Days

Penalty Per Day Rs: 1,000/-

**SUBJECT:** DESILTING/IMPROVEMENT OF NALLAH AHMED DOLLAH GALI  
CHIBA MOHALLAH BHIT ISLAND UC.No:04, KEAMARI ZONE.

(03)

S.No:	DESCRIPTION OF WORK	QUANTITY	RATE	PER
1.	Dismantling cement concrete R.C.C. (1:2:4) disposal lead upto 10 miles etc.	<u>863 Cft</u>	<u>5445.00</u>	<u>%Cft</u>
2.	Earth work excavation undressed in ashes sand soil or silt clearance slush daldal etc.	<u>4,350 Cft</u>	<u>5188.13</u>	<u>1000 Cft</u>
3.	R.C.C. working roof slab beams, column, rafts, lintels and other structural members laid in sit or per-cast laid in position complete in all respect 1:2:4.	<u>863 Cft</u>	<u>337.00</u>	<u>P/Cft</u>
4.	P/L fabrication of mild steel reinforcement bars using for bars i/c cutting, bending, binding, laying using binding wire etc.	<u>30.82 Cwt</u>	<u>5001.70</u>	<u>P/Cwt</u>
5.	Removal old debris and rubbish of all kinds and sizes within 03 miles.	<u>5,213 Cft</u>	<u>1227.80</u>	<u>%Cft</u>

Nomenclature, Quantities and Rates etc checked and found correct.

  
ASSTT: EX-ENGINEER (B&R)  
KEAMARI ZONE

  
EXECUTIVE ENGINEER  
KEAMARI ZONE

\*\*\*\*\*

I/We hereby quoted Rates @ \_\_\_\_\_ % above/below the S/R.

Contractor's Signature: \_\_\_\_\_

Address : \_\_\_\_\_



# BIDDING DATA

Work No: 04

- (a). Name of Procuring Agency KEAMARI ZONE, DMC(WEST), KARACHI
- (b). Brief Description of Works IMPROVEMENT/CONSTRUCTION OF NALLAH BABA ISLAND UC.No:04, KEAMARI ZONE.
- (c). Procuring Agency's address: Mauri Pur Grex, Main Hawksbay Road Karachi
- (d). Estimated Cost: Rs: 5,81,167/-
- (e). Amount of Bid Security: Rs: 29,058/- (05.00% of Estimated/Offered Amount)
- (f). Period of Bid Validity (days): 90 Days
- (g). (i). Security Deposit:-(i/c bid security): 05.00% of Estimated/Offered amount  
(ii). 5% Retention Money of bill amount will be deducted from Running Bill.
- (h). Percentage, if any, to be deducted from bills : (i). 07% Income Tax  
(ii). 01% Water Charges
- (i). Deadline for Submission of Bids along with time : 25.11.2013 at 02:00pm
- (j). Venue, Time and Date of Bid Opening: Office of the Executive Engineer, Keamari Zone, DMC(West), Karachi, at Main Hawksbay Road, Mauripur, Grex, Karachi at 02:30pm on 25.11.2013
- (k). Time for Completion from written order of commence: 45 Days
- (l). Liquidity damages: Rs: 1,000/- Per Day  
(0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).
- (m). Tender Cost Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: Rs: 1,000/- (Rupees: One Thousand Only).  
(in words and figures)
- (n). Bidding Document issued to: M/S: \_\_\_\_\_

CONTRACTOR

EXECUTIVE ENGINEER  
KEAMARI ZONE, DMC(WEST)

# **DISTRICT MUNICIPAL CORPORATION (WEST)** **KEAMARI ZONE, KARACHI**

Estimated Cost Rs: 5,81,167/-

Earnest Money Rs: 29,058/-


Time Limit: 45 Days

Penalty Per Day Rs: 1,000/-

SUBJECT: IMPROVEMENT/CONSTRUCTION OF NALLAH BABA ISLAND UC.No.04, KEAMARI ZONE (04)

S.No:	DESCRIPTION OF WORK	QUANTITY	RATE	PER
1.	Dismantling cement concrete R.C.C. (1:2:4) disposal lead upto 10 miles etc.	<u>863 Cft</u>	<u>5445.00</u>	<u>%Cft</u>
2.	Earth work excavation undressed in ashes sand soil or silt clearance slush daldal etc.	<u>4,500 Cft</u>	<u>5188.13</u>	<u>1000 Cft</u>
3.	R.C.C. working roof slab beams, column, rafts, lintels and other structural members laid in sit or per-cast laid in position complete in all respect 1:2:4.	<u>863 Cft</u>	<u>337.00</u>	<u>P/Cft</u>
4.	P/L fabrication of mild steel reinforcement bars using for bars i/c cutting, bending, binding, laying using binding wire etc.	<u>30.82 Cwt</u>	<u>5001.70</u>	<u>P/Cwt</u>
5.	Removal old debris and rubbish of all kinds and sizes within 03 miles.	<u>5,363 Cft</u>	<u>1227.80</u>	<u>%Cft</u>

Nomenclature, Quantities and Rates etc checked and found correct.

  
ASSTT: EX-ENGINEER (B&R)  
KEAMARI ZONE

  
EXECUTIVE ENGINEER  
KEAMARI ZONE

\*\*\*\*\*

I/We hereby quoted Rates @ \_\_\_\_\_ % above/below the S/R.

Contractor's Signature: \_\_\_\_\_

Address : \_\_\_\_\_

# BIDDING DATA

WORK No: 05

- (a). Name of Procuring Agency KEAMARI ZONE, DMC(WEST), KARACHI
- (b). Brief Description of Works IMPROVEMENT/DESILTING OF NALLAH BLOCK-A  
SHER SHAH UC.No:07, KEAMARI ZONE.
- (c). Procuring Agency's address: Mauri Pur Grex, Main Hawksbay Road Karachi
- (d). Estimated Cost: Rs: 9,91,430/-
- (e). Amount of Bid Security: Rs: 49,572/- (05.00% of Estimated/Offered Amount)
- (f). Period of Bid Validity (days): 90 Days
- (g). (i). Security Deposit:-(i/c bid security): 05.00% of Estimated/Offered amount  
(ii). 5% Retention Money of bill amount will be deducted from Running Bill.
- (h). Percentage, if any, to be deducted from bills : (i). 07% Income Tax  
(ii). 01% Water Charges
- (i). Deadline for Submission of Bids along with time : 25.11.2013 at 02:00pm
- (j). Venue, Time and Date of Bid Opening: Office of the Executive Engineer, Keamari Zone,  
DMC(West), Karachi, at Main Hawksbay Road,  
Mauripur, Grex, Karachi at 02:30pm on 25.11.2013
- (k). Time for Completion from written order of commence: 45 Days
- (l). Liquidity damages: Rs: 1,000/- Per Day  
(0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).
- (m). Tender Cost Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: Rs: 1,000/- (Rupees: One Thousand Only).  
(in words and figures)
- (n). Bidding Document issued to: M/S:

CONTRACTOR

  
EXECUTIVE ENGINEER  
KEAMARI ZONE, DMC(WEST)

**DISTRICT MUNICIPAL CORPORATION (WEST)**  
**KEAMARI ZONE, KARACHI**

Estimated Cost Rs: 9,91,430/-

Earnest Money Rs: 49,572/-

Time Limit: 45 Days

Penalty Per Day Rs: 1,000/-

SUBJECT: IMPROVEMENT/DESILTING OF NALLAH BLOCK-A SHER SHAH UC.No.07, KEAMARI ZONE. (05)

S.No:	DESCRIPTION OF WORK	QUANTITY	RATE	PER
1.	Dismantling cement concrete R.C.C. (1:2:4) disposal lead upto 10 miles etc.	<u>1,500 Cft</u>	<u>5445.00</u>	<u>%Cft</u>
2.	Earth work excavation undressed in ashes sand soil or silt clearance slush daldal etc.	<u>6,750 Cft</u>	<u>5188.13</u>	<u>1000 Cft</u>
3.	R.C.C. working roof slab beams, column, rafts, lintels and other structural members laid in sit or per-cast laid in position complete in all respect 1:2:4.	<u>1,500 Cft</u>	<u>337.00</u>	<u>P/Cft</u>
4.	P/L fabrication of mild steel reinforcement bars using for bars i/c cutting, bending, binding, laying using binding wire etc.	<u>53.57 Cwt</u>	<u>5001.70</u>	<u>P/Cwt</u>
5.	Removal old debris and rubbish of all kinds and sizes within 03 miles.	<u>8,250 Cft</u>	<u>1227.80</u>	<u>%Cft</u>

Nomenclature, Quantities and Rates etc checked and found correct.

  
ASSTT. EX-ENGINEER (B&R)  
KEAMARI ZONE

  
EXECUTIVE ENGINEER  
KEAMARI ZONE

\*\*\*\*\*

I/We hereby quoted Rates @ \_\_\_\_\_ % above/below the S/R.

Contractor's Signature: \_\_\_\_\_


Address : \_\_\_\_\_

# BIDDING DATA

WORK No.06

- (a). Name of Procuring Agency KEAMARI ZONE, DMC(WEST), KARACHI
- (b). Brief Description of Works PROVIDING, FIXING & SUPPLYING STREET LIGHTS AT DIFFERENT AREA OF KEAMARI ZONE, DMC(WEST), KARACHI.
- (c). Procuring Agency's address: Mauri Pur Grex, Main Hawksbay Road Karachi
- (d). Estimated Cost: Rs: 15,50,000 ( + ) OPEN RATE
- (e). Amount of Bid Security: Rs: 77,500 ( + ) 5% of Offered Amount
- (f). Period of Bid Validity (days): 90 Days
- (g). (i). Security Deposit:-(i/c bid security): 05.00% of Estimated ( + ) Offered amount  
(ii). 5% Retention Money of bill amount, will be deducted from Running Bill.
- (h). Percentage, if any, to be deducted from bills : 07% Income Tax
- (i). Deadline for Submission of Bids along with time : 25.11.2013 at 02:00pm
- (j). Venue, Time and Date of Bid Opening: Office of the Executive Engineer, Keamari Zone, DMC(West), Karachi, at Main Hawksbay Road, Mauripur, Grex, Karachi at 02:30pm on 25.11.2013
- (k). Time for Completion from written order of commence: 60 Days
- (l). Liquidity damages: Rs: 2,000/- Per Day  
(0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).
- (m). Tender Cost Vide Pay Order No: \_\_\_\_\_ Dated: \_\_\_\_\_  
Amount: Rs: 2,000/- (Rupees: Two Thousand Only).  
(in words and figures)
- (n). Bidding Document issued to: M/S: \_\_\_\_\_

CONTRACTOR

  
EXECUTIVE ENGINEER  
KEAMARI ZONE, DMC(WEST)

# **DISTRICT MUNICIPAL CORPORATION (WEST)** **KEAMARI ZONE, KARACHI**

Estimated Cost Rs: 15,50,000/- (+) Open Rate Earnest Money Rs: 77,500/- (+) 5% of O/R

Time Limit: 60 Days Penalty Per Day Rs: 2,000/-

**SUBJECT:** PROVIDING, FIXING & SUPPLYING STREET LIGHTS AT DIFFERENT AREA OF KEAMARI ZONE, DMC(WEST), KARACHI. **(06)**

S.No:	DESCRIPTION OF WORK	QUANTITY	RATE	PER
1.	Providing and fixing 400-Watts (SON-T) Lamp at the height with the help of hydraulic crane as per site requirement and instruction of Engineer Incharge.	<u>20 Nos</u>	<u>2132.00</u>	<u>Each</u>
2.	Providing and fixing 400-Watts (SON-T) Choke at the height with the help of hydraulic crane as per site requirement and instruction of Engineer Incharge.	<u>20 Nos</u>	<u>4958.00</u>	<u>Each</u>
3.	Providing and fixing 250-Watts (SON) igniter in all respect at the height upto 40 feet with the help of hydraulic crane and manual labor as per site requirement and instruction of Engineer Incharge.	<u>20 Nos</u>	<u>1202.00</u>	<u>Each</u>
4.	Providing and fixing 250-Watts (SON) capacitor in all respect at the height upto 40 feet with the help of hydraulic crane and manual labor as per site requirement and instruction of Engineer Incharge.	<u>20 Nos</u>	<u>1366.00</u>	<u>Each</u>
5.	Providing and laying (Main or Sub-Main) PVC insulated and PVC sheeted with two core conductor 300/500 Volts size 4MM2.	<u>20 Nos</u>	<u>170.00</u>	<u>Each</u>
6.	Providing and fixing of flood light 400-Watts (HPIT) having IP65 classification with 400-Watts Lamp, Choke, Capacitor, Igniter and Internal wiring complete in all respect at the height upto 40 feet with the help hydraulic crane and manual labour as per site requirement and instruction of Engineer Incharge.	<u>05 Nos</u>	<u>16980.00</u>	<u>Each</u>
7.	Providing and fixing 400-Watts (SON) Igniter in all respect the height upto 40 feet with the help of hydraulic crane and manual labour as per site requirement and instruction of Engineer Incharge.	<u>25 Nos</u>	<u>1119.00</u>	<u>Each</u>
8.	Providing and fixing 400-Watts (SON) Capacitor all respect the height upto 40 feet with the help of hydraulic crane and manual labour as per site requirement and instruction of Engineer Incharge.	<u>25 Nos</u>	<u>1174.00</u>	<u>Each</u>
9.	Providing and laying (Main or Sub-Main) PVC insulated and PVC sheeted with two core conductor 300/500 Volts size 4MM2.	<u>200 Nos</u>	<u>170.00</u>	<u>Each</u>
10.	Providing and laying (Main or Sub-Main) PVC insulated and PVC sheeted with two core conductor 300/500 Volts size 6MM2.	<u>200 Nos</u>	<u>233.00</u>	<u>Each</u>

11.	Providing and fixing circuit breaker 15, 20, 30, 40, 50 & 60 Amperes TP {XE-100CS(CB)} on prepared board as required.	<u>05 Nos</u>	<u>5521.00</u>	<u>Each</u>
12.	Providing and fixing 125-Watts (HPMV) Lamp at the height as per site requirement and instruction of Engineer Incharge.	<u>50 Nos</u>	<u>470.00</u>	<u>Each</u>
13.	Providing and fixing 125-Watts (HPMV) Choke at the height as per site requirement and instruction of Engineer Incharge.	<u>50 Nos</u>	<u>1020.00</u>	<u>Each</u>
14.	P/Laying (main or sub-main) PVC insulated and PVC sheathed with two core copper conductor 300/500 volts size 10 MM2.	<u>114 Mtrs</u>	<u>375.00</u>	<u>P/Mtr</u>
15.	P/Laying (main or sub-main) PVC insulated and PVC sheathed with single core copper conductor 250/440 volts size (2-7/.036) 4MM2.	<u>200 Mtrs</u>	<u>147.00</u>	<u>P/Mtr</u>
16.	P/Laying (main or sub-main) PVC insulated and PVC sheathed with single core copper conductor 250/440 volts size (2-7/.044) 6MM2.	<u>200 Mtrs</u>	<u>213.00</u>	<u>P/Mtr</u>
17.	Providing and fixing of street light 250-Watt (HPMV) having IP54 classification with 250-Watt Lamp, Choke, Capacitor and Internal Wiring complete in all respect at the height upto 31 feet as per site required and instruction of Engineer Incharge make of the above light is as follow.	<u>35 Nos</u>	<u>8455.00</u>	<u>Each</u>
18.	Providing and fixing of street light 125-Watt (HPMV) having IP54 classification with 125-Watt Lamp, Choke, Capacitor and Internal Wiring complete in all respect at the height upto 31 feet as per site requirement and instruction of Engineer Incharge make of the above light in as follow.	<u>35 Nos</u>	<u>6365.00</u>	<u>Each</u>
19.	Providing and fixing of street light 250-Watt (SON) having IP54 classification with 250-Watt Lamp, Choke, Capacitor and Igniter and Internal Wiring complete.	<u>28 Nos</u>	<u>10105.00</u>	<u>Each</u>
20.	Providing and fixing Junction Box as per following specification size of Box 10" x 8" x 5" M.S Plate size 16 gauge thick clamp with nuts and bolts cover plate with screw painting two coats of rust preventive red oxide and two coats of I.C.I. Oil paint as per site requirement and instruction of Engineer Incharge.	<u>02 Nos</u>	<u>1020.00</u>	<u>Each</u>
21.	Manufacturing providing and fixing G.I. Single Arm Double Arch as per site requirement instruction of Engineer Incharge with following specification G.I. Pipe 2" Dia 10 SWG 5' Long 02 Nos M.S. clamps with nuts and bolts.	<u>01 No</u>	<u>1546.00</u>	<u>Each</u>
22.	Manufacturing providing and fixing angle iron bracket in square shape to accommodate 3 to 4 Nos flood light fitting 250-Watt 400-Watt with following specification as per site requirement and instruction of Engineer Incharge angle iron 1.5" Dia length 02 feet x 02 feet with supporting angles canopy 5' Dia 01 feet long with nuts.	<u>02 Nos</u>	<u>3207.00</u>	<u>Each</u>
23.	Providing and fixing Energy Saver 85-Watt SOGO make to be fixed given light.	<u>100 Nos</u>	<u>          </u>	<u>Each</u>

06

24. Providing and fixing M.S. tabular pole 31 feet long peried in the ground as per following specification 20 feet (6" Dia) x 5.5 feet (5" Dia) x 5.5 feet (4" Dia) x 31 feet wall thickness 08 SWG base plate 16" x 16" x 1/4" two coats red oxide as rust preventive two coats oil paint excavation of hard/soft soil 2' x 2' x 6' lean size 2' x 2' x 6' with 1:4:8 ratio C.C. work 1:3:6 cast in situ in one could 1 1/2 Dia including from work rodding curing etc complete with C.C. collar about 02 feet light from the ground level duly plastered.

02 Nos      26956.00      Each

25. Providing and fixing Moon Light fitting complete with Lamp, Choke 125-Watt PHILIPS make to be fixed on given pole at the light of 25 feet 28 feet from the ground level.

100 Nos      \_\_\_\_\_      Each      \_\_\_\_\_

**Nomenclature, Quantities and Rates etc checked and found correct.**

**ASSTT: EX-ENGINEER (M&E)  
KEAMARI ZONE**

**EXECUTIVE ENGINEER  
KEAMARI ZONE**

\*\*\*\*\*

I/We hereby quoted Rates @ \_\_\_\_\_ % above / below S/R  
(+) Open Rate Rs: \_\_\_\_\_ for complete work.

Contractor's Signature: \_\_\_\_\_

Address : \_\_\_\_\_



**DISTRICT MUNICIPAL CORPORATION (WEST), KARACHI**

**KEAMARI ZONE**

Mauri Pur Grex, Main Hawksbay Road Karachi.

Phone No: 021-99241320-25

Fax: 021-99241321 E-mail: [Keamaritown@gmail.com](mailto:Keamaritown@gmail.com)

**BIDDING DOCUMENT  
FOR  
PROCUREMENT OF WORKS**

**According  
to  
SPPRA Rules-2010**

## Instructions to Bidders/ Procuring Agencies.

### General Rules and Directions for the Guidance of Contractors.

This section of the bidding documents should provide the information necessary for bidders to prepare responsive bids, in accordance with the requirements of the Procuring Agency. It should also give information on bid submission, opening and evaluation, and on the award of contract.

Matters governing the performance of the Contract or payments under the Contract, or matters affecting the risks, rights, and obligations of the parties under the Contract are included as Conditions of Contract and *Contract Data*.

The *Instructions to Bidders* will not be part of the Contract and will cease to have effect once the contract is signed.

1. All work proposed to be executed by contract shall be notified in a form of Notice Inviting Tender (NIT)/Invitation for Bid (IFB) hoisted on website of Authority and Procuring Agency and also in printed media where ever required as per rules.

NIT must state the description of the work, dates, time and place of issuing, submission, opening of bids, completion time, cost of bidding document and bid security either in lump sum or percentage of Estimated Cost/Bid Cost. The interested bidder must have valid NTN also.

2. Content of Bidding Documents must include but not limited to: Conditions of contract, Contract Data, specifications or its reference, Bill of Quantities containing description of items with scheduled/item rates with premium to be filled in form of percentage above/ below or on item rates to be quoted, Form of Agreement and drawings.

3. **Fixed Price Contracts:** The Bid prices and rates are fixed during currency of contract and under no circumstance shall any contractor be entitled to claim enhanced rates for any item in this contract.

4. The Procuring Agency shall have right of rejecting all or any of the tenders as per provisions of SPP Rules 2010.

5. **Conditional Offer:** Any person who submits a tender shall fill up the usual printed form stating at what percentage above or below on the rates specified in Bill of Quantities for items of work to be carried out: he is willing to undertake the work and also quote the rates for those items which are based on market rates. Only one rate of such percentage, on all the Scheduled Rates shall be framed. Tenders, which propose any alternative in the works specified in the said form of invitation to tender or in the time




### BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

- (a). Name of Procuring Agency \_\_\_\_\_
- (b). Brief Description of Works \_\_\_\_\_
- (c). Procuring Agency's address:- \_\_\_\_\_
- (d). Estimated Cost:- \_\_\_\_\_
- (e). Amount of Bid Security:- \_\_\_\_\_ (Fixed sum amount  
or in % age of bid amount /estimated cost, but not exceeding 10%)
- (f). Period of Bid Validity (days):- \_\_\_\_\_ (Not more than sixty days).
- (g). Security Deposit:- (including bid security):- \_\_\_\_\_  
(in % age of bid amount /estimated cost up to 10%)
- (h). Percentage, if any, to be deducted from bills :- \_\_\_\_\_
- (i). Deadline for Submission of Bids along with time :- \_\_\_\_\_
- (j). Venue, Time and Date of Bid Opening:- \_\_\_\_\_
- (k). Time for completion from written order of commence: - \_\_\_\_\_
- (L). Liquidity damages:- \_\_\_\_\_ (0.05 of Estimated Cost or Bid cost  
per day of delay, but total not exceeding 10%).
- (m). Deposit Receipt No: Date: Amount:(in words and figures)

(Executive Engineer/Authority issuing bidding document)



### Conditions of Contract

**Clause – 1: Commencement & Completion Dates of work.** The contractor shall not enter upon or commence any portion or work except with the written authority and instructions of the Engineer-in-charge or of in subordinate-in-charge of the work. Failing such authority the contractor shall have no claim to ask for measurements of or payment for work.

The contractor shall proceed with the works with due expedition and without delay and complete the works in the time allowed for carrying out the work as entered in the tender shall be strictly observed by the contractor and shall reckoned from the date on which the order to commence work is given to the contractor. And further to ensure good progress during the execution of the work, contractor shall be bound, in all in which the time allowed for completion of any work exceeds one month, to achieve progress on the prorated basis.

**Clause – 2: Liquidated Damages.** The contractor shall pay liquidated damages to the Agency at the rate per day stated in the bidding data for each day that the completion date is later than the Intended completion date; the amount of liquidated damage paid by the contractor to the Agency shall not exceed 10 per cent of the contract price. Agency may deduct liquidated damages from payments due to the contractor. Payment of liquidated damages does not affect the contractor's liabilities.

### **Clause – 3: Termination of the Contract.**

- (A) Procuring Agency/Executive Engineer may terminate the contract if either of the following conditions exists:-
- (i) contractor causes a breach of any clause of the Contract;
  - (ii) the progress of any particular portion of the work is unsatisfactory and notice of 10 days has expired;
  - (iii) in the case of abandonment of the work owing to the serious illness or death of the contractor or any other cause.
  - (iv) contractor can also request for termination of contract if a payment certified by the Engineer is not paid to the contractor within 60 days of the date of the submission of the bill;
- (B) The Executive Engineer/Procuring Agency has power to adopt any of the following courses as may deem fit:-
- (i) to forfeit the security deposit available except conditions mentioned at A (iii) and (iv) above;
  - (ii) to finalize the work by measuring the work done by the contractor.

**Clause – 7: Payments.**

- (A) **Interim/Running Bill.** A bill shall be submitted by the contractor as frequently as the progress of the work may justify for all work executed and not included in any previous bill at least once in a month and the Engineer-in-charge shall take or cause to be taken the requisite measurements for the purpose of having the same verified and the claim, as far as admissible, adjusted, if possible before the expiry of ten days from the presentation of the bill, at any time depute a subordinate to measure up the said work in the presence of the contractor or his authorized agent, whose countersignature to the measurement list will be sufficient to warrant and the Engineer-in-charge may prepare a bill from such list which shall be binding on the contractor in all respects.

The Engineer /Procuring Agency shall pass/certify the amount to be paid to the contractor, which he considers due and payable in respect thereof, subject to deduction of security deposit, advance payment if any made to him and taxes.

All such intermediate payment shall be regarded as payments by way of advance against the final payment only and not as payments for work actually done and completed, and shall not preclude the Engineer-in-charge from recoveries from final bill and rectification of defects and unsatisfactory items of works pointed out to him during defect liability period.

- (B) **The Final Bill.** A bill shall be submitted by the contractor within one month of the date fixed for the completion of the work otherwise Engineer-in-charge's certificate of the measurements and of the total amount payable for the works shall be final and binding on all parties.

**Clause – 8: Reduced Rates.** In cases where the items of work are not accepted as so completed, the Engineer-in-charge may make payment on account of such items at such reduced rates as he may consider reasonable in the preparation of final or on running account bills with reasons recorded in writing.

**Clause – 9: Issuance of Variation and Repeat Orders.**

- (A) Agency may issue a Variation Order for procurement of works, physical services from the original contractor to cover any increase or decrease in quantities, including the introduction of new work items that are either due to change of plans, design or alignment to suit actual field conditions, within the general scope and physical boundaries of the contract.
- (B) Contractor shall not perform a variation until the Procuring Agency has authorized the variation in writing subject to the limit not exceeding the contract cost by of 15% on the same conditions in all respects on which he agreed to do them in the

- (ii) If the Engineer considers that rectification/correction of a defect is not essential and it may be accepted or made use of; it shall be within his discretion to accept the same at such reduced rates as he may fix therefore.

**Clause – 11:**

- (A) **Inspection of Operations.** The Engineer and his subordinates, shall at all reasonable times have access to the site for supervision and inspection of works under or in course of execution in pursuance of the contract and the contractor shall afford every facility for and every assistance in obtaining the right to such access.
- (B) **Dates for Inspection and Testing.** The Engineer shall give the contractor reasonable notice of the intention of the Engineer-in-charge or his subordinate to visit the work shall have been given to the contractor, then he either himself be present to receive orders and instructions, or have a responsible agent duly accredited in writing present for that purpose, orders given to the contractor's duly authorized agent shall be considered to have the same force an effect as if they had been given to the contractor himself.

**Clause – 12: Examination of work before covering up.**

- (A) No part of the works shall be covered up or put out of view/beyond the reach without giving notice of not less than five days to the Engineer whenever any such part of the works or foundations is or are ready or about to be ready for examination and the Engineer shall, without delay, unless he considers it unnecessary and advises the contractor accordingly, attend for the purpose of examining and measuring such part of the works or of examining such foundations;
- (B) If any work is covered up or placed beyond the reach of measurement without such notice having been given, the same shall be uncovered at the contractor's expense, and in default thereof no payment or allowance shall be made for such work, or for the materials with which the same was executed.


**Clause – 13: Risks.** The contractor shall be responsible for all risks of loss of or damage to physical property or facilities or related services at the premises and of personal injury and death which arise during and in consequence of its performance of the contract. if any damage is caused while the work is in progress or become apparent within three months of the grant of the certificate of completion, final or otherwise, the contractor shall make good the same at his own expense, or in default the Engineer may cause the same to be made good by other workmen, and deduct the expenses from retention money lying with the Engineer.

**Clause -18: Financial Assistance /Advance Payment.**


- (A) **Mobilization advance** is not allowed.
- (B) **Secured Advance against materials brought at site.**
- (i) Secured Advance may be permitted only against imperishable materials/quantities anticipated to be consumed/utilized on the work within a period of three months from the date of issue of secured advance and definitely not for full quantities of materials for the entire work/contract. The sum payable for such materials on site shall not exceed 75% of the market price of materials;
- (ii) Recovery of Secured Advance paid to the contractor under the above provisions shall be affected from the monthly payments on actual consumption basis, but not later than period more than three months (even if unutilized).

**Clause -19: Recovery as arrears of Land Revenue.** Any sum due to the Government by the contractor shall be liable for recovery as arrears of Land Revenue.

**Clause -20: Refund of Security Deposit/Retention Money.** On completion of the whole of the works (a work should be considered as complete for the purpose of refund of security deposit to a contractor from the last date on which its final measurements are checked by a competent authority, if such check is necessary otherwise from the last date of recording the final measurements), the defects notice period has also passed and the Engineer has certified that all defects notified to the contractor before the end of this period have been corrected, the security deposit lodged by a contractor (in cash or recovered in installments from his bills) shall be refunded to him after the expiry of three months from the date on which the work is completed.

  
Divisional Accountant

Contractor

  
Executive Engineer/Procuring Agency