



KARACHI WATER & SEWERAGE BOARD
OFFICE OF THE EXECUTIVE ENGINEER (WATER-II)
GULISTAN-E-JAUHAR DIV. / GULSHAN-E-IQBAL TOWN,
DISTRICT EAST

Block-16, Gulistan-e-Jauhar, Karachi.
Cell # 0302-2923490

NOTICE FOR INVITING TENDER
THROUGH AUTHORITY'S WEBSITE (On Item Rate Basis).
(Under 1.00 Million)

Sealed tenders are invited under SPP Rules-2010 for the work mentioned below :-

1.	Name of work :-	PROVIDING, LAYING OF 6" DIA "UPVC" WATER PIPE LINE AT HOUSE NO.C-259 BLOCK-14 TO HOUSE NO.C-152/1 BLOCK-14 FOR IMPROVEMENT OF WATER SUPPLY IN GULISTAN-E-JAUHAR DIV. / GULSHAN-E-IQBAL TOWN.
2.	Eligibility of Contactor:	All eligible Contactor / Bidder should having N.T.N Certificate. / GST Number / Registration.
3.	Tender can be purchased.	Tenders documents can be purchased from the Office of the Accounts Officer (Revenue), KW&SB at KW&SB Head Office, at 1 st Floor Old KBCA Annexy Building, Behind Civic Centre, Gulshan-e-Iqbal Karachi, between 9.00 am to 1.00 pm in any working day except the date of opening of the tenders.
4.	Source of Funding.	KW&SB's own funds.
5.	Bid Security.	2% of bid security of the quoted cost / price in shape of pay order / Bank Draft for any schedule bank of Pakistan in favour of KW&SB. Bid Security must be accompanied with the Tender otherwise the tenders shall be treated as invalid & rejected.
6.	Tender Fee.	Rs.1000/= Non-Refundable in shape of Pay Order in favour of KW&SB.
7.	Start date issuing tender documents.	w.e.f. 1 st date of Hoisting on SPPRA Website.
8.	Last date of issuing tender documents.	One day before the date of opening tender.
9.	Date & time of submission of tenders & Opening of Tenders.	09-12-2013 , upto 2.00 PM and will be opened at 2.30 PM.
10.	Place of opening.	Tenders will be opened by the Procurement Committee-I , at the office of the Chief Engineer (IP&D), KW&SB at 9 th Mile Karsaz, Shahrah-e-Faisal, Karachi.
11.	Scope of work	Improvement of Water Supply System.

Note :-

- The Procuring Agency may reject all or any bids subject to the relevant provision of SPP Rules-2010.
- Tender / bidding documents may be downloaded from SPPRA Website.
- In case of undesirable circumstances on submission of opening date & time or if Government declares Holiday the tender shall be submitted / opened on the next working day at the same time & venue".
- No tender shall be issued on the date of opening of tender.

KARACHI WATER & SEWERAGE BOARD



TENDER DOCUMENTS

FOR THE WORK OF

**PROVIDING , LAYING OF 6"DIA
"UPVC" WATER PIPE LINE AT HOUSE
NO.C-259 BLOCK-14 TO HOUSE NO.C-
152/1 BLOCK-14 FOR IMPROVEMENT OF
WATER SUPPLY IN GULISTAN-E-JAUHAR
DIV. / GULSHAN-E-IQBAL TOWN.**

**EXECUTIVE ENGINEER (WATER-II)
GULISTAN-E-JAUHAR DIVISION /
GULSHAN-E-IQBAL TOWN, DISTRICT EAST**

KARACHI WATER & SEWERAGE BOARD

KARACHI WATER & SEWERAGE BOARD
OFFICE OF THE EXECUTIVE ENGINEER (WATER-II)
GULSHAN-E-IQBAL TOWN, DISTRICT EAST

SUBJECT:- **PROVIDING , LAYING OF 6"DIA "UPVC" WATER PIPE LINE AT HOUSE NO.C-259 BLOCK-14 TO HOUSE NO.C-152/1 BLOCK-14 FOR IMPROVEMENT OF WATER SUPPLY IN GULISTAN-E-JAUHAR DIV. / GULSHAN-E-IQBAL TOWN.**

Estimated Cost On Item Rate Basis.
Tender Cost. Rs.1000/=
Time Limit. 07 Days.
Penalty Rs.500/= Per Day

Issued to M/s. _____
Pay Order No. _____ Dated: _____

ISSUING AUTHORITY

S.NO.	DESCRIPTION	QTY.	RATE		PER UNIT / ITEM	AMOUNT IN RUPEES
			Rupees in Figures.	Rupees in Words.		
1.	Dismantling & removing road metaling.	1250 Cft			% Cft	
2.	Excavation for pipe line in trenches and pits in all kinds of soils of murum i/c trimming and dressing sides to true alignment and shape, leveling of beds of trenches to correct level and grade, cutting joint holes and disposal of surplus earth within one chain as directed by Engineer Incharge, providing fence guards, lights, flags and temporary crossing for non vehicular traffic wherever required lift up to 5 ft (1.52 m) and lead upto one chain (30.5 m).	6250 Cft			%0Cft	
3.	Excavation for pipe line in trench and pits in wet soils clay or mud i/c trimming & dressing sides to true alignment and shape, leveling of beds of trenches to correct level and grade, cutting, joint holes and disposal of surplus earth in one chain as directed by Engineer Incharge, providing fence guards, lights, flags and temporary crossing for non vehicular traffic where ever required lift upto 5 ft (1.52m) and lead up to one chain (30.5m).	5000 Cft			%0Cft	
4.	Excavation for pipe line in trench & pits in hard rock by hammering chiseling i/c trimming & dressing sides to true alignment & shape, cutting joint holes and disposal of surplus earth within a one chain as directed by Engineer Incharge. Providing fence guards, lights, flags and temporary crossing for non vehicular traffic wherever required lift upto 5 ft (01.52 m) and lead upto one chain (30.5m)					

(Continued on Next Page)

Name of work :

**PROVIDING , LAYING OF 6"DIA "UPVC" WATER PIPE LINE
AT HOUSE NO.C-259 BLOCK-14 TO HOUSE NO.C-152/1
BLOCK-14 FOR IMPROVEMENT OF WATER SUPPLY IN
GULISTAN-E-JAUHAR DIV. / GULSHAN-E-IQBAL TOWN.**

S.NO.	DESCRIPTION	QTY.	RATE		PER UNIT / ITEM	AMOUNT IN RUPEES
			Rupees in Figures.	Rupees in Words.		
5.	Full hire charges of the Pumping set per day inclusive of wages of driver and assistant fuel or electric energy plate form required for placing pumps etc at lowest depth with suction end delivery pipes for pumping out water found at various depths from trenches i/c the cost of erection and dismantling after completion of the job. Hire charges of Pumping set upto 10 HP Pumping and water from 10' deep trenches.	15 Days			P/Day	
6.	P/F M.S split collar tee wide fabricated with thick M.S plate for "PRCC" pipe including cost of 3/4" M.S square bars on both ends i/c cost of nuts, bolts, rubber packing, labour , labour and sealing material i/c loading un-loading & testing. Wt:2'-6" 163.16 Kg (18" x 18")	01 No.			Each	
7.	P/L & Jointing of UPVC pipe of Class-"C" and fixing in trench i/c cutting fixing and jointing with solvent cement i/c testing with water pressure lead 300 ft. 6" Dia	1000 Rft			P/Rft	
8.	P/F "C.I" specials for UPVC/AC pressure pipes CI (Standard) weight for AC Class-"B". Reducer 6" dia x 4" dia Tee 6" dia x 4" dia Tee 4" dia x 4" dia	02 Nos. 03 Nos. 02 Nos.			Each Each Each	
9.	Providing C.I Sluice Valve heavy pattern (Test Pressure 21.0 Kg/sq.com or 300 lb/sq.inch) imported. 4" dia 6" dia 12" dia	02 Nos. 02 Nos. 01 No.			Each Each Each	
10.	Fixing of sluice valve heavy with 2 C.I tail pieces one end flanged and other with socket i/c the cost of nuts & bolts rubber packing, labour etc comp. 4" dia 6" dia 12" dia	02 Nos. 02 Nos. 01 No.			Each Each Each	

Name of work :

**PROVIDING , LAYING OF 6"DIA "UPVC" WATER PIPE LINE
AT HOUSE NO.C-259 BLOCK-14 TO HOUSE NO.C-152/1
BLOCK-14 FOR IMPROVEMENT OF WATER SUPPLY IN
GULISTAN-E-JAUHAR DIV. / GULSHAN-E-IQBAL TOWN.**

S.NO.	DESCRIPTION	QTY.	RATE		PER UNIT / ITEM	AMOUNT IN RUPEES
			Rupees in Figures.	Rupees in Words.		
11.	Construction of block masonry chambers or size 4'x4'x4' with 24" x 24" cover frame with 65 Kg RCC 1:2;4 slabs 5" thick with steel 1/2" tor bar @ 6" c/c 1/4" dia @ 8" i/c distribution bars 6" thick C.C 1:3;6 block masonry walls set 1"6 6" tick 1:4:8 in foundation 2" thick C.C 1:2;4 flooring 1/2" thick C.P thick 1:3 inside wall surface top and bottom slab outer slab i/c M.S foot rest 5/8" dia bars at every 2" deep i/c curing dewatering excavation earth etc refilling and disposal of surplus earth etc complete. (4'x4'x4)	01 No.			Each	
12.	Add or deduct for extra depth P/inch beyond 4'-0" i/c cost footrest etc.	12" Inch			P/Inch	
13.	Repair of leaking joints (External vatta) On PRCC pipe i/c excavation, labour, sealing materials, gunny bags, dewatering and refilling the excavated stuff etc complete.	18" dia 12" dia 03 Nos. 03 Nos.			Each Each	
14.	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete.	12232.88 Cft			%0Cft	
TOTAL						

[Signature]
**EXECUTIVE ENGINEER (WATER-II)
 GULISTAN-E-JAUHAR DIV /
 GULSHAN-E-IQBAL TOWN, DISTRICT EAST
 K.W.&S.B.**

I hereby quoted Amounting to Rs. _____ (In words) _____

Note :- All existing SPPRA Rule will be abide.

Signature & Stamp of the Contractor

Address _____