



KARACHI WATER AND SEWERAGE BOARD
OFFICE OF THE EXECUTIVE ENGINEER (SEW) GULSHAN-E-IQBAL (TOWN), KW&SB
ST-2 BLOCK 14 SCHEME-24 MAIN UNIVERSITY ROAD NEAR CIVIC CENTER

CELL NO: 0321-8283312

NOTICE INVITING TENDER (THROUGH PRESS/WEB SITE)

1. KW&SB invites sealed tenders on composite schedule of Rates (CSR) / Basis from interested contractors / firms :-

S.No	Name of Work	Estimated Cost (In rupees)	Bid Security + 2% of offer Rates	Tender Fees	Time for completion
1.	REHABILITATION/REPLACEMENT OF 15", 12" AND 8" DIA SUNK DOWN / BROKEN SEWERAGE LINES AT DIFFERENT LOCATIONS IN UNION COUNCIL NOS. 05, 09 & 11 OF GULSHAN-E-IQBAL TOWN.	Rs.9,95,210/=	Rs.19,904/= In shape of pay order / Demand Draft / Bank Guarantee in favour of KW&SB.	Rs.1000/=	20 Days

2. **Eligibility :** (i) Having National Tax Number.
(ii) One Year relevant work experience.

3. **Method of Procurement:** Single Stage, Single Envelope Basis.

4. **Bidding / Tender Documents :**

- (i) **Issuance:** Documents will be issued downloaded from the date of Hoisting on SPPRA website Publication to 23-12-2013 on attached Bid Security / Payment of tender fee (Non refundable).

- (ii) **Submission:** will be 24-12-2013, time 2:00 Pm.

- (iii) **Opening:** will be opened on 24-12-2013, time 2:30 Pm.

- (iv) **Place of issuance:** Office of the Accounts Officer (Revenue), KW&SB / Director (Accounts), KW&SB, at KW&SB Head Office, at 1st floor old KBCA annexy building, behind Civic Centre, Gulshan-e-Iqbal, Block-14 Karachi, from 9:00 am to 1: pm on all working days except date of opening / Downloaded from Authority Website.

- Place of submission :** Office of the Chief Engineer (IP&D), KW&SB at 9th Mile Karsaz, Shahrah-e-Faisal Karachi.

- (v) Un-reponded tenders will be again issued / submitted / opened on following dates.

2nd Attempt: (a) Issuance upto 26-12-2013 (b) Submission 27-12-2013 at 2.0 pm & opening on 27-12-2013 at 2:30 pm

5. **Terms & Conditions:**

- (a) Under following conditions bids / tenders will be rejected.

- (i) Conditional and telegraphic bids / tenders.
(ii) Bids not accompanied by Bid security of required amount and form.
(iii) Bids received after specified date and time.
(iv) Black listed firms.

- (b) Bid validity Period : 90 days

- (c) Procuring Agency reserves the rights to reject all or any bids subject to the relevant provision of Sindh Public Procurement Rules-2010.

KARACHI WATER & SEWERAGE BOARD


Syed Ejaz Ahmad
EXECUTIVE ENGINEER (SEW)
Gulshan-e-Iqbal (Town) K.W. & S.B.

OFFICE OF THE EXECUTIVE ENGINEER (SEW) GULSHAN-E-IQBAL (TOWN)
KARACHI WATER AND SEWERAGE BAOR

SCHEDULE "B"

NAME OF WORK:- **REHABILITATION / REPLACEMENT OF 15", 12" AND 8" DIA
 SUNK DOWN / BROKEN SEWERAGE LINES AT DIFFERENT
 LOCATIONS IN UNION COUNCIL NOS. 05, 09 & 11 OF
 GULSHAN-E-IQBAL TOWN.**

Estimated Cost: 9,95,210/= Quotation Issued to M/S _____
 Earnest Money 2% of Bidding Cost
 Tender Cost: Rs. 1000/= Vide Receipt No. _____ Dated: _____
 Time Limit: 20 - Days
 Penalty: Rs. 500/= per day.

S NO	DESCRIPTION	QUANTITY	RATE	PER	
1.	Scarifying the existing road surface.	3770 Sft.	116.16	%Sft	
2.	Dismantling and removal road matling. (Ref:- P-13/51, Pb-52)	3770 Cft.	605.00	%Cft	
3.	Excavation for pipe line in trenches and pits in all kinds of soils of murum i.c trimming and dressing sides to true alignment and shape, leveling of beds of trenches to correct level and grade, cutting joint holes and disposal of surplus earth within one chain as directed by Engineering In charge, providing fence guards, lights, flags and temporary crossing for non vehicular traffic where ever required lift up to 5 ft and lead up to one chain. Lift 00'- 05'	10935 Cft.	4650.00	%0Cft	
4.	Excavation for pipe line in trench and pits in wet soils, clay or mud i/c trimming & dressing sides to true alignment and shape, leveling of beds of tranches to correct level and grade, cutting joint holes and disposal of surplus earth in one chain as directed by Engineer In-charge, providing fence guards, lights, flags, and temporary crossing for non vehicular traffic where ever required lift up to 5ft and lead up to one chain	Lift 00'- 05'	3020 Cft.	5400.00	%0Cft
		Lift 05'- 08'	4650 Cft.	5950.00	%0Cft
		Lift 08'- 11'	280 Cft.	6500.00	%0Cft


5.	Providing & Laying of R.C.C. pipe with Rubber ring joint and fitting in trench including cutting, fitting and jointing with rubber ring i/c testing with water to specified pressure. 15" dia pipe 12" dia pipe 08" dia pipe	80 Rft. 715 Rft. 300 Rft.	436.00 367.00 206.00	Rft. Rft. Rft.
6.	Providing manhole 4ft dia (inside) and 5ft clear depth, with C.I. Frame (15 kg) cast in situ with 1:2:4 C.C in 9" thick wall, 1:4:8 C.C. in 6ft dia and 6" inch thick in foundation 1:2:4 C.C. in benching, 1/2" thick cement plastering with 1:3 C.M. on all inside wall surfaces, channel and benching i/c making required Nos of main and branch channels, 3/4" dia M.S footrest @ 12" c/c i/c cost of excavation in all kinds of soil, backfilling and disposal of excavated stuff etc complete as per design and instruction of the Engineer In-charge.	13 Nos.	14529.29	Each
7.	Add or deduct for extra / less depth than 5ft of 4ft dia manholes i/c footrest.	(+) 26.0 Ft.	2538.62	P/Rft
8.	Full hire charges of the pumping set per day i/c of wages of driver and Assistant fuel or Electric Energy plate form required for placing pumps etc at lower depth with suction and delivery pipes for pumping out water found at various depth from trenches i/c the cost of erection and dismantling after completion of the job. Hire charges of pumping set upto 10 HP pumping out water from 10 feet deep trench.	40 Days	1500.00	Day
9.	Making connection with the existing manhole i.c the cost of cutting hole in wall, making them good in C.C 1:2:4 and making required channel etc complete.	20 Nos	180.00	Each
10.	Manufacturing and Supplying of R.C.C manhole covers cast in 1:2:4 cement concrete ratio 3" deep at center, reinforced with 1/2" dia tor steel bars @ 4" c/c welded to a 3/16" thick 2" wide M.S plate and two hook of 3/8" dia tor bars including compacting, curing and transportation within 10 miles. 21" dia.	13 Nos.	913.63	Each
11	Sand Haro or any other source sand of same modulus of the fineness (Hill Sand).	3473 Cft.	2425.00	%Cft
12.	Refilling the excavated stuff in trenches 6"thick layer i.c watering, ramming to full compaction etc complete.	15998 Cft.	2760.00	%0Cft

13.	Carriage of 100 Cft/ 5 tons of all materials like stone aggregate, spawl, coal, lime, surkhi etc; B.G. Rail fastening points and crossing bridges, Girders, pipes sheets Rail, M.S. Bars etc; or 1000 Nos: bricks, 10"x5"x3" or 1000 Nos: tiles, 12"x6"x2" or 150 Cft of timber or 100 Maunds of fuel wood by trucks or any other means owned by the contractors. <u>Carriage for 07 Miles</u> (407.00 + 95.52 + 76.89 + 70.45 + 64.43 + 57.67 + 32.56 = 804.52)	6657 Cft.	804.52	%Cft
-----	--	-----------	--------	------

I/We hereby quoted _____% above/below the schedule Rate in Words _____) and also shall undertake to abide by prescribed terms and conditions of the contract.

Sign:/Stamp of Bidder _____

Address of Bidder _____


 Executive Engineer (Sew)
 Gulshan-e-Iqbal (Town), KW&SB