



KARACHI METROPOLITAN CORPORATION
OFFICE OF THE SUPERINTENDING ENGINEER (CM)
ENGINEERING DEPARTMENT

ENF-1: 291/13-14

No. S.E/(CM)/ED/KMC/ 414 /13

Dated: - 10/12/2013

NOTICE INVITING TENDERS

Through Website of SPPRA & KMC

Tenders in sealed covers are invited on Schedule Plus offer rate basis for the following works from the reputable and experienced firm / contractor having valid NTN and paid up original challan of Professional Tax prescribed fee.

S. No.	Tender Reference No.	Name of Scheme	Estimated Cost	Bid Security	Tender Cost
1.	KMC/CM/ED/90/2013-14	Construction of Speed Breaker in Block-4. Clifton District South, KMC.	Rs.9,71,129/=	Rs.20,000/=	Rs.2,500/=
2.	KMC/CM/ED/91/2013-14	Providing & Fixing Kerb Block, Paving Block along Plot No.Com-2/7 in Block-3 Scheme-5, Clifton District South, KMC.	Rs.9,75,274/=	Rs.20,000/=	Rs.2,500/=
3.	KMC/CM/ED/92/2013-14	Providing & Fixing Kerb Block & CC Flooring from Shell Petrol Pump to Sailing Club, along Boat Basin side in Scheme-5, Clifton District South, KMC.	Rs.9,77,778/=	Rs.20,000/=	Rs.2,500/=
4.	KMC/CM/ED/93/2013-14	Improvement / Rehabilitation of Road at Shah Vilayat Imam Bargah, Liaquatabad Zone, District (Central), KMC.	Rs.9,78,460/=	Rs.20,000/=	Rs.2,500/=
5.	KMC/CM/ED/94/2013-14	Improvement / Rehabilitation of Road at Noor-ul-Amin Imam Bargah, Liaquatabad Zone, District (Central), KMC.	Rs.9,77,871/=	Rs.20,000/=	Rs.2,500/=
6.	KMC/CM/ED/95/2013-14	Repair / Maintenance of 2200 Road from 5100 Road to 7000 Road at North Karachi Zone, District (Central).	Rs.9,76,488/=	Rs.20,000/=	Rs.2,500/=
7.	KMC/CM/ED/96/2013-14	Repair / Maintenance of 7000 Road from 4300 to 6000 Road (Right Track) at North Karachi Zone, District (Central).	Rs.9,73,856/=	Rs.20,000/=	Rs.2,500/=
8.	KMC/CM/ED/97/2013-14	Improvement / Rehabilitation of Road from Rizvia Imam Bargah to Gadeer Chowk Liaquatabad Zone, District (Central), KMC.	Rs.9,67,779/=	Rs.20,000/=	Rs.2,500/=
9.	KMC/CM/ED/98/2013-14	Repair / Maintenance at Shahrah-e-Pakistan Gulberg Town District Central.	Rs.9,49,072/=	Rs.19,000/=	Rs.2,500/=
10.	KMC/CM/ED/99/2013-14	Repair of Road & Pot Holes from Surrounding to Imam Bargah Zain-ul-Abideen in Sector 15/A-3 and 14/B Buffer Zone Karachi.	Rs.9,15,000/=	Rs.18,300/=	Rs.2,500/=
11.	KMC/CM/ED/100/2013-14	Repair/Maintenance in way of Jalous Askari Imam Bargah Block-9 Federal "B" Aarea, Gulberg Town District Central.	Rs.9,13,930/=	Rs.18,300/=	Rs.2,500/=
12.	KMC/CM/ED/101/2013-14	Repair of Road & Pot Holes along Routes & Surrounding to Imam Bargah Babul-Ilm (5 star Round About and Imam Bargah Sajjadiah near Ziauddin Hospital) North Nazimabad Zone.	Rs.8,93,000/=	Rs.18,000/=	Rs.2,500/=

FORWARD DIARY
 NO. 8118
 DATED: 11/12/13

Tender schedule shall be as follows:

SCHEDULE	DATE & TIME	VENUE
1. Receiving of Application & Issuance of Tender	From <u>16-12-2013</u> to <u>30-12-2013</u> During Office Hours	Office of Director Accounts, Engineering Department of 4 th Floor Civic Centre Gulshan-e-Iqbal.

2. Dropping of Tender	<u>31-12-2013</u> 2:00 pm	Committee Room of D.G. (TS) 4 th Floor, Civic Centre, Gulshan-e-Iqbal.
3. Opening of Tender	<u>31-12-2013</u> At 2:30 pm	Committee Room of D.G. (TS) 4 th Floor, Civic Centre, Gulshan-e-Iqbal.

TERMS & CONDITIONS.

1. In case due to any reason, if the tenders are not responded on the above date, the next date of submission and opening will be 16-01-2014 and the tender documents will be available for sale up to 15-01-2014.
2. The tender documents will be issued to the contractor on submission of written request on letter head and on payment of non-refundable cost of tender price through pay order from any schedule Bank in favor of KMC. Bid Security in shape of pay order / bank guarantee from any schedule Bank in favor of KMC as mentioned above should be enclosed with the bid otherwise the tender will be rejected. No tender will be sold on the tender opening date.
3. In Case the date of opening or last date of sale is declared as public holiday by the Government or non working day due to any reason, the next official working day shall be deemed to be the date of sale and submission and opening of tenders accordingly. The time and venue shall remain the same.
4. The total bid amount as well as the rates of items must be filled both in figures and words and in case any correction made by the contractor himself then each correction must be initialed by the Contractor, otherwise the tenders are liable to be summarily rejected.
5. **Substantial Responsive Bid:**
Only those bids, which comply with each eligibility criteria as well as minimum qualification criteria attached with the tender documents shall be declared substantially responsive bids at the time of tender opening and will be eligible for further evolution, otherwise the same will be declared as non-responsive / rejected.
6. The bidder is required to submit the above information, the signed evidence against evaluation criteria along with their bids. However Joint venture between two or more firms is allowed subject to compliance of conditions of stipulated rules of PEC.
7. If any fake documents are found then the tender is liable to be rejected/cancelled with out any compensation and with penalty as per rules.
8. Canvassing in connection with tenders is strictly prohibited and tenders submitted by the contractors who report canvassing will liable for rejection.
9. If a bidder submits a seriously unbalanced bid then he may be required to deposit extra performance security to a level sufficient to protect the procuring agency against financial losses, failing which the submitted bid will be rejected.
10. Bid Security of the unsuccessful bidder shall be released once the contract has been finalized with the successful bidder or the validity period has expired.
11. The procuring agency may reject all or any bid subject to the relevant provisions of SPPRA Rules 2010.
12. The conditions of contract are available on KMC website (www.karachicity.gov.pk).


Superintending Engineer (CM)
Engineering Department, KMC.

Not to be Published

Director (CB)SPPRA, GOS.

With the request to upload on the SPPRA's website (with 12 sets of tender documents).

Add: Director (I.T)Computer Section,

Administrator Secretariat, KMC.

With the request to upload on the KMC's website.

1. D.G(TS), KMC.
2. Chief Engineer,(CM)E.D, KMC.
3. Chief Engineer(Concerned).
4. PS to Administrator, KMC.
5. Director (Accounts)E.D, KMC.
6. Office file.

Sr. NO. 01.

KARACHI METROPOLITAN CORPORATION
ENGINEERING DEPARTMENT



Tender Reference No.KMC/CM/ED/ 90 /2013-14

BILL OF QUANTITIES

**CONSTRUCTION OF SPEED BREAKER IN BLOCK-4, CLIFTON,
DISTRICT SOUTH, KMC.**

NOTE:
The Condition of contract will be available on KMC website (www.karachicity.gov.pk).

Estimate Cost: - Rs.9,71,129/=
Bid Security: - Rs.20,000/=
Tender Cost: - Rs.2,500/=

MINIMUM QUALIFICATION / ELIGIBILITY CRITERIA

The evidence / documents of the following minimum qualification / eligibility criteria will be checked during opening process of tender & if anyone is missing then the tender will be summarily rejected at the moment by the tender opening committee.

Eligibility:

- i). NTN Certificate
- ii). Valid Professional TAX.

Minimum Qualification Criteria:

- iii). Bid Security, as mentioned in the NIT & Bidding Documents, is furnished.
- iv). All rates quoted including the total amount of the bid shall be in figures & words (both).
- v). All corrections / overwriting shall be clearly re-written with initials & duly stamped by the bidder.
- vi). The bid shall be properly signed, named & stamped by the authorized person of the firm and authorization letter for signatory shall be enclosed with the tender by the authorized Person, if other than the signatory of the firm.
- vii). The minimum turn over / work experience with satisfactory completion report in last 2 years or at least two or more works in hand and their aggregate cost should be equal to the work cost in which bidder interested to participate.

Signature of the Bidder with Stamp

KARACHI METROPOLITAN CORPORATIN
ENGINEERING DEPARTMENT

Subject:- CONSTRUCTION OF SPEED BREAKER IN BLOCK-4, CLIFTION
DISTRICT SOUTH, KMC.

Estimated Cost: **Rs.9,71,129/=**

Earnest Money: **Rs.20,000/=**

Tender Cost: **Rs.2,500/=**

S.No.	DESCRIPTION	QTY	UNIT	Rate (in figure)	Rate (in figure)	AMOUNT
1.	Dismantling and removing of road metalling etc complete.	873.18	% Cft	605.00	Six Hundred & Five Only.	5,283
2.	Earth Work Excavation undressed lead up to a single throw of Kassi Phawarah or Shovel.	1800	% 0 Cft	1361.25	Thirteen Hundred Sixty One & Paisa Twenty Five Only.	2,450
3.	Cartage of 100 Cft / 5 Tones of all materials like stone aggregate, spawl, coal, lime, surkhi etc. B.G Rail fastenings points and crossing bridge girders pipes sheets Rails M.S Bars etc or 1000 Nos. bricks 10'x5'x3' or 1000 Maunds of fuel wood by trucks or any other means owned by the contractors (lead up to 15 miles etc).	2673.18	% Cft	1065.04	One Thousand Sixty Five & Four Paisa Only	28,470
4.	P/L Granular Sub-Base Course as per (AASHTO) standard specifications i/c compacting to the required density by approved mechanical means (vibratory roller road packer and smooth wheel roller etc) i/c watering withal lead and lift etc complete.	675	% Cft	3341.71	Thirty Three Hundred Forty One & Seventy One Paisa Only.	22,557
5.	P/L Aggregate base course in proper grade and camber having CBR 80% as per (AASHTO) standard specification i/c compacting to the required density by the approved mechanical means (Vibratory roller road packer and smooth wheel roller etc) i/c watering with all lead and lift etc complete.	675	% Cft	5542.24	Fifty Four Hundred Forty Two & Twenty Four Paisa Only.	37,410
6.	P/S prime coat with medium curing cut back asphalt of pen: grade 60/70 prime coat shall be use at the rate of 11 litters %Sft at 70-C temperature mixed with	1350	P/Sft	O/R		

	adequate quantity of Kerosene Oil using uniformly pressure spray boiler with automatic temperature controller prior to the application of prime coat all loose material shall be removed by mean of mechanical sweeper/blower & hard grooms and disposal the same within three chain after application traffic shall be kept off from the surface till laying of bituminous course Martial and methodology shall fully comply the specification of AASHTO and as directed by the Engineer incharge.					
7.	Providing and laying asphalt concrete binder course compacted as per approved job mix formula using crush aggregate from hub sources and equivalent. Using asphalt of grade 60/70 during laying temperature not less then 140 C compacted by steel wheel and PTR roller. The procedure of lying binder course material & methodology shall fully comply with AASHTO and as directed by the Engineer incharge. Minimum bitumen content should be minimum 3.5% binder course shall be spread using paver machines. Rolling and finishing to design proper aggregate line level and camber etc (6 cm).	659.25	P/Cft	O/R		
8.	Asphalt course laying to proper line & grade plant mixed asphalt concrete pavers finished (hydraulic / electronic) prepared to specified formula according to job mix formula approved by Engineer incharge i/c rolling & fixed using to proper line grade level and camber etc complete tack coat with bitumen 80/100 penetration all cost of material roller T&P and carriage of material from sand of supply to plant & plant to site of work 5 CM wearing course.	5700	% Sft	8274.73 <u>-706.00</u> <u>7568.73</u>	Seventy Five Hundred Sixty Eight & Seventy Three Paise Only.	4,31,418

9.	Pavement marking in Reflective Thermo Plastic Paint for lines of 6" width.	1296	P/Rft	41.24	Forty One Rupees & Twenty Four Paisa Only.	53,447
10.	Supplying and fixing of reflectorize road studs double face flush surface type.	720	Each	596.26	Five Hundred Ninety Six & Twenty Six Paisa Only.	4,29,307
11.	Raising / Lowering of Sewerage Manholes with cement concrete 1:2:4 up to 24" height i/c fixing of manhole cover with ring rubber etc complete.	1	Each	O/R	-	

KARACHI METROPOLITAN CORPORATION
ENGINEERING DEPARTMENT

Subject: **CONSTRUCTION OF SPEED BREAKER IN BLOCK-4, CLIFTION DISTRICT SOUTH, KMC.**

Estimated Cost:- Rs. 9,71,129/=

Bid Security:- Rs. 20,000/=

Tender Cost: - Rs.2,500/=

I / We hereby quoted as follows:

1.	<u>PART - A:</u> (Items Based on S/R) amounting to Rs.10,10,342/= % Below the S/R.	Rs. _____
2.	<u>PART - B:</u> (Items Based on O/R)	Rs. _____
TOTAL A + B		Rs. _____

The total amount is Rs. _____ (Rupees _____
(in Figure) (In Words) _____
for complete job.

I / We have attached a pay order bearing No. _____ dated _____ issued from
_____ amounting to Rs. _____ as per NIT.
(Name of Bank)

Completion Time : 15 Days

Penalty per day: Rs. 2,500/=

Note:

- Tender must be quoted in figure & in words both otherwise liable to be cancelled.
- All over writing & correction if any must be initialed & stamped by the bidder.
- All prevailing rules regarding condition of contract will be applicable.
- 15% below is the maximum ceiling on schedule items 2012 by the authority.

Signature of the Contractor with Stamp

Address: _____

Checked By:- _____

ST. NO. 02.

KARACHI METROPOLITAN CORPORATION
ENGINEERING DEPARTMENT



Tender Reference No.KMC/CM/ED/ 91 /2013-14

BILL OF QUANTITIES

**PROVIDING & FIXING KERB BLOCK, PAVING BLOCK ALONG PLOT
NO.COM-2/7 IN BLOCK-3, SCHEME-5 CLIFTON, DISTRICT SOUTH, KMC.**

NOTE:

The Condition of contract will be available on KMC website (www.karachicity.gov.pk).

Estimate Cost: - Rs.9,75,274/=

Bid Security: - Rs.20,000/=

Tender Cost: - Rs.2,500/=

MINIMUM QUALIFICATION / ELIGIBILITY CRITERIA

The evidence / documents of the following minimum qualification / eligibility criteria will be checked during opening process of tender & if anyone is missing then the tender will be summarily rejected at the moment by the tender opening committee.

Eligibility:

- i). NTN Certificate
- ii). Valid Professional TAX.

Minimum Qualification Criteria:

- iii). Bid Security, as mentioned in the NIT & Bidding Documents, is furnished.
- iv). All rates quoted including the total amount of the bid shall be in figures & words (both).
- v). All corrections / overwriting shall be clearly re-written with initials & duly stamped by the bidder.
- vi). The bid shall be properly signed, named & stamped by the authorized person of the firm and authorization letter for signatory shall be enclosed with the tender by the authorized Person, if other than the signatory of the firm.
- vii). The minimum turn over / work experience with satisfactory completion report in last 2 years or at least two or more works in hand and their aggregate cost should be equal to the work cost in which bidder interested to participate.

Signature of the Bidder with Stamp

✓
OK.

KARACHI METROPOLITAN CORPORATIN
ENGINEERING DEPARTMENT

Subject:- PROVIDING & FIXING KERB BLOCK, PAVING BLOCK ALONG PLOT NO.COM-2/7 IN BLOCK-3, SCHEME-5 CLIFTION DISTRICT SOUTH, KMC.

Estimated Cost: **Rs.9,75,274/=**

Earnest Money: **Rs.20,000/=**

Tender Cost: **Rs.2,500/=**

S.No.	DESCRIPTION	QTY	UNIT	Rate (in figure)	Rate (in figure)	AMOUNT
1.	Dismantling of cement concrete plain 1:2:4	680	% Cft	3327.50	Thirty Three Hundred Twenty Seven & Fifty Only.	22,627
2.	Earth Work Excavated undressed lead up to a single throw of Kassi Phawarah or Shovel.	4000	% 0 Cft	1361.25	Thirteen Hundred Sixty One & Paisa Twenty Five Only.	5,445
3.	Cartage of 100 Cft / 5 Tones of all materials like stone aggregate, spawl, coal, lime, surkhi etc. B.G Rail fastenings points and crossing bridge girders pipes sheets Rails M.S Bars etc or 1000 Nos. bricks 10'x5'x3' or 1000 Cft. Of timer or 100 Maunds of fuel wood by trucks or any other means owned by the contractors (lead up to 15 miles etc).	4680	% Cft	1065.04	One Thousand Sixty Five & Four Paisa Only	49,844
4.	P/L Aggregate base course in proper grade and camber having CBR 80% as per (AASHTO) standard specification i/c compacting to the required density by the approved mechanical means (Vibratory roller road packer and smooth wheel roller etc) i/c watering with all lead and lift etc complete.	1860	% Cft	5542.24	Fifty Four Hundred Forty Two & Twenty Four Paisa Only.	1,03,086
5.	Providing & fixing precast kerb block 3750 PSI Industrial Made size 6 inches thick x 12 inches long x 18 inches high including the cost of cartage, 1450 PSI lean concrete 1:4 cement sand mortar.	825	P/Rft	O/R		

6.	Providing and fixing cement paving block flooring having size of 197 x 97 x 60 (mm) of city / quadra / coble shape with pigmented having strength between 5000 psi to 8500 psi i/c filling the joints with hill sand and laying specified manner / pattern and design etc complete.	3720	P/Sft	199.77	One Hundred Ninety Nine & Seventy Seven Paise Only	7,43,144
----	---	------	-------	--------	--	----------

KARACHI METROPOLITAN CORPORATION
ENGINEERING DEPARTMENT

Subject: **PROVIDING & FIXING KERB BLOCK, PAVING BLOCK ALONG PLOT NO.COM-2/7 IN BLOCK-3, SCHEME-5 CLIFTON DISTRICT SOUTH, KMC.**

Estimated Cost:- Rs. 9,75,274/=

Bid Security:- Rs. 20,000/=

Tender Cost: - Rs.2,500/=

I / We hereby quoted as follows:

1.	<u>PART – A:</u> (Items Based on S/R) amounting to Rs.9,24,145/= % Below the S/R.	Rs. _____
2.	<u>PART – B:</u> (Items Based on O/R)	Rs. _____
TOTAL A + B		Rs. _____

The total amount is Rs. _____ (Rupees _____
(in Figure) (In Words) _____
for complete job.

I / We have attached a pay order bearing No. _____ dated _____ issued from
_____ amounting to Rs. _____ as per NIT.
(Name of Bank)

Completion Time : 15 Days

Penalty per day: Rs. 2,500/=

Note:

- Tender must be quoted in figure & in words both otherwise liable to be cancelled.
- All over writing & correction if any must be initialed & stamped by the bidder.
- All prevailing rules regarding condition of contract will be applicable.
- 15% below is the maximum ceiling on schedule items 2012 by the authority.

Signature of the Contractor with Stamp

Address: _____

Checked By:- _____

KARACHI METROPOLITAN CORPORATION
ENGINEERING DEPARTMENT



Tender Reference No.KMC/CM/ED/ 92 /2013-14

BILL OF QUANTITIES

**PROVIDING & FIXING KERB BLOCK & CC FLOORING FROM SHELL
PETROL PUMP TO SAILING CLUB, ALONG BOAT BASIN SIDE IN
SCHEME-5 CLIFTON, DISTRICT SOUTH, KMC.**

NOTE:

The Condition of contract will be available on KMC website (www.karachicity.gov.pk).

Estimate Cost: - Rs.9,77,778/=

Bid Security: - Rs.20,000/=

Tender Cost: - Rs.2,500/=

MINIMUM QUALIFICATION / ELIGIBILITY CRITERIA

The evidence / documents of the following minimum qualification / eligibility criteria will be checked during opening process of tender & if anyone is missing then the tender will be summarily rejected at the moment by the tender opening committee.

Eligibility:

- i). NTN Certificate
- ii). Valid Professional TAX.

Minimum Qualification Criteria:

- iii). Bid Security, as mentioned in the NIT & Bidding Documents, is furnished.
- iv). All rates quoted including the total amount of the bid shall be in figures & words (both).
- v). All corrections / overwriting shall be clearly re-written with initials & duly stamped by the bidder.
- vi). The bid shall be properly signed, named & stamped by the authorized person of the firm and authorization letter for signatory shall be enclosed with the tender by the authorized Person, if other than the signatory of the firm.
- vii). The minimum turn over / work experience with satisfactory completion report in last 2 years or at least two or more works in hand and their aggregate cost should be equal to the work cost in which bidder interested to participate.

Signature of the Bidder with Stamp

KARACHI METROPOLITAN CORPORATION
ENGINEERING DEPARTMENT

Subject:- PROVIDING & FIXING KERB BLOCK & CC FLOORING FROM SHELL PETROL PUMP TO SAILING CLUB, ALONG BOAT BASIN SIDE IN SCHEME-5 CLIFTON DISTRICT SOUTH, KMC.

Estimated Cost: **Rs.9,77,778/=**

Earnest Money: **Rs.20,000/=**

Tender Cost: **Rs.2,500/=**

S.No.	DESCRIPTION	QTY	UNIT	Rate (in figure)	Rate (in figure)	AMOUNT
1.	Dismantling of cement concrete plain 1:2:4	680	% Cft	3327.50	Thirty Three Hundred Twenty Seven & Fifty Only.	22,627
2.	Earth Work Excavated undressed lead up to a single throw of Kassi Phawarah or Shovel.	15900	% 0 Cft	1361.25	Thirteen Hundred Sixty One & Paisa Twenty Five Only.	21,644
3.	Cartage of 100 Cft / 5 Tones of all materials like stone aggregate, spawl, coal, lime, surkhi etc. B.G Rail fastenings points and crossing bridge girders pipes sheets Rails M.S Bars etc or 1000 Nos. bricks 10'x5'x3' or 1000 Cft. Of timer or 100 Maunds of fuel wood by trucks or any other means owned by the contractors (lead up to 15 miles etc).	16580	% Cft	1065.04	One Thousand Sixty Five & Four Paisa Only	1,76,584
4.	Cement Concrete plain including placing compacting finishing and curing complete (i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8).	2340.53	% Cft	11288.75	Eleven Thousand Two Hundred Eighty Eight & Seventy Five Paisa Only.	2,64,216
5.	Providing and laying 2" thick topping cement concrete 1:2:4 i/c surface finishing and dividing into panel.	7092.50	% Sft	3275.50	Thirty Two Hundred Seventy Five & Fifty Paisa Only.	2,32,315
6.	Providing & fixing precast kerb block 3750 PSI Industrial Made size 6 inches thick x 12 inches long x 18 inches high including the cost of cartage, 1450 PSI lean concrete 1:4 cement sand mortar.	1600	P/Rft	O/R		

KARACHI METROPOLITAN CORPORATION
ENGINEERING DEPARTMENT

Subject: **PROVIDING & FIXING KERB BLOCK & CC FLOORING FROM SHELL PETROL PUMP TO SAILING CLUB, ALONG BOAT BASIN SIDE IN SCHEME-5 CLIFTION DISTRICT SOUTH, KMC.**

Estimated Cost:- Rs. 9,77,778/=

Bid Security:- Rs. 20,000/=

Tender Cost: - Rs.2,500/=

I / We hereby quoted as follows:

1.	<u>PART – A:</u> (Items Based on S/R) amounting to Rs.7,17,385/= % Below the S/R.	Rs. _____
2.	<u>PART – B:</u> (Items Based on O/R)	Rs. _____
TOTAL A + B		Rs. _____

The total amount is Rs. _____ (Rupees _____ (In Words) _____ for complete job.
(in Figure)

I / We have attached a pay order bearing No. _____ dated _____ issued from _____ amounting to Rs. _____ as per NIT.
(Name of Bank)

Completion Time : 15 Days

Penalty per day: Rs. 2,500/=

Note:


- Tender must be quoted in figure & in words both otherwise liable to be cancelled.
- All over writing & correction if any must be initialed & stamped by the bidder.
- All prevailing rules regarding condition of contract will be applicable.
- 15% below is the maximum ceiling on schedule items 2012 by the authority.

Signature of the Contractor with Stamp

Address: _____

Checked By:- _____

KARACHI METROPOLITAN CORPORATION
ENGINEERING DEPARTMENT



Tender Reference No.KMC/CM/ED/ 93 /2013-14

BILL OF QUANTITIES

**IMPROVEMENT / REHABILITATION OF ROAD AT SHAH VILAYAT IMAM
BARGAH, LIAQUATABAD ZONE, DISTRICT(CENTRAL), KMC.**

NOTE:

The Condition of contract will be available on KMC website (www.karachicity.gov.pk).

Estimate Cost: - Rs.9,78,460/=

Bid Security: - Rs.20,000/=

Tender Cost: - Rs.2,500/=

MINIMUM QUALIFICATION / ELIGIBILITY CRITERIA

The evidence / documents of the following minimum qualification / eligibility criteria will be checked during opening process of tender & if anyone is missing then the tender will be summarily rejected at the moment by the tender opening committee.

Eligibility:

- i). NTN Certificate
- ii). Valid Professional TAX.

Minimum Qualification Criteria:

- iii). Bid Security, as mentioned in the NIT & Bidding Documents, is furnished.
- iv). All rates quoted including the total amount of the bid shall be in figures & words (both).
- v). All corrections / overwriting shall be clearly re-written with initials & duly stamped by the bidder.
- vi). The bid shall be properly signed, named & stamped by the authorized person of the firm and authorization letter for signatory shall be enclosed with the tender by the authorized Person, if other than the signatory of the firm.
- vii). The minimum turn over / work experience with satisfactory completion report in last 2 years or at least two or more works in hand and their aggregate cost should be equal to the work cost in which bidder interested to participate.

Signature of the Bidder with Stamp

✓ok.

KARACHI METROPOLITAN CORPORATIN ENGINEERING DEPARTMENT

Subject:- IMPROVEMENT / REHABILITATION OF ROAD AT SHAH VILAYAT
IMAM BARGAH, LIAQUATABAD ZONE, DISTRICT (CENTRAL),
KMC.

Estimated Cost: **Rs.9,78,460/=**

Earnest Money: **Rs.20,000/=**

Tender Cost: **Rs.2,500/=**

S.No.	DESCRIPTION	QTY	UNIT	Rate (in figure)	Rate (in figure)	AMOUNT
1.	Dismantling and removing of Road Metalling etc complete.	1504	% Cft	605.00	Six Hundred & Five Only.	9,099
2.	Earth Work Excavated undressed lead up to a single throw of Kassi Phawarah or Shovel in ordinary soil etc complete.	34848	% 0 Cft	1361.25	Thirteen Hundred Sixty One & Paisa Twenty Five Only.	47,437
3.	Cartage of 100 Cft / 5 Tones of all materials like stone aggregate, spawl, coal, lime, surkhi etc. B.G Rail fastenings points and crossing bridge girders pipes sheets Rails M.S Bars etc or 1000 Nos. bricks 10'x5'x3' or 1000 Cft. Of timer or 100 Maunds of fuel wood by trucks or any other means owned by the contractors (lead up to 15 miles etc).	36352	% Cft	1065.04	One Thousand Sixty Five & Four Paisa Only	3,87,163
4.	Preparing sub-base by supplying and spreading well graded pit or bed run gravel having a liquid limit not greater than 25 and plasticity index not great than 6 in proper camber and grade including watering rolling and compacting in layers, thickness of each compacted layer not exceeding 6" compacted up to 98-100% density as per modified AASHTO density (Rate i/c all cost of materials T&P and carriage up to 3 chains.	3008	% Cft	3341.71	Thirty Three Hundred Forty One & Seventy One Paisa Only.	1,00,519
5.	P/L Aggregate base course in proper grade and camber having CBR 80% as per (AASHTO) standard specification i/c spreading and compacting by approved mechanical means (Motor Grader, Vibratory roller and smooth wheel roller etc) watering to maintain the	3489.28	% Cft	5542.24	Fifty Four Hundred Forty Two & Twenty Four Paisa Only.	1,93,384

	moisture content the compaction of each layer shall 100 percent to the max dry density (rate i/c all cost of materials T&P and carriage up to 3 chains).					
6.	Laying to proper line and grade plant mixed Asphalt concrete paver finished (Hydraulic / Electronic control) prepared to specified formula according to job mix formula approved by Engineer incharge including rolling and finishing to proper line grade level and camber etc (Machinery with POLs cost of material carriage) 4CM (50 mm) Thick Asphalt concrete wearing course plant mix.	6016	% Sft	6873.79	Sixty Eight Hundred Seventy Three & Seventy Nine Paise Only.	4,13,527

**KARACHI METROPOLITAN CORPORATION
ENGINEERING DEPARTMENT**

Subject: **IMPROVEMENT / REHABILITATION OF ROAD AT SHAH VILAYAT IMAM BARGAH,
LIAQUATABAD ZONE, DISTRICT (CENTRAL), KMC.**

Estimated Cost:- Rs. 9,78,460/=

Bid Security:- Rs. 20,000/=

Tender Cost: - Rs.2,500/=

I / We hereby quoted as follows:

1.	<u>PART – A:</u> (Items Based on S/R) amounting to Rs.11,51,129/=	Rs. _____
	% Below the S/R.	
TOTAL		Rs. _____

The total amount is Rs. _____ (Rupees _____ (In Words)
(in Figure) _____ (In Words)
_____ for complete job.

I / We have attached a pay order bearing No. _____ dated _____ issued from
_____ amounting to Rs. _____ as per NIT.
(Name of Bank)

Completion Time : 15 Days
Penalty per day: Rs. 2,500/=

Note:

- Tender must be quoted in figure & in words both otherwise liable to be cancelled.
- All over writing & correction if any must be initialed & stamped by the bidder.
- All prevailing rules regarding condition of contract will be applicable.
- 15% below is the maximum ceiling on schedule items 2012 by the authority.

Signature of the Contractor with Stamp

Address: _____

Checked By:-

KARACHI METROPOLITAN CORPORATION
ENGINEERING DEPARTMENT



Tender Reference No.KMC/CM/ED/ 94 /2013-14

BILL OF QUANTITIES

**IMPROVEMENT / REHABILITATION OF ROAD AT NOOR-UL-AMIN
IMAM BARGAH, LIAQUATABAD ZONE, DISTRICT(CENTRAL), KMC.**

NOTE:
The Condition of contract will be available on KMC website (www.karachicity.gov.pk).

Estimate Cost: - Rs.9,77,871/=
Bid Security: - Rs.20,000/=
Tender Cost: - Rs.2,500/=

MINIMUM QUALIFICATION / ELIGIBILITY CRITERIA

The evidence / documents of the following minimum qualification / eligibility criteria will be checked during opening process of tender & if anyone is missing then the tender will be summarily rejected at the moment by the tender opening committee.

Eligibility:

- i). NTN Certificate
- ii). Valid Professional TAX.

Minimum Qualification Criteria:

- iii). Bid Security, as mentioned in the NIT & Bidding Documents, is furnished.
- iv). All rates quoted including the total amount of the bid shall be in figures & words (both).
- v). All corrections / overwriting shall be clearly re-written with initials & duly stamped by the bidder.
- vi). The bid shall be properly signed, named & stamped by the authorized person of the firm and authorization letter for signatory shall be enclosed with the tender by the authorized Person, if other than the signatory of the firm.
- vii). The minimum turn over / work experience with satisfactory completion report in last 2 years or at least two or more works in hand and their aggregate cost should be equal to the work cost in which bidder interested to participate.

Signature of the Bidder with Stamp

✓
ok.

KARACHI METROPOLITAN CORPORATIN
ENGINEERING DEPARTMENT

Subject:- IMPROVEMENT / REHABILITATION OF ROAD AT NOOR-UL-AMIN
IMAM BARGAH, LIAQUATABAD ZONE, DISTRICT (CENTRAL),
KMC.

Estimated Cost: **Rs.9,77,871/=**

Earnest Money: **Rs.20,000/=**

Tender Cost: **Rs.2,500/=**

S.No.	DESCRIPTION	QTY	UNIT	Rate (in figure)	Rate (in figure)	AMOUNT
1.	Dismantling and removing of Road Metalling etc complete.	1610	% Cft	605.00	Six Hundred & Five Only.	9,741
2.	Earth Work Excavated undressed lead up to a single throw of Kassi Phawarah or Shovel in ordinary soil etc complete.	30492	% 0 Cft	1361.25	Thirteen Hundred Sixty One & Paisa Twenty Five Only.	41,507
3.	Cartage of 100 Cft / 5 Tones of all materials like stone aggregate, spawl, coal, lime, surkhi etc. B.G Rail fastenings points and crossing bridge girders pipes sheets Rails M.S Bars etc or 1000 Nos. bricks 10'x5'x3' or 1000 Cft. Of timer or 100 Maunds of fuel wood by trucks or any other means owned by the contractors (lead up to 15 miles etc).	32102	% Cft	1065.04	One Thousand Sixty Five & Four Paisa Only	3,41,899
4.	Preparing sub-base by supplying and spreading well graded pit or bed run gravel having a liquid limit not greater than 25 and plasticity index not great than 6 in proper camber and grade including watering rolling and compacting in layers, thickness of each compacted layer not exceeding 6" compacted up to 98-100% density as per modified AASHTO density (Rate i/c all cost of materials T&P and carriage up to 3 chains.	3220	% Cft	3341.71	Thirty Three Hundred Forty One & Seventy One Paisa Only.	1,07,603
5.	P/L Aggregate base course in proper grade and camber having CBR 80% as per (AASHTO) standard specification i/c spreading and compacting by approved mechanical means (Motor Grader, Vibratory roller and smooth wheel roller etc) watering to maintain the	3735.20	% Cft	5542.24	Fifty Four Hundred Forty Two & Twenty Four Paisa Only.	2,07,014

	moisture content the compaction of each layer shall 100 percent to the max dry density (rate i/c all cost of materials T&P and carriage up to 3 chains).					
6.	Laying to proper line and grade plant mixed Asphalt concrete paver finished (Hydraulic / Electronic control) prepared to specified formula according to job mix formula approved by Engineer incharge including rolling and finishing to proper line grade level and camber etc (Machinery with POLs cost of material carriage) 2" (50 mm) Thick Asphalt concrete wearing course plant mix.	6440	% Sft	6873.79	Sixty Eight Hundred Seventy Three & Seventy Nine Paise Only.	4,42,672

KARACHI METROPOLITAN CORPORATION
ENGINEERING DEPARTMENT

Subject: IMPROVEMENT / REHABILITATION OF ROAD AT NOOR-UL-AMIN IMAM BARGAH, LIAQUATABAD ZONE, DISTRICT (CENTRAL), KMC.

Estimated Cost:- Rs. 9,77,871/=

Bid Security:- Rs. 20,000/=

Tender Cost: - Rs.2,500/=

I / We hereby quoted as follows:

1.	PART – A: (Items Based on S/R) amounting to Rs.11,50,436/=	Rs. _____
	% Below the S/R.	
TOTAL		Rs. _____

The total amount is Rs. _____ (Rupees _____
(in Figure) (In Words)

_____ for complete job.

I / We have attached a pay order bearing No. _____ dated _____ issued from

_____ amounting to Rs. _____ as per NIT.

(Name of Bank)

Completion Time : 15 Days

Penalty per day: Rs. 2,500/=

Note:

- Tender must be quoted in figure & in words both otherwise liable to be cancelled.
- All over writing & correction if any must be initialed & stamped by the bidder.
- All prevailing rules regarding condition of contract will be applicable.
- 15% below is the maximum ceiling on schedule items 2012 by the authority.


Signature of the Contractor with Stamp

Address: _____

Checked By:- _____

Sr. No. 06.

KARACHI METROPOLITAN CORPORATION
ENGINEERING DEPARTMENT



Tender Reference No.KMC/CM/ED/ 95 /2013-14

BILL OF QUANTITIES

**REPAIR / MAINTENANCE OF 2200 ROAD FROM 5100 ROAD TO 7000 ROAD
AT NORTH KARACHI ZONE, DISTRICT(CENTRAL).**

NOTE:

The Condition of contract will be available on KMC website (www.karachicity.gov.pk).

Estimate Cost: - Rs.9,76,488/=

Bid Security: - Rs.20,000/=

Tender Cost: - Rs.2,500/=

MINIMUM QUALIFICATION / ELIGIBILITY CRITERIA

The evidence / documents of the following minimum qualification / eligibility criteria will be checked during opening process of tender & if anyone is missing then the tender will be summarily rejected at the moment by the tender opening committee.

Eligibility:

- i). NTN Certificate
- ii). Valid Professional TAX.

Minimum Qualification Criteria:

- iii). Bid Security, as mentioned in the NIT & Bidding Documents, is furnished.
- iv). All rates quoted including the total amount of the bid shall be in figures & words (both).
- v). All corrections / overwriting shall be clearly re-written with initials & duly stamped by the bidder.
- vi). The bid shall be properly signed, named & stamped by the authorized person of the firm and authorization letter for signatory shall be enclosed with the tender by the authorized Person, if other than the signatory of the firm.
- vii). The minimum turn over / work experience with satisfactory completion report in last 2 years or at least two or more works in hand and their aggregate cost should be equal to the work cost in which bidder interested to participate.

Signature of the Bidder with Stamp

KARACHI METROPOLITAN CORPORATIN
ENGINEERING DEPARTMENT

Subject:- **REPAIR / MAINTENANCE OF 2200 ROAD FROM 5100 ROAD TO 7000 ROAD AT NORTH KARACHI ZONE, DISTRICT (CENTRAL).**

Estimated Cost: **Rs.9,76,488/=**

Earnest Money: **Rs.20,000/=**

Tender Cost: **Rs.2,500/=**

S.No.	DESCRIPTION	QTY	UNIT	Rate (in figure)	Rate (in figure)	AMOUNT
1.	Dismantling of bitumen's carpet of average thickness in between 3" to 4" etc complete as required.	2250	% Sft	605.00	Six Hundred & Five Only.	13,613
2.	Dismantling of cement concrete work cast in situ in foundation basement and plinth i/c disposal of surplus material with in three chain.	50	% Cft	3327.50	Thirty Three Hundred Twenty Seven & Fifty Paise Only.	1,664
3.	Excavation or cutting in all kinds of soil (expect gravelly, murum, wet, silt, clay or mud and rock) to a required grade, camber and site slopes i/c dressing top and sides and excavated stuff stacking at site in suitable place.	4250	% 0 Cft	2722.50	Twenty Seven Hundred Twenty Two & Fifty Paise Only.	11,571
4.	Cartage of 100 Cft / 5 Tones of all materials like stone aggregate, spawl, coal, lime, surkhi etc. B.G Rail fastenings points and crossing bridge girders pipes sheets Rails M.S Bars etc or 1000 Nos. bricks 10'x5'x3' or 100 Maunds of fuel wood by trucks or any other means owned by the contractors (lead up to 10 miles etc).	6550	% Cft	714.29	Seven Thousand Fourteen & Twenty Nine Paise Only	46,786
5.	P/L Aggregate base course in proper grade and camber having CBR 80% as per (AASHTO) standard specification i/c spreading and compacting by approved mechanical means (Motor Grader, Vibratory roller and smooth wheel roller etc) watering to maintain the moisture content the compaction of each layer shall 100 percent to the max dry density (rate i/c all cost of materials T&P and carriage up to 3 chains).	4575	% Cft	5542.24	Fifty Four Hundred Forty Two & Twenty Four Paise Only.	2,53,557

6.	Laying to proper line and grade plant mixed Asphalt concrete paver finished (Hydraulic / Electronic control) prepared to specified formula according to job mix formula approved by Engineer incharge including rolling and finishing to proper line grade level. 1-1/2" thick.	12015.85	% Sft	6837.79	Sixty Eight Hundred Thirty Seven & Seventy Nine Paise Only.	8,21,619

KARACHI METROPOLITAN CORPORATION
ENGINEERING DEPARTMENT

Subject: REPAIR / MAINTENANCE OF 2200 ROAD FROM 5100 ROAD TO 7000 ROAD AT NORTH KARACHI ZONE, DISTRICT (CENTRAL).

Estimated Cost:- Rs. 9,76,488/=

Bid Security:- Rs. 20,000/=

Tender Cost: - Rs.2,500/=

I / We hereby quoted as follows:

1.	<u>PART – A:</u> (Items Based on S/R) amounting to Rs.11,48,809/= % Below the S/R.	Rs. _____
TOTAL		Rs. _____

The total amount is Rs. _____ (Rupees _____
(in Figure) (In Words) _____
for complete job.

I / We have attached a pay order bearing No. _____ dated _____ issued from
_____ amounting to Rs. _____ as per NIT.
(Name of Bank)

Completion Time : 15 Days
Penalty per day: Rs. 2,500/=

Note:

- Tender must be quoted in figure & in words both otherwise liable to be cancelled.
- All over writing & correction if any must be initialed & stamped by the bidder.
- All prevailing rules regarding condition of contract will be applicable.
- 15% below is the maximum ceiling on schedule items 2012 by the authority.

Signature of the Contractor with Stamp

Address: _____

Checked By:-

ST. No. 07.

KARACHI METROPOLITAN CORPORATION

ENGINEERING DEPARTMENT



Tender Reference No.KMC/CM/ED/ 96 /2013-14

BILL OF QUANTITIES

**REPAIR / MAINTENANCE OF ROAD 7000 FROM ROAD 4300 TO 6000
(RIGHT TRACK) ROAD AT NORTH KARACHI ZONE, DISTRICT(CENTRAL).**

NOTE:

The Condition of contract will be available on KMC website (www.karachicity.gov.pk).

Estimate Cost: - Rs.9,73,856/=

Bid Security: - Rs.20,000/=

Tender Cost: - Rs.2,500/=

MINIMUM QUALIFICATION / ELIGIBILITY CRITERIA

The evidence / documents of the following minimum qualification / eligibility criteria will be checked during opening process of tender & if anyone is missing then the tender will be summarily rejected at the moment by the tender opening committee.

Eligibility:

- i). NTN Certificate
- ii). Valid Professional TAX.

Minimum Qualification Criteria:

- iii). Bid Security, as mentioned in the NIT & Bidding Documents, is furnished.
- iv). All rates quoted including the total amount of the bid shall be in figures & words (both).
- v). All corrections / overwriting shall be clearly re-written with initials & duly stamped by the bidder.
- vi). The bid shall be properly signed, named & stamped by the authorized person of the firm and authorization letter for signatory shall be enclosed with the tender by the authorized Person, if other than the signatory of the firm.
- vii). The minimum turn over / work experience with satisfactory completion report in last 2 years or at least two or more works in hand and their aggregate cost should be equal to the work cost in which bidder interested to participate.

Signature of the Bidder with Stamp

KARACHI METROPOLITAN CORPORATIN
ENGINEERING DEPARTMENT

Subject:- **REPAIR / MAINTENANCE OF ROAD 7000 FROM ROAD 4300 TO 6000**
(RIGHT TRACK) ROAD AT NORTH KARACHI ZONE,
DISTRICT(CENTRAL).

Estimated Cost: **Rs.9,73,856/=**

Earnest Money: **Rs.20,000/=**

Tender Cost: **Rs.2,500/=**

S.No.	DESCRIPTION	QTY	UNIT	Rate (in figure)	Rate (in figure)	AMOUNT
1.	Dismantling of bitumen's carpet of average thickness in between 3" to 4" etc complete as required.	1948	% Sft	605.00	Six Hundred & Five Only.	11,785
2.	Dismantling of cement concrete work cast in situ in foundation basement and plinth i/c disposal of surplus material with in three chain.	122.76	% Cft	3327.50	Thirty Three Hundred Twenty Seven & Fifty Paise Only.	4,085
3.	Excavation or cutting in all kinds of soil (expect gravelly, murum, wet, silt, clay or mud and rock) to a required grade, camber and site slopes i/c dressing top and sides and excavated stuff stacking at site in suitable place.	3971	% 0 Cft	2722.50	Twenty Seven Hundred Twenty Two & Fifty Paise Only.	10,811
4.	Cartage of 100 Cft / 5 Tones of all materials like stone aggregate, spawl, coal, lime, surkhi etc. B.G Rail fastenings points and crossing bridge girders pipes sheets Rails M.S Bars etc or 1000 Nos. bricks 10'x5'x3' or 100 Maunds of fuel wood by trucks or any other means owned by the contractors (lead up to 10 miles etc).	6042	% Cft	714.29	Seven Thousand Fourteen & Twenty Nine Paise Only	43,156
5.	P/L Aggregate base course in proper grade and camber having CBR 80% as per (AASHTO) standard specification i/c compacting to the required density by the approved mechanical means (Vibratory roller road packer and smooth wheel roller etc) i/c watering with all lead and lift etc complete.	4258.49	% Cft	5542.24	Fifty Four Hundred Forty Two & Twenty Four Paise Only.	2,36,016

6.	Laying to proper line and grade plant mixed Asphalt concrete paver finished (Hydraulic / Electronic control) prepared to specified formula according to job mix formula approved by Engineer incharge including rolling and finishing to proper line grade level. 1-1/2" thick. i/c the cost of prime cost.	12282.63	% Sft	6837.79	Sixty Eight Hundred Thirty Seven & Seventy Nine Paise Only.	8,39,861
----	---	----------	-------	---------	---	----------

KARACHI METROPOLITAN CORPORATION
ENGINEERING DEPARTMENT

Subject: REPAIR / MAINTENANCE OF ROAD 7000 FROM ROAD 4300 ROAD TO 6000 ROAD (RIGHT TRACK) AT NORTH KARACHI ZONE, DISTRICT (CENTRAL).

Estimated Cost:- Rs. 9,73,856/=

Bid Security:- Rs. 20,000/=

Tender Cost: - Rs.2,500/=

I / We hereby quoted as follows:

1.	<u>PART - A:</u> (Items Based on S/R) amounting to Rs.11,45,713/= % Below the S/R.	Rs. _____
TOTAL		Rs. _____

The total amount is Rs. _____ (Rupees _____
(in Figure) (In Words) _____
for complete job.

I / We have attached a pay order bearing No. _____ dated _____ issued from _____
amounting to Rs. _____ as per NIT.
(Name of Bank)

Completion Time : 15 Days

Penalty per day: Rs. 2,500/=

Note:

- Tender must be quoted in figure & in words both otherwise liable to be cancelled.
- All over writing & correction if any must be initialed & stamped by the bidder.
- All prevailing rules regarding condition of contract will be applicable.
- 15% below is the maximum ceiling on schedule items 2012 by the authority.

Signature of the Contractor with Stamp

Address: _____

Checked By:- _____

KARACHI METROPOLITAN CORPORATION
ENGINEERING DEPARTMENT



Tender Reference No.KMC/CM/ED/ 97 /2013-14

BILL OF QUANTITIES

**IMPROVEMENT / REHABILITATION OF ROAD FROM RIZVIA IMAM
BARGAH TO GADEER CHOWK LIAQUATABAD ZONE, DISTRICT(CENTRAL), KMC.**

NOTE:

The Condition of contract will be available on KMC website (www.karachicity.gov.pk).

Estimate Cost: - Rs.9,67,779/=

Bid Security: - Rs.19,400/=

Tender Cost: - Rs.2,500/=

MINIMUM QUALIFICATION / ELIGIBILITY CRITERIA

The evidence / documents of the following minimum qualification / eligibility criteria will be checked during opening process of tender & if anyone is missing then the tender will be summarily rejected at the moment by the tender opening committee.

Eligibility:

- i). NTN Certificate
- ii). Valid Professional TAX.

Minimum Qualification Criteria:

- iii). Bid Security, as mentioned in the NIT & Bidding Documents, is furnished.
- iv). All rates quoted including the total amount of the bid shall be in figures & words (both).
- v). All corrections / overwriting shall be clearly re-written with initials & duly stamped by the bidder.
- vi). The bid shall be properly signed, named & stamped by the authorized person of the firm and authorization letter for signatory shall be enclosed with the tender by the authorized Person, if other than the signatory of the firm.
- vii). The minimum turn over / work experience with satisfactory completion report in last 2 years or at least two or more works in hand and their aggregate cost should be equal to the work cost in which bidder interested to participate.

Signature of the Bidder with Stamp

✓
OK

KARACHI METROPOLITAN CORPORATIN
ENGINEERING DEPARTMENT

Subject:- **IMPROVEMENT / REHABILITATION OF ROAD FROM RIZVIA**
IMAM BARGAH TO GADEER CHOWK LIAQUATABAD ZONE,
DISTRICT (CENTRAL), KMC.

Estimated Cost: **Rs.9,67,779/=**

Earnest Money: **Rs.19,400/=**

Tender Cost: **Rs.2,500/=**

S.No.	DESCRIPTION	QTY	UNIT	Rate (in figure)	Rate (in figure)	AMOUNT
1.	Dismantling and removing of Road Metalling etc complete.	1750	% Cft	605.00	Six Hundred & Five Only.	10,588
2.	Earth Work Excavated undressed lead up to a single throw of Kassi Phawarah or Shovel in ordinary soil etc complete.	23100	% 0 Cft	1361.25	Thirteen Hundred Sixty One & Paisa Twenty Five Only.	31,445
3.	Cartage of 100 Cft / 5 Tones of all materials like stone aggregate, spawl, coal, lime, surkhi etc. B.G Rail fastenings points and crossing bridge girders pipes sheets Rails M.S Bars etc or 1000 Nos. bricks 10'x5'x3' or 1000 Cft. Of timer or 100 Maunds of fuel wood by trucks or any other means owned by the contractors (lead up to 15 miles etc).	24850	% Cft	1065.04	One Thousand Sixty Five & Four Paisa Only	2,64,662
4.	Preparing sub-base by supplying and spreading well graded pit or bed run gravel having a liquid limit not greater than 25 and plasticity index not great than 6 in proper camber and grade including watering rolling and compacting in layers, thickness of each compacted layer not exceeding 6" compacted up to 98-100% density as per modified AASHTO density (Rate i/c all cost of materials T&P and carriage up to 3 chains.	4690	% Cft	3341.71	Thirty Three Hundred Forty One & Seventy One Paisa Only.	1,56,726
5.	P/L Aggregate base course in proper grade and camber having CBR 80% as per (AASHTO) standard specification i/c spreading and compacting by approved mechanical means (Motor Grader, Vibratory roller and smooth wheel roller etc) watering to maintain the	3500	% Cft	5542.24	Fifty Four Hundred Forty Two & Twenty Four Paisa Only.	1,93,978

	moisture content the compaction of each layer shall 100 percent to the max dry density (rate i/c all cost of materials T&P and carriage up to 3 chains).					
6.	Laying to proper line and grade plant mixed Asphalt concrete paver finished (Hydraulic / Electronic control) prepared to specified formula according to job mix formula approved by Engineer incharge including rolling and finishing to proper line grade level and camber etc (Machinery with POLs cost of material carriage) 2" (50 mm) Thick Asphalt concrete wearing course plant mix.	7000	% Sft	6873.79	Sixty Eight Hundred Seventy Three & Seventy Nine Paise Only.	4,81,165

KARACHI METROPOLITAN CORPORATION
ENGINEERING DEPARTMENT

Subject: IMPROVEMENT / REHABILITATION OF ROAD FROM RIZVIA IMAM BARGAH TO GADEER CHOWK LIAQUATABAD ZONE, DISTRICT (CENTRAL), KMC.

Estimated Cost:- Rs. 9,67,779/=
Bid Security:- Rs. 19,400/=
Tender Cost: - Rs.2,500/=

I / We hereby quoted as follows:

1.	<u>PART – A:</u> (Items Based on S/R) amounting to Rs.11,38,564/= % Below the S/R.	Rs. _____
TOTAL		Rs. _____

The total amount is Rs. _____ (Rupees _____
(in Figure) (In Words) _____
for complete job.

I / We have attached a pay order bearing No. _____ dated _____ issued from _____
amounting to Rs. _____ as per NIT.
(Name of Bank)

Completion Time : 15 Days
Penalty per day: Rs. 2,500/=

Note:

- Tender must be quoted in figure & in words both otherwise liable to be cancelled.
- All over writing & correction if any must be initialed & stamped by the bidder.
- All prevailing rules regarding condition of contract will be applicable.
- 15% below is the maximum ceiling on schedule items 2012 by the authority.

Signature of the Contractor with Stamp


Address: _____

Checked By:- _____

Sl. No. 09

KARACHI METROPOLITAN CORPORATION

ENGINEERING DEPARTMENT



Tender Reference No.KMC/CM/ED/ 98 /2013-14

BILL OF QUANTITIES

**REPAIR / MAINTENANCE AT SHAHRAH-E-PAKISTAN, GULBERG TOWN,
DISTRICT(CENTRAL).**

NOTE:

The Condition of contract will be available on KMC website (www.karachicity.gov.pk).

Estimate Cost: - Rs.9,49,072/=
Bid Security: - Rs.19,000/=
Tender Cost: - Rs.2,500/=

MINIMUM QUALIFICATION / ELIGIBILITY CRITERIA

The evidence / documents of the following minimum qualification / eligibility criteria will be checked during opening process of tender & if anyone is missing then the tender will be summarily rejected at the moment by the tender opening committee.

Eligibility:

- i). NTN Certificate
- ii). Valid Professional TAX.

Minimum Qualification Criteria:

- iii). Bid Security, as mentioned in the NIT & Bidding Documents, is furnished.
- iv). All rates quoted including the total amount of the bid shall be in figures & words (both).
- v). All corrections / overwriting shall be clearly re-written with initials & duly stamped by the bidder.
- vi). The bid shall be properly signed, named & stamped by the authorized person of the firm and authorization letter for signatory shall be enclosed with the tender by the authorized Person, if other than the signatory of the firm.
- vii). The minimum turn over / work experience with satisfactory completion report in last 2 years or at least two or more works in hand and their aggregate cost should be equal to the work cost in which bidder interested to participate.

Signature of the Bidder with Stamp

KARACHI METROPOLITAN CORPORATIN
ENGINEERING DEPARTMENT

Subject:- **REPAIR / MAINTENANCE AT SHAHRAH-E-PAKISTAN GULBERG**
TOWN DISTRICT(CENTRAL).

Estimated Cost: **Rs.9,49,072/=**

Earnest Money: **Rs.19,000/=**

Tender Cost: **Rs.2,500/=**

S.No.	DESCRIPTION	QTY	UNIT	Rate (in figure)	Rate (in figure)	AMOUNT
1.	Dismantling of bitumen's carpet of average thickness in between 3" to 4" etc complete as required.	1428	% Sft	605.00	Six Hundred & Five Only.	8,639
2.	Dismantling of cement concrete work cast in situ in foundation basement and plinth i/c disposal of surplus material with in three chain.	25.51	% Cft	3327.50	Thirty Three Hundred Twenty Seven & Fifty Paise Only.	849
3.	Excavation or cutting in all kinds of soil (expect gravelly, murum, wet, silt, clay or mud and rock) to a required grade, camber and site slopes i/c dressing top and sides and excavated stuff stacking at site in suitable place.	6775	% 0 Cft	2722.50	Twenty Seven Hundred Twenty Two & Fifty Paise Only.	18,445
4.	Cartage of 100 Cft / 5 Tones of all materials like stone aggregate, spawl, coal, lime, surkhi etc. B.G Rail fastenings points and crossing bridge girders pipes sheets Rails M.S Bars etc or 1000 Nos. bricks 10'x5'x3' or 100 Maunds of fuel wood by trucks or any other means owned by the contractors (lead up to 10 miles etc).	8229	% Cft	714.29	Seven Thousand Fourteen & Twenty Nine Paise Only	58,779
5.	P/L Aggregate base course in proper grade and camber having CBR 80% as per (AASHTO) standard specification i/c compacting to the required density by the approved mechanical means (Vibratory roller road packer and smooth wheel roller etc) i/c watering with all lead and lift etc complete.	5874	% Cft	5542.24	Fifty Four Hundred Forty Two & Twenty Four Paise Only.	3,25,551

6.	Laying to proper line and grade plant mixed Asphalt concrete paver finished (Hydraulic / Electronic control) prepared to specified formula according to job mix formula approved by Engineer incharge including rolling and finishing to proper line grade level. 1-1/2" thick. i/c the cost of prime cost/tack coat.	10300	% Sft	6837.79	Sixty Eight Hundred Thirty Seven & Seventy Nine Paise Only.	7,04,292
----	--	-------	-------	---------	--	----------

**KARACHI METROPOLITAN CORPORATION
ENGINEERING DEPARTMENT**

Subject: REPAIR / MAINTENANCE AT SHAHRAH-E-PAKISTAN GULBERG TOWN, DISTRICT CENTRAL.

Estimated Cost:- Rs. 9,49,072/=

Bid Security:- Rs. 19,000/=

Tender Cost: - Rs.2,500/=

I / We hereby quoted as follows:

1.	<u>PART – A:</u> (Items Based on S/R) amounting to Rs.11,16,555/= % Below the S/R.	Rs. _____
TOTAL		Rs. _____

The total amount is Rs. _____ (Rupees _____
(in Figure) (In Words) _____
for complete job.

I / We have attached a pay order bearing No. _____ dated _____ issued from
_____ amounting to Rs. _____ as per NIT.
(Name of Bank)

Completion Time : 15 Days
Penalty per day: Rs. 2,500/=

Note:

- Tender must be quoted in figure & in words both otherwise liable to be cancelled.
- All over writing & correction if any must be initialed & stamped by the bidder.
- All prevailing rules regarding condition of contract will be applicable.
- 15% below is the maximum ceiling on schedule items 2012 by the authority.

Signature of the Contractor with Stamp

Address: _____

Checked By:-

Sr. NO. 10.

KARACHI METROPOLITAN CORPORATION
ENGINEERING DEPARTMENT



Tender Reference No.KMC/CM/ED/ 99 /2013-14

BILL OF QUANTITIES

**REPAIR OF ROAD & POT HOLES FROM SURROUNDING TO IMAM
BARGAH ZAIN-UL-ABIDEEN IN SECOT 15/A-3 AND 14/B BUFFER
ZONE KARACHI.**

NOTE:

The Condition of contract will be available on KMC website (www.karachicity.gov.pk).

Estimate Cost: - Rs.9,15,000/=

Bid Security: - Rs.18,300/=

Tender Cost: - Rs.2,500/=

MINIMUM QUALIFICATION / ELIGIBILITY CRITERIA

The evidence / documents of the following minimum qualification / eligibility criteria will be checked during opening process of tender & if anyone is missing then the tender will be summarily rejected at the moment by the tender opening committee.

Eligibility:

- i). NTN Certificate
- ii). Valid Professional TAX.

Minimum Qualification Criteria:

- iii). Bid Security, as mentioned in the NIT & Bidding Documents, is furnished.
- iv). All rates quoted including the total amount of the bid shall be in figures & words (both).
- v). All corrections / overwriting shall be clearly re-written with initials & duly stamped by the bidder.
- vi). The bid shall be properly signed, named & stamped by the authorized person of the firm and authorization letter for signatory shall be enclosed with the tender by the authorized Person, if other than the signatory of the firm.
- vii). The minimum turn over / work experience with satisfactory completion report in last 2 years or at least two or more works in hand and their aggregate cost should be equal to the work cost in which bidder interested to participate.

Signature of the Bidder with Stamp

KARACHI METROPOLITAN CORPORATIN
ENGINEERING DEPARTMENT

Subject:- **REPAIR OF ROAD & POT HOLES FROM SURROUNDING TO IMAM**
BARGAH ZAIN-UL-ABIDEEN IN SECTOR 15/A-3 AND 14/B BUFFER
ZONE KARACHI.

Estimated Cost: **Rs.9,15,000/=**

Earnest Money: **Rs.18,300/=**

Tender Cost: **Rs.2,500/=**

S.No.	DESCRIPTION	QTY	UNIT	Rate (in figure)	Rate (in figure)	AMOUNT
1.	Dismantling of bitumen's carpet of average thickness in between 3" to 4" etc complete as required.	3190	% Sft	605.00	Six Hundred & Five Only.	19,300
2.	Cartage of 100 Cft / 5 Tones of all materials like stone aggregate, spawl, coal, lime, surkhi etc. B.G Rail fastenings points and crossing bridge girders pipes sheets Rails M.S Bars etc or 100 Maunds of fuel wood by trucks or any other means owned by the contractors (lead up to 10 miles etc).	3190	% Cft	902.00	Nine Hundred & Two Only	28,774
3.	P/L Aggregate base course in proper grade and camber having CBR 80% as per (AASHTO) standard specification i/c compacting to the required density by the approved mechanical means (Vibratory roller road packer and smooth wheel roller etc) i/c watering with all lead and lift etc complete.	4683	% Cft	5542.24	Fifty Four Hundred Forty Two & Twenty Four Paise Only.	2,59,543
4.	Providing and laying 3 CM wearing course of compacted thickness on the following job mix formula sign crush aggregate from hub source on equivalent. Using asphalt of grade 60/70 during laying temperature not less then 140 C compacted by steel wheel and PTR roller i/c the cost of prime coat or take coat.	18730	% Sft	4107.84	Four Thousand One Hundred Seven & Eighty Four Paise Only	7,69,398

KARACHI METROPOLITAN CORPORATION
ENGINEERING DEPARTMENT

Subject: **REPAIR OF ROAD & POT HOLES FROM SURROUNDING TO IMAM BARGAH ZAIN-UL-ABIDEEN IN SECTOR 15/A-3 AND 14/B BUFFER ZONE KARACHI.**

Estimated Cost:- Rs. 9,15,000/=

Bid Security:- Rs. 18,300/=

Tender Cost: - Rs.2,500/=

I / We hereby quoted as follows:

1.	<u>PART – A:</u> (Items Based on S/R) amounting to Rs.10,77,015/=	Rs. _____
	% Below the S/R.	
	TOTAL	Rs. _____

The total amount is Rs. _____ (Rupees _____ (In Words)
(in Figure) _____ for complete job.

I / We have attached a pay order bearing No. _____ dated _____ issued from
_____ amounting to Rs. _____ as per NIT.
(Name of Bank)

Completion Time : 15 Days
Penalty per day: Rs. 2,500/=

Note:

- Tender must be quoted in figure & in words both otherwise liable to be cancelled.
- All over writing & correction if any must be initialed & stamped by the bidder.
- All prevailing rules regarding condition of contract will be applicable.
- 15% below is the maximum ceiling on schedule items 2012 by the authority.

Signature of the Contractor with Stamp

Address: _____

Checked By:-

Sr. NO. 11.

KARACHI METROPOLITAN CORPORATION
ENGINEERING DEPARTMENT



Tender Reference No.KMC/CM/ED/ 100 /2013-14

BILL OF QUANTITIES

**REPAIR / MAINTENANCE IN WAY OF JALOUS, ASKARI IMAM BARGAH
BLOCK-9, FEDERAL "B" AREA, GULBERG TOWN ZONE, DISTRICT(CENTRAL).**

NOTE:

The Condition of contract will be available on KMC website (www.karachicity.gov.pk).

Estimate Cost: - Rs.9,13,930/=

Bid Security: - Rs.18,300/=

Tender Cost: - Rs.2,500/=

MINIMUM QUALIFICATION / ELIGIBILITY CRITERIA

The evidence / documents of the following minimum qualification / eligibility criteria will be checked during opening process of tender & if anyone is missing then the tender will be summarily rejected at the moment by the tender opening committee.

Eligibility:

- i). NTN Certificate
- ii). Valid Professional TAX.

Minimum Qualification Criteria:

- iii). Bid Security, as mentioned in the NIT & Bidding Documents, is furnished.
- iv). All rates quoted including the total amount of the bid shall be in figures & words (both).
- v). All corrections / overwriting shall be clearly re-written with initials & duly stamped by the bidder.
- vi). The bid shall be properly signed, named & stamped by the authorized person of the firm and authorization letter for signatory shall be enclosed with the tender by the authorized Person, if other than the signatory of the firm.
- vii). The minimum turn over / work experience with satisfactory completion report in last 2 years or at least two or more works in hand and their aggregate cost should be equal to the work cost in which bidder interested to participate.

Signature of the Bidder with Stamp

KARACHI METROPOLITAN CORPORATIN
ENGINEERING DEPARTMENT

Subject:- **REPAIR / MAINTENANCE OF IN WAY OF JALOS, ASKARI IMAM**
BARGAH BLOCK-9, FEDERAL "B" AREA GULBERG TOWN
DISTRICT(CENTRAL).

Estimated Cost: **Rs.9,13,930/=**

Earnest Money: **Rs.18,300/=**

Tender Cost: **Rs.2,500/=**

S.No.	DESCRIPTION	QTY	UNIT	Rate (in figure)	Rate (in figure)	AMOUNT
1.	Dismantling of bitumen's carpet of average thickness in between 3" to 4" etc complete as required.	1470	% Sft	605.00	Six Hundred & Five Only.	8,894
2.	Dismantling of cement concrete work cast in situ in foundation basement and plinth i/c disposal of surplus material with in three chain.	25.51	% Cft	3327.50	Thirty Three Hundred Twenty Seven & Fifty Paise Only.	849
3.	Excavation or cutting in all kinds of soil (expect gravelly, murum, wet, silt, clay or mud and rock) to a required grade, camber and site slopes i/c dressing top and sides and excavated stuff stacking at site in suitable place.	14800	% 0 Cft	2722.50	Twenty Seven Hundred Twenty Two & Fifty Paise Only.	40,293
4.	Cartage of 100 Cft / 5 Tones of all materials like stone aggregate, spawl, coal, lime, surkhi etc. B.G Rail fastenings points and crossing bridge girders pipes sheets Rails M.S Bars etc or 1000 Nos. bricks 10'x5'x3' or 100 Maunds of fuel wood by trucks or any other means owned by the contractors (lead up to 10 miles etc).	16295.48	% Cft	714.29	Seven Thousand Fourteen & Twenty Nine Paise Only	1,16,397
5.	P/L Aggregate base course in proper grade and camber having CBR 80% as per (AASHTO) standard specification i/c compacting to the required density by the approved mechanical means (Vibratory roller road packer and smooth wheel roller etc) i/c watering with all lead and lift etc complete.	4800	% Cft	5542.24	Fifty Four Hundred Forty Two & Twenty Four Paise Only.	2,66,028

6.	Laying to proper line and grade plant mixed Asphalt concrete paver finished (Hydraulic / Electronic control) prepared to specified formula according to job mix formula approved by Engineer incharge including rolling and finishing to proper line grade level. 1-1/2" thick. i/c the cost of prime cost/tack coat.	9400	% Sft	6837.79	Sixty Eight Hundred Thirty Seven & Seventy Nine Paise Only.	6,42,752
----	---	------	-------	---------	---	----------

KARACHI METROPOLITAN CORPORATION
ENGINEERING DEPARTMENT

Subject: REPAIR / MAINTENANCE IN WAY OF JALOUR, ASKARI IMAM BARGAH BLOCK-9, FEDERAL "B" AREA, GULBERG TOWN, DISTRICT CENTRAL.

Estimated Cost:- Rs. 9,13,930/=

Bid Security:- Rs. 18,300/=

Tender Cost: - Rs.2,500/=

I / We hereby quoted as follows:

1.	PART – A: (Items Based on S/R) amounting to Rs.10,75,212/=	Rs. _____
	% Below the S/R.	
	TOTAL	Rs. _____

The total amount is Rs. _____ (Rupees _____ (in Figure) _____ (In Words) _____ for complete job.

I / We have attached a pay order bearing No. _____ dated _____ issued from _____ amounting to Rs. _____ as per NIT.
(Name of Bank)

Completion Time : 15 Days
Penalty per day: Rs. 2,500/=

Note:

- Tender must be quoted in figure & in words both otherwise liable to be cancelled.
- All over writing & correction if any must be initialed & stamped by the bidder.
- All prevailing rules regarding condition of contract will be applicable.
- 15% below is the maximum ceiling on schedule items 2012 by the authority.

Signature of the Contractor with Stamp

Address: _____

Checked By:- _____

Sl. No. 12.

KARACHI METROPOLITAN CORPORATION
ENGINEERING DEPARTMENT



Tender Reference No.KMC/CM/ED/ 101 /2013-14

BILL OF QUANTITIES

**REPAIR OF ROAD & POT HOLES ALONG ROUTES & SURROUNDING TO
IMAM BARGAH BAB-UL-ILM (5 STAR ROUND ABOUT & IMAM BARGAH
SAJJADIAH NEAR ZIAUDDIN HOSPITAL) NORTH NAZIMABAD ZONE.**

NOTE:

The Condition of contract will be available on KMC website (www.karachicity.gov.pk).

Estimate Cost: - Rs.8,93,000/=

Bid Security: - Rs.18,000/=

Tender Cost: - Rs.2,500/=

MINIMUM QUALIFICATION / ELIGIBILITY CRITERIA

The evidence / documents of the following minimum qualification / eligibility criteria will be checked during opening process of tender & if anyone is missing then the tender will be summarily rejected at the moment by the tender opening committee.

Eligibility:

- i). NTN Certificate
- ii). Valid Professional TAX.

Minimum Qualification Criteria:

- iii). Bid Security, as mentioned in the NIT & Bidding Documents, is furnished.
- iv). All rates quoted including the total amount of the bid shall be in figures & words (both).
- v). All corrections / overwriting shall be clearly re-written with initials & duly stamped by the bidder.
- vi). The bid shall be properly signed, named & stamped by the authorized person of the firm and authorization letter for signatory shall be enclosed with the tender by the authorized Person, if other than the signatory of the firm.
- vii). The minimum turn over / work experience with satisfactory completion report in last 2 years or at least two or more works in hand and their aggregate cost should be equal to the work cost in which bidder interested to participate.

Signature of the Bidder with Stamp

KARACHI METROPOLITAN CORPORATIN
ENGINEERING DEPARTMENT

Subject:- **REPAIR OF ROAD & POT HOLES ALONG ROUTES AND**
SURROUNDING OF IMAM BARGAH BABUL-ILM (5 STAR ROUND
ABOUT AND IMAM BARGAH SAJJADIAH NEAR ZIAUDDIN
HOSPITAL) NORTH NAZIMABAD ZONE.

Estimated Cost: **Rs.8,93,000/=**

Earnest Money: **Rs.18,000/=**

Tender Cost: **Rs.2,500/=**

S.No.	DESCRIPTION	QTY	UNIT	Rate (in figure)	Rate (in figure)	AMOUNT
1.	Dismantling of bitumen's carpet of average thickness in between 3" to 4" etc complete as required.	3125	% Sft	605.00	Six Hundred & Five Only.	18,907
2.	Cartage of 100 Cft / 5 Tones of all materials like stone aggregate, spawl, coal, lime, surkhi etc. B.G Rail fastenings points and crossing bridge girders pipes sheets Rails M.S Bars etc or 100 Maunds of fuel wood by trucks or any other means owned by the contractors (lead up to 10 miles etc).	3125	% Cft	902.00	Nine Hundred & Two Only	28,188
3.	P/L Aggregate base course in proper grade and camber having CBR 80% as per (AASHTO) standard specification i/c compacting to the required density by the approved mechanical means (Vibratory roller road packer and smooth wheel roller etc) i/c watering with all lead and lift etc complete.	4599	% Cft	5542.24	Fifty Four Hundred Forty Two & Twenty Four Paise Only.	2,54,888
4.	Providing and laying 3 CM wearing course of compacted thickness on the following job mix formula sign crush aggregate from hub source on equivalent. Using asphalt of grade 60/70 during laying temperature not less then 140 C compacted by steel wheel and PTR roller i/c the cost of prime coat or take coat.	18388	% Sft	4107.84	Four Thousand One Hundred Seven & Eighty Four Paise Only	7,55,350

KARACHI METROPOLITAN CORPORATION
ENGINEERING DEPARTMENT

Subject: REPAIR OF ROAD & POT HOLES ALONG ROUTES AND SURROUNDING OF IMAM BARGAH BABUL-ILM (5 STAR ROUND ABOUT AND IMAM BARGAH SAJJADIAH NEAR ZIAUDDIN HOSPITAL) NORTH NAZIMABAD ZONE.

Estimated Cost:- Rs. 8,93,000/=

Bid Security:- Rs. 18,000/=

Tender Cost: - Rs.2,500/=

I / We hereby quoted as follows:

1.	<u>PART - A:</u> (Items Based on S/R) amounting to Rs.10,57,333/= % Below the S/R.	Rs. _____
TOTAL		Rs. _____

The total amount is Rs. _____ (in Figure) (Rupees _____ (In Words) _____ for complete job.

I / We have attached a pay order bearing No. _____ dated _____ issued from _____ amounting to Rs. _____ as per NIT.

(Name of Bank)

Completion Time : 15 Days

Penalty per day: Rs. 2,500/=

Note:

- Tender must be quoted in figure & in words both otherwise liable to be cancelled.
- All over writing & correction if any must be initialed & stamped by the bidder.
- All prevailing rules regarding condition of contract will be applicable.
- 15% below is the maximum ceiling on schedule items 2012 by the authority.

Signature of the Contractor with Stamp

Address: _____

Checked By:- _____