



# **KARACHI WATER & SEWERAGE BOARD**

## **OFFICE OF THE EXECUTIVE ENGINEER (SEW)**

### **(CLIFTON / SADDAR DISTRICT SOUTH)**

DEFUNT K.D.A OFFICE OPP: BILAWAL HOUSE  
NEAR BILAWAL CHOWRANGI CLIFTON KARACHI.

Cell: 0334-3324756

#### **NOTICE INVITING TENDER THROUGH AUTHORITY'S WEBSITE (ON SCHEDULE RATE BASIS + OFFER RATE BASIS)**

1. KW&SB invites Sealed Tenders on Composite Schedule of Rates (CSR) / Offer Rates Basis Offer Rate Basis from interested contractors / firms:-

<b>Name of Work</b>	<b>Estimated Cost (in Rupees)</b>	<b>Bid Security + 2% of Offer Rates.</b>	<b>Tender Fee</b>	<b>Time for completion</b>
REPLACEMENT OF OLD UNSERVICEABLE DAMAGED 8" DIA, 12" DIA & 18" DIA SEWER LINE TAKERY COLONY FAREER TOWN BLOCK NO.5, UC-9, HIJRAT COLONY CLIFTON, SADDAR DISTRICT SOUTH.	Rs.9,18,354/=	Rs.18,367/= in Shape of Payorder / Demand Draft / Bank Guarantee in favour of KW&SB.	Rs.500/=	30 Days.

#### **2. Eligibility:**

- Having National Tax Number.
- One Year Relevant Work Experience.

3. **Method of Procurement:** Single Stage, Single Envelope Basis.

#### **4. Bidding / Tender Documents:**

- Issuance:** Documents will be issued / downloaded from the date of first Published / Hoisting on SPPRA Website on attached Bid Security / Payment of Tender Fee (Non Refundable). Up to 03-01-2014.
- Submission:** Last Date Will be **06-01-2014**, time 2:00 Pm.
- Opening:** Tender Will be opened on **06-01-2014**, time 2:30 Pm.
- Place of Issuance:** Office of the Accounts Officer (Revenue), KW&SB at KW&SB Head Office, at 1<sup>st</sup> Floor Old KBCA Building, Behind Civic Centre, Gulshan-e-Iqbal Karachi, from 9:00 am to 1:00 Pm on all working days except date of opening / Downloaded from Authority's Website.
- Place of Submission & Opening:** Office of the Chief Engineer (IP&D), KW&SB at 9<sup>th</sup> Mile Karsaz, Shahrah-e-Faisal, Karachi.

#### **5. Terms & Conditions:**

- Under following conditions bids / tenders will be rejected:
  - Conditional and telegraphic bids / tenders.
  - Bids not accompanied by bid Security of required amount and from:
  - Bids received after specified date and time.
  - Black listed firms.
- Bid Validity Period:** 90 Days.
- Procuring Agency reserves the rights all or any bids subject to the relevant provision of Sindh Public Procurement Rule-2010.
- If any undesirable circumstances aris on the opening date on Govt. declare the Holiday the Tender shall be opened on the next working day at the same time and venue.

**(KARACHI WATER & SEWERAGE BOARD)**



# KARACHI WATER & SEWERAGE BOARD

OFFICE OF THE EXECUTIVE ENGINEER (SEW)

(CLIFTON / SADDAR DISTRICT SOUTH)

DEFUNT K.D.A OFFICE OPP: BILAWAL HOUSE  
NEAR BILAWAL CHOWRANGI CLIFTON KARACHI.  
Cell: 0334-3324756

SUBJECT:- **REPLACEMENT OF OLD UNSERVICEABLE DAMAGED 8" DIA, 12" DIA & 18" DIA SEWER LINE TAKERY COLONY FAREER TOWN BLOCK NO.5, UC-9, HIJRAT COLONY CLIFTON, SADDAR DISTRICT SOUTH.**


Estimated Cost On Item Rate Basis. Issued to M/S. \_\_\_\_\_  
Time Limit 30 Days  
Tender Cost Rs.500/= Pay Order No. \_\_\_\_\_ Dated: \_\_\_\_\_  
Penalty Rs.500/=

## ISSUING AUTHORITY

Sr.	Description	Quantity	Rate	Per	Amount
01.	Scarifying the existing road surface.	3655 Sft.		% Sft	
02.	Dismantling and removing road metalling.	7430 Cft.		% Cft	
03.	Excavation for Pipe line in trenches, and pits in all kinds of Soils or murum i/c. trimming and dressing sides to true alignment and shape leveling of bads of trenches to correct level and grade cutting joint holes and disposal of surplus earth within a one chain as directed by the Engineer Incharge. Providing fence guard's ligts, flags and temporary crossing for non-vehicular traffic where over required lifts upto 5 ft (1.52m) and lead upto one chain (30.5m). iii. Lift 0' - 5' iv. Lift 5' to 8'	8354 Cft.		% 0Cft.	
		1260 Cft.		% 0Cft.	
04.	Full Hire Charges of Pumping set per day inclusive of the wages of driver and assistant, fuel and electric energy plate from required for placing the pump etc, at lower depth with suction and delivery pipe for pumping out water pound at various depth from trenches including the cost of erection and dismantling after completion of job of 10HP form 10 Feet Depth.	18 Days.		P/Day	
05.	Providing laying RCC Pipes with (Rubber Ring Joint and fitting i/c. cutting, fitting and jointing with rubber ring i/c. testing with water to specified pressure. 8" dia 12" dia 18" dia	414 Rft.		P/Rft	
		735 Rft.		P/Rft	
		95 Rft.		P/Rft	
06.	Providing M/H 4 feet internal diameter without RCC manhole cover with CI frame (15Kg) and feet clear depth cast in situ 1:2: 9" thick wall 1:4:8 cement concrete in 6ft dia and 6 inch thick in foundation, 1:2:4 CC in benching ½" thick cement plaster 1:3 cement mortar on inside wall and surface of channel and benching to top including making required numbers of main and branches channels ¾" dia bars M.S foot rest at 12" C/C including cost of excavation in all kinds of soil, back filling and disposal of excavated stuff etc complete, as per design and instruction of the Engineer Incharge. Including C.I frame 15 Kg.	19 Nos.		Each	

SUBJECT:- **REPLACEMENT OF OLD UNSERVICEABLE DAMAGED 8" DIA, 12" DIA & 18" DIA SEWER LINE TAKERY COLONY FAREER TOWN BLOCK NO.5, UC-9, HIJRAT COLONY CLIFTON, SADDAR DISTRICT SOUTH.**

Sr.	Description	Quantity	Rate	Per	Amount
07.	Add or deduct for extra / less depth then 5ft of 4 ft dia manhole i/c. footrest.	7 Inches.		P/Inch.	
08.	Making connection with existing Manholes i/c. her cost of cutting holes in walls making them goodd in cement concrete 1:2:4 and making the required channel etc complete.	12 Nos.		Each	
09.	Refilling the excavated stuff in trenches 6" thick layer i/c. watering ramming to full compaction etc complete.	5941 Cft.		% OCft	
10.	Sand Haro or any other source Sand of the same modules of the Finences (Hill Sand).	3155 Cft		% Cft	
11.	Carriage of 100 Cft./5 Tons of all materials like stone aggregate. Spawl, coal, lime, surkhi, etc. B.G Rail fastening points and crossing bridge, Girders, Pipes, Sheet Rail, M.S Bars etc. Nos: 1000 Nos: titles, 12"x16"x2" or 150 Cft of timber or 100 Maunds of fuel wood by trucks or any other means owned by the contractors. 7 <sup>th</sup> Mile	4503.26 Cft		% Cft	
				<b>Total</b>	

  
 EXECUTIVE ENGINEER (SEW)  
 CLIFTON / SADDAR DISTRICT SOUTH  
 (KW&SB)

I hereby quoted bid amount of Rs. \_\_\_\_\_ (Rupees in words \_\_\_\_\_)

\_\_\_\_\_

Signature of Contractor \_\_\_\_\_

Address \_\_\_\_\_