



KARACHI WATER & SEWERAGE BOARD

OFFICE OF THE EXECUTIVE ENGINEER (WATER)

LYARI TOWN DISTRICT (SOUTH), KW&SB

JAMILA PUMPING STATION, JAMILA STREET GHASS MANDI LYARI KARACHI

Cell # 0331-2539812

NOTICE FOR INVITING TENDER THROUGH AUTHORITY'S WEBSITE(UNDER 1.00 MILLION).


01.	Name of work.	REPAIRING / CONSTRUCTION OF BROKEN MASONRY CHAMBER AT MIRZA ADAM KHAN ROAD, MAURIPUR ROAD AND DIFFERENT STREETS OF LYARI TOWN (WATER), DIST. (SOUTH), KW&SB.
02.	Eligibility of Contractor:	All eligible Contractor Bidder should having N.T.N Certificate.
03.	Tender can be purchased.	Tender documents can be purchased from the Office of the Accounts Officer (Revenue), KW&SB at KW&SB Head Office, at 1 st Floor Old KBCA, Annexy Building, Behind Civic Centre, Gulshan-e-Iqbal Karachi, between 9:00 am to 1:00 pm in any working day except the date of opening of the tenders.
04.	Source of Funding.	KW&SB's own funds under B.G. NO. E-013-17 (2013-2014).
05.	Bid Security.	2% of bid security of the quoted cost / price in shape of pay order / Bank Draft for any schedule bank of Pakistan in favour of Karachi Water & Sewerage Board.
06.	Note.	(i) No tender will be issued on the date of opening of tender. (ii) Bid Security in Shape of Pay Order / Bank Draft from any Schedule Bank of Pakistan in favour of KW&SB must be accompanied with the Tender otherwise the tenders shall be treated as invalid & rejected.
07.	Tender Fee.	RS. 1,000/= Non-Refundable in shape of Pay Order in favour of KW&SB.
08.	Start date / Last date of issuing of tender documents.	w.e.f 1 st hoisting upto 03-04-2014 , during working hours from 9:00 am to 1:00 pm.
09.	Date & Time of submission of tenders & Opening of Tenders.	04-04-2014 , upto 02:00 PM and will be opened at 02:30 PM.
10.	Place of Opening.	Tender will be opened by the Procurement Committee-I , at the Office of the Chief Engineer, (IP&D), KW&SB at 9 th Mila Karsaz, Shahrah-e-Faisal, Karachi.
11.	Scope of work:	Improvement of Water Supply System.

Note :- i) The Procuring Agency may reject all or any bids subject to the relevant provision of SPPRA Rules-2010.

ii). Tender can be seen on SPPRA's Website.

iii). In case of any unforeseen situation in closure of office on the date of opening or if Government declares Holiday the tender shall be submitted / opened on the next working day at the same time & venue.

KARACHI WATER & SEWERAGE BOARD


SYED NASIR ALI SHAH
EXECUTIVE ENGINEER (W)
LYARI TOWN, KW&SB

OFFICE OF THE EXECUTIVE ENGINEER (WATER)
LYARI TOWN, DIST. (SOUTH), KW&SB.

SUBJECT:- **REPAIRING / CONSTRUCTION OF BROKEN MASONRY CHAMBER AT MIRZA ADAM KHAN ROAD, MAURIPUR ROAD AND DIFFERENT STREETS OF LYARI TOWN (WATER), DIST. (SOUTH), KW&SB.**

ESTIMATE COST:- On Item Rate Basis. Issued to M/S. _____
TENDER COST:- Rs. 1500/= Pay Order NO: _____
TIME LIMIT:- _____ Days Dated:- _____
PENALTY:- 1000/= Per Day.

SUPERINTENDENT (REVENU)

S.N.	DESCRIPTION.	QUANTITY	RATE		PER	AMOUNT
			In Figure	In Words		
01.	Const: of Block Masonry Chambers size 4'x4'x4' C.I Cover and frame weight (65 Kg) fixed 4" RCC 1:2:4 slab with steel 1/2" dia for main bars 6' c/c 1/4" CI 8" c/c distribution bar 6" thick c.c 1:3:6 block masonry walls set 1: 6 cm 6" thick c.c 1:4:8 in foundation 2" thick c.c 1:2:4 flooring 1/2" thick cement plaster 1:3 ration to all inside wall surface and M.S Foot rest Etc.	02 Nos.			Each	
02.	Const: of C.C Block Masonry Chambers size 6'x6'x6' inside dimension with 24" x 24" C.I Cover and frame weight (65 Kg) fixed in RCC 1:2:4 slab 6" thick with steel 1/2" dia for main bars 6' c/c 1/4" CI 8" c/c distribution bar 6" thick c.c 1:3:6 block masonry walls set 1: 6 cm 6" thick c.c 1:4:8 in foundation 2" thick c.c 1:2:4 flooring 1/2" thick cement plaster 1:6 ration to all inside wall surface top and bottom slab excavation dewatering refilling Etc.	07 Nos.			Each	
	CONT....PAGE....02					

PAGE....02						
S.N.	DESCRIPTION.	QUANTITY	RATE		PER	AMOUNT
			In Figure	In Words		
03.	Const: of C.C Block Masonry Chambers size 8'x8'x8' inside dimension with 24" x 24" C.I Cover and frame weight (05 Kg) fixed in RCC 1:2:4 slab 8" thick with steel ½" dia for main bars 6' c/c ¼" CI 8" c/c distribution bar 6" thick c.c 1:3:6 block masonry walls set 1: 6 cm 6" thick c.c 1:4:8 in foundation 2" thick c.c 1:2:4 flooring ½" thick cement plaster 1:6 ration to all inside wall surface top and bottom slab and fixing MS foot rest excavation dewatering refilling Etc.	03 Nos.			Each	
04.	Providing Cast Iron Sluice Valve heavy Pattern. (Test pressure 21.0 Kg) Imported.					
	8" Dia.	02 Nos.			Each	
	12" Dia.	03 Nos.			Each	
05.	Fixing of C . I Sluice Valve with tow tail pieces one end Flange and other end socket i/c of Nuts, bolts & rubber packing Etc.					
	8" Dia.	02 Nos.			Each	
	12" Dia.	03 Nos.			Each	
				TOTAL:-	RS.	


EXECUTIVE ENGINEER (WATER)
LYARI TOWN DIST. (SOUTH)

I hereby quoted Amounting to Rs. _____ (Inwards) _____

Signature & Stamp of the Contractor:-

Address. _____
