



KARACHI WATER & SEWERAGE BOARD

Office of the Executive Engineer (Sew)
S.T-7 Block-1 KDA Building Liaquatabad Zone

NO/EE/LQT/NIT/Sew/ KW&SB/2014/25-

DATED 12-3-2014

NOTICE INVITING TENDER THROUGH WEBSITE (BELOW ONE MILLION) (ON ITEM RATE BASIS)

Tender in Sealed Covers are invited under SPPRA Rules 2010 for the works mentioned below:

1	Name of Work	1.Emergent Repairing of Broken / Setteled Manholes at Nazimabad & Gulbehar Area in Liaquatabad Zone (Sewerage).
2	Eligibility of Contractors	Bidder / Contractors should be Tax Payee / NTN
3.	Experience	1 year experience in similar job, attached with tender
4	Tender cab be purchase	1.Office of the Accounts Officer (Revenue KW&SB Head Office at 1 st Floor Old KBCA Building (annex) behind Civic Centre Gulshan-e- Iqbal Karachi
5	Bid Security	2% of quoted bid in shape of pay order / Bank Draft in favour of KW&SB
6	Tender Cost	Rs.1000/- (Non-Refundable) is shape of Pay Order in favor of KW&SB
7	Last date of issuing	w.e.f 1 st hosting up to 31-3-2014 from 9.AM to 1 P.M
8	Date and time of Receiving	1-4-2014 at 2.00 P.M
9	Date and time of opening	1-4-2014 at 3.00 P.M
10	Place of Opening	Tender will be opened by the Procurement Committee-I Office of the Convener / Chief Engineer (IPD),KW&SB Block-B at 9 th Mile Kasrsaz main Shahra-e-Faisal Karachi
11	Source of Funding	KW&SB Fund.
12	Scope of work	Improvement of Sewerage System.
13	Estimate Cost	Rs.8,26,215/-

Condition: -

1. Tender would be download from SPPRA web site & www.kw&sb.gos.com website
2. The participants must quote the rates both in figure & in words, incomplete / conditional tender will not be accepted.
3. In case of any unforeseen situation resulting in closure of office on the day of opening or Government declares Holiday the tender shall be submitted/opened on the next working day at the same time & venue.
4. The procuring agency may reject all or any bid subject to the relevant provision of SPPRA rules 2010.
5. Debarred contractor bid cannot be accepted.

Executive Engineer (Sew)
Liaquatabad Zone, KW&SB



KARACHI WATER & SEWREAGE BOARD
OFFICE OF THE EXECUTIVE ENGINEER (SEW)
ST-7 KDA BUILDING LIAQUATABAD ZONE

Estimate on item rate basis

M/s _____

Time Limit 15 Days

Penalty Rs.500/ Per Day

Pay order No. _____ Dt _____ Bank/Br _____

Tender Cost Rs.1000/-

Earnest Money 2% of Total Bid

Amount _____ B/No _____ Dt _____


Date of Receiving 1-4-2014 at 2.00 P.M

Date of opening 1-4-2014 at 3.00 P.m.

Name of Work: - Emergent Repairing of Broken / settled Manholes at Nazimabad & Gulbehar Area in Liaquatabad Zone

SR No	DESCRIPTION	QUANTITY	RATE in Rupees / in Figer	PER	AMOUNT
1	Excavation for pipe line in trenches, and pits in all kind of soils of murum i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade, cutting joint holes and disposal of surplus earth within a one chain as directed by engineer In charge, Providing fence guards, lights, flags and temporary crossing for non vehicular traffic where ever required lift up to 5 ft. (1.52m) and lead up to one chain (30.5m).	916.3 cft		%0cft	
2	Full hire charges of the pumping per day inclusive of wage of driver & Assistant, fuel or Electric. Energy plate from required for placing pumps etc. at lower depth with suction and delivery pipes for pumping out water found at various depths from trenches i/c the cost of erection and dismantling after completion of the job. Hire charges pumping set of up to 10 HP pumping out water from 10 ft deep trench.	12 day		Each	
3	Cement concrete plain i/c placing compacting finishing and curing and complete i/c screening and washing at stone aggregate ratio 1:2:4	1876.12 cft		%cft	
4	Steel shuttering for construction of Manholes (Circular) at site i/c its erection in proper position and removal after concrete i/c transportation complete etc.	192.5 P/rft		P/rft	
5	C.I Frame	420 Kg		P/Kg	
6	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc. complete.	916.3 Cft		%0Cft	

7	<p>Manufacturing and supplying of 21" dia RCC manhole covers cast in 1:2:4 concrete raion 3 inch deep at centre, reinforced with 1/2" inch dia to steel bars at 4" c/c welded to 3/16" thick 2" wide M.SW plate two hook of 3/8" dia tor bar including compacting i/c curing, and transportation with in 10 miles</p> <p style="text-align: center;">21"dia</p> <p style="text-align: center;">24"dia</p>	<p>200 Nos</p> <p>50 Nos</p>		<p>Each</p> <p>Each</p>	
8	<p>Manufacturing and supplying of RCC ring slabs of 21" inside 36" dia outside 7.5" width and 6" thick i/c 3/8" dia tor steel bars two hook concentric rings with 3/8" dia 8 Nos cross linked bars welded and two sunk type hooks casted in 1:1:-1/2:3 concrete with embedded 15 kg C.I frame in perfect position i/c transportation charges for an average lead of 20 km per trip from casting yard to Town office (A minimum of 25 slabs per trip will be transported.</p>	<p>100 Nos</p>		<p>Each</p>	
9	<p>Shifting to the site and fixing of 36" dia ring slab in perfect position on damaged manholes i/c cutting of damaged portion of manholes in proper shape and laying of cement mortar of 2" thickness and disposal of debris.</p>	<p>100 Nos</p>		<p>Each</p>	


 Executive Engineer
 Liaquatabad Zone (Sew)

Note: Participant /Contractor shall be bound to compliance all instruction / rule of SPPRA, 2010 /PEC as well as KW&SB.

I/we hereby quoted Rs_____

Rupees_____

Contractor Signature_____