

**KARACHI WATER AND SEWERAGE BOARD**  
**OFFICE OF THE EXECUTIVE ENGINEER (SEW) GULSHAN-E-IQBAL (TOWN), KW&SB**  
**ST-2 BLOCK 14 SCHEME-24 MAIN UNIVERSITY ROAD NEAR CIVIC CENTER**

**CELL NO: 0321-8283312**

**NOTICE INVITING TENDER (THROUGH PRESS/WEB SITE)**  
**(ON ITEM RATES BASIS)**

Sealed Tender is invited signal stage one Envelop System as per SPPRA Rules-2010 for the work mentioned below.

NO: EE/SEW/GIT/NIT/EAST/KW&SB/2014/102

Date 11-03-2014

Special Tender are invited SPPRA Rule-2010 for the work mentioned below:-

**NOTE:-**

1.	Name of Work	1.	<b>DESILTING/ CLEANING OF CHOKED &amp; SILTED 15" DIA AND 12" DIA SEWERAGE LINE BY WINCHING MACHINES AT DIFFERENT LOCATIONS IN UC-04 NEAR PAKHTOON CHOWK, GHANI FOOTBALL GROUND AND MANNU GOTH OF GULSHAN-E-IQBAL (TOWN).</b>
2.	Eligibility of bidder		Bidder / Contractor should having N.T.N/Sales Tax
3.	Experience Certificate		1 year Experience Certificate of Similar of job must be attached with the Tender.
4.	Tender can be Purchase		Office of the Accounts Officer (Revenue), KW&SB / Director (Accounts), KW&SB, at KW&SB Head Office, at 1 <sup>st</sup> floor old KBCA annex building, behind Civic Centre, Gulshan-e-Iqbal, Block-14 Karachi, and Director (Planning Office), KW&SB, at Block "E", 9 <sup>th</sup> Mile Karsaz, Shakra-e-Faisal, Karachi.
5.	Bid Security		2% quoted amount in shape of pay order/ Bank draft from any schedule bank of Pakistan in the favor of KW&SB must be accompanied with the tender otherwise the tenders shall be treated as invalid & rejected.
6.	Tender Cost		Tender Fee Rs. 1000/= Non Refundable in shape of Pay Order in favor of K.W.&S.B.
7.	Last Date of Issuing		Before 1 hours of the opening Time & Date.
8.	Date and Time of submission and opening of Tender.		Submission at 2:00P.M on <b>31-03-2014</b> & same will be opened at 2:30 P.M
9.	Place of Opening		Tender will be opened in the office of conveyor procurement committee-1 Chief Engineer (IPD) KW&SB, at Block-B, 9 <sup>TH</sup> Mile Karsaz Shahrah-e- Faisal Karachi.
10.	Source of Funding		KW&SB's own funds
11.	Scope of work		For improvement of sewerage system position.
12.	Estimate Cost		Rs.9,82,100/=

1. Tender would be download from KW&SB website [www.kw&sb.com.pk](http://www.kw&sb.com.pk)

- The participants must quote the rates both in words and figures. Incomplete / conditional tenders will not be accepted.
- In case the date of opening is declared as a public holiday by the Government, or non-working day due to any reason, the next official working day shall be deemed to be the date for submission and opening of tenders at the same time.
- The procuring agency may reject all or any bids subject to the relevant provisions of SPPRA-2010 Rules.
- Conditional bid cannot be accepted.
- Bid must be in sealed cover and experience certificate for 1 year of similar nature of job must be attached with the bid.
- Debarred contractors bid cannot be accepted.

**EXECUTIVE ENGINEER (SEW)**  
**GULSHAN-E-IQBAL (TOWN)**  
**KW&SB**

**OFFICE OF THE ASSISTANT EXECUTIVE ENGINEER (SEW) GULSHAN-E-IQBAL (TOWN)**  
**KARACHI WATER AND SEWERAGE BOARD**

**SCHEDULE "B"**

NAME OF WORK:- **DESILTING/ CLEANING OF CHOKED & SILTED 15" DIA AND 12" DIA SEWERAGE LINE BY WINCHING MACHINES AT DIFFERENT LOCATIONS IN UC-04 NEAR PAKHTOON CHOWK, GHANI FOOTBALL GROUND AND MANNU GOTH OF GULSHAN-E-IQBAL (TOWN).**

Estimated Cost: On Item Rate Basis  
 Earnest Money: 2% of Biding Cost  
 Tender Cost: Rs. 1000/=   
 Time Limit: 20 - Days  
 Penalty: Rs. 500/= per day.

Quotation Issued to M/S \_\_\_\_\_

Vide Receipt No, \_\_\_\_\_ Dated: \_\_\_\_\_

S. NO	DESCRIPITATION	QUANTITY	RATE	PER	AMOUNT
1.	Cleaning inside sewerage line completely restoring original silt free space / diameter of pipe line by labour and equipment (mechanically / Electrically driven ) i.c accessories like pulleys, steel ropes, buckets and draggers sizing from 6" to 18" dia their " to and fro " pulling action (No of passes shell be as many as required) would be under taken in two faces Phases (1 <sup>st</sup> phase entire land to down stream to up stream ) bringing down peak hours sewerage to flow inside pipe line (as free flow) and in 2 <sup>nd</sup> face from up stream to down stream of entire length insuring no silt is observed in buckets (6" dia to 18" dia) except only sewerage water and finally passing a steel ball of dia 12" less than the diameter of pipe. But not exceeding 48" dia ball even for larger dia of pipe to insure perfect cleaning . The job include all the hire / cost of equipment and accessories of above winching machine / devises along with / engine with winching drum sets having steel rope, pulley mounted over it , steel bucket from 6" dia to 18" dia, hocks and other protections like safety barriers, traffic signs, traffic cones, ensuring no damage to pipe line along with ensuring safety to labour and other public property / lives and removal of silt / solid during desalting and clearance of site etc complete as per full satisfaction of site engineer. <b>15" dia</b> <b>12" dia</b>	5000 Rft 6200 Rft		P/Rft P/Rft	

*[Signature]*  
**Executive Engineer (Sew)**  
**Gulshan-e-Iqbal (Town), KW&SB**

Bidder Quoted Amount Rs. \_\_\_\_\_ /= Rupees \_\_\_\_\_

Sign:/Stamp of Bidder \_\_\_\_\_

Address of Bidder \_\_\_\_\_