

University Engineer



Phone: 99261366
99261300-6
Ext: 2247

Ref. No. _____

Engineering Department
University of Karachi
Karachi-75270

Tender Notice

July 11th, 2014

Open Tenders in Sealed Cover are invited on item Rate basis from Reputable Contractor; who has experience of such works.

Sr.#	Name of Work	Estimated Cost	Completion Period	Tender Fee
1.	Repair & Maintenance work at House No.B-04, Staff Town, University of Karachi	Rs.1,08,600/-	30 days	Rs. 100/-

- 1) Tender Documents can be purchased from the Office of the Undersigned with effect from 15-07-2014 on payment of the amount noted above (Non-refundable) between **09:00 a.m** till **03:00 Noon** on any Working Day except the Day of Opening of Tender.
- 2) Sealed Tender accompanied by Pay Order of Earnest Money @2% of the Bid amount in favour of University of Karachi will be received in **the Office of the Director Finance, University of Karachi** up to 2:30 p.m. on 07-08-2014 and will be opened on the same day at **2:30 p.m.** In presence of the Contractors or their Representatives who will be present at that time. Any Tender not accompanied by Earnest Money or Short Amount of Earnest Money or Conditional Tenders will NOT be considered. No Cheque will be entertained along with Tender as Earnest Money. All Contractors have to submit Proof of Proprietorship of Company along with the CNIC copy and work completion certificate for issuance of Tender "copy of valid NTN". Contractor have to submit copy of work order for execution of work.
- 3) All Bids should be valid for a period of (90) Days.
- 4) The Successful Bidders who refuse to do work after Opening of Tenders, shall be liable to be forfeited their Earnest Money as a Penalty.
- 5) Competent Authority may reject all or any bids subject to relevant provisions of SPPRA Rules.
- 6) In case of any unforeseen situation resulting in closure of office on the date of opening or Government declares holiday the tender shall be submitted / opened on the next working day at the same time and venue.
- 7) Tender notice is also available on SPPRA's and University of Karachi web-site (www.uok.edu.pk).

Copy to :-

01. Advisor to Vice Chancellor.
02. Director Finance
- 03) Deputy Director Finance
- 04) Resident Auditor
- 05) Purchase Officer
- 06) Chief Accountant
- 07) Campus Engineer
- 08) University official web-site
- ✓ 09) SPPRA
- 10) Notice Board.
- 11) Concerned File.


UNIVERSITY ENGINEER

14/7
DD(A-F)

NO: 395
DATED: 14-7-14

University Engineer



Phone: 99261366
99261300-6
Ext: 2247

Ref. No. _____

Tender

Engineering Department
University of Karachi
Karachi-75270

Date of Opening:- 07-08-2014.

Time of Opening:- 02:30 P.M.

Ter der # 01

Place of Opening:- Office of Director Finance, University of Karachi.

Work:- Repair & maintenance work at House No.B-04, Staff, University of Karachi.

	ITEMS OF WORK.	Q T Y.	RATE.	UNIT.	AMOUNT.
01.	Dismantling toilet floor, dado or skirting in ground floor i/c base mortar and stacking salvaged material and disposing of surplus stuff as directed by In-charge.	500		Sft.	
02.	P/L 1:4:8 C. Conc. Bed under floor using graded stone ballast 2" and down gauge with leveling, ramming, watering and curing etc complete.	150		Cft.	
03.	P/L floor of 2" thick 1:2:4 C. Conc. Using graded and down gauge in ground floor laid in panels with glass Patti 1-1/2" i/c form work consolidation, finishing and curing etc complete.	300		Sft.	
04.	P/L glazed tiles of 3/4" thick 12"x12" in ground floor laid over 1" thick cement mortar 1:2 i/c jointing and washing the tiles with white cement slurry and curing etc complete.	500		Sft.	
05.	Taking out existing door shutter with frame i/c cutting of RCC wall up to 12" height and re-filling etc complete.	5 Nos.		Each	
06.	Taking out existing marble slab with block masonry re-fixing with all new fitting etc complete.	45		Sft.	
07.	Taking out existing kitchen & re-fixing with all new fitting etc. complete.	100		Sft.	
08.	P/L 1:3:6 Block masonry 1:2 i/c raking out joints and curing ext complete.	12		Cft.	
09.	3/4" thick C. plaster 1:4 on walls, column in ground floor i/c making edges, corners, and curing etc complete.	75		Sft.	
10.	P/F 1-1/2" thick solid flush door fixed with side ply i/c iron hinges, handles, door lock etc complete.	21		No.	
11.	P/F Gas stove (Marshal) twin family size fix in line etc complete.	1 No.		No.	
12.	P/F just door frame 2"X5" with hold fast complete.	17		ft.	
				TOTAL	

UNIVERSITY ENGINEER

CAMPUS ENGINEER

CONTRACTOR (With seal)