



**QUAID-E-AWAM UNIVERSITY OF ENGINEERING,  
SCIENCE & TECHNOLOGY, NAWABSHAH**  
Phone (0244) 382260 PABX (0244) 9370381-5 Ext: 2509

No. QUEST/NH/DW/-735

of 2014

Dated: 13-11-2014


**TENDER NOTICE**

All the interested Contractors / Firms, which are Pre-qualified in Category – C & D at QUEST Nawabshah are invited to participate in the following tenders.

| Sr | Name of Work  | Tender Fee | Completion period | Earnest Money   | Date of Purchase               | Date of Submission & opening |
|----|---|------------|-------------------|-----------------|--------------------------------|------------------------------|
| 1  | Construction of C.C. Approach Road in front of Newly Constructed Computer System Engineering Department | Rs. 1000/- | 02 Months         | 2% of bid value | 17-11-2014<br>To<br>03-12-2014 | 04-12-2014                   |

The tender documents can be had from office of the undersigned on the payment of Tender Fee (Non-refundable) mentioned above in the shape of Pay Order / Demand Draft in favour of Director Finance, QUEST Nawabshah, on working day and will be submitted at 11:00 am on dated 04-12-2014 and opened on same day at 12:00 noon in presence of the contractors or their representatives, who so ever will be present at that time. Any conditional or un-accompanied of the earnest money tender will not be considered in the competition. In case of any disturbance, the tender will be opened on next day.

The procuring agency reserved the right to reject all or any bids subject to relevant provisions of SPPRA Rules.

  
13.11.14  
Director Works  
QUEST Nawabshah

**Construction of C.C. Approach Road in front of Newly Constructed Computer System  
Engineering Department in QUEST Nawabshah**

**Schedule - B**

| Sr. | Description of Items   | QTY     | Unit | Rate      | Unit   | Amount     |
|-----|--|---------|------|-----------|--------|------------|
| 1   | Supplying and filling sand under floor and plugging in walls   | 6500    | Cft  | 1,141.25  | % Cft  | 74,181.25  |
| 2   | Excavation in foundation of building bridges and other structures including dagbelling dressing, refilling around structure with excavated earth watering and ramming lead upto 5 ft b) In ordinary soil | 562.5   | Cft  | 3,176.25  | %0 Cft | 1,786.64   |
| 3   | Cement concrete brick or stone ballast 1 1/2" to 2" gauge b) ratio 1:4:8   | 1350.50 | Cft  | 9,416.28  | % Cft  | 127,166.86 |
| 4   | Pacca brick work in foundation and plinth in cement sand mortar 1:4  | 562.5   | Cft  | 12,501.41 | % Cft  | 70,320.43  |
| 5   | Providing and laying 1" thick topping cement concrete (1:2:4) including surface finishing and dividing into panels d) 3" thick   | 2326    | Sft  | 4,411.82  | % Sft  | 102,618.93 |
| 6   | Formation, dressing and preparing sub grade in bed   | 3250    | Cft  | 326.70    | % Sft  | 10,617.75  |
| 7   | Cement plaster 1:4 upto 12' height b) 1/2" thick   | 1000    | Sft  | 2,283.93  | % Sft  | 22,839.30  |


**Total** **409,531.17**

Add \_\_\_\_\_% Above / Below premium

Rs. \_\_\_\_\_

**G.Total** **Rs.** \_\_\_\_\_

**Contractor**

  
13.11.14

**Director Works  
QUEST Nawabshah**

  
Sub Divisional Officer (Civil)  
QUEST Nawabshah