

University Engineer



Phone: 99261366
99261300-6
Ext: 2247

Ref. No. 14
20/2/2015

Tender Notice

Engineering Department
University of Karachi
Karachi 75270
February 20th, 2015

Open Tenders in Sealed Cover are invited on item Rate basis from Reputable Contractors who has experience of such works.

Sr.#	Name of Work	Estimated Cost	Completion Period	Tender Fee
1.	Repair & Maintenance work at House No.B-04, Staff Town, University of Karachi	Rs.2,79,997/-	30 days	Rs.250/-

- 1) Tender Documents can be purchased from the Office of the Undersigned with effect from 25-02-2015 on payment of the amount noted above (Non-refundable) between **09:00 a.m** till **03:00 Noon** on any Working Day except the Day of Opening of Tender.
- 2) Sealed Tender accompanied by Pay Order of Earnest Money @2% of the Bid amount in favour of University of Karachi will be received in the **Office of the Director Finance, University of Karachi** up to 2:30 p.m. on 17-03-2015 and will be opened on the same day at **2:30 p.m.** In presence of the Contractors or their Representatives who will be present at that time. Any Tender not accompanied by Earnest Money or Short Amount of Earnest Money or Conditional Tenders will NOT be considered. No Cheque will be entertained along with Tender as Earnest Money. All Contractors have to submit Proof of Proprietorship of Company along with the CNIC copy and work completion certificate for issuance of Tender "copy of valid NTN". Contractor have to submit copy of work order for execution of work.
- 3) All Bids should be valid for a period of (90) Days.
- 4) The Successful Bidders who refuse to do work after Opening of Tenders, shall be liable to be forfeited their Earnest Money as a Penalty.
- 5) Competent Authority may reject all or any bids subject to relevant provisions of SPPRA Rules.
- 6) In case of any unforeseen situation resulting in closure of office on the date of opening or Government declares holiday the tender shall be submitted / opened on the next working day at the same time and venue.
- 7) Tender notice is also available on SPPRA's and University of Karachi web-site (www.uok.edu.pk).

Copy to :-

01. Advisor to Vice Chancellor.
02. Director Finance
- 03) Deputy Director Finance
- 04) Resident Auditor
- 05) Purchase Officer
- 06) Chief Accountant
- 07) Campus Engineer
- 08) University official web-site
- ✓ 09) SPPRA
- 10) Notice Board.
- 11) Concerned File.

R. Waheed / OED
→ New exam / P.O.

24/2

DD (E-S)
Asst. Prof.

[Signature]
UNIVERSITY ENGINEER

SPPRA INWARD DIARY

NO: 12804

DATED: 24-2-2015

University Engineer



Phone: 99261366
99261300-6
Ext: 2247

Ref. No.

Date of Opening: 17-03-2015
Time of Opening: 02:30 P.M.
Place of Opening: Office of Director Finance, University of Karachi.
Work: Repair & Maintenance work at House No.B-04, Staff Town, University of Karachi.

Engineering Department
University of Karachi
Tender # 01
Karachi-75270

S. #.	ITEMS OF WORK.	Q T Y.	RATE.	UNIT.	AMOUNT.
	<u>Wooden Door work at House No.B-04</u>				
01.	P/F 1-1/2" thick solid flush door with iron hinges, tower bolt etc complete.	98.75		Sft.	
02.	P/F Door lock 808 or equivalent fix in door as required at site.	03 Nos.		Each	
03.	P/F Aluminum sheet fix in door shutter with iron hinges, glue etc complete.	30		Sft.	
04.	Oil painting iron /wood works with super glass enamel paint of approved make and shade two coats over and including the cost of one coat of priming complete at any height in any floor.	225		Sft.	
	<u>Renovation of Toilet work.</u>				
05.	Dismantling of existing floor dado & disposal off the material as directed by In-charge.	510		Sft.	
06.	P/L floor of 1/4" thick colored tiles 12"x12" of (Pakistani) 1st grade in ground floor laid over 1" thick C.M 1:2 i/c jointing and washing the tiles with white cement slurry and curing etc complete.	510		Sft.	
07.	P/L U.Pvc P-Trap 4" dia with trap jail i/c cutting holes and making good damages.	5 Nos		Each	
08.	P/F U.Pvc pipe 3" dia with special i/c cutting, joints and making good damages.	60		Rft.	
09.	P/F U.Pvc pipe 4" dia with special i/c cutting, joints and making good damages.	60		Rft.	
10.	P/F C. Pvc pipe 1/2" dia with specials i/c cutting for concealed piping etc complete.	120		Rft.	
11.	P/F Muslim shower with 3' long plastic connection.	1 No.		Each	
12.	P/F chrome shower with rod fix in line etc complete.	3 Nos.		Each	
13.	P/F chrome double bib cock 1/2" dia fix in line.	1 No.		Each	
14.	P/F chrome bib cock 1/2" dia fix in line.	5 Nos.		Each	
15.	P/F concealed stop cock 1/2" dia i/c fix in line	18 Nos.		Each	
16.	P/F W.C / Commode with low level flush tank i/c Pvc flushing pipe suitable for this style with fitting etc complete. With U.Pvc P-Trap Commode. W.C	1 No. 1 No.		Each Each	
	<u>Glazed tiles</u>				
17.	Dismantling of mosaic floor and skirting i/c disposal off the material as directed by In-charge.	725		Sft.	
18.	P/L floor of 1/4" thick colored glazed tiles 12"x12" of (Pakistani) 1 grade in ground floor laid over 1" thick C.M. 1:2 i/c jointing & washing the tiles with white cement slurry and curing etc complete.	725		Sft.	
19.	Taking & re-fixing door with filling complete.	4 Nos.		Each	


UNIVERSITY ENGINEER

CAMPUS ENGINEER

CONTRACTOR (With seal)