

University Engineer



Phone: 99261366
99261300-6
Ext: 2247

Ref. No. 182
2014/2015

Engineering Department
University of Karachi
K April 20th 2015 0

Tender Notice

Open Tenders in Sealed Cover are invited on item Rate basis from Reputable Contractors who has experience of such works.

Sr.#	Name of Work	Estimated Cost	Completion Period	Tender Fee
1.	Repair & Maintenance work at House No.B-31, Staff Town, University of Karachi	Rs.1,80,510/-	30 days	Rs. 150/-

- 1) Tender Documents can be purchased from the Office of the Undersigned with effect from 22-04-2015 on payment of the amount noted above (Non-refundable) between **09:00 a.m** till **03:00 Noon** on any Working Day except the Day of Opening of Tender.
- 2) Sealed Tender accompanied by Pay Order of Earnest Money @2% of the Bid amount in favour of University of Karachi will be received in the **Office of the Director Finance, University of Karachi** up to 2:30 p.m. on 13-05-2015 and will be opened on the same day at **2:30 p.m.** In presence of the Contractors or their Representatives who will be present at that time. Any Tender not accompanied by Earnest Money or Short Amount of Earnest Money or Conditional Tenders will NOT be considered. No Cheque will be entertained along with Tender as Earnest Money. All Contractors have to submit Proof of Proprietorship of Company along with the CNIC copy and work completion certificate for issuance of Tender "copy of valid NTN". Contractor have to submit copy of work order for execution of work.
- 3) All Bids should be valid for a period of (90) Days.
- 4) The Successful Bidders who refuse to do work after Opening of Tenders, shall be liable to be forfeited their Earnest Money as a Penalty.
- 5) Competent Authority may reject all or any bids subject to relevant provisions of SPPRA Rules.
- 6) In case of any unforeseen situation resulting in closure of office on the date of opening or Government declares holiday the tender shall be submitted / opened on the next working day at the same time and venue.
- 7) Tender notice is also available on SPPRA's and University of Karachi web-site (www.uok.edu.pk).


UNIVERSITY ENGINEER

Copy to :-

01. Advisor to Vice Chancellor.
02. Director Finance
- 03) Deputy Director Finance
- 04) Resident Auditor
- 05) Purchase Officer
- 06) Chief Accountant
- 07) Campus Engineer
- 08) Prof. Dr.Zulqarnain Ahmed
- 09) University official web-site
- ✓ 10) SPPRA
- 11) Notice Board.
- 12) Concerned File.

N: waist w/o SD
→ then exam / P.V.
MRP
23/4

PA INWARD DIARY
NO. 15766
DATED: 23-04-15

University Engineer



Phone: 9261366
9261300-6
Ext: 2247

Ref. No. _____

182/2014/2015

Tender

Engineering Department
University of Karachi
Karachi-75270
Tender # 01

Date of Opening:- 13-05-2015.
Time of Opening:- 02:30 P.M.
Place of Opening:- Office of Director Finance, University of Karachi.

Work:- Repair & maintenance work at House No.B-31, Staff Town, University of Karachi.

P-1

S. #.	ITEMS OF WORK.	Q T Y.	RATE.	UNIT.	AMOUNT.
	Renovation of Kitchen work.				
01.	Providing and fixing cabinet of lamination lasani or equivalent sheet fix with Formica sheet on side i/c brass hinges, cather, handle etc complete as required at site.	115		Sft.	
02.	Providing and fixing door lock fix I door complete.	12 Nos.		Each	
	Steel Door works.				
03.	Providing and fixing Galvanized single / double leaf steel door of G.I sheet 18 gauge with fame 1-1/2" x 1-1/2" i/c iron hinges, sliding bolts, (heavy) etc complete.	28		Sft.	
04.	Oil painting iron /wood works with super glass enamel paint of approved make and shade two coats over and including the cost of one coat of priming complete at any height n any floor.	63		Sft.	
	Providing & Fixing wiring for Gate light / Call bell.				
05.	Providing wiring for Gate light i/c Call bell with 4.3/029 and earth wire 1.5mm in PVC Pipe ¾ PVC Channel patti ¾ on surface of the wall roof column with Call bell switch / wooden board as required.	190		Rft.	
06.	Providing & fixing Gate light energy saver lamp 25 watt as required.	4 Nos.		Each	
07.	Providing & fixing board 8"x5" Fibber sheet five holes hole with switch / socket controlling board as required.	2 Nos.		Each	
	Flooring work				
08.	Dismantling of C.Conc. Floor up to 2" thick i/c disposal off the material as directed by In-charge.	2200		Sft.	
09.	P/L 1:4:8 C.Conc. bed under floor using graded stone ballast 2" thick and down gauge with leveling, ramming, watering and curing etc complete	560		Cft.	
10.	P/L floor of 2" thick 1:2:4 C.Cone Using graded screened bajri 2/4" and down gauge in ground floor lain in panels i/c form work consolidation, finishing and curing etc complete.	2200		Sft.	


UNIVERSITY ENGINEER

CAMPUS ENGINEER

CONTRACTOR (With seal)