

**OFFICE OF THE
EXECUTIVE ENGINEER
BUILDINGS DIVISION SHIKARPUR
Shikarpur Dated: 26.01.2016.**

NOTICE INVITING TENDERS

The Sealed tenders on S.B.D forms are invited from interested Contractors/Firms/parties as per (SPPRA) rules 2010 for the following works.

S.No	NAME OF WORK	Estimated Cost	Earnest Money	Tender Fee	Period
1.	Renovation of Mosque Karbala Moula Shikarpur District Shikarpur	1000000/-	20000/-	2000/-	12 Months
2.	Construction of Sports Stadium Complex Madeji (Inte: Ext;/W/S, sainatory& drainage)	980000/-	20000/-	2000/-	12 Months
3.	Construction of Bus / Wagon Terminal Chak Lavatory block	800000/-	16000/-	2000/-	12 Months
4.	Renovation / Rehabilitation of District Administration Colony (Electrification)	500000/-	10000/-	1000/-	12 Months

1. The Blank tender forms can be obtained from the office of the undersigned, on payment of tender fee shown against each work.
 2. The Blank tender Forms will be issued from the date of publication of this N.I.T up to **11.02.2016** at 1.00 P.M and will be received back on **15.02.2016** at 2-00 P.M and open on same day at 3-00 (PM) in presence of all intending contractors and tendering committee.
 3. Earnest money in shape of call deposit as showing against each work should be deposited in favour of undersigned from any scheduled Bank and call deposit must be attached with tender in envelope as SPPRA rules.
 4. The undersigned and competent authority to accept the tender reserve the right to reject any or all tenders as per SPPRA rules 2010.
 5. Contract documents, estimates, drawings and design and specification etc can be seen in the office of the undersigned on any working day during office hours.
 6. The contractor will have to produce the following documents while submitting the tender documents.
 - i) N.T.N / S.R.B Certificate
 - ii) Registration certificate with Pakistan Engineering Council For the Calendar year 2016.
 7. No conditional tender will be accepted.
 8. If any holiday is announced by the Government on the dates stated above, the tenders will be issued, received back and opened on next working day.
 - 9/- In case any of the works remain UN responded the tenders will be issued upto **18.02.2016** At 2-00 P.M and will be received back on **19.02.2016** at 1-00 P.M and opened on same day at 2-00 P.M
- Note:- This N.I.T can be seen on SPPRA web site at www.ppra.sindh.gov.pk

EXECUTIVE ENGINEER
BUILDINGS DIVISION SHIKARPUR

Copy FWC's to:-

1. The Secretary to Government of Sindh Information Technology Karachi is for website Sindh Secretariat Block No.06 Karachi for information to place the N.I.T on Website.
2. The Deputy Commissioner Shikarpur for information.
3. The Chief Engineer Buildings Department Government of Sindh, Sukkur / Hyderabad for favour of information.
4. The Director (A&F) Govt. of Sindh, Sindh Public Procurement Regulatory Authority, Planning & Development Department Karachi.
5. Copy along with (7 copies) is forwarded to the, Director Public Relation department (Adv:) Government of Sindh Block No.96 Pakistan Secretariat Karachi for printing in leading News Papers viz Sindhi/ Urdu/ English
6. The Superintending Engineer Works & Service Shikarpur for favour of information & necessary approval please.
7. The Executive Engineer Highway Division Shikarpur, for vide publicity.
8. The Assistant Engineer Buildings Sub-division Shikarpur, they are directed to submit schedule "B" within 7 days from the date of issue of NIT.
9. The Notice Board / Drawing Branch.


EXECUTIVE ENGINEER
BUILDINGS DIVISION SHIKARPUR

7383
28-01-16

NOTIFICATION

No. E&A(W&S)3-9/91/2014: With the approval of competent authority, Procurement Committee is formed of Rule-7 of Sindh Public Procurement Rules-2011, hereby constituted for procurement of Goods, Works at the office of Executive Engineer, Buildings Division, Shikarpur, on the following composition for an exchange with the following composition:

- (i) ✓ Superintending Engineer, Works & Services, Shikarpur. Chairman
- (ii) Executive Engineer, Buildings Division, Shikarpur. Member
- (iii) Executive Engineer, Public Health Engineering Division, Shikarpur. Member

2. The Functions & Responsibilities of the Committee, as per of Para-8 of SPPR 2011 shall be as under:

- a) Preparing of bidding documents.
- b) Carrying out Technical as well as Financial Evaluation of the bids.
- c) Preparing Evaluation report as provided in Rule-15.
- d) Making recommendation for the award of contract to the competent authority and
- e) Perform any other function ancillary and incidental to the above.

GAZI SHAHID PERVEZ
SECRETARY TO GOVT. OF SINDH

January 20 of 2014

No. E&A(W&S)3-9/91-2014

A copy is forwarded for information to:

- 1. The Accountant General, Sindh, Karachi
- 2. The Secretary to Govt. of Sindh, Public Health (engg.) Department, Karachi.
- 3. The Managing Director, SPPRA, Karachi
- 4. The Chief Engineer (Buildings), Sukkur.
- 5. The Superintending Engineer, Works & Services, Shikarpur
- 6. The Deputy Secretary (Staff) to Chief Secretary Sindh, Karachi
- 7. The Deputy Director, FIASE Cell, W&SD
- 8. The Chairman / Members of the Committee
- 9. PS to Minister Works & Services Sindh, Karachi.
- 10. PS to Secretary Works & Services Department
- 11. PA to Additional Secretary (Tech), Works & Services Department
- 12. P.A to Deputy Secretary (Tech), Works & Services Department.
- 13. P.A to Deputy Secretary (Admin), Works & Services Department.
- 14. Notification file

(MUHAMMAD ZAKIR)
SECTION OFFICER (GENERAL)
FOR SECRETARY TO GOVT. OF SINDH

SUPERINTENDING ENGINEER
WORKS & SERVICES SHIKARPUR

No. SE: 126
Shikarpur Date: 03.02.2014

Handwritten notes:
1000
03/01/14
SUPERINTENDING ENGINEER
WORKS & SERVICES SHIKARPUR
B1-9/10
P.C.
4/2/14



0726920183

No.FB/SF/(W&S)/SHP/2013-14/ 65

Office of the

SUPERINTENDING ENGINEER
WORKS & SERVICES SHIKARPUR

Dated: 16/01/2014.

To,

The Secretary
Work & Services Department
Government of Sindh
Karachi

SUBJECT: **APPROVAL OF PROCUREMENT COMMITTEES**

Pursuant of Rule 7 of Sindh Public Procurement Regulatory Authority (SPPRA), for Procurement of Works, Goods with function, and responsibilities i) Preparing bidding documents, ii) Carrying out technical as well as financial evaluation of the bids, iii) Preparing evaluation report as provided in Rule-45, iv) Making recommendation for the award of contract to the competent authority and v) Perform any other function ancillary and incidental to the above, procurement committees are proposed as under & submitted for kind approval.

Committee No.01 Procurement of Works in Education Works Division Shikarpur.

01.	Superintending Engineer Works & Services Shikarpur	Chairman
02.	Executive Engineer Education Works Division Shikarpur	Member
03.	Executive Engineer Drainage Division Shikarpur	Member

Committee No.01 Procurement of Works in Buildings Division Shikarpur.

01.	Superintending Engineer Works & Services Shikarpur	Chairman
02.	Executive Engineer Buildings Division Shikarpur	Member
03.	Executive Engineer Public Health Division Shikarpur	Member

Committee No.01 Procurement of Works in Highway Division Shikarpur.

01.	Superintending Engineer Works & Services Shikarpur	Chairman
02.	Executive Engineer Highway Division Shikarpur	Member
03.	Executive Engineer Public Health Division Shikarpur	Member

(ENGR.SHABIR AHMED KHOOHARO)
SUPERINTENDING ENGINEER
WORKS & SERVICES SHIKARPUR

1. The Managing Director, Sindh Public Procurement Regulatory Authority, Government of Sindh Karachi.
2. The Executive Engineer Education Works Division, Buildings Division, Highway Division & Public Health Engineering Division Shikarpur.
3. Officer / Official Concerned

(ENGR.SHABIR AHMED KHOOHARO)
SUPERINTENDING ENGINEER
WORKS & SERVICES SHIKARPUR

BIDDING DATA

NO:TC/G-55/

Shikarpur Dated: / / 2016.

(This section should be filled in by the Engineer/Procuring Agency before issuance of the (Bidding Documents)

- (a). Name of Procuring Agency :- Executive Engineer Buildings Division
Shikarpur
- (b). Brief Description of Works:- **1. Renovation of Mosque Karbala Moola
Shikarpur District Shikarpur.**
- (c). Procuring Agency Address:- Executive Engineer Buildings Division
Khanpur Road Shikarpur
- (d). Estimated Cost **1.000 (M)**
- (e). Amount of Bid Security: 5%(Fill in Lump Sum amount or in %age
of bid amount/estimated cost, but not
exceeding 5%)
- (f). Period of Bid Validity(days) 60 Days (Not more than Sixty days)
- (g). Security Deposit(i/c bid security) 10% (In %age of bid amount/estimated
cost equal to 10%)
- (h). Percentage, if any to be deducted
From bills 7.5% Income Tax
- (i). Deadline for submission of Bids
alongwith time As per N.I.T
- (j). Venue,Time & Date of Bid Opening Khanpur Road Shikarpur (As per NIT)
- (k). Time for completion from written
order of commence 12 Months
- (L). Liquidity damages NIL
(0.05 of Estimated Cost or Bid)cost per day of delay, but total not exceeding 10%)
- (M). Deposit Receipt No: _____ Dated: _____ Amount _____
- (N). D.R No: Date & Time _____
- (O). Tender issued to (Mr/ M/S) _____)

(Executive Engineer/Authority issuing bidding documents)


EXECUTIVE ENGINEER
BUILDINGS DIVISION SHIKARPUR

BIDDING OF DOCUMENTS FOR WORK.

BILL OF QUANTITIES.

DESCRIPTION AND RATE OF ITEM BASED ON COMPOSITE SCHEDULE OF R.A.P.

NO:	QTY:	DESCRIPTION OF ITEM TO BE EXECUTED AT SITE.	RATE:	UNIT:	AMOUNT
1/-	3250	Applying floating coat of cement 1/32" thick. (S.I.NO:31 P.NO:11) .	660/-	%ft	21450/
1/-	3250	Cement plaster 1:6 upto 20ht: 1/2" thick. (S.I.NO: 11 P.NO: 47) .	2206/60	%ft	71715/
1/-	3250	Cement plaster 1:4 upto 20ht: 3/8" thick. (S.I.NO: 11 P.52) .	2197/52	%ft	71419/
1/-	38	Excavation in foundation of bulidings bridge & other than structure i.e dedooling dressing refilling around the the structure with executed refilling around the structure earth watering raining lead upto 5'ft: ordenry soil. (S.I.No:18 P= No:4).	3176/5225	%ft	1207 1217
1/-	763	Cement concrete brick or stone ballast 1 1/2 to 2" gauge Ratio 1:2:8 (S.I.No:4 p.No:12)	9416/28	%ft	71846/
1/-	45	R.C.C work i/c all labour & material except the cost of steel reinforcement and its labour for bending & binding which will be paid sepretly this rate also i/c kinds of forms mould lifting shuttering & curring laid in cite of precast laid in position Ratio (1:2:4). (S.I.NO: 1 P.NO: 13) .	337/-	P.cft	15165/
7/-	2.25	Fabrication of mild steel reinforcement i/c cutting bending laying in position making joints and fastening i/c cost of binding wire also i/c removal of rust from using ter bars. (S.I.NO: 6 P.NO: 18) .	5001/70	P.cwt	11284/
8/-	100	M/P steel grated doors complete with locking arrangement angle iron frames 2x2x3/8" 3/4" with 1/16" thick sheeting i/c sq:bars x 24" ub: to center to center (S.I.NO: 24 P.NO: 90) .	726/72	P.sft	72672/
9/-	64	1st: class deodar wood wrough joinery work in door and window etc fixed in position i/c chowkats held fast hinges iron tower belts choks cleats handle and with hooks. (S.I.NO: 7 P.NO: 58) .	1273/76	P.sft	81521/
10/-	2585	P/F cement paving block flooring using size 197x97x60 of citern quadra cibble shape with nature color having strenght filling b/w 5000psi i/c filling the joints with hils and laying inspection (S.I.NO: 71 P.NO: 49) .	199/77	P.sft	516405

NO: QTY: S: DESCRIPTION OF ITEM TO BE EXECUTED AT SITE. RATE: UNIT: AMOUNT

11/- 99 ✓	M/F inposition iron steel grill of 3/4"1/4" flate iron approved design i/c painting 3 coats.(S.I.NO: 26 P.NO: 91) .	197/-	P.sft	19503/
12/- 2380 ✓	Prepering surface and painting with emusial paint.(S.I.NO: 29 P.NO:72).	1763/75	%sft	41977/

TOTAL: RS : 995048

AMOUNT TOTAL: (CSR) _____

%Above/Bellow _____ TOTAL: AMOUNT _____



Ami

BIDDING DATA

NO:TC/G-55/

Shikarpur Dated: 20/01/2016.

(This section should be filled in by the Engineer/Procuring Agency before issuance of the (Bidding Documents)

- (a). Name of Procuring Agency :- Executive Engineer Buildings Division
Shikarpur
- (b). Brief Description of Works:- **1. Construction of Sports Stadium Complex Madeji (Inte:Ext:/W&S, sanitary & drainage.**
- (c). Procuring Agency Address:- Executive Engineer Buildings Division
Khanpur Road Shikarpur
- (d). Estimated Cost **0.9800 (M)**
- (e). Amount of Bid Security: 5%(Fill in Lump Sum amount or in %age of bid amount/estimated cost, but not exceeding 5%)
- (f). Period of Bid Validity(days) 60 Days (Not more than Sixty days)
- (g). Security Deposit(i/c bid security) 10% (In %age of bid amount/estimated cost equal to 10%)
- (h). Percentage, if any to be deducted From bills 7.5% Income Tax
- (i). Deadline for submission of Bids alongwith time As per N.I.T
- (j). Venue,Time & Date of Bid Opening Khanpur Road Shikarpur (As per NIT)
- (k). Time for completion from written order of commence 12 Months
- (L). Liquidity damages NIL
(O.05 of Estimated Cost or Bid)cost per day of delay, but total not exceeding 10%)
- (M). Deposit Receipt No: _____ Dated: _____ Amount: _____
- (N). D.R No: Date & Time _____
- (O). Tender issued to (Mr/ M/S) _____

(Executive Engineer/Authority issuing bidding documents)


EXECUTIVE ENGINEER
BUILDINGS DIVISION SHIKARPUR

CONSTRUCTION OF SPORTS STADIUM COMPLEX AT MADEJI (INTERNAL
EXTERNAL WATER SUPPLY & DRAINAGE) TALUKA GARNI HASSIN: : : : : :

BIDDING OF DOCUMENTS FOR WORK.

BILLS OF QUANTITIES.

DESCRIPTION AND RATE OF ITEMS BASES OF COMPOSITE SCHEDULE OF RATE.

PART "A"

ITEM NO:	QUANTITY:	DESCRIPTION OF ITEMS TO BE EXECUTED AT SITE.	RATE.	UNIT.	AMOUNT.
1.	05	P/F sawating true white glazed earthen ware w.c pan with i/c the cost of flushing cistern with internal fitting and flush pipe & making requisite number of holes in wall plinth & floor for pipe connection and making good in c.c (1:2:4) with 4" dia earthen ware etc. (S.I.No: 1 (b) P-1)	4846/60	Each	24233/-
2.	03	P/F 24"x18" lavatory basin in white glazed earthen ware compl: with i/e the cost of w.i or c.i earthen ware bracket 6 inches built into wall painted white in two coats after a primary coat of red lead paint and pair of 1/2" dia rubber plug & chrome plate brass chain 1-2/4" dia malleable. etc. (S.I.No: 8 P-3)	4253/90	Each	12762/-
3.	03	Add extra labour for providing and fixing of earthen ware pedestal- white or coloured glazed (foreign or equivalent) (S.I.No: 9 P-3)	938/47	Each	2815/-
4.	03	P/F 6"x2" or 6"x3" C.I gully trap of the approved self cleaning- design with C.I screwed down grating or without a vent arm complete with & i/c the making requisite number of holes plinth & floor for pipe connection & making good c.c 1:2:4 (S.N: 20 P-6)	2024/43	Each	6073/-
5.	03	Providing and fixing in position nylon connection complete etc. (S.I.No: 23 P-6)	447/15	Each	1341/-

ITEM NO:	QUANTITY	DESCRIPTION OF ITEMS TO BE EXECUTED AT SITE.	RATE.	UNIT.	AMOUNT.
6.	03	P/F 4"x4" dia C.I branch of the required degree with excess door, rubber, washer 3/8" thick and bolts and nuts and extra painting to match the colour of building. (S.I.No: 3 P-9)	702/-	Each	2106/-
7.	03	P/F 4"x4" dia plain C.I branch of the required degree i/c extra painting to match the colour of building. (S.I.No: 7 P-9)	704/-	Each	2113/-
8.	03	P/F 4" dia C.I off sets of various length i/c extra painting to match the colour of building. (S.I.No: 8 P-10)	702/-	Each	2106/-
9.	03	P/F 4" dia C.I plain of the required degree i/c extra painting to match the colour of building. (S.I.No: 9 P-10)	566/70	Each	1700/-
10.	03	P/F 4" dia bend of the required degree with access door rubber washer 1/8" thick and bolts and nuts and extra painting to match the colour of building. (S.I.No: 9 P-10)	599/60	Each	1799/-
11.	03	P/F 4" dia C.I terminal guard i/c extra painting to match the colour of building. (S.I.No: 11 P-10)	389/70	Each	1169/-
12.	03	P/F C.I waste and vent pipe i/c cutting fitting and extra paint; to match the colour of building. (S.I.No: 13 P-10)	289/25	Each	868/-
13.	06	P/F lead cauld joints 4" dia C.I pipe and fitting. (S.I.No: 12 P-10)	341/85	Each	2051/-
14.	22	P/F 4" dia C.I soil & vent pipe i/c cutting and fitting and extra painting to match the colour of building. (S.N: 1 P-9)	333/29	P. Rft	7332/-

ITEM NO.	QUANTITY	DESCRIPTION OF ITEMS TO BE EXECUTED AT SITE.	RATE.	UNIT.	AMOUNT.
15.	50	<u>1 1/2"</u> P/P G.I special and clamps etc i/c fixing cutting fitts complete with and i/c the cost of breaking through walls and roof, making good etc painting two coats after cleaning the pipe etc with white zinc paint with pigment to match the colour of bldg; and testing with water to a pressure head of 200 feet and handling. (S.I.No: 1 P-12)	153/19	P.Rft	7659/-
(b)	60	<u>1"</u>	128/55	P.Rft	7713/-
(c)	120	<u>3/4"</u>	95/79	P.Rft	11495/-
(d)	40	<u>1/2"</u>	73/21	P.Rft	2928/-
16.	40	Add extra labour for concealed- G.I pipe & fitting i/c making recess in the wall for pipe & making good in cement mortar etc compl:(S.I.No: 2P-12)	7/82	P.Rft	313/-
17.	05	Supplying and fixing in position- brass bib cock 1/2" dia. (S.I.No: 1(ii)P-16)	337/92	Each	1690/-
18.	01	S/P fiber glass tank of approved- quality and design and wall thickness as specified i/c cost of nuts bolts and fixing in plate form of cement concrete 1:3:6 and making connection for in let & outlet & over flow pipe etc complete (250 gallons) 3.5mm. (S.N: 3P-21)	21989/61	Each	21990/-
19.	100	RCC pipe with collers class 'B' and digging the trenches to required depth & fixing in position i/c cutting fitting & joints with maxphaltic comp: & cement mortar 1:1 and testing with water pressure 4 feet. etc. (S.I.No: 2 P-23) <u>6" dia.</u>	199/25	P.Rft	19925/-
(b)	100	<u>9" dia</u>	250/50	P.Rft	25060/-

ITEM NO:	QUANTITY:	DESCRIPTION OF ITEMS TO BE EXECUTED AT SITE.	RATE.	UNIT.	AMOUNT.
20.	20	P/F C.C pressure pipe with collar (Dadex or equivalent) i/c digging the trenches to required depth and fixing in position with rubber ring i/c testing to water pressure head of 200 feet.(S.I.No:3 P-24) <u>4"dia.</u>	188/44	P.Rft	3769/-
(b)	30	<u>3"dia.</u>	141/11	P.Rft	4233/-
21.	60	Boaring for tubewell in all watering boaring soils from ground level upto 100 ft; or 30.5 meter long depth i/c sinking and with curring of causing pipe.(S.I.N:3 P-24)	160/-	P.Rft	9600/-
22.	09	Construction of main hole or inspection chamber for requ: dia of circular sewer and 1061mm depth with wall B.B in cement mortar 1:1 cement plaster 1/2"thick wall 1"(25) mm thick over with iron of clean sponing 1/2"thick 457x457mm of 1.75wt 889 k.g embeded in e.c plain 1:2:4 etc.(S.I.N(P.R. P-)	14748/-	Each	132732/-

Total Rs: 317575/-

_____ %Above/below on the Rate of CSR

Amount to be added/deducted on the Rs: _____

g; total (A)

Total amount in wards _____

CONSTRUCTION OF SPORTS STADIUM COMPLEX AT MADEJI (INTERNAL
EXTERNAL WATER SUPPLY & DRAINAGE) TALUKA GARHI KASIN.:

BIDDING OF DOCUMENTS FOR WORK.

BILLS OF QUANTITIES.

DESCRIPTION AND RATE OF COMPOSITE SCHEDULE OF RATE.

PART "B"

S. NO.	QUANTITY	DESCRIPTION OF ITEMS TO BE EXECUTED AT SITE.	RATE.	UNIT.	AMOUNT.
1.	1584	Excavation in foundation of building bridges and other structure i/c bag belling dressing refilling around structure with excavated earth watering and raiming lead up to 5 feet (In ordinar soils) (S.I.No: 18(b)P-5)	3176/25	%cft	5031/-
2.	1056	Supplying and filling sand under floor and plugging in to wall S.I.No: 29 P-30)	1141/25	%cft	1205/-
3.	396	Cement concrete brick or stone ballast 1 1/2"x2" guage ratio:(1:4:8)(S.I.No:4 P-16)	9416/28	%cft	37288/-
4.	528	Providing and laying 1"thick topping cement concrete (1:2:4) i/c surface finishing and dividing into pannels 2" thick. (S.I.No: 16 P-46)	4411/82	%Sft	23294/-
5.	190	Pacca brick work in foundation in cement sand mortar 1:6 ratio: (S.I.No:4 P-24)	11948/36	%cft	22702/-
6.	776	Cement plaster (1:6) upto 20' height 1/2"thick.(S.I.N: 13(b)P-54)	2206/60	%Sft	17123/-
7.	6656	Cement plaster (1:4) upto 20' height 3/8"thick.(S.N: 11(b)P-58)	2197/52	%Sft	146267/-
8.	7432	Extra for lime mud or cement plaster and pointing from 12" and above for each additional 10"height.	140/-	%Sft	10405/-

ITEM NO:	QUANTITY:	DESCRIPTION OF ITEMS TO BE EXECUTED AT SITE.	RATE.	UNIT.	AMOUNT.
9.	634	P/L Halla or pattern tile glazed 8"x8"x1/4" on floor or wall facing in required pattern of STILE specification- jointed in white cement and pigment over a base of 1:2 cement mortar 3/4" thick i/c washing and filling joints with slurry of white cement (S.I.NO:62 P-54)	34520/31	%Sft	218859/-
10.	4661	White washing three coats. (S.I.No:26 (c)P-60)	829/95	%Sft	38684/-
11.	3407	Primary coat of chalk under disteper on wall two coats.	442/75	%Sft	15084/-
12.	3407	Distepering on wall three coats.	1079/25	%Sft	36770/-
13.	422	Painting new surface painting door and windows.	2116/41	%Sft	8931/-
14.	1245	Dismantling brick work in lime or cement mortar.(S.I.N: 13 P-10)	1285/63	%Sft	16006/-
Total Rs:					<u>597647/-</u>

_____ %Above/below on the Rate of CSR
Amount to be added/deducted on the Rs: _____

G: Total(B)
Total Amount in wards _____

(Signature)

CONSTRUCTION OF SPORTS STADIUM COMPLEX AT MADEJI.
(INTERNAL/EXTERNAL WATER SUPPLY & DRAINAGE) :::::

BIDDING OF DOCUMENTS FOR WORK.

BILLS OF QUANTITIES.

DESCRIPTION AND RATE OF ITEMS BASES OF COMPOSITE SCHEDULE OF RATE.

PART "A" NON SCHEDULE ITEMS.

ITEM NO:	QUANTITY	DESCRIPTION OF ITEMS TO BE EXECUTED AT SITE.	RATE.	UNIT.	AMOUNT.
----------	----------	--	-------	-------	---------

1.	12	Making and fixing stainer filter pipe i/c wire cover pipe etc complete.		P. Rft	
----	----	---	--	--------	--

2.	01	Providing and fixing 1 H.P electric motor (3 star comp;) i/c pump 1-1/4" dia with wire plug etc complete.		Each	
----	----	---	--	------	--

3.	01	Supplying and fixing union check valve 1-1/4" dia.		Each	
----	----	--	--	------	--

4.	01	Providing and fixing hand pump machine complete.		Each	
----	----	--	--	------	--

Total Rs: _____

G. Total (G)

Total amount in words _____

(Signature)
5)

BIDDING DATA

NO:TC/G-55/

Shikarpur Dated: / / 2016.

(This section should be filled in by the Engineer/Procuring Agency before issuance of the (Bidding Documents)

- (a). Name of Procuring Agency :- Executive Engineer Buildings Division
Shikarpur
- (b). Brief Description of Works:- **1. Construction of Bus / Wagon Terminal
Chak Lavatory block.**
- (c). Procuring Agency Address:- Executive Engineer Buildings Division
Khanpur Road Shikarpur
- (d). Estimated Cost **0.8000 (M)**
- (e). Amount of Bid Security: 5%(Fill in Lump Sum amount or in %age
of bid amount/estimated cost, but not
exceeding 5%)
- (f). Period of Bid Validity(days) 60 Days (Not more than Sixty days)
- (g). Security Deposit(i/c bid security) 10% (in %age of bid amount/estimated
cost equal to 10%)
- (h). Percentage, if any to be deducted
From bills 7.5% Income Tax
- (i). Deadline for submission of Bids
alongwith time As per N.I.T
- (j). Venue,Time & Date of Bid Opening Khanpur Road Shikarpur (As per NIT)
- (k). Time for completion from written
order of commence 12 Months
- (L). Liquidity damages NIL
(0.05 of Estimated Cost or Bid)cost per day of delay, but total not exceeding 10%)
- (M). Deposit Receipt No: _____ Dated: _____ Amount _____
- (N). D.R No: Date & Time _____
- (O). Tender issued to (Mr/ M/S) _____

(Executive Engineer/Authority issuing bidding documents)


EXECUTIVE ENGINEER
BUILDINGS DIVISION SHIKARPUR

CONSTRUCTION OF LAVANTRY BLOCK AT BUS TERMINAL AT CHAK TALUKA LAHRI DISTRICT SHIKARPUR. ::

BIDDING OF DOCUMENT FOR WORK

BISS OF QUANTITIES.

DESCRIPTION AND RATE OF ITEM BASED ON COMPOSITE SCHDULE OF RATE.

S.NO:	QTY'S	DESCRIPTION OF ITEM TO BE EXECUTED AT SITE.	RATE:	UNIT	AMOUNT
1/-	1051	Execution in foundation of building brides and other str:i/c dag belling dressing redining arround str:with exevavated earth watering and raimming lead up to 5"feet(in ordenary soil) (S.I.NO:18(b)P.NO:4)	3176/ 23 ²⁵	%cft	3338/- 33382/- 3338/-
2/-	176	Cement concrete brick or stone balast 1½to 2"guage ratio:1:4:8) (S.I.NO:4 P.NO:15)	9416/28	%cft	16572/-
3/-	580	pacca brick work foundation &plinth ratio:1:6 etc. complete(S.I.NO:4(c) P.NO:20)	11948/36	%cft	69300/-
4/-	409	Coursed rubble masonry i/c hammer dressing in cement mortar (1:6) (S.I.No:2 P-27)	XX25321/-	%cft	103562/-
5/-	159	RCC work i/c all labour and material except the cost of Steel reinforcement and its labour for bending and Winding which will be paid sepreptly.This rate also i/c all kind m ould lifting shutt: curring and rendering (1:2@4)RCC work in roof slab beams columns rafts and other structure etc.(S.I.No:6 P-16)	337/-	P.cft	53583/-
6/-	8.745	Fabrication of mild steel reinforcement for cement concrete i/c laying in position i/c making joints fastening i/c cost of binding wire also i/c removal of rust from bars.(S.I.No:8P-17)	5001/70	P.Cwt	43739/-
7/-	4 496	pacca brick work in ground floor in cement mortar ratio:(1: 6)(S.I.N:5 P-21)	12674/36	%cft	62864/-
8/-	701	Filling watering raimming earth in floor with surplus earth from foundation lead one chain.(S.I.No: P-)	1512/50	%cft	1060/- 1060/-
9/-	170	Filling watering raimming earth under floor with new earth from outside lead extra 3 mile.(S.I.No: P-)	9424/10	%cft	1602/- 1602/-
10/-	74	S/filling sand under floor and plugging into wall.(S.I.No: P-)	1720/66	%cft	1273/-

NO.	QUNTTY:	DESCRIPTION OF ITEMS TO BE EXECUTED AT SITE.	RATE.	UNIT.	AMOUNT.
11/-	49	C ement concrete brick or stone ballast 1½"x2"guage ratio:(1:5:10)	8694/95	%C ft	4260/-
12/-	495	pacca brick work in ground floor in cement mortar (1:6) (S.I.NO:5 P-31)	12674/36	%Cft	62738/-
13/-	781	Cement plaster (1:6) upto 20'height 1/2'thick.(S.I.No:13(b)P-52)	2206/60	%Sft	17233/-
14/-	619	providing and laying tile glazed 6'x6'x1/4'on floor or wall facing in required colour and pattern of STILE specification jointed in white cement and pigment over a base of 1:2 grey cement mortar 3/4"thick i/c washing etc. (S.I.No:60 P-47)	30509/77	%Sft	188855/-
15/-	82	1st class deodar wood wrought joinary work in door and windows etc fixed in position i/c chokats hold fasts hinges iron tower bolts cleats 3/4"thick.(S.I.No :7(b)P-58)	1273/76	P.Sft	10448/-
16/-	367	Cement plaster (1:4) upto 20'height 3/8"thick.(S.I.N o:11(a)P-52)	2197/52	%Sft	8064/-
Total Rs:					741456/-

_____ %Above/Below on the rate of CSR amount to be added on RS: _____

Total Amount in words _____

Signature

BIDDING DATA

NO:TC/G-55/
Shikarpur Dated: 22/11/2016.

(This section should be filled in by the Engineer/Procuring Agency before issuance of the (Bidding Documents)

- (a). Name of Procuring Agency :- Executive Engineer Buildings Division
Shikarpur
- (b). Brief Description of Works:- **4. Renovation / Rehabilitation of District Administration colony (Electrification).**
- (c). Procuring Agency Address:- Executive Engineer Buildings Division
Khanpur Road Shikarpur
- (d). Estimated Cost **0.5000 (M)**
- (e). Amount of Bid Security: 5%(Fill in Lump Sum amount or in %age of bid amount/estimated cost, but not exceeding 5%)
- (f). Period of Bid Validity(days) 60 Days (Not more than Sixty days)
- (g). Security Deposit(i/c bid security) 10% (in %age of bid amount/estimated cost equal to 10%)
- (h). Percentage, if any to be deducted From bills 7.5% Income Tax
- (i). Deadline for submission of Bids alongwith time As per N.I.T
- (j). Venue, Time & Date of Bid Opening Khanpur Road Shikarpur (As per NIT)
- (k). Time for completion from written order of commence 12 Months
- (L). Liquidity damages NIL
(0.05 of Estimated Cost or Bid)cost per day of delay, but total not exceeding 10%)
- (M). Deposit Receipt No: _____ Dated: _____ Amount _____
- (N). D.R No: Date & Time _____
- (O). Tender issued to (Mr/ M/S) _____

(Executive Engineer/Authority issuing bidding documents)


EXECUTIVE ENGINEER
BUILDINGS DIVISION SHIKARPUR

RENOVATION/REHABILITATION OF DISTRICT ADMINISTRATION
COLONY SHIKARPUR. (ELECTRIFICATION)

BIDDING OF DOCUMENT FOR WORK.
BILLS OF QUANTITIES.

DESCRIPTION AND RATE OF ITEMS ON COMPOSITE SCHEDULE OF RATE.

PART "A" SCHEDULE ITEMS 2012.

ITEM NO:	QUANTITY:	DESCRIPTION OF ITEMS TO BE EXECUTED AT SITE.	RATE.	UNIT.	AMOUNT.
1.	80	Wiring for light or fan point with 3/029 PVC insulated wire in 20mm (3/4")PVC conduit recessed in the wall or columns: as required.(S.I.No:124p -15)	1130/-	Each	90400/-
2.	20	Wiring for plug point with 3/029 PVC insulated wire in 20mm (3/4") conduit recessed in the wall or columns as req:(S.I.No:6 P-15)	985/-	Each	19700/-
3.	04	Wiring for call bell point 3/029 insulated wire in 20mm (3/4)conduit recessed in the wall or columns as required.(S.I.No:128 P-15)	1764/-	Each	7056/-
4.	363	Providing and laying (Main or sub-main PVC insulated wire 2-7/029 ofcopper conduit in (3/4)dia in the wall or columns as required. (S.I.No:10 P-2)	222/-	P.Rft	80586/-
5.	130	Providing and laying (Main or sub-main)PVC insulated wire 2-7/036 copper conductor in(3/4")dia in the wall or columns as required (S.I.No:11 P-2)	252/-	P.Rft	32760/-
6.	80	Providing and laying (Main or sub-main)PVC insulated wire with 2-7/044 copper conduit in (3/4") in the wall or columns as required (S.I.No:12 P-2)	341/-	P.Rft	27280/-
7.	70	Providing and laying (Main or sub-main)PVC insulated wire 2-7/064-16mm 2 core copper conductor in 3/4"dia in the wall or column as required.(S.I.No:14 P-2)	641/-	P.Rft	44870/-
8.	104	P/F one way s.p 5Amp switch flush type.(S.I.No:219 P-33)	54/-	Each	5616/-

ITEM NO:	QUANTITY:	DESCRIPTION OF ITEMS TO BE EXECUTED AT SITE.	RATE.	UNIT.	AMOUNT.
9.	12 Nos:	P/F 2pin 5Amp plug socket switch.(S.I.No:22 P-33)	80/-	Each	960/-
10.	05 "	P/F 3pin 10/15Amp plug and socket switch.(S.I.No:227P-30)	162/-	Each	810/-
11.	15 "	P/F bakelite ceiling rose with two terminal. (S.I.No:228 P-30)	72/-	Each	1080/-
12.	080 "	P/F brass button holder. (S.I.No:232 P-30)	70/-	Each	1400/-
13.	25 "	Providing and laying (Main or sub-main)PVC insulated wire 2-3/029 copper conduit in (3/4")PVC wire.(S.I.N:8 P-2)	173/-	P.Rft	4325/- #844/-
14.	15 "	P/F brass ceiling fan ⁴⁸ size (good quality)(S.I.N:234 P-34)	3020/-	Each	45300/-
15.	12 "	P/F circuit breaker 6-10-15-20-40 and 63Amp (TB-S5)on a required.(S.I.No:203 P-31)	916/-	Each	10992/-
16.	02 "	P/F circuit breaker 6-10-15-20-20-30-40-50 &63Amp D.P (TB-5S)on a prepared board as required.(S.I.No:204 P-31)	2456/-	Each	4912/-
17.	02 "	P/F circuit breaker 3-5-10-15-20-30Amp TP (X5-30SNB)on a prepared board.(S.I.No:205P-31)	5301/-	Each	10602/-
TOTAL RS:					389168/-

_____ %Above/below on the Rate of CSR
amount to be added/deducted on the Rs: _____

Total Amount in wards _____

(Handwritten Signature)

(Handwritten Markings)

RENOVATION/REHABILITATION OF DISTRICT ADMINISTRATION
COLON-Y SHIKARPUR. (ELECTRIFICATION)

BIDDING OF DOCUMENTS FOR WORK.

BILLS OF QUANTITIES.

DESCRIPTION AND RATE OF ITEMS BASES ON COMPOSITE SCHED:OF RATE.

PART "B" SCHEDULE ITEMS 2014.

ITEM NO:	QUANTIT:	DESCRIPTION OF ITEMS TO BE EXECUTED AT SITE.	RATE.	UNIT.	AMOUNT.
1.	10	P/F 1-40 watts tube light 4' long complete with chock, starter & putty i/c necessary electric connection. (S.I.No:1 P-33)	396/-	Each	3960/-
2.	10	P/F 2-40 watts tube light 4' long complete with chock starter & putty i/c necessary electric connection. (S.I.No:2 P-33)	1677/-	Each	16770/-
3.	02	P/F wall bracket fancy type superior quality i/c necessary electric connection.(S.N:5P-33)	497/-	Each	994/-
4.	30	P/F energy saver superior qlty: i/c fixing on existing holder. (S.I.No:6 P-33)	497/-	Each	14910/-
5.	10	P/F bulb 100 watts.(S.N:7 P-33)	25/-	Each	250/-
6.	09	P/F mild steel bar fan clamps 5/8"dia for RCC roof. (S.I.No:1 P-14)	141/01	Each	1269/-
7.	XXXX 15	Errrection of ceiling fan 56"size i/c wiring for down rod with 3/029 PVC wire fixing of regulator blade canopy etc as required. (S.I.No:1 P-14)	82/16	Each	1232/-
8.	04	P/F S.W board to accomodate main or sub-main control switch for similar jobs as required. (S.I.No:3 P-13)	105/88	P.Sft	424/-

(Cont:page No:02)

ITEM NO:	QUANTITY:	DESCRIPTION OF ITEMS TO BE EXECUTED AT SITE.	RATE.	UNIT.	AMOUNT.
9.	04	Providing and fixing A.C or D.C electric bell 200/220 w- 70mm.(S .I.No:21 P-11)	150/70	Each	603/-
10.	04	Providing and fixing flush type electric bell push button (S.I.No:23 P-12)	25/19	Each	101/-
11.	02	Providing and fixing earthing set with 2"x2"x1/4" copper plate buried in the ground at the depth of 12' or less if water comes from out from ground level as required. (S.I.No:23 P-26)	2570/37	Each	5141/-
12.	15	Providing and fixing of fan regulator on a given board. (S.I.No: P-)	91/30	Each	1370/-
13.	xxxxix 1.50	Providing and fixing distribution- board double shutter to accommodate circuit breaker i/c painting with enameled paint & for other similar jobs. (S.I.No:5 P-13)	907/96	Each	1362/-

TOTAL RS: 48386/-

_____ %Above/below on the Rate of CSR
Amount to be added/deducted on the Rs: _____

Total amount in wards. _____

RD

RENOVATION/REHABILITATION OF DISTRICT ADMINISTRATION
COLONY SILKARPOUR. (ELECTRIFICATION)

BINDING OF DOCUMENTS FOR WORK.

BILLS OF MATERIALS.

DESCRIPTION AND NATURE OF WORK TO BE DONE ON THE BASIS OF WHICH ESTIMATE OF RATE.

PART "C" NO. 34/10/1977.

ITEM NO.	QUANTITY:	DESCRIPTION OF THE WORK TO BE EXECUTED AT SITE.	UNIT.	AMOUNT.
1.	300	e/f service wire with 2-7/8 Ø/4 pvc insulated wire aluminum conductor twin core from pole to main switch.	p.ftt	
2.	04	providing and fixing exhaust fan 8'x10' size complete i/c connection.	each	
3.	02	providing and fixing wall fan medium size complete with fixing & necessary electric connection.	each	

TOTAL AMOUNT:

PART "C"

TOTAL AMOUNT IN TABLE:

REPLY OF PARA NO.02

S.NO.	NAME OF WORK	ESTIMATE COST	PERIOD
1.	Renovation of Mosque Karbala Moula Shikarpur District Shikarpur	1.00 (M)	12 months
2.	Construction of Sports Stadium Complex Madeji (Inte: Ext:/W/S, sainatory & drainage)	0.980 (M)	12 months
3.	Construction of Bus / Wagon Terminal Chak Lavatory block	0.800 (M)	12 months
4.	Renovation / Rehabilitation of District Administration Colony (Electrification)	0.500 (M)	12 months


Executive Engineer
Buildings Division Shikarpur.