


**OFFICE OF THE EXECUTIVE ENGINEER, EDUCATION WORKS DIVISION-II,
EDUCATION & LITERACY DEPARTMENT, GOVERNMENT OF SINDH, KARACHI**

Tender form issued to M/S. _____, Government Contractor,
and charged Rs. 3000/= Vide D.R. No. _____, Dated: _____


**EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION-II
EDUCATION & LITERACY DEPARTMENT
GOVT. OF SINDH KARACHI**

NAME OF WORK:- ESTABLISHMENT OF CADET COLLEGE AT GADAP TOWN KARACHI
(BALANCE WORK OF GYMNASIUM HALL, SQUASH COURT, SWIMMING POOL)

I/We hereby tender for execution of the works of Government of Sindh (herein before / after) referred to as Government of Sindh, specified in the under written memorandum within the time modified in each memorandum at:

- | | |
|------------|--------------------------|
| 1. Part-A: | @ _____ (Above / Below), |
| 2. Part-B: | @ _____ (Above / Below), |
| 3. Part-C: | @ _____ (Above / Below), |
| 4. Part-D: | @ _____ (Above / Below), |
| 5. Part-E: | @ _____ (Above / Below), |
| 6. Part-F: | @ _____ (Above / Below), |

The estimate carried out & according to all respect with the specification design / drawing & instruction, in writing referred to rule-I here of the clause-12 of the annexed condition of the contract & agreement, that when material for the work are provided by the Government such materials & rates to paid for then shall be as provided in Schedule-B here to:

GENERAL DESCRIPTION:

| | | | |
|-------|--|----|-----------------|
| i). | Estimated Cost | :- | Rs. 4,000,000/= |
| ii). | Earnest Money 2% | :- | Rs. 80,000/= |
| iii). | Security Deposit (8%) in/c Earnest Money (2%) Total (10%) | :- | Rs. 40,000/= |
| iv). | Income Tax (7.50%) | :- | Rs. 300,000/= |
| v). | Time allowed for completion of work | :- | 04 Months |

**EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION-II
EDUCATION & LITERACY DEPARTMENT
GOVT. OF SINDH KARACHI**

CONTRACTOR'S UNDERTAKING

I/We have offered that above rates after taking into consideration all the terms and conditions as per B-I, printed tender & this memorandum and shall be base to fill-up & completed the B-I, tender form co, as to complete the agreement. In case of failure, the Department will be at liable to take action against me/us.

- | | |
|-----------------|-------------------|
| i) Schedule-A: | Nil |
| ii) Schedule-B: | Attached herewith |

(SIGNATURE OF CONTRACTOR)

SUMMARY OF COST.

Name of Work:- ESTABLISHMENT OF CADET COLLEGE AT GADAP
TOWN KARACHI (Remaining / Allied Work of
Gymnasium Hall, Siwmming Pool).

1 COST OF CIVIL WORK

Rs:

2 COST OF NON SCHEDULE ITEM

Rs:

CHECKED
DRAFTSMAN
Education Division-II

Million in Rs:-

EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION-II
EDUCATION & LITERACY DEPARTMENT
GOVT. OF SINDH KARACHI.

SCHEDULE - B

NAME OF WORK:-

ESTABLISHMENT OF CADET COLLEGE AT GADAP TOWN KARACHI
(Remaining / Allied Work of Gymnasium Hall, Siwmming Pool).

| S.No | Description of Item | Qty | Rate | Unit | Amount |
|----------------------|--|----------|---------|-------|------------|
| SCHEDULE ITEM | | | | | |
| 1 | Excavation in foundation of building bridges and other structure in/c degebilling dressing, refilling around structure with excavated earth watering and ramming lead upto 5ft (b) in ordinary soil (S.I.No.18/P-4) | 11200.00 | 3176.25 | %ocft | 35,574.00 |
| 2 | Cement Concrete brick or stone ballast 1-1/2" to 2" guage ratio 1:4:8 (S.I.No.4b/P-15) | 2100.00 | 9416.28 | %cft | 197,742.00 |
| 3 | Filling watering and ramming earth in floor with new earth excavated from outside lead upto one chain and left upto 5 feet (S.I.No.22 P-4) | 12225.00 | 3630.00 | %ocft | 44,377.00 |
| 4 | R.C.C work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms, moulds, lifting, shuttering, curing, rendering and finishing the exposed surface (including screening and washing of shingle (a) R.C.C work in roof slab, beams, columns, rafts, lintels and other structural members laid in situ or precast laid in position. Complete in all respects (i) Ratio 1:2:4 90 lbs. (S.I.No. 6(a)/i/C-4) Ratio 1:2:4 | 1548.00 | 337.00 | P.cft | 521,676.00 |
| 5 | Fabrication of Tor steel reinforcement for cement concrete including cutting, bending, laying in position, making joints and fastening including cost of binding wire (also includes removal of rust from bars. (S.I.No. 7(b)/C-4) Tor Steel | 82.93 | 5001.70 | P.cwt | 414,784.00 |
| 6 | Damp Proof Course with Cement and Ratio (1:2) mixed with dampo (S.I.No.69 P-112) 3/4" thick | 280.00 | 2401.58 | %sft | 6,724.00 |
| 7 | Vertical damp proof course of 3/4" thick cement plaster 1:2 with bitumen at (20 lbs per %Sft). (S.I.No.70 P-107) Educator Division II | 440.00 | 2760.99 | %sft | 12,148.00 |
| 8 | P/L 3" thick topping cement concrete 1:2:4 in/c surface finishing and dividing into pannels pannels (S.I.No.16b P-46) | 144.00 | 4411.82 | %sft | 6,353.00 |
| 9 | P/L 2" thick topping cement concrete 1:2:4 in/c surface finishing and dividing into pannels pannels (S.I.No.16c P-42) | 528.00 | 3275.50 | %Sft | 17,295.00 |
| 10 | P/F cement paving blocks flooring having size of 197 x 97 x 60(mm) of city / quddra / cobble shape with pigmented having strength b/w 5000 psi to 8500 psi in/c filling the joints with hill sand and laying in specified manner / patter and design etc complete (S.I.No.74 P-50) | 3200.00 | 223.97 | P.Sft | 716,704.00 |
| 11 | Providing & Fixing precast Edge Block 3750 Psi Industrial made size 6 inches thick x 12 inches long x 12 inches high in/c the cost of carriage excavation form work for hunching 1450 Psi lean concrete 2250Psi concrete for haunching 1:4 cement sand mortor (S.I.No.14 Highway P-16). | 2100.00 | 297.00 | P.Sft | 623,700.00 |

- 12 Carriage of 100 Cft 5 Tons of all materials like stone aggregate, Spawl, coal, lime surkhi etc. B.G rail fastening points and crossing bridges Girders, Pipes, Sheets rail, M.S barsetc 1000 Nos. of 10" x 5" x 3" or 1000 Nos. tiles 12" x 6" x 2" or 150 Cft of timber or 100 Maunds of fuel wood by trucks or any other means owned by the contractors. (S.I.No.1Page-2 Carriage of Materials Vol:-1 Part-I Sixth Edition 2011) (30 Miles).

CHECKED

12225.00

1921.30

%ocft

23,487.89

[Signature]
DRAFTSMAN
Education & Literacy Division-II

 2,620,564.89

NON SCHEDULE ITEM

- | | | | |
|---|---|--------|-------|
| 1 | Providing & Fixing of steel pipe railing required design using 2" dis. Horz: pipe 1/2" dia vertical pipe in/c revetting complete (L.Q.R) | 162.00 | P.Rft |
| 2 | Red Marandy Wood Shutter fixed in position in/c tower bolts, cleats, handles, cord with hooks and cost of nails and screws, etc complete.(L.Q.R). | 196.00 | P.sft |
| 3 | French polishing complete a) on new work (L.Q.R) | 392.00 | P.Sft |

[Signature]
EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION-II
EDUCATION & LITERACY DEPARTMENT
GOVT. OF SINDH KARACHI