


**OFFICE OF THE EXECUTIVE ENGINEER, EDUCATION WORKS DIVISION-II,
EDUCATION & LITERACY DEPARTMENT, GOVERNMENT OF SINDH, KARACHI**

Tender form issued to M/S. _____, Government Contractor,
and charged Rs. 3000/= Vide D.R. No. _____, Dated: _____


**EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION-II
EDUCATION & LITERACY DEPARTMENT
GOVT. OF SINDH KARACHI**

NAME OF WORK:- ESTABLISHMENT OF CADET COLLEGE AT GADAP TOWN KARACHI
(ACADEMIC BLOCK (A+B+C) IN/C AUDITORIUM HALL) (CABLE WORK)

I/We hereby tender for execution of the works of Government of Sindh (herein before / after) referred to as Government of Sindh, specified in the under written memorandum within the time modified in each memorandum at:

- | | |
|------------|--------------------------|
| 1. Part-A: | @ _____ (Above / Below), |
| 2. Part-B: | @ _____ (Above / Below), |
| 3. Part-C: | @ _____ (Above / Below), |
| 4. Part-D: | @ _____ (Above / Below), |
| 5. Part-E: | @ _____ (Above / Below) |
| 6. Part-F: | @ _____ (Above / Below) |

The estimate carried out & according to all respect with the specification design / drawing & instruction, in writing referred to rule-I here of the clause-12 of the annexed condition of the contract & agreement, that when material for the work are provided by the Government such materials & rates to paid for then shall be as provided in Schedule-B here to:

GENERAL DESCRIPTION:

i).	Estimated Cost	:-	Rs. 13,000,000/=
ii).	Earnest Money 2%	:-	Rs. 2,60,000/=
iii).	Security Deposit (8%) in/c Earnest Money (2%) Total (10%)	:-	Rs. 1,300,000/=
iv).	Income Tax (7.50%)	:-	Rs. 9,75,000/=
v).	Time allowed for completion of work	:-	04 Months

**EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION-II
EDUCATION & LITERACY DEPARTMENT
GOVT. OF SINDH KARACHI**

CONTRACTOR'S UNDERTAKING

I/We have offered that above rates after taking into consideration all the terms and conditions as per B-I, printed tender & this memorandum and shall be base to fill-up & completed the B-I, tender form co, as to complete the agreement. In case of failure, the Department will be at liable to take action against me/us.

- | | |
|-----------------|-------------------|
| i) Schedule-A: | Nil |
| ii) Schedule-B: | Attached herewith |

(SIGNATURE OF CONTRACTOR)

NAME OF WORK:- ESTABLISHMENT OF CADET COLLEGE GADAP TOWN, KARACHI

ACADEMIC BLOCK (A+B+C) I/C AUDITORIUM HALL

(CABLE WORK) (ADP NO: 223)

SCHEDULE OF PRICE .


S.NO.	ITEM OF WORK.	QTY		RATE	UNIT	AMOUNT
1	P/F circuit breaker 15,2,30,40,50 & 60 amps TP (XS-100 CS (CB) on prepared board as required. (S.NO:P-31/206)	5	Nos	5521.00	Each	27605.00
2	Providing & Laying (Main or Sub-Main) PVC insulated with size 2-7/1.029 copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required. (S.I.No: P-2/10)	3040.00	Mtr.	222.00	P.Mtr.	674880.00
3	P/F circuit breaker 400 amps TP setting 250-400 amps (XS-400CJ) on prepared board as required. (S.No:P-31/210)	4	Nos	39401.00	Each	157604.00
4	Providing & Laying (Main or Sub-Main) PVC insulated & PVC Sheeted with 4- core copper conductor 600/1000 volts size 16mm2. (S.I.No:113/13)	152.43	Mtr.	1679.00	P.Mtr.	255929.97
5	Providing & Laying (Main or Sub-Main) PVC insulated & PVC Sheeted with 4- core copper conductor 600/1000 volts size 35mm2. (S.I.No:113/14)	332.31	Mtr.	3008.00	P.Mtr.	999588.48
6	Providing & Laying (Main or Sub-Main) PVC insulated & PVC Sheeted with 4 core copper conductor 600/1000 volts size 70mm2. (S.I.No:113/15)	266.15	Mtr.	4722.00	P.Mtr.	1256760.30
7	Excavation in rock dressed to designed section grade and profile (S.No: 5/P-2)	3151.00	Cft	7260.00	%0Cft	22876.00
8	Construction of man hole inspection chamber for the required dia of circular sewer and 3' 6" (1067mm) depth walls of B.B in CM 1:3 cement plastered 1:3 1/2" thick inside of walls & 1" 25mm) tick over benching & channel i/c fixing C.I man hole cover with frame of opening 1-1/2" 1"x1/2" embedded in plain c.c 1:2:4 and fixing 1" (25mm) dia M.S steps 6" (1150mm) side projecting 4" from the face to well at 12" c.c duly painted complete as per specification and drawing No: PD public health circle southern (a) 4" to 12" dia.(S.NO:1/p-39).	4	Nos.	14748.00	Each	58992.00
				Total Rs:		3426630.75
				G.Total Rs:		
<u>PART-B (NON-SCHEDULE ITEM)</u>						
1	Providing PVC pipe i/c excavation of earth size (1.5" x 1.5") and refilling the surface after laying the cable etc complete.					
i.	PVC pipe 3" dia	2463.00	Rft		P.Rft	
ii	PVC pipe 4" dia	688.00	Rft		P.Rft	

CHECKED

DRAFTSMAN
 Education Division-II

	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
	P/F on a prepared board iron clad bus bar with 4 copper strips of 400 amps in 19mmx4(3/4"x5/32") i/c necessary electric connection as approved by Engineer/Incharge.	4	Nos	Each	
3	P/F main pannel board double shutter for accomodate circiut breaker and busbar i/c painting with enemelled paint as approved by Engineer.	8.00	Sft	P.Sft	
4	P/F Electric Cooler matelic bidy 60 gallons National make or approved quality i/c filter etc complete.	3	Nos	Each	
5	P/F earthing set size (2x2) copper plate i/c excavation of rock earth 12" depth or ifwater comes out i/c salt/ choracale mixed with (G.I Rod with nuts , bolts testing toping etc complete (R.A)	2	Nos	Each	
6	P/F L.E.D light 8" square / circle shop (09) watts in plastic cover fany type (china make).	120	Nos	Each	
7	P/F L.E.D Tube light 18 watts (Light emitting Diod) classification with L.E.D driver complete plastic covered and base etc complete.	100	Nos	Each	
8	P/L 300mm2 Cable 4 core 660/1000 voltage armoured i/c excavation of earth and refiling the surface surface i/c necessary connection with copper luggs etc complete (Pakistan AG/Piloeermake etc(R.A)	210.00	Mtr	P.Mtr	
9	S/F Power factor improvement bank for 200 K.Wload approximately rating of the power is 160 KVAR (0.9) being maxdatory magnet of KESC for obtaing new connection/ Testing commissioning as required.	1	Job	Each	
9	Providing , Install of L.T PANEL , cubical design double shutter to accomodate heavy duty circiut breaker & bus bar suitable for 3 phase ,4 wire 50Hz A/C system & equipped with 1x400 amps TP / change over & 400 amps busbar and 4X100 amp TPN / protection electrically & machinicaly i/c current transformer / inter locked such that if one is "ON" theother is "OFF" & vice versa system	2	No	Each	

ITEM OF WORK	QTY	RATE	UNIT	AMOUNT
10 P/F Water pumping set 5HP 2800 RPM Three phase 440 volts 2".0x1-1/2 section and delivery 12571 head in clouding base plate & also making c.c 1:3:6 plate form required size & along with nuts & bolts complete in all respect as a approved by Engineer/ Incharge .(RA).	2	No	Each	

CHECKED

TSMAN
Division-II

Total Part-B Rs: _____
 Total Part-A Rs: _____
 G.Total Rs: _____
 Says Rs: _____

(Contractor signature)

EXECUTIVE ENGINEER
 EDUCATION WORKS DIVISION-II
 KARACHI