


**OFFICE OF THE EXECUTIVE ENGINEER, EDUCATION WORKS DIVISION-II,  
EDUCATION & LITERACY DEPARTMENT, GOVERNMENT OF SINDH, KARACHI**

Tender form issued to M/S. \_\_\_\_\_, Government Contractor,  
and charged Rs. 3000/= Vide D.R. No. \_\_\_\_\_, Dated: \_\_\_\_\_

  
**EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION-II  
EDUCATION & LITERACY DEPARTMENT  
GOVT. OF SINDH KARACHI**

**NAME OF WORK:-** ESTABLISHMENT OF CADET COLLEGE AT GADAP TOWN KARACHI  
(BALANCE WORK OF ACADEMIC BLOCK (A+B+C) IN/C AUDITORIUM HALL)

I/We hereby tender for execution of the works of Government of Sindh (herein before / after) referred to as Government of Sindh, specified in the under written memorandum within the time modified in each memorandum at:

- |            |         |                  |
|------------|---------|------------------|
| 1. Part-A: | @ _____ | (Above / Below), |
| 2. Part-B: | @ _____ | (Above / Below), |
| 3. Part-C: | @ _____ | (Above / Below), |
| 4. Part-D: | @ _____ | (Above / Below), |
| 5. Part-E: | @ _____ | (Above / Below)  |
| 6. Part-F: | @ _____ | (Above / Below)  |

The estimate carried out & according to all respect with the specification design / drawing & instruction, in writing referred to rule-I here of the clause-12 of the annexed condition of the contract & agreement, that when material for the work are provided by the Government such materials & rates to paid for then shall be as provided in Schedule-B here to:

**GENERAL DESCRIPTION:**

i).	Estimated Cost	:-	Rs. 16,000,000/=
ii).	Earnest Money 2%	:-	Rs. 320,000/=
iii).	Security Deposit (8%) in/c Earnest Money (2%) Total (10%)	:-	Rs. 1,600,000/=
iv).	Income Tax (7.50%)	:-	Rs. 1,200,000/=
v).	Time allowed for completion of work	:-	04 Months

**EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION-II  
EDUCATION & LITERACY DEPARTMENT  
GOVT. OF SINDH KARACHI**

**CONTRACTOR'S UNDERTAKING**

I/We have offered that above rates after taking into consideration all the terms and conditions as per B-I, printed tender & this memorandum and shall be base to fill-up & completed the B-I, tender form co, as to complete the agreement. In case of failure, the Department will be at liable to take action against me/us.

- |                 |                   |
|-----------------|-------------------|
| i) Schedule-A:  | Nil               |
| ii) Schedule-B: | Attached herewith |

(SIGNATURE OF CONTRACTOR)

## SUMMARY OF COST.

Name of Work:- ESTABLISHMENT OF CADIT COLLEGE  
BALANCE WORK OF ACCADMIC BLOCK-A+B+C  
and AUDITORIUM HALL

1 COST OF CIVIL WORK

Rs:

2 COST OF NON SCHEDULE ITEM

3 Less 20 Below on S.I (Ply Door, Marble Tile)

Rs:

4 COST OF WATER SUPPLY & SANITARY FITTING

Rs:

5 COST OF SUI GAS FITTING

Rs:

CHECKED  
[Signature]  
CRAFTSMAN  
Education - Division-II

Million in Rs:-

[Signature]  
EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION-II  
EDUCATION & LITERACY DEPARTMENT  
GOVT. OF SINDH KARACHI.



**SCHEDULE - B**

**NAME OF WORK:-**

**ESTABLISHMENT OF CADIT COLLEGE BALANCE WORK OF  
ACCAADMIC BLOCK-A+B+C and AUDITORIUM HALL**

<i>S.No</i>	<i>Description of Item</i>	<i>Qty</i>	<i>Rate</i>	<i>Unit</i>	<i>Amount</i>
-------------	----------------------------	------------	-------------	-------------	---------------

**SCHEDULE ITEM**

1	Two coats of bitumen laid hot using 34 lbs for % Sft over roof and blinded with sand @ 1 Cft per % Sft. (S.I.No. 13/P-7)	18593.82	1887.46	%Sft	350,951.00
2	P/F collapsible gate with channel framing of section 3/4" x 5/16" at 4" in/c revitted with 3/4" x 1/8" flat iron patti placed diagonally and provided with top & bottom T-Section 1" x 1" 1/8" along with rollers also in/c locking arrangement and fixing in floor / ceilling or wall etc complete.	945.90	387.04	P.Sft	366,101.00
3	Painting new surface © preparing surface and painting guard bars gates of iron bars grating railing (in/c standard braccess etc) & similar opening work. (S.I.No.5d P-76)	1741.80	1270.83	%Sft	22,135.00
4	S/F in position Aluminium channels framing for hinged doors or Alcop made with 5mm thick tinted glass glazing (belgium) and Alpha (Japan) Locks in/c handles stoppers etc. (S.I.No.83 P-114)	969.20	1507.66	P.Sft	1,461,224.00
5	White glazed tiles 1/4" thick dado jointed in white cement and laid over 1:2 cement sand mortor 3/4" thick in/c finishing (S.I.NO.37/P-45)	640.00	28253.61	% Sft	180,823.00
6	Glazed tile dado 1/4" thick laid in pigment over 1:2 cement sand mortor 3/4" thick in/c finishing (S.I.No.38 P-45)	576.00	28299.3	% Sft	163,004.00
<b>Total :-</b>					<b>2,544,238.00</b>

**CHECKED**  
**DRAFTSMAN**  
**Education - Division-II**

**NON SCHEDULE ITEM**

1	S/F Jaffri Lasani shutter 1-3/4" thick imported quality lasani in/c imported 5mm glass in specification pattern and design in/c all materaial for making and fixing in position as approved by Engineer Incharge etc complete (L.Q.R).	589.75	P.Sft
2	French Polishing complete On new Work. (L.Q.R)	4396.00	P.Sft
3	Teak wood wrought framed and fixed in place including chowkhats hold fasts tower bolts, chowks, cleats, handles cord with hooks and cost of nails and screws etc complete b) Panelled or Panelled and glazed or fully glazed 1-3/4"thick) (L.Q.R).	100.00	P.Sft
4	Providing & Fixing of stailless steel pipe railing required design using 2" dia Horz: pipe in/c reveitting complete (L.Q.R).	152.00	P.Rft

- 5 Providing & laying granite stone prepolished of size 6' x 1.6' or 6' x 2' on floor or step in required shape colour and patterns 3/4" thick in white cement and pigment over base of 1:2 grey cement mortar 3/4" thick in/c washing and filling of joints with slurry of white cement and pigment in desired shape with finishing cleaning and coat of wax polish in/c half round edges etc complete and directed by Engineer Incharge (L.Q.R)

302.99

P.Sft

- 6 Providing & laying granite stone prepolished of size 2' x 6" on floor or walls in required shape colour and patterns 3/8" thick in white cement and pigment over base of 1:2 grey cement mortar 3/4" thick in/c washing and filling of joints with slurry of white cement and pigment in desired shape with finishing cleaning and coat of wax polish in/c half round edges etc complete and directed by Engineer Incharge (L.Q.R)

CHECKED

121.00

P.Sft

- 7 Providing & Fixing limited lasani both side 3/4" Almirah 9" - 12" depth in/c boxing with back shelves shutters brass fitting etc complete. (L.Q.R)

DRAFTS  
Education - Division-II

3000.53

P.Sft

- 8 Supplying & Fixing false ceiling of plaster of paris in pannels in/c making frame work of deodar wood in/c painting with soligia paint.(L.Q.R)

6769.54

P.Sft

- 9 Red Marandy Wood Shutter fixed in position in/c tower bolts, cleats, handles, cord with hooks and cost of nails and screws, etc complete. 1-3/4" thick (L.Q.R).

1833.63

P.Sft

- 10 S/F in position U.P.V framing for slidding windows & ventilators of Alcop made with 5mm thick tinted glass glazing (Belgium) & Aluminium fly screen in/c handles stopper & locking arrangement etc complete.

624.00

P.Sft

- 11 P/F Fibre Glass Dome Shade required size of approved quality design & colour desired shape with finishing cleaning upto 20ft height as per instruction of the Engineer Incharge Rate in/c all costs of labour, material etc complete (L.Q.R).

1325.00

P.Sft

Total N.S.I :-

\_\_\_\_\_

EXECUTIVE ENGINEER  
EDUCATION WORKS DIVISION-II

EDUCATION & LITERACY DEPARTMENT


GOVT. OF SINDH KARACHI



**PART-B (W/S & S/F)**

**NAME OF WORK:-** ESTABLISHMENT OF CADIT COLLEGE BALANCE WORK OF  
ACCADMIC BLOCK-A+B+C and AUDITORIUM HALL

S.No.	Description.	Qty	Rate	Unit	Amount.
<b>SCHEDULE ITEM</b>					
1	Providing and fixing in position nyloon connections complete with 1/2" dia brass stop cock with pair of brass nuts and lining to nyloon connection (S.I.No: 23/P-6)	8.00	447.15	Each	3,577.20
2	Supplying and fixing bib cock of Superior Quality with c.p. head 1/2" dia. (S.I.No: 1.B/P-16)	7.00	337.92	Each	2,365.44
3	S/Fixing in long bib cocks of crystal head with 1/2" dia (S.I.No.13.B P-19)	9.00	1384.24	Each	12,458.16
4	S/Fixing Jet Shower with rod of superior quality single C.P head 1/2" dia (S.I.No.15 P-19)	2.00	1142.24	Each	2,284.48
5	S/Fixing in position brass stop cocks standard patterns 1/2" dia (S.I.No.1.B P-16)	18.00	337.92	Each	6,082.56
6	Supplying & Fixing Wash Basin Mixture of superior quality with C.P head 1/2" dia (S.I.No.14-BP-19)	18.00	3179.00	Each	57,222.00
7	Supplying & Fixing sawn type pillar cock of superior quality with crystal head 1/2" dia (S.I.No.16-BP-19)	18.00	877.80	Each	15,800.40
8	Providing and fixing 15"x12" beveled edge minor of belgium glass complete with 1/8" thick hard board and C.P screws fixed to wooden plate Superior Quality.(S.I.No: 4/b/P-7)	7.00	2047.76	Each	14,334.32
9	S/F soap tray earthenware C.P screw etc complete (S.I.NO.5 P-8)	7.00	497.20	Each	3,480.40
10	P/F chrome plated brass towel rail complete with brackets fixing on wooden cleats with 1" long C.P brass screw 3/4" round or square (Super Quality) (S.I.No.1 (iiib) P-7) Towel rail 24" long	7.00	972.95	Each	6,810.65
11	S/Fixing C.P Muslim Shower with Crystal head etc complete (S.I.No.19-B P-19)	6.00	3432.00	Each	20,592.00
12	P/F 24" x 18" x 8" white glazed fire clay sinks complete with & in/c the cost of C.I or W.I brackets 6inches built into walls 1-1/2" c.p brass washer 1-1/2" dia malleable iron or c.p brass trap with malleable iron or brass unions & making requisit No. of holes in walls plinth & floor for pipe connection & making good in cement concrete 1:2:4 (Foreign or Equivalent) (S.I.No.18 P-5)	16.00	4722.30	Each	75,556.80
					<b>220,564.41</b>

  
EXECUTIVE ENGINEER  
EDUCATION & RES. DIVISION-II

**NON SCHEDULE ITEM**

- 1 S/Fixing suction set with 2 H.p motor single phase with 2x 1/2" suction & delivery duoble belt in/c fixing & necessary connection (L.Q,R)

**CHECKED**

4.00

Each

*[Signature]*  
EDUCATION WORKS DIVISION-II

*[Signature]*  
**EXECUTIVE ENGINEER**  
EDUCATION WORKS DIVISION-II  
EDUCATION & LITERACY DEPARTMENT  
GOVT. OF SINDH KARACHI.