

OFFICE OF THE EXECUTIVE ENGINEER EDUCATION WORKS DIVISION SANGHAR

No.TC/G-55/ 1922

of 2016 Sanghar

Dated: 22 / 02 / 2016

Sealed Tenders on standard Bid Documents forms are invited from all interested persons/ parties/ contractors / firms meeting with eligibility criteria of SPPRA Rules 2010 for the following works.

S.#	Name of Schemes / School	Estimated Cost	Bid Security	Tender Fee	Time for Completion
	Rehabilitation of existing Primary Schools in District Sanghar under Pak MDGs Community Development Programme 2014-15 (03-Units).				
1	GPS. Village Syed Mureed Ali Shah Deh Chotiyaryoon UC Chotiyaryoon Taluka Sanghar.				
	(a) Civil Work.	2.400	0.0480	3000	10 Months
	(b) Electrification.	0.115	0.0023	500	10 Months
2	GPS. Village Madan Khan Jalalani Deh Thaheem UC Syed Sabghatullah Shaheed Rashdi Taluka Sinjhora				
	(a) Civil Work.	1.800	0.0360	3000	10 Months
	(b) Electrification.	0.115	0.0023	500	10 Months

TERMS & CONDITIONS OF THE TENDERS.


- The procuring agency Executive Engineer, Education Works Division Sanghar invites sealed bid from interested firms or persons meeting with eligibility criteria of SPPRA 2010.
- The complete set of Bidding Documents may be purchased by any interested eligible / bidder on submission of a written application to the office given below and upon payment of Bid price / Tender Fee mentioned against each work from the date of publication NIT upto **17-03-2016** at 12:00 PM.
- All bids must be accompanied by a Bid Security / Earnest Money in the amount mentioned against each work in the form of Call Deposit from any scheduled Bank duly pledged in the name of Executive Engineer, Education Works Division Sanghar and must be to this office on **18-03-2016** upto 2:00 PM Bids will be opened at 3:00 PM on the same day in the presence of bidders representatives who choose to attend, at the same address.
- If the undersigned is out of head quarter, the bid be issued and opened on next working day as per standard time schedule.
- Registration with Income Tax Department (NTN Certificates) and copy of C.N.I.C.
- Registration with SRB (Sindh Revenue Board).
- In case of works costing to above Rs: 4.00 (M) the PEC Certificate will be applicable.
- Affidavit to the effect that the Firm / Contractor have not been black listed previously by any executing agency.
- The detail of all works can be seen at web site www.sindh.gov.pk Govt: of Sindh and SPPRA web site www.pprasinhd.gov.pk.
- In case the tenders are cancelled / rejected or un-responded, the next date for issue and opening will be as under:
- Conditional and Telegraphic tender will not be entertained.
- The competent authority reserved the right to reject any or all tenders / bid proposals as per provision of SPPRA Rules and shall be communicated to bidder on request.

Contd....P/02

Received Date & Time


2nd Attempt.

Date of Issue upto 29-3-2016 at 12:00 PM & will be received back on 30-03-2016 upto 2:00 PM and Open on 3:00 PM.


EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION
SANGHAR

C.C to :


- 1/- The Director Information (Advertisement) Relation Sindh Directorate Block No. 96 Sindh Karachi, for publication in three leading News Papers English, Urdu & Sindhi (07 copies NIT enclosed)
- 2/- The Director (CB) Sindh Public Procurement Regularity Authority (SPPRA) Barrack No. 8 Secretariate A4 Court Road Karachi.
- 3/- The Chief Engineer Education Works Sukkur for information.
- 4/- The Deputy Commissioner Sanghar for information.
- 5/- The Superintending Engineer, Education Works Circle Shaheed Benazirabad.
- 6/- The Executive Engineer all under Superintending Engineer Education Works Circle Shaheed Benazirabad for information.
- 7/- The Assistant Engineer (all) under Executive Engineer, Education Works Division Sanghar.
- 8/- Copy to Notice Board / C.B/ D.B (Local).


EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION
SANGHAR

ANNUAL PROCUREMENT PLAN

OFFICE OF THE EXECUTIVE ENGINEER EDUCATION WORKS DIVISION SANGHAR FOR THE YEAR 2015-16

Sl#	Description of Procurement	Quantity (where applicable)	Estimated Total Cost (Million)	Funds Allocated (Million)	Source of Funds ADP/Non ADP	Proposed Procurement Method	Timing of Procurement				Remarks
							1st Qtr.	2nd Qtr.	3rd Qtr.	4th Qtr.	
<u>Rehabilitation of existing Primary Schools in District Sanghar under Pak MDGs Community Development Programme 2014-15 (03-Units).</u>											
1	GPS. Village Syed Mureed Ali Shah Deh Chotiyaryoon UC Chotiyaryoon Taluka Sanghar.			2.566							
	(a) Civil Work.		2.400		MDGs Prog:	Open Competitive Bidding	--	--	--	--	
	(b) Electrification.		0.115		..do..	..do..	--	--	--	--	
2	GPS. Village Madan Khan Jalalani Deh Thaheem UC Syed Sabghatullah Shaheed Rashdi Taluka Sinjhora			1.962							
	(a) Civil Work.		1.800		..do..	..do..	--	--	--	--	
	(b) Electrification.		0.115		..do..	..do..	--	--	--	--	


 EXECUTIVE ENGINEER
 EDUCATION WORKS DIVISION
 SANGHAR



GOVERNMENT OF SINDH
WORKS & SERVICES DEPARTMENT

Karachi dated the November, 2013.

CORRIGENDUM

No. E&A(W&S)3-9/91/2013: In supersession of this Department's Notification of even number and with the approval of competent authority, a Procurement Committee with the following composition, in terms of Rule-7 of Sindh Public Procurement Rules-2010, is hereby constituted for procurement of "Goods & Works" in the Office of Superintending Engineer, Works & Services Department, Sanghar, excluding procurement involving foreign exchange with the following composition:-

- | | | |
|------|---|----------|
| i) | Superintending Engineer
Works & Services Department,
Sanghar. | Chairman |
| ii) | Executive Engineer
Concerned Division. | Member |
| iii) | Assistant Engineer
Public Health Engineering Sub-Division,
Sanghar, | Member |

2. The Functions & Responsibilities of the Committee, in term of Rule-7 & 8 of SPPRA-2010, shall be as under:

- Preparing of bidding documents.
- Carrying out Technical as well as Financial Evaluation of the Lids
- Preparing Evaluation report as provided in Rule-45;
- Making recommendation for the award of contract to the competent authority and
- Perform any other function ancillary and incidental to the above.

QAZI SHAHID PERVEZ
SECRETARY TO GOVT. OF SINDH

No. E&A(W&S)3-9/91-2013

Karachi dated the November, 2013.

A copy is forwarded for information to:-

1. The Accountant General, Sindh, Karachi.
2. The Secretary to Govt. of Sindh, Public Health Engg. Department, Karachi.
3. The Managing Director, SPPRA, Karachi.
4. The Chief Engineer (Buildings/ Highways), Hyderabad.
5. The Chairman / Members of the Committee.
6. PS to Minister Works & Services Department.
7. PS to Secretary Works & Services Department.
8. PA to Additional Secretary (Tech), Works & Services Department.
9. The Deputy Secretary (Tech) Works & Services Department.
10. The Deputy Secretary (Admin), W&SD.
11. The Deputy Secretary Staff to Chief Secretary Sindh,
12. The Deputy Director, PM&E Cell, W&SD
13. Notification file.

(MUHAMMAD ZAKIR)
SECTION OFFICER (GENERAL)
FOR SECRETARY TO GOVT. OF SINDH



GOVERNMENT OF SINDH
WORKS & SERVICES DEPARTMENT

Karachi, dated the December, 2015.

NOTIFICATION

No.E&A(W&S)3-9/91-2015: With the approval of Competent Authority, a Committee comprising following is hereby constituted in accordance with Rule-11 of Sindh Public Procurement Rules-2010 (Amended 2013), for the purpose of redressal of grievances complaints and settlement of disputes / issues thereof with regard of procurement process in the Office of Executive Engineer, Highways / Buildings Division (Works & Services), Sanghar.

- | | | |
|------|---|----------|
| i) | Chief Engineer (Highways / Buildings), Hyderabad | Chairman |
| ii) | Deputy Commissioner / Project Director, District Development Committee, Sanghar or his representative (not below the rank of BS-15) | Member |
| iii) | District Accounts Officer, Sanghar | Member |

2. The Functions & Responsibilities of the Committee will be same as specified in Rules-31(4) and (5) of Sindh Public Procurement Rules-2010

AJIAZ AHMED MEMON
SECRETARY TO GOVT. OF SINDH

No.E&A(W&S)3-9/91-2015:

Karachi, dated the 17th December, 2015

A copy is forwarded for information to:-

1. The Accountant General, Sindh, Karachi.
2. The Managing Director, SPPRA, Karachi.
3. The Chief Engineer (Buildings), Hyderabad.
4. The Deputy Secretary (Staff) to Chief Secretary Sindh, Karachi.
5. The Superintending Engineer, Works & Services, Sanghar.
6. The Chairman / Members of the Committee.
7. The Executive Engineer, Highways / Buildings Division, Sanghar.
8. The Deputy Director, PM&E Cell, W&S Department, Govt. of Sindh, Karachi.
9. P.S to Secretary, W&S Department, Govt. of Sindh, Karachi.
10. Notification file.

SECTION OFFICER (GENERAL)
FOR SECRETARY TO GOVT. OF SINDH

SCHEDULE OF PRICES (BOQ)

(Description and rate of items based on Composite Schedule of Rates)

**Name of Work :- Rehabilitation of existing Primary Schools in District Sanghar under Pak MDGs
Community Development Programme 2014-15 (03-Units) @ GPS. Village Syed Mureed Ali Shah UC
Chotiyaryoon.**

S.No.	Name of Item	Quantity	Rate	Unit	Amount
	PART-A CIVIL WORK.				
1	Dismantling cement concrete plain 1:2:4	205.00	3327.50	%Cft	6821.38
2	Dismantling R.C.C	462.00	5445.00	%Cft	25155.90
3	Dismantling Brick Work	1050.00	1285.63	%Cft	13499.12
4	Excavation in Foundation of Building Bridges and Other Structures Including Dagbelling Dressing Refilling around Structure with Excavated Earth Watering and Ramming lift upto 5ft (Ordinary soil)	875.00	3176.25	%0Cft	2779.22
5	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10	1080.00	8694.95	%Cft	93905.46
6	Pacca brick work in foundation and plinth in cement sand mortar.	1850.00	11948.36	%Cft	221044.66
7	Filling watering ramming earth under floor surplus earth excavated from foundation lead upto one chain and lift upto 5'	1033.00	1512.50	%0Cft	1562.41
8	Filling watering ramming earth under floor with new earth excavated from outside lead upto one chain and lift upto 5'	1169.00	3630.00	%0Cft	4243.47
9	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. The rate includes all kinds of forms, moulds, lifting, centering, shuttering, curring rendering and finishing the exposed surface (including screening and washing of shingle). RCC work in roof slab beams, coloumn, rafts, lintels and other structural members laid in situ or precast laid in position complete in all respects (i) Ratio 1:2:4 90 Lbs of cement 2 Cft sand and 4 Cft shingle 1/8" to 3/4" gauge.	1050.00	337	Cft	353850.00
10	Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position making joints and fastening including cost of binding wire (also removal of rust from bars) (Tor Bars).	62.00	5001.00	Cwt	310062.00
11	Pacca brick work in ground floor in cement sand mortar 1:6.	1424.00	12674.36	%Cft	180482.89
12	Pacc Brick Work in Other than Building	440.00	12346.65	%Cft	54325.26
13	Cement plaster 1:6 upto 20' Ft. height (1/2" thick)	4349.00	2206.6	%Sft	95965.03
14	Cement plaster 1:4 upto 20' Ft height (3/8" thick)	4349.00	2179.52	%Sft	94787.32
15	Cement plaster 1:4 upto 20' Ft. height (3/4" thick)	255.00	3015.76	%Sft	7690.19
16	Extra labour rate for making cement plaster patter pattas/band around straight or covered openings and around the edges of roof slabs, the width not less than 6" with fine finishing as directed by Engineer Incharge.	228.00	19.36	Rft	4414.08
17	Providing & Laying Hala or Pattern Tile Glazed 8"x8"x1/4" on Wall Facing in required Floor & Pattern of Style specification jointed in White Cement & Pigments over Base of 1:2 Grey Cement Mortar 3/4" Thick etc....	498.00	34520.31	%Sft	171911.14
18	Cement pointing struck joints on walls.	1919.00	1287.44	%Sft	24705.97
19	Providing & fixing G.I fixed/Chowkhats of size 7"x2" or 4 1/2"x3" for Doors using 20 gauge G.I sheet i/c welded hinges an dfixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c all carriag tools and plants used in making and fixing.	53.00	228.9	Rft	12131.70
20	Providing & fixing G.I fixed/chowkats of size 7"x2" or 4 1/2" x 3" for windows using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1:6 and preparing the jambs. The cost also i/c all carriage tools and plants used in making and fixing.	100.00	240.50	Rft	24050.00
21	Supplying and fixing in position iron/steel grill of 3/4" * 1/4" flat iron of approved design including painting 3 coats etc. complete (weight not less than 3.70 Lbs per sq. ft. of finished grill.	63.00	180.5	Sft	11371.50
22	First class deodar wood wrought framed and fixed in place including chowkhats hold fasts, tower bolts, chocks, cleats, handles, cord with hooks and cost of nails and screws, etc (Panelled or panelled and glazed or fully glazed 1-1/2" thick).	198.00	902.93	Sft	178780.14

S.No.	Name of Item	Quantity	Rate	Unit	Amount
23	Making and Fixing Steel Grated Door with 1/16" thick sheeting i/c angle iron frame 2"x2"x 3/8" size and 3/4" square bars at 4" center to center i/c locking arrangements (S.I.No 24 P.No 91)	48.00	726.72	P-Sft	34882.56
24	Providing and laying 1" thick topping of cement concrete (1:2:4) including surface finishing & dividing into panels. (3" thick)	986.00	4411.82	%Sft	43500.55
25	Providing and laying 1" thick topping of cement concrete (1:2:4) including surface finishing & dividing into pannels. (2" thick)	1935.00	3275.50	%Sft	63380.93
26	White Washing (Three Coats)	1042.00	829.95	%Sft	8648.08
27	Colour Washing (Three Coats)	2850.00	859.90	%Sft	24507.15
28	Priming coat of chalk under distemper. (In lime mortar 1:3)	3950.00	442.75	%Sft	17488.63
29	Distempering (Three coats)	3950.00	1079.65	%Sft	42646.18
30	Two coats of bitumen laid hot using 34 Lbs %Sft over roof and blinded with sand @ 1Cft %Sft	1143.00	1887.40	%Sft	21572.98
31	Preparing surface and painting doors and windows any type (including edges) Three Coats.	302.00	2116.41	%Sft	6391.56
32	Preparing surface and painting guard bars gates, iron bars, grating, railing (including standard braces etc) and similar open work. (Three coat).	248.00	1270.83	%Sft	3151.66
33	Making notice Board with Cement Sand	76.00	58.11	P-Sft	4416.36
Total :					2164125.46

PART- B : PLUMBING WORKS

1	Providing and fixing squaring type white glazed flushline cistern with internal fittings and flush pipe with bend and making requisite numbers of holes in wall plinth and floor for pipe connection and making good in cement concrete 1:2:4				
	B. WC pan of not less than 19" clear opening between flusing rims and 3 gallons flushing tank with 4" dia CI trap and CI thumble.	2.00	5044.6	Each	10089.20
2	Supplying and fixing in position long bib cocks with c.p head	2.00	337.92	Each	675.84
3	1/2" dia bib cock standard pattern.	1.00	478.28	Each	478.28
4	Providing and fixing electric motor 1/2" horse power i/c pumping set made 1 H.P etc.	1.00	5115.00	Each	5115.00
5	Providing installing hand pump machine i/c boaring with wooden sheo and C.C plate form.				
	a). Filter	10.00	136	P/Rft	1360.00
	b) Boaring	90.00	19	P/Rft	1710.00
6	Providing and fixing handle volve (china)				
	i). 1/2" dia	1.00	200.42	Each	200.42
	ii) 3/4" dia	1.00	271.92	Each	271.92
7	Providing GI pipes specials and clamps etc including fixing cutting and fittings complete with and i/c the cost of breaking through walls and roof making good etc painting two coats after cleaning the pipe etc with white zink paint with pigment to match t				
	i). 1/2" dia pipe	50.00	75.21	P/Rft	3760.50
	ii). 3/4" dia pipe	50.00	95.79	P/Rft	4789.50
8	Supplying and fixing fibre glass tank of approved quality and design and wall thickness as specified i/c cost of nuts bolts and fixing in plateform of cement concrete 1:3:6 and making connection for in-let out-let and over flow in-let out-let flow pipes				
	200 gallons wall thickness 4.0 mm.	200.00	87.95	P.Galan	17590.00
9	Providing U-PVC pipes fixing in trench i/c cutting, fitting and jointing with solvent cement i/c testing with water to a head of 122 meter or 400ft.				
	3/4" dia	20.00	19.00	P/Rft	380.00
	4" dia	10.00	226.00	P/Rft	2260.00
Total :					48680.66
G. TOTAL (A+B)					2212806

Note: Any variation in the description on item Quantites, Rates if any as per Sanctioned Estimate will be accepted


 EXECUTIVE ENGINEER
 EDUCATION WORKS DIVISION
 SANGHAR.

SCHEDULE OF PRICES (BOQ)

(Description and rate of items based on Composite Schedule of Rates)

Rehabilitation of existing Primary Schools in District Sanghar under Pak MDGs Community Development Programme 2014-15 (03-Units) @ GPS. Village Syed Mureed Ali Shah UC Chotiyaryoon (Electrification).

S.No.	Name of Item	Quantity	Rate	Unit	Amount
1	Wiring for light or fan point with 1.1.13(3/029) pvc insulated wire in PVC in channel patti (S.I.NO.129 P.15)	24	910.00	Point	21840.00
2	Wiring for plug point with 1.1.13(3/029) PVC insulated wire in 20mm (3/4") PVC in channel patti (S.I.No.130 P. 15)	4	742.00	Point	2968.00
3	P/L (Main or sub-main) PVC insulated with size 2-1/0.78(7/029) copper conducted in 20mm (3/4") PVC in channel patti. (S.I.No. 03 P.No. 01).	70	171.00	Rft	11970.00
4	Providing and fixing A.C one way S.P 10 to 15 Amp switch flush type on given prepared board (S.I.No. 218 P.33).	24	58.00	Rft	1392.00
5	Providing and fixing flush type 2 pin 5 ampers S.P plug socket switch and shoe unit on a given prepared board on surface as required (S.I.No:225 P.No: 33).	4	83.00	Rft	332.00
6	Providing and fixing flush type 3 pin 10 to 15 ampers S.P plug socket switch and shoe unit on a given prepared board on surface as required (S.I.No:225 P.No: 33).	1	151.00	Each	151.00
7	Providing and fixing B.C Brass batton holder and 254mm(10") E.I Shade(S.I.No. 232 P. 33).	18	70	Each	1260.00
8	Providing and fixing S.W canopy block and bakelite ceiling rose SW block (S.I.No: 28-B P.33).	6	72	Each	432.00
9	P/F Circuit breaker 10,15,20,30,40,50, 63, Amps 5P on prepared board. (S.I.No: 203 P.31).	5	916	P/Sft	4580.00
10	P/F Circuit breaker 10,15,20,30,40,50, 63, Amps DP on prepared board. (S.I.No: 204 P.31).	1	2456	Each	2456.00
11	P/F Voltmeter size 96/96 mm 500 volts as required (S.I.No:285 P41)	1	999	Each	999.00
12	P/L (Main or sub-main) PVC insulated with size 2-7/0.44(7/44) copper conductor in (1") PVC conducted on surface (S.I.No. 05 P.No. 01).	23	305	Each	7015.00
13	Wiring for main with 2-7/0.85 (7/1.064) pvc insulated in 30 mm (1/4") pvc installed wire (S.I.No: 7 P.1).	50	605	Each	30250.00
14	P/F Brass Ceiling Fan 56 good quality (S.I.N 235 P.No 34)	6	3185	Each	19110.00
				Total:-	104755.00

Part-B Non-Schedule Item

1	P/F Energy Sever superior quality i/c fixing 24 watts i/c fixing on existing holder etc complete (L.Q.R)	10	497.0	Each.	4970
2	P/F blue 100 Watts phillips (L.Q.R)	9	30.0	Each.	270
3	Providing and fixing distribution board double shutter to accommodate circuit breakers including painting with enamelled paint and for other similar job fixing in the wall i/c cutting, fitting, plastering & finishing (L.Q.R)	1	2933.00	P.Sft	2933
4	Fixing A.C ceiling fan regulator on metal board recessed in the wall or column covered with plastic sheet (L.Q.R)	6	195.00	Each	1170
5	Erection of ceiling fan i/c wiring of down road with 1/1.13 mm (3/029) PVC wire fixing or regulators plate canopy etc as required (L.Q.R).	6	150.00	Each	900
				Total No-Schedule:	10243
				TOTAL :-	114998

Note: Any variation in the description on item Quantities, Rates if any as per Sanctioned Estimate will be accepted


 EXECUTIVE ENGINEER
 EDUCATION WORKS DIVISION
 SANGHAR.

SCHEDULE OF PRICES (BOQ)

(Description and rate of items based on Composite Schedule of Rates)

**Name of Work : - Rehabilitation of existing Primary Schools in District Sanghar under Pak MDGs
Community Development Programme 2014-15 (03-Units) @ GPS. Village Madan Khan Jalalani UC**

Syed Sabghatullah Shaheed Rashdi.

S.No.	Name of Item	Quantity	Rate	Unit	Amount
	PART-A CIVIL WORK.				
1	Dismantling cement concrete plain 1:2:4	805.00	3327.50	%Cft	26786.38
2	Dismantling R.C.C	502.00	5445.00	%Cft	27333.90
3	Dismantling Brick Work	1180.00	1285.63	%Cft	15170.43
4	Excavation in Foundation of Building Bridges and Other Structures Including Dagbelling Dressing Refilling around Structure with Excavated Earth Watering and Ramming lift upto 5ft (Ordinary soil)	1549.00	3176.25	%OCft	4920.01
5	Cement concrete brick or stone ballast 1-1/2" to 2" guage ratio 1:5:10	880.00	8694.95	%Cft	76515.56
6	Pacca brick work in foundation and plinth in cement sand mortar.	1242.00	11948.36	%Cft	148398.63
7	Filling watering ramming earth under floor surplus earth excavated from foundation lead upto one chain and lift upto 5'	1033.00	1512.50	%OCft	1562.41
8	Filling watering ramming earth under floor with new earth excavated from outside lead upto one chain and lift upto 5'	1169.00	3630.00	%OCft	4243.47
9	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. The rate includes all kinds of forms, moulds, lifting, centering, shuttering, curring rendering and finishing the exposed surface (including screening and washing of shingle). RCC work in roof slab beams, coloumn, rafts, lintels and other structural members laid in situ or precast laid in position complete in all respects (i) Ratio 1:2:4 90 Lbs of cement 2 Cft sand and 4 Cft shingle 1/8" to 3/4" guage	945.00	337	Cft	318465.00
10	Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position making joints and fastening including cost of binding wire (also removal of rust from bars) (Tor Bars).	56.71	5001.00	Cwt	283606.71
11	Pacca brick work in ground floor in cement sand mortar 1:6.	1180.00	12674.36	%Cft	149557.45
12	Cement plaster 1:6 upto 20' Ft. height (1/2" thick)	2566.00	2206.6	%Sft	56621.36
13	Cement plaster 1:4 upto 20' Ft height (3/8" thick)	2566.00	2179.52	%Sft	55926.48
14	Cement plaster 1:4 upto 20' Ft. height (3/4" thick)	155.00	3015.76	%Sft	4674.43
15	Extra labour rate for making cement plaster patter pattas/band around straight or covered openings and around the edges of roof slabs, the width not less than 6" with fine finishing as directed by Engineer Incharge.	228.00	19.36	Rft	4414.08
16	Providing & Laying Hala or Pattern Tile Glazed 8"x8"x1/4" on Wall Facing in required Floor & Pattern of Style specification jointed in White Cement & Pigments over Base of 1:2 Grey Cement Mortar 3/4" Thick etc....	485.00	34520.31	%Sft	167423.50
17	Cement pointing struck joints on walls.	1019.00	1287.44	%Sft	13119.01
18	Providing & fixing G.I fixed/Chowkhats of size 7"x2" or 4 1/2"x3" for Doors using 20 gauge G.I sheet i/c welded hinges an dfixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1"6 and repairing the jambs. The cost also i/c all carriag tools and plants used in making and fixing.	53.00	228.9	Rft	12131.70


S.No.	Name of Item	Quantity	Rate	Unit	Amount
19	Providing & fixing G.I fixed/chowkats of size 7"x2" or 4 1/2" x 3" for windows using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1:6 and preparing the jambs. The cost also i/c all carriage tools and plants used in making and fixing.	100.00	240.50	Rft	24050.00
20	Supplying and fixing in position iron/steel grill of 3/4" * 1/4" flat iron of approved design including painting 3 coats etc, complete (weight not less than 3.70 Lbs per sq. ft. of finished grill).	57.00	180.5	Sft	10288.50
21	First class deodar wood wrought framed and fixed in place including chowkhats hold fasts, tower bolts, chocks, cleats, handles, cord with hooks and cost of nails and screws, etc (Panelled or panelled and glazed or fully glazed 1-1/2" thick).	125.00	902.93	Sft	112866.25
22	Providing and laying 1" thick topping of cement concrete (1:2:4) including surface finishing & dividing into panels. (3" thick)	986.00	4411.82	%Sft	43500.55
23	Providing and laying 1" thick topping of cement concrete (1:2:4) including surface finishing & dividing into pannels.(2" thick)	1286.00	3275.50	%Sft	42122.93
24	White Washing (Three Coats)	1042.00	829.95	%Sft	8648.08
25	Colour Washing (Three Coats)	1797.00	859.90	%Sft	15452.40
26	Priming coat of chalk under distemper. (In lime mortar 1:3)	2565.00	442.75	%Sft	11356.54
27	Distemping (Three coats)	2565.00	1079.65	%Sft	27693.02
28	Two coats of bitumen laid hot using 34 Lbs %Sft over roof and blinded with sand @ 1Cft %Sft	1143.00	1887.40	%Sft	21572.98
29	Preparing surface and painting doors and windows any type (including edges) Three Coats.	232.00	2116.41	%Sft	4910.07
30	Preparing surface and painting guard bars gates, iron bars, grating, railing (including standard braces etc) and similar open work. (Three coat).	152.00	1270.83	%Sft	1931.66
31	Making notice Board with Cement Sand	76.00	58.11	P-Sft	4416.36
Total :					1699679.86

PART- B : PLUMBING WORKS

1	Providing and fixing squatting type white glazed flushline cistern with internal fittings and flush pipe with bend and making requisite numbers of holes in wall plinth and floor for pipe connection and making good in cement concrete 1:2:4 B. WC pan of not less than 19" clear opening between flusing rims and 3 gallons flushing tank with 4" dia CI trap and CI thumble.	1.00	5044.6	Each	5044.60
2	Supplying and fixing in position long bib cocks with c.p head	2.00	337.92	Each	675.84
3	1/2" dia bib cock standard pattern.	1.00	478.28	Each	478.28
4	Providing and fixing electric motor 1/2" horse power i/c pumping set made 1 H.P etc.	1.00	5115.00	Each	5115.00
5	Providing installing hand pump machine i/c boaring with wooden sheo and C.C plate form.				
	a). Filter	10.00	136	P/Rft	1360.00
	b) Boaring	90.00	19	P/Rft	1710.00
6	Providing and fixing handle volve (china)				
	i). 1/2" dia	1.00	200.42	Each	200.42
	ii). 3/4" dia	1.00	271.92	Each	271.92
7	Providing GI pipes specials and clamps etc including fixing cutting and fittings complete with and i/c the cost of breaking through walls and roof making good etc painting two coats after cleaning the pipe etc with white zink paint with pigment to match t				

S.No.	Name of Item	Quantity	Rate	Unit	Amount
	i). 1/2" dia pipe	50.00	75.21	P/Rft	3760.50
	ii). 3/4" dia pipe	50.00	95.79	P/Rft	4789.50
8	Supplying and fixing fibre glass tank of approved quality and design and wall thickness as specified i/c cost of nuts bolts and fixing in plateform of cement concrete 1:3:6 and making connection for in-let out-let and over flow in-let out-let flow pipes				
	200 gallons wall thickness 4.0 mm.	200.00	87.95	P.Galan	17590.00
9	Providing U-PVC pipes fixing in trench i/c cutting, fitting and jointing with solvent cement i/c testing with water to a head of 122 meter or 400ft.				
	3/4" dia	20.00	19.00	P/Rft	380.00
	4" dia	10.00	226.00	P/Rft	2260.00
Total :					43636.06
GRAND TOTAL (A+B)					1743316

Note: Any variation in the description on item Quantities, Rates if any as per Sanctioned Estimate will be accepted


 EXECUTIVE ENGINEER
 EDUCATION WORKS DIVISION
 SANGHAR.

SCHEDULE OF PRICES (BOQ)

(Description and rate of items based on Composite Schedule of Rates)


**Name of Work :- Rehabilitation of existing Primary Schools in District Sanghar under Pak MDGs
Community Development Programme 2014-15 (03-Units) @ GPS. Village Madan Khan Jalalani UC Syed
Sabghatullah Shaheed Rashdi (Electrification).**

S.No.	Name of Item	Quantity	Rate	Unit	Amount
1	Wiring for light or fan point with 1.1.13(3/.029) pvc insulated wire in PVC in channel patti (S.I.No.129 P.15)	24	910.00	Point	21840.00
2	Wiring for plug point with 1.1.13(3/.029) PVC insulated wire in 20mm (3/4") PVC in channel patti (S.I.No.130 P. 15)	4	742.00	Point	2968.00
3	P/L (Main or sub-main) PVC insulated with size 2-1/0.78(7/.029) copper conducted in 20mm (3/4") PVC in channel patti. (S.I.No. 03 P.No. 01).	70	171.00	Rft	11970.00
4	Providing and fixing A.C one way S.P 10 to 15 Amp switch flush type on given prepared board (S.I.No. 218 P.33).	24	58.00	Rft	1392.00
5	Providing and fixing flush type 2 pin 5 ampers S.P plug socket switch and shoe unit on a given prepared board on surface as required (S.I.No:225 P.No: 33).	4	83.00	Rft	332.00
6	Providing and fixing flush type 3 pin 10 to 15 ampers S.P plug socket switch and shoe unit on a given prepared board on surface as required (S.I.No:225 P.No: 33).	1	151.00	Each	151.00
7	Providing and fixing B.C Brass batton holder and 254mm(10") E.I Shade(S.I.No. 232 P. 33)	18	70	Each	1260.00
8	Providing and fixing S.W canopy block and bakelite ceiling rose SW block (S.I.No: 28-B P.33)	6	72	Each	432.00
9	P/F Circuit breaker 10,15,20,30,40,50, 63, Amps 5P on prepared board. (S.I.No: 203 P.31).	5	916	P/Sft	4580.00
10	P/F Circuit breaker 10,15,20,30,40,50, 63, Amps DP on prepared board. (S.I.No: 204 P.31).	1	2456	Each	2456.00
11	P/F Voltmeter size 96/96 mm 500 volts as required (S.I.No:285 P41)	1	999	Each	999.00
12	P/L (Main or sub-main) PVC insulated with size 2-7/0.44(7/44) copper conductor in (1") PVC conducted on surface (S.I.No. 05 P.No. 01).	23	305	Each	7015.00
13	Wiring for main with 2-7/0.85 (7/.064) pvc insulated in 30 mm (1/4") pvc instilled wire (S.I.No: 7 P.1)	50	605	Each	30250.00
14	P/F: Brass Ceiling Fan 56 good quality (S.I.N 235 P.No 34)	6	3185	Each	19110.00
Total:-					104755.00

Part-B Non-Schedule Item

1	P/F Energy Sever superior quality i/c fixing 24 watts i/c fixing on existing holder etc complete (L.Q.R)	10	497.0	Each.	4970
2	P/F blub 100 Watts phillips (L.Q.R)	9	30.0	Each.	270
3	Providing and fixing distribution board double shutter to accommodate circuit breakers including painting with enamelled paint and for other similar job fixing in the wall i/c cutting, fitting, plastering & finishing (L.Q.R)	1	2933.00	P.Sft	2933
4	Fixing A.C ceiling fan regulator on metal board recessed in the wall or column covered with plastic sheet (L.Q.R)	6	195.00	Each	1170
5	Errrection of ceiling fan i/c wiring of down road with 1/1.13 mm (3/.029) PVC wire fixing or regulators blate canopy etc as required (L.Q.R).	6	150.00	Each	900
Total No-Schedule:					10243
TOTAL					114998

Note: Any variation in the description on item Quantites, Rates if any as per Sanctioned Estimate will be accepted


EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION
SANGHAR.



**GOVERNMENT OF SINDH
WORKS & SERVICES DEPARTMENT**

Karachi

Dated:-

/

/2015

NOTIFICATION

No._____ with approval of Competent Authority, a Redressal of Grievances Committee with the following composition, in terms of Rule-31 of Sindh Public Procurement Rules-2010 is hereby constituted in the office of Executive Engineer Highways Division Sanghar for Redressal of Grievances and settlement of disputes if any, arises between procuring agency and bidders:-

- | | | |
|-------|--|----------|
| i). | Deputy Commissioner / PD
District Development Committee
Sanghar. | Chairman |
| ii). | District Accounts Officer
Sanghar of his representative. | Member |
| iii). | Executive Engineer
Education Works Division
Sanghar | Member |

2. The Functions & Responsibilities of the Committee will be same as specified in Rules-31 (4) and (5) of Sindh Public Procurement Rules-2010

SECRETARY TO GOVT. OF SINDH