



## ESTABLISHMENT OF GOVT POLYTECHNIC INSTITUTE CHACHRO

### BILL OF QUANTITIES

CIVIL WORKS					
CIVIL WORKS			SCHEDULE ITEM		
QTY.	S.#	DESCRIPTION	RATE	UNIT	AMOUNT
1400	2	Dismantling cement concrete plain 1:2:4 (S.I.No. 19 P-10)	3327.5	%cft	46585.00
3600	3	Providing and fixing iron steel grill using solid square bars of size 1/2" x 1/2" place at 4" I/c and frame of flat iron patti of 3/4" x 3/4" I/c circle shape at 1-0 apart equivalent fitted with 1st coat of re oxide paint etc .	194.16	Psft	698976
9135	4	laying white marble flooring fine dressed on the surface without winding set in lime mortar 1:2 including rubbing and polishing of the joints. 3/4" thick flooring	567.48	Psft	5183929.80
7797	5	Laying floors of approved coloured glazed tile 1/4" thick laid in white cement and pigment on a bed of 3/4"thick cement mortor 1:2	27747.06	%sft	2163438.27
1400	6	C. C Plain Including Placing Compacting finishing and curing complete including screening and washing at stone aggregate. Ratio 1:2:4	14429.25	%cft	202009.50
4320	7	Pacca brick work in ground floor in cement sand mortar 1:4	13227.41	%cft	571424.112
27450	9	Providing and lying cement concrete topping (1:2:4) i/c dividing in to penal i/c surface finising 2" thick	3275.5	%sft	899124.75
27450	10	Two coat of bitumen laid hot using 34 lbs %sft over roofoard blinded with sand at onecftper%sft	1887.4	%sft	518091.30
5760	19	Cement plaster 1:6 Upto 20" height (a) 1/2" thick (S.I.No 13-b P-57)	2206.6	%sft	127100.16
5760	20	Cement plaster 1:4 Upto 20" eight. (a) 3/8 "thick (S.I.No. 11a P-57)	2197.52	%sft	126577.15
5760	21	Applying floating coat of cement 1/32" thick	660	%sft	38016.00
2360	23	Providing anti-termmite treatment by sparying sprinkling spreading Neptachier 0.5% Emulsion as an overal pre construction treatment in saln type construction along external foundation trenches of the building over complete parimter of the foundation trench etc as per direction of engineer incharge .	40.1	Prft	94636.00
392	25	Providing and laying HALA or pattern tile glazed 6"x6" x1/4" on fooring wall facing ( Srno 61 Page No 47 Chep Flooring )	47651.56	%sft	186794.12
Sub Total					10856702.16
% below/ above					
Total Cost of Scheduled items					

