

## ESTABLISHMENT OF GPI AT RAZZAKABAD, MALIR, KARACHI

**[REMAINING WORK] BILL OF QUANTITIES**

(Civil Works)

Sindh Schedule of Rates 2012

S.NO	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	<b>DISMANTLING</b> Dismantling cement concrete plain 1:2:4 (Page No. 10, Item No. 19-c)	5,500.00	%Cft	3,327.50	183,012.50
2	<b>CHEMICAL POLISHING</b> Applying chemical polishing on existing mosaic / marble flooring / dado including cleaning, grinding with carborandum stone / sand paper and applying chemical polish as per requirement. (Page No. 48, Item No. 70)	16,000.00	P.Sft	36.60	585,600.00
3	<b>WINDOWS</b> First class deodar wood wrought, joinery in doors and windows etc. fixed in position including chowkats hold fasts hinges, iron tower bolts, chocks cleats handles and cords with hooks, etc. (Page No. 57, Item No. 7b)  Rate of Door: Rs. 1,227.36 - G.I. Frame Rs. 228.90 = Door & Windows (Rs. 998.46)	2,050.00	Per Sft	998.46	2,046,843.00
4	<b>IRON GRILL</b> Providing and fixing iron steel grill using solid square bars of size ½" X ½" placed at 4" including and frame of flat iron patti of ¾" X ¾" including circle shape at 1-0 apart equivalent fitted with screws are pins with painting 3 coats with 1st coat of red oxide paint etc. (Page No. 93, Item No. 30)	1,422.00	Per Sft	194.16	276,095.52
5	<b>ALUMINUM SHEET IN EXPANSION</b> Providing and fixing Aluminum sheet 6" to 9" with V-Notch for expansion joints including fixing with nails / screws. (Page No. 108, Item No. 88)	256.00	Per Rft	207.51	53,122.56
6	<b>MARBLE TILE FLOORING</b> Laying 1" thick white marble flooring fine dressed on the surface without winding set in lime mortar 1:2 including rubbing and polishing of the joints. (Page No. 42, Item No. 28-b)	12,560.00	P.Sft	628.93	7,899,360.80

## ESTABLISHMENT OF GPI AT RAZZAKABAD, MALIR, KARACHI

**[REMAINING WORK] BILL OF QUANTITIES**

(Civil Works)

Sindh Schedule of Rates 2012

S.NO	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
7	<b>ENAMEL PAINT ON WOOD WORKS</b> Preparing surface and painting of doors and windows any type (including edges) 3 Coats (Page No. 68, Item No. 5-C-i+ii)	462.00	%Sft	2,116.41	9,777.81
8	<b>WEATHER COAT ON COMPOUND WALL</b> Preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick / sand paper, filling the voids with chalk / plaster of paris and then painting with weather coat of approved make. (Page No. 55, Item No. 38-a&b)	28,000.00	%Sft	2,567.95	719,026.00
9	<b>HALA TILES</b> Providing and laying HALA or pattern tiles glazed 6" X 6" X ¼" on floor or wall facing in required colour and pattern of STILE as per specification jointed in white cement and pigment over a base of 1:2 grey cement mortar ¾" thick including washing and filing of joints with slurry of white cement and pigment in desired shape with finishing, cleaning and cost of wax polish etc. complete including cutting tiles to proper profile. (Page No. 47, Item No. 61) fixing the tile for matching of existing elevation, pattern & colour wherever required at any height.	700.00	%Sft	47,651.56	333,560.92
10	<b>CC PLAIN</b> Cement concrete plain Ratio 1:3:6 including placing compacting, finishing and curing complete (including screining and washing at stone aggregate without shuttering (Page No. 15, Item No. 5)	10,700.00	%Cft	11,288.75	1,207,896.25
11	<b>PAVING / TOUGH BLOCKS</b> Providing and fixing cement paving / tough blocks flooring having size of 197 X 97 X 80 mm of city / quddra / cobble shape with pigmented having strength between 5000 psi to 8500 psi including filling the joints with hill sand and laying in specified manner / pattern and desing etc. complete (Page No. 49, Item No. 74)	7,000.00	Per Sft	248.17	1,737,190.00

## ESTABLISHMENT OF GPI AT RAZZAKABAD, MALIR, KARACHI

**[REMAINING WORK] BILL OF QUANTITIES**

(Civil Works)

Sindh Schedule of Rates 2012

S.NO	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
12	<b>MAIN CABLE</b> Providing & laying (Main or Sub Main) PVC insulated & PVC sheeted with 4 core armoured copper conductor 600 / 1000 volts size 16mm <sup>2</sup> . (Electrical Works: Page No. 13, Item No. 113)	90.00	Per Meter	1,679.00	151,110.00
Sub Total				Rs=	15,202,595.36
____ % above / below				Rs=	
<b>Cost of Scheduled Items (Civil Work)</b>			<b>(A)</b>	<b>Rs=</b>	

## ESTABLISHMENT OF GPI AT RAZZAKABAD, MALIR, KARACHI

**[REMAINING WORK] BILL OF QUANTITIES**

Non-Schedule Items (Civil Work)

S.NO	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
13	<b>IRON / AERO GRILL</b> Providing and fixing iron steel grill with required section of steel iron as per approved design including welding all sides of the section at the junction, and embedding in cement concrete 1:2:4. Complete in all respect as shown on drawings, specifications and as per instructions of the Architect / Engineer-in-Charge.	500.00	Per Rft		
14	<b>FACING TILE</b> Providing and fixing best quality approved Facing Tiles of required size of approved pattern and colour on ¾" thick cement plaster base ratio 1:4 (with matching colour slurry) upto any height. Complete in all respect as per drawings, specifications and instructions of the Engineer-in-Charge.	2,000.00	P.Sft		
<b>Cost of Non-Schedule Item (Civil Work)</b>				<b>Rs=</b>	

<b>Total Cost of Civil Work (Remaining Work)</b>	<b>(A+B) =</b>	<b>Rs=</b>
--	----------------	------------

 \_\_\_\_\_  
**The Director (Works & Services)**

Dated: \_\_\_\_\_

 \_\_\_\_\_  
 Contractor's Signature with Stamp

Dated: \_\_\_\_\_